

An overall review of research on prefabricated construction supply chain management

Journal:	<i>Engineering, Construction and Architectural Management</i>
Manuscript ID	ECAM-07-2021-0668.R3
Manuscript Type:	Original Article
Keywords:	Risk Management, Construction, Supply Chain Management
Abstract:	

SCHOLARONE™
Manuscripts

Dear Reviewer and Editors,

We would like to express our sincere gratitude for your constructive comments on our manuscript. We have made every attempt to fully address these comments in the revised manuscript, and we believe these revisions have led to significant improvements and enhancements to the manuscript. Your original comments are listed below followed by our response to each comment (in red).

We look forward to hearing from you regarding our submission. We would be glad to respond to any further questions and comments that you may have.

Best Regards.

Referee: 1

Comments:

More depth is required in the discussion and conclusion section. Some discussions about lean supply-chain management processes/techniques (like Just-in-time delivery) or Industry 4.0 tools and technologies (IoT-based tracking tools) should be added to the paper. A separate section about the implications for the industry and academy is required.

We truly appreciate all your insightful suggestions and constructive comments. We have added a discussion of articles related to project delivery and lean supply chain management, please see section 5.1.4 in red, lines 474 to 486. Because the original section 5.1.6 is an information technology-related study, which overlaps with the topic of Industry 4.0, it is combined into one section for discussion. Other articles related to Industry 4.0 technologies (such as IOT) are added in section 5.1.6, please see lines 519 to 559 in red. The implications for the industry and academy is added in section 6.1 implications, please see line 685-694.

Additional Questions:

1. Originality: Does the paper contain new and significant information adequate to justify publication?: Yes, the revised paper is improved, and currently it contains contributions to the supply chain management in prefabricated construction research domain. However, there are still some rooms for improvement.

Thank you for your comments, we have made some modifications.

2. Relationship to Literature: Does the paper demonstrate an adequate understanding of the relevant literature in the field and cite an appropriate range of literature sources? Is any significant work ignored?: There is still room for improvement. For instance, in section 5.1.4 line 469 about research on project delivery and schedule, There should some reference to and discussion about

1
2
3 just-in-time delivery for prefabricated projects and how scholars investigated this topic in the
4 Lean+prefabrication supply-chain literature.
5

6 **Thank you for your comments, we have added a discussion of articles related to project delivery**
7 **and lean supply chain management, please see section 5.1.4 in red, lines 474 to 486. Changes have**
8 **also been made to the corresponding table. Please see Table 9 in the document titled "Table" for**
9 **details.**
10
11

12
13 3. Methodology: Is the paper's argument built on an appropriate base of theory, concepts or other
14 ideas? Has the research or equivalent intellectual work on which the paper is based been well
15 designed? Are the methods employed appropriate?: The paper methodology is improved,
16 particularly in the qualitative analysis section.
17

18 **Thank you for your confirmation of the modification we have made.**
19

20
21 4. Results: Are results presented clearly and analysed appropriately? Do the conclusions
22 adequately tie together the other elements of the paper?: The result section is improved, however
23 there is still room for improvement. For instance, the overall outcomes of this study for the
24 industry practitioners and academic researchers should be provided in the conclusion or discussion
25 section.
26

27 **Thank you for your comments. We have added relevant content, please see the conclusion, lines**
28 **685to 694.**
29

30
31 5. Implications for research, practice and/or society: Does the paper identify clearly any
32 implications for research, practice and/or society? Does the paper bridge the gap between theory
33 and practice? How can the research be used in practice (economic and commercial impact), in
34 teaching, to influence public policy, in research (contributing to the body of knowledge)? What is
35 the impact upon society (influencing public attitudes, affecting quality of life)? Are these
36 implications consistent with the findings and conclusions of the paper?: This part needs to be
37 provided, as I could not find a specific section which provides implications for research, practice
38 and/or society.
39

40 **Thank you for your comments. We have added relevant content, please see the conclusion, lines**
41 **685 to 694.**
42

43
44 6. Quality of Communication: Does the paper clearly express its case, measured against the
45 technical language of the fields and the expected knowledge of the journal's readership? Has
46 attention been paid to the clarity of expression and readability, such as sentence structure, jargon
47 use, acronyms, etc.: The readability of the paper is improved in the revised version.
48

49 **Thank you for your confirmation of the modification we have made, this revision we further**
50 **improved the readability of the article.**
51
52
53
54
55
56
57
58
59
60

1 An overall review of research on prefabricated construction supply 2 chain management

3 Abstract

4 Purpose

5 As a strand in industrialization movement in Architecture, Engineering and Construction (AEC)
6 industry, prefabricated construction (PC) has gained widespread popularity due to its high
7 efficiency, energy saving, low environmental impacts, safety and other advantages. Well
8 managed supply chain can further leverage the advantages of PC. However, there is a lack of
9 more systematic overview of the prefabricated construction supply chain (PCSC). This paper
10 aims to comb the current status and look into the future direction of PCSC by reviewing the
11 existing research.

12 Design/methodology/approach

13 131 articles related to prefabricated construction supply chain management (PCSCM) from 2000
14 to 2022 have been collated to i) conduct a bibliometric analysis by using VOSviewer, including
15 the following: literature sources, keywords co-occurrence, co-authorships, authorship citation
16 and country active in the field of PCSCM, ii) classify and summarize the status of research in
17 PCSCM through qualitative discussion, and iii) point out the future research directions.

18 Findings

19 131 articles are carried out for bibliometric analysis and in-depth qualitative discussion, the
20 visualization maps and the main research themes in the field of PCSCM are obtained. The results
21 show that supply chain intelligentization and informatization are hot topics. Finally, future
22 research directions that should be paid attention to in the field of PCSCM are pointed out.

23 Practical implications

24 This study can help project managers understand the current status and problems of PCSC
25 operations and provide a basis for future management decisions.

26 Originality/value

27 Compared with previous studies, this study adds the dimension of "article authorship" to the
28 quantitative analysis and discusses the research themes in the field of PCSCM in a
29 comprehensive manner. In addition, this paper deeply discusses the the main research topics
30 from both the specific contents and research methods adopted.

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

31 **Keywords**

32 Prefabricated construction, supply chain management, Bibliometric analysis, qualitative
33 discussion, literature review

1. Introduction

PC as an alternative and novel construction technology is a construction method. Using this method, most on-site activities are performed off-site, usually in a safe and controlled factory environment away from the construction site (Jaillon and Poon, 2014), and the prefabricated components manufactured in a factory are then transported to the site for assembly. Compared to conventional construction methods which normally are labor-intensive, produce high volumes of construction waste and have lower efficiency (Wang et al., 2018a), PC has attracted remarkable attention from both scholars and practitioners due to its advantages, e.g. green building features, controllable environmental impacts, reduced energy consumption, high production efficiency, lower costs, enhanced safety and sustainability (Liu et al., 2020a; Wang et al., 2019b; Zhong et al., 2015).

The PCSC plays a key role in connecting construction sites and off-site factories (Wang et al., 2019b). As early as 1999, Jardim et al. (1999) suggested that the effective exchange of resources, materials and cash flow among all stakeholders in construction projects was the key factor to avoid project delays, cost overruns and to ensure the success of the project. Later in 2003, Kahkonen et al. (2003) made it clear that standardization of supply chain processes in the delivery of high-level prefabricated components was likely to reduce performance differences and improve quality. It was not until recent years that the PCSCM received further attention (Liu et al., 2020a). However, due to the characteristics of large investments, long construction period, groups of suppliers and subcontractors involved, and more complex processes, the PCSC tends to be more complex, inefficient and costly (Xun et al., 2019). Supply chain operation problems, such as ineffective supply of prefabricated components and poor cooperation among participants, are the main bottlenecks that hinder the development of PC. Poor PCSCM can increase transportation cost, affect production efficiency and make later maintenance more complicated (Maas and Eekelen, 2004). The literature review can help to quickly understand the current state of research in a particular research area and highlight research gaps. Unfortunately, there are few review articles in PCSC, and the current study does not provide a comprehensive view of the latest developments in PCSC, although the PCSC has received more and more attention in recent years and the number of publications has also increased greatly. Therefore, the literature since the year of 2000 was reviewed combining bibliometric analysis with qualitative discussion to show latest research progress and future direction in PCSC.

The remainder of this paper is structured as follows. The related research background is

1
2
3
4 66 described in Section 2. The methodologies adopted in this research are explained in Section 3.
5 67 The results via visual data analysis are presented in Section 4. The qualitative discussion on
6
7 68 stratified review results from varied aspects is showed in Section 5. Concluding remarks,
8
9 69 contribution and future research directions are summarized in Section 6.

10 11 70 2. Background

12 13 14 71 2.1 General supply chain management

15
16 72 PC is a new technology integrating construction with manufacturing, and PCSC belongs to
17
18 73 both the construction supply chain and the manufacturing supply chain. On the one hand,
19
20 74 modern manufacturing supply chain, which is vulnerable to various risks, is a complex network
21
22 75 spanning different geographical locations. On the other hand, the operational efficiency of the
23
24 76 supply chain is further affected by the weak technical foundation, low management level, lack of
25
26 77 effective information communication and inefficient cooperation in the traditional construction
27
28 78 supply chain. In summary, as far as the PCSC is concerned, it involves a variety of stakeholders,
29
30 79 such as contractors, designers, manufacturers, transporters, assembly subcontractors, etc., and
31
32 80 requires various technical and information exchanges in design, manufacturing, transport and
33
34 81 assembly. The frequent information exchange between independent companies increases the
35
36 82 vulnerability and complexity of PCSCM. Therefore, the PCSCM should be based on the existing
37
38 83 manufacturing supply chain management and traditional construction supply chain
39
40 84 management. Subsection 2.1.1 and 2.1.2 respectively summarize the mainstream research on
41
42 85 supply chain management in manufacturing and construction industries in recent years.

43 44 86 2.1.1 Manufacturing supply chain management

45
46 87 Esfahbodi et al. (2016) developed and empirically evaluated a comprehensive sustainable
47
48 88 supply chain management (SSCM) performance framework based on resource dependence
49
50 89 theory (RDT), which linked SSCM practice with organizational performance. Ahmadi et al. (2017)
51
52 90 proposed a framework to study the social sustainability of supply chain. Feng et al. (2018)
53
54 91 studied the mediating effects of environmental and operational performance on green supply
55
56 92 chain management (GSCM) and financial performance. Based on the manufacturing supply
57
58 93 chain in developing countries, Mangla et al. (2018) identified 16 important obstacles to the
59
60 94 adoption of circular supply chain in India through literature review and expert interviews, and
95 analyzed these obstacles by using the comprehensive explanation structure model. Mani et al.

1
2
3
4 96 (2018) used co-variance-based structural equation modeling to investigate the social
5 97 sustainability of suppliers in Indian manufacturing industry. Kusi-Sarpong et al. (2019) put
6
7 98 forward a framework of sustainable innovation standards to study the sustainable supply chain
8
9 99 consisted of manufacturing enterprises. Qaiser et al. (2019) proposed the road map of
10 100 sustainable reverse supply chain operation, and revealed the relationship between Industry 4.0
11 101 and circular economy by solving the case-based model that affected economic and
12 102 environmental performance. Wang et al. (2020a) analyzed 260 samples based on three
13 103 measurement periods of Chinese manufacturing industry by hierarchical multiple regression
14 104 method, and revealed the influence of corporate social responsibility on green supply chain
15 105 management. Sarkar et al. (2021) studied waste management in manufacturing sustainable
16 106 supply chain based on a three-level sustainable supply chain model, which consisted of a single
17 107 supplier, a single manufacturer and multiple retailers.

108 2.1.2 Construction supply chain management

109 The one-off nature of the project, the arduousness of the project scale and life cycle make
110 the supply chain management within the construction industry extremely complicated (AlMaian
111 et al., 2015). Isatto et al. (2015) discussed the ways of supply chain members fulfilling their
112 commitments from the perspective of language-action (LAP) and how these ways affected the
113 integration and coordination of the make-to-order supply chain. Woo et al. (2016) empirically
114 tested the communicational ability of green supply chain management in construction industry
115 and the relationship among external green integration, green cost reduction and enterprise
116 competitiveness from the perspective of suppliers. Kim and Nguyen (2018) used factor analysis
117 technique and two-step Structural Equation Modeling (SEM) model to reveal the characteristics
118 of construction supply chain relationship and its influence on project performance. Rudolf and
119 Stefan (2018) provided a systematic and structured view for the key supply chain risks in
120 large-scale general contracting projects. Zeng et al. (2018) verified that supply chain integration
121 contributed to the sustainable utilization of building materials by using the partial least squares
122 structural equation model. Meng (2019) discussed the implementation of the lean principle in
123 the project-based construction supply chain. Ps and Sash (2019) put forward a comprehensive
124 risk management method for construction project supply chain by using grounded theory, fuzzy
125 cognitive map and grey relational analysis. Shahbaz et al. (2020) identified three types of risks in
126 the supply chain of construction industry through empirical investigation, which were
127 supply-side risk, process-side risk and demand-side risk. Mojumder and Singh (2021) discussed

1
2
3
4 128 various driving factors, contributing factors and obstacles of green supply chain in Indian
5 129 construction industry.

6 7 130 2.2 PCSCM

8
9 131 Poorang and Farts (2013) suggested that there were many technical terms associated with
10 132 modern methods of construction including but not limited to prefabrication and draw up on
11 133 their similarities and differences in detail. They provided a specific definition of prefabrication
12 134 after Klotz (1986) in *Vision der Moderne: das Prinzip Konstruktion*, where he described the term
13 135 prefabrication as: "...manufacture of parts of a building in a factory before they are brought to
14 136 the site for incorporation in the finished structure". Although some might anecdotally believe
15 137 that the relationship between architecture and prefabrication has always been problematic, to a
16 138 greater or lesser extent, the building construction process has always been associated with
17 139 prefabrication in its entire documented history (Poorang and Farts, 2013).

18
19 140 The construction industry has been under tremendous pressure since the beginning of the
20 141 20th century, due to the population growth around the world, so the demand for construction
21 142 continues growing. It is suggested that to alleviate the pressure, one of the solutions is to
22 143 integrate and utilize the benefits of manufacturing industries in the building and construction
23 144 industry (Ricardo, 2019). Under such circumstances, PC came into being and vigorously
24 145 promoted the industrial development of the construction industry. Compared to traditional
25 146 construction methods, prefabricated methods have the several advantages including green and
26 147 sustainability, better environmental impacts, (including energy saving), higher and better
27 148 efficiency (throughout the production process and of the final product), arguably lower costs,
28 149 lower incident rates and better health and safety features (Liu et al., 2020a; Wang et al., 2019b;
29 150 Zhong et al., 2015). However, the biggest difference between PC and traditional construction is
30 151 that in PC prefabricated components are produced in a controlled factory environment and
31 152 transported to the construction site for installation or assembly (Razkenari et al., 2018). This
32 153 extends the PCSC and holds it responsible for the whole process of manufacturing,
33 154 transportation, delivery and installation of prefabricated products (Hasim et al., 2018).
34 155 Therefore, the PCSC is very complex and involves multiple processes and stakeholders (Luo et
35 156 al., 2020). It is precisely because the PCSC is different from the traditional construction supply
36 157 chain that the PCSC must be focused on exclusively. Good supply chain management can
37 158 promote PC to give full play to its advantages and maximize the benefits of construction
38 159 projects.

1
2
3
4 160 Figure.1. reflects the development trend of related research on PCSCM from 2011 to 2022
5 161 (data is from the sample in this paper). Before 2010, PCSCM has not received enough attention,
6 162 and this field has attracted significant attention only in the past ten years or so. This is also
7 163 mentioned in the research of Wang et al. (2019b). Therefore, the literature published from 2011
8 164 to 2022 are selected to show the research and development trend of PCSC.
9
10 165 It can be seen from Figure 1 that the related research began to increase significantly from 2014.
11 166 The overall upward trend shows that the development speed of PCSCM is accelerating, and
12 167 people increasingly realize the importance of PCSCM. However, even with the rapid
13 168 development of related research on PCSCM, the operation of PCSC in practice has not made
14 169 perfect progress. One of the reasons is the lack of understanding on PCSC (Li and Mao, 2017).
15 170 Literature review is considered to be a convenient and viable method for gaining insight into a
16 171 particular area of research (He et al., 2017), and therefore is promising to help lay the
17 172 groundwork, systematically provide information to navigate research and address issues related
18 173 to PCSCM. Liu et al. (2020b) discussed four topics, mainly focusing on strategic research and
19 174 project evaluation, design and optimization for PCSC process, supply chain integration and
20 175 management, and the application of advanced technologies. Wang et al. (2019b) classified the
21 176 existing research in PCSCM, in order to reveal the research gaps and put forward future research
22 177 opportunities. However, the existing studies do not provide a holistic overview of PCSCM
23 178 research. Compared with previous studies, the perspective involved in the bibliometric analysis
24 179 in this article is more complete, involving five aspects: literature sources, co-occurrence of
25 180 keywords, co-authorships, authorship citation and country active. Furthermore, this study
26 181 discusses the existing articles in a more comprehensive classification, which can help readers to
27 182 grasp the current status, the research hotspots and the research gaps of PCSCM more
28 183 effectively.

29
30
31
32
33
34
35
36
37
38
39
40
41
42 184 Figure.1 Trends of publications in PCSCM
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

185 3. Methodology

186 This paper makes a bibliometric analysis and categorization summary of the literature
187 related to PCSCM through the following three steps: (1) "Web of Science" is selected as the
188 database resource to collect relevant literature, (2) VOSviewer, a visual analysis tool, is used to
189 conduct quantitative bibliometric analysis, (3) the qualitative discussion in depth is adopted to
190 comprehensively stratify the PCSCM from different perspectives. The technical route for this
191 study is shown in Figure 2.

192 Figure 2. Technical route for this study

194 3.1 Data collection

195 Web of Science (WoS) is chosen as a database because it is one of the world's leading
196 citation databases (Zhu and Liu, 2020). WoS, where high-quality scientific papers are stored
197 (Blanco-Mesa et al., 2017), is considered as one of the most important databases in terms of
198 academic research and practice, hence it is widely used in literature review in various fields,
199 including medical related fields (Zhu et al., 2020), sports entrepreneurship (María et al., 2019),
200 as well as internet research and analysis (Moreno-Guerrero et al., 2020).

201 This study conducted a preliminary search for articles published between 2000 and 2022.
202 As initially mentioned by Poorang and Farts (2013) and then reiterated by others such as Zakaria
203 et al. (2018), other alternatives have been used with different degrees of overlap with the
204 concept of prefabrication in the building and construction industry, such as "industrialized
205 buildings", "off-site construction", "modular building", etc. Finally, the retrieval formula is
206 determined as follows: "prefabricated and (construct* or building or house) supply chain" OR
207 "precast construct* supply chain" OR "modular* and (construct* or building) supply chain" OR
208 "off-site construct* supply chain" OR " industrialized and (construct* or building) supply chain"
209 (wildcard character "*" can represent single or multiple characters). The initial number of
210 retrieved literature is 308. As WoS core is considered to be a more authoritative database (Liu et
211 al., 2020b; Blanco-Mesa et al., 2017), firstly, the WoS core is selected as the filter, and articles
212 belonging to the WoS core are retained after filtering. At the next stage, 9 review articles and
213 other irrelevant literature is excluded, which brings down the final number of papers to 131 to
214 be analyzed in the next stage.

215 3.2 Bibliometric analysis

216 The use of bibliometrics is becoming more and more prevalent in different disciplines (Aria
217 and Cuccurullo, 2018). Bibliometrics belongs to the research field of library and information, and
218 it is a statistical method, but it is not exclusively limited to just quantitative analysis, strictly
219 speaking, the measurement of physical units of publications, bibliographic citations and their
220 substitutes are called "bibliometrics" (Broadus, 1987), which is then enriched by an in-depth
221 qualitative review of the results to provide enough ground for discussion and further research in
222 the area of the study focus. Another explanation is that bibliometric analysis refers to visual
223 analysis of specific large-scale scientific data sets(Liu et al., 2020b).

224 Bibliometrics, which can be described as a science, is used to build bibliometric maps
225 (Blanco-Mesa et al., 2017). There are several visualized and analytical tools which can be used to
226 produce bibliometric maps with different features, capabilities and limitations. VOSviewer was
227 designed by van Eck and Waltman and first introduced in a paper in *Journal of Scientometrics* in
228 2010 (Eck and Waltman, 2010). It is an open source application that can be used to review and
229 analyze literature data retrieved from different databases, including WoS. It is favored by
230 scholars because of its extensive search options, high interoperability with different scientific
231 databases, as well as ease of learning and use. Unlike some other applications used for
232 bibliometric mapping, VOSviewer is a professional software, which illustrates scientific maps of
233 various knowledge fields based on the principle of literature co-citation and coupling (Eck and
234 Waltman, 2010; Hu et al., 2019). It can overcome the serious problems such as rather simple
235 graphic representation and overlapping labels of SPSS and Pajek bibliometrics maps (Eck and
236 Waltman, 2010), and clearly and intuitively reflect the current situation of research fields from
237 all aspects. In this paper, VOSviewer is used for visual analysis of existing literature because of
238 its advantages and capabilities. There are five main categories in visual analysis: 1) journal
239 sources, 2) keywords co-occurrence, 3) co-author analysis, 4) authorship citation, and 5) country
240 active. This paper presents a bibliometric analysis of the existing literature on PCSCM from the
241 five above-mentioned aspects.

242 3.3 Qualitative discussion

243 Quantitative visual analysis of existing literature by itself cannot provide a complete and
244 comprehensive understanding of the existing research status. A detailed qualitative discussion
245 on the existing literature is necessary to further capture the research state on PCSCM.
246 Taxonomy is a viable way to categorize and summarize the existing literature. In addition,

1
2
3
4 247 taxonomy has been used to discuss the performance of modular buildings in terms of cost,
5 248 schedule, environmental, health and safety (Kamali and Hewage, 2016). Wang et al. (2019b)
6
7 249 used taxonomy to create a classification system to reveal research gaps and opportunities in
8
9 250 prefabricated supply chain management. The classified discussion method adopted in this study
10
11 251 can help understand research results by splitting the complex PCSC into different aspects.
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

252 4. Results of visual analysis

253 4.1 Analysis of publication sources

254 In this study, VOSviewer is used to analyze the journal sources of literature related to
255 PCSCM. Cluster analysis of journal sources can reflect the contribution of journals to the entire
256 research field to some extent (Liu et al., 2020b). Figure 3 shows the clustering of journal sources
257 and their relationship. In the past research on scientific cartography, different thresholds were
258 tested using text mining tools, and it was finally concluded that the minimum number of articles
259 and citations to help achieve ideal and meaningful results were 3 and 20 respectively (Oraee et
260 al., 2017; Jin et al., 2018). However, some other studies had set the minimum number of articles
261 to 3 and the minimum number of citations to 10 (Liu et al., 2020b). In this study, the minimum
262 number of articles is set to 3 and the minimum number of citations is set to 20 through several
263 tests. In Figure 3, larger nodes and font sizes represent journals with a larger number of
264 published articles, and the link between nodes indicates the mutual citation among journals. For
265 example, *Automation in Construction* has a strong correlation with *Journal of Cleaner
266 Production*. Nodes of the same color can be classified into one category. Therefore, as shown in
267 Figure 3, *Journal of Management in Engineering*, *Automation in Construction* and *Journal of
268 Cleaner Production* can be classified into the same cluster, and journals belonging to the same
269 cluster generally have higher relevance, that is, they are considered to have higher mutual
270 citation rating.

271 Table 1 shows the number of articles published in each journal, total link strength, total
272 citations, average citations and average published years. The first three indices are highly
273 correlated, which can be used to quantitatively analyze the influence of journals in this research
274 field. As shown in Table 1, the journals with the highest total number of articles are *Journal of
275 Cleaner Production* and *Journal of Construction Engineering and Management*, and the journal
276 with the highest total citations is *Automation in Construction*. However, according to the
277 average citations, although the numbers of articles of *Journal of Management in Engineering*
278 and *International Journal of Production Economics* are not among the best, they still have higher
279 influence. In addition, according to the average published year, it can be seen that
280 *Sustainability*, *Journal of Cleaner Production* and *Journal of Management in Engineering* are
281 active in recent years and are expected to have great development potential.

282

283

284

Figure 3: Analysis of Publication Sources (Scientific Journal Outlets)

285 Table 1: Publication Sources (Scientific Journal Outlets): Total link strength, Number of articles,

286 Total citations, Average citations, Average published year, Average normalization citations

287

288 4.2 Analysis of keywords co-occurrence

289 Keywords can reflect the research topic of literature (Jin et al., 2018; Su and Lee, 2010) and
290 the research concentration in a particular study area (Liu et al., 2020b). The visual analysis of
291 keyword co-occurrence gives us a preliminary understanding of the current research hotspots.
292 There are three types of keyword analysis in VOSviewer, which are author keyword, keyword
293 plus and all keywords. "Author keywords" (Jin et al., 2018) or "all keywords" (Liu et al., 2020b)
294 can be used for clustering analysis of keywords. The co-occurrence frequency indicates the
295 strength of the connection between two keywords (Wang et al., 2019a). The minimum
296 co-occurrence times of keywords is set to 3 (Liu et al., 2020b; Jin et al., 2018). Therefore, 102 of
297 all the 1150 keywords meeting the preset minimum threshold were screened. First, keywords
298 with no significance were removed, such as "supply chain", "prefabricated construction", and
299 "supply chain management". The second step was to remove irrelevant keywords, such as
300 "social responsibility", "selection" and "project management". Finally, synonymous keywords,
301 for example, "supply chain integration" and "integration", "RFID" and "radio frequency
302 identification technology", "BIM" and "building information model", etc., were merged. As a
303 result, 30 valid keywords are retained, and the scientific map for visual analysis is obtained and
304 shown in Figure 4. Node size indicates the number of keywords co-occurrence, and 30 keywords
305 are roughly classified into four categories according to different node colors. Red nodes reflect
306 that Asian countries and regions have made more contributions to the innovation and
307 sustainable development research on PCSC. Yellow nodes reflect that advanced information
308 technologies, such as BIM, RFID, genetic algorithms, etc., are used to optimize the PCSC. Blue
309 nodes indicate that the simulation is often used to study how to improve the flexibility of PCSC
310 and how to facilitate the integration of the supply chain. Green nodes reflect that the game
311 theory is often used to study the inventory, cost and risk in the PCSC.

312 Table 2 shows the total link strength, co-occurrence times and average published year of
313 each keyword. It can be concluded that keywords such as "innovation", "optimization",

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

314 "integration" and "logistics" are mentioned more frequently. According to the average
315 published year, "genetic algorithm", "sustainability", "risk" and "lean" are popular topics.

Figure 4: Analysis of Keyword Co-occurrence

317 Table 2: Analysis of Keyword Co-occurrence: including Total link strength, Occurrence, Average
318 citations, Average published year, Average normalization citations

319 4.3 Analysis of co-authorship

320 Understanding the authorship partnerships in a certain research field not only increases the
321 possibility of obtaining professional knowledge and funds, but also improves the research
322 efficiency and prevents an author from being isolated (Jin et al., 2018; Hosseini et al., 2018). In
323 order to study authorship partnerships, the threshold usually set for the minimum number of
324 articles published by an author is 3, and the minimum number of articles cited by scholars is 20
325 when using VOSviewer (Jin et al., 2018). However, since the number of existing articles in the
326 field of PCSCM is not large enough, the minimum number of articles published by authors in this
327 study is set to 2 after several tests with the purpose of avoiding missing authors with few
328 articles but great influence. Therefore, 12 out of the 642 authors who meet the threshold
329 requirements are retained. The visualization analysis results of co-authorship is shown in Figure
330 5. According to the color of nodes in the figure, author clusters can be roughly divided into five
331 categories. There are two notable research groups. One is composed of Zhai, Zhong and Xu, and
332 the other is composed of Xue, Shen, Li and Xu. As shown in the Figure 5, these two research
333 groups have contributed many papers in the field of PCSCM.

334
335 Figure 5: Analysis of Co-authorship

336
337 Table 3 shows the results of quantitative analysis on co-authorship, including total link
338 strength, number of articles, total citations, average citations, average published year and
339 average normalization citations. According to number of articles published in the past decade,
340 the top 3 authors who have published in the field of PCSCM are Shen, Hu, and Wang. According
341 to the average citations, some authors have great influence, such as Xue, Xu, Mao and Pan,
342 although they have published a small number of articles. In recent years, the more active
343 authors are Shen, Li, et al., which means that these authors will be the potential force for
344 further development in the field of PSCSM.

345
346 Table 3: Analysis of Co-authorship, including: Total link strength, Number of articles, Total
347 citations, Average citations, Average published years, Average normalization citations

349 4.4 Analysis of authorship citation

350 In order to find the authoritative publications in the field of PCSCM, this paper analyzes the

1
2
3
4 351 citations of existing documents. After many tests, the desirable results can be obtained by
5 352 setting the minimum citations of articles to 10. 15 out of the 117 articles meet the threshold
6
7 353 requirements. Figure 6 shows the most frequently cited articles in the field of PCSCM and the
8
9 354 links among the articles, which can measure the influence of the articles in the research
10 355 community.

11
12 356 Table 4 shows a quantitative analysis of authorship citation, including title, links, citations
13 357 and normalization citations. According to Table 4, The article titled Stakeholder-Associated
14 358 Supply Chain Risks and Their Interactions in a Prefabricated Building Project in Hong Kong (Luo
15 359 et al., 2019) has the strongest links. Cheng et al. (2010) and Pan et al. (2012) entered the field of
16 360 PCSCM earlier and studied the integration of PCSC. Li et al.(2016) achieved high-level
17 361 achievements in the study on schedule risk in prefabricated housing in Hong Kong. In addition,
18 362 the research conducted by Demiralp et al. (2012) and Wang et al. (2017) on the combination of
19 363 RFID technology with PCSC also have high influence.
20
21
22
23
24
25

26 364
27 365 Figure 6: Analysis of Authorship Citation

28 366 Table 4: Analysis of Authorship Citation: Title, Links, Citations, Normalization citations
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

367 4.5 Analysis of country active

368 The contribution and relationship of each country to the field of PCSCM are discussed in
369 this section. Setting the minimum number of articles published in one country as 3 and the
370 minimum number of citations as 20 (Jin et al., 2018), 14 out of the 47 countries meet the
371 threshold standard and are retained. The countries and regions active in the research field of
372 PCSCM are shown in Figure 7 and Table 5. It can be seen from Figure 7 that the United States
373 and China are respectively the core developed and developing countries in this research field,
374 with the largest number of publications widely cited by other countries. Other active countries
375 are Britain, Germany and Australia, while Japan and France with only some publications interact
376 less with other countries. Table 5 shows the quantitative analysis results of country active.
377 According to the Figure 7, Sweden enters the field of PCSCM earlier, and its publications are
378 more influential. Although China has the largest number of publications, its international
379 influence is not significant. The United States and Australia are the mainstays of the current
380 development in PCSCM.

381

382 Figure 7: Analysis of Country Active

383 Table 5: Analysis of Country Active : Total link strength, Number of articles, Total citations,
384 Average citations, Average published year, Average normalization citations

385

386 5. Qualitative discussion

387 5.1 Stratified Review

388 At present, researchers and practitioners have paid more and more attention to PCSCM
389 (Zhang et al., 2019). In the previous sections, the relevant literature in the field of PCSCM has
390 been quantitatively analyzed by using VOSviewer. This section categorizes and qualitatively
391 discusses the existing research on PCSCM from seven aspects to more clearly grasp the current
392 research progress in the field of PCSCM: logistics and transportation, inventory planning, supply
393 chain costs, delivery and schedule, risks and resiliency, supply chain intelligentization and
394 informatization, .

395 5.1.1 Research on logistics and transportation

396 The research on logistics of PCSC is shown in Table 6. Logistics plays an important role in
397 the successful completion of PC (Gosling et al., 2016). The transportation process also serves as
398 a link between the construction site and the prefabricated plants (Shukor et al., 2016). As a
399 result of the transformation from on-site construction to off-site construction, the traditional
400 construction supply chain needs to be updated. The most remarkable change in the PCSC is that
401 the supply chain should focus on the transportation of prefabricated components. The logistics
402 optimization is the key to the new time-sensitive PCSC and can reduce the uncertainty in the
403 transportation process of prefabricated components (Liu and Lu, 2018; Hsu et al., 2018).
404 Ahmadian et al. (2016) used the results of case studies to emphasize the importance of
405 considering the transportation time of off-site materials in the planning of large-scale
406 industrialized projects and proposed a framework for estimating the duration of off-site
407 transportation. Fang and Ng (2019) examined the potential for deriving logistics plans for
408 materials production, supply and consumption using genetic algorithms (GAs). Hsu et al. (2018)
409 established a mathematical model to optimize the logistics process of modular structure, which
410 included three processes: manufacturing, storage and assembly. In order to emphasize logistics
411 and supply chain management, a special simulation template was developed to facilitate the
412 simulation modeling of the manufacturing, transportation, assembly and installation process of
413 preforms (Liu et al., 2017). Zhang and Yu (2020) considered the interdependence, dynamic
414 interaction and coordination among stakeholders in different stages and solved the dynamic
415 traffic planning problem of PCSC.

416 5.1.2 Research on inventory planning

417 The research on inventory planning involved in PCSC is shown in Table 7. Prefabricated
418 components need to be stored in a factory, warehouse or construction site before being
419 transported or assembled. The layout and inventory arrangement of warehouses can both affect
420 the production efficiency of PC (Wang et al., 2019b). Hsu et al. (2017) determined the most
421 suitable production plan and the best outsourcing quantity of prefabricated components in the
422 manufacturing environment with uncertain productivity, and established a two-stage stochastic
423 programming model and a mixed programming model to confirm the most favorable plan to
424 deal with inventory changes. In order to optimize the inventory arrangement and reduce related
425 costs, the optimal order batch and delivery batch could be obtained through the master-slave
426 decision-making model with centralized distribution centers (Zhang et al., 2017). Based on the

1
2
3
4 427 traditional EOQ (economic order quantity) model and the construction supply chain theory, the
5 428 inventory cost model and ordering strategy were obtained and optimized by combining with
6
7 429 sequential decision-making, which was proved to be effective (Yang et al., 2018). Furthermore,
8
9 430 in order to avoid the adverse effects caused by improper delivery of prefabricated components,
10
11 431 transportation companies needed to reserve some buffer space in their intermediate
12
13 432 warehouses. Nash model had been proved to be effective in alleviating the pressure on logistics
14
15 433 providers, reducing buffer space and related inventory costs (Zhai et al., 2019; Yue et al., 2019;
16
17 434 Zhai et al., 2018).

17 435 5.1.3 Research on supply chain costs

19 436 The research on the costs of PCSC. is shown in Table 8. In order to decrease the total cost
20
21 437 of PCSC, it is necessary to establish a supply chain cost model to identify the sources of various
22
23 438 costs and how they affect the total cost of the supply chain, so as to find countermeasures to
24
25 439 reduce the total cost (Kim et al., 2016). Demiralp et al. (2012) used simulation-based decision
26
27 440 support tools to simulate cost savings by using RFID for various participants in PCSC and
28
29 441 calculated the cost of technology investment that should be shared among all parties through
30
31 442 the cost-share ratio. To reduce the total material management cost in PCSC, Ko (2013) proposed
32
33 443 a material supply chain framework that allowed finding the most profitable transshipment
34
35 444 strategy by simulating different order lead time, demand, transportation cost and shortage cost.
36
37 445 Estimating the total cost of the supply chain by using activity-based costing is also helpful to find
38
39 446 out the key areas to reduce the total cost (Wang et al., 2018c). Feng et al. (2017) used
40
41 447 evolutionary game theory to deduce the cooperative relationship between producers and
42
43 448 promoted participants and stabilized this relationship by establishing an effective reward and
44
45 449 punishment mechanism, which could reduce the initial cost of PCSC. Zhang and Yu (2021)
46
47 450 proposed a multi-objective optimization model to study the resilience of construction schedule
48
49 451 dependence of PCSC plan by considering transportation cost. Zhang et al. (2021a) put forward
50
51 452 an evaluation model to guide the cost-controllable supply chain of PC and quantified and
52
53 453 distinguished the influence degree of direct or indirect factors related to cost performance in
54
55 454 the supply chain.

51 455 5.1.4 Research on project delivery and scheduling

53 456 Timely delivery of prefabricated components is very important for the successful
54
55 457 completion of PC (Kim et al., 2020), while production scheduling plays an important role in

1
2
3
4 458 timely delivery of prefabricated components. Reasonable schedule can promote the timely
5 459 delivery of prefabricated components and projects (Wang and Hu, 2018). Production scheduling
6 460 of components should require consideration on economic and environmental impacts (Kong et
7 461 al., 2018) and should focus on each stage before and after the production of components. Wang
8 462 and Hu (2017) integrated the process of mold manufacturing, components storage and
9 463 transportation from the perspective of the whole PCSC and considered the three situations of
10 464 day, night and all day, so as to revise the traditional production scheduling model. Liu and Lu
11 465 (2018) established a schedule optimization model based on constrained programming to deduce
12 466 the project schedule meeting the variable material delivery time and limited human resource
13 467 availability. Lee et al. (2019) presented the classification of PC projects as manufacturing driven,
14 468 on-site driven or a combination to improve scheduling strategies based on a schedule-driven
15 469 approach. Si et al. (2021) proposed a dynamic compensation mechanism to realize timely
16 470 component delivery, through which the factory could share the possible changes of the delivery
17 471 date of each component with its customers. Aiming to achieve lean PCSC, Chen et al. (2020a)
18 472 started from the concept of lean management and constructed an integrated BIM-RFID
19 473 database system that links information on material demands with look-ahead plans to better
20 474 manage material flow processes. Wang et al. (2020d) investigate the process optimization of a
21 475 precast concrete component production line by using value stream mapping, which is an
22 476 innovative application of lean production theory and value stream mapping in complex precast
23 477 concrete component production lines. Based on Lean Construction Principles, Goh and Goh
24 478 (2020) developed baseline (As-Is) simulation model of an ongoing precast prefabricated
25 479 volumetric construction (PPVC) project case study, which can reduce project delivery time by
26 480 applying lean concepts. Du et al. (2022) characterized the production scheduling of the
27 481 prefabricated components problem into a permutation flow shop scheduling problem (PFSSP)
28 482 with multi-optimization objectives based on the principles of value-based management (VBM)
29 483 and just-in-time (JIT) lean construction. Table 9 shows the related research on the delivery of
30 484 prefabricated construction and the progress of supply chain up to now.

485 5.1.5 Research on supply chain risk and resiliency

486 The research on supply chain risk and resilience of PC is summarized in Table 10. The
487 structure of PCSC is becoming more complex, which makes the related risks more prominent
488 (Wang, 2019). The risks of PCSC are inevitable, so they must be anticipated to ensure the
489 success of the project (Hatmoko et al., 2018). Li et al. (2016) paid attention to the schedule risks

1
2
3
4 490 in the PCSC earlier, and BIM as the central strategy could effectively reduce the key schedule
5 491 risks. On this basis, Vensim software package was applied to discuss the possible impacts of
6 492 various risks on the progress (Li et al. 2017), and then a hybrid dynamic model was developed to
7
8 493 analyze the relationships among schedule risks by further evaluating the schedule risks using the
9
10 494 Anylogic (Li et al., 2018a). In addition, the overall management risks of PCSC (Wang et al., 2018b;
11 495 Hatmoko et al., 2018; Wang, 2019) and stakeholder risks (Luo et al., 2019) have also been
12
13 496 studied recently. Wang et al.(2018b) proposed a global disturbance evaluation model to
14
15 497 evaluate the uncertainty of prefabricated supply chain. Hatmoko et al.(2018) identified risk
16
17 498 factors in PCSC and found out the key risk factors according to five dimensions of supply chain
18
19 499 operation reference (SCOR) model. Wang (2019) explored the similarity between the risk
20
21 500 management in PCSC and discussed the biological immune system. From a stakeholder
22
23 501 perspective, Luo et al. (2019) established a risk network for the PCSC in Hong Kong by using
24
25 502 social network analysis (SNA) and ranked the risks in PCSC by severity. Hsu et al.(2019) put
26
27 503 forward a mathematical model to design and optimize risk-average logistics configurations for
28
29 504 PC projects under operational uncertainty. Zhang et al. (2021b) constructed a conceptual model
30
31 505 of factors influencing the resilience of PCSC and further conducted empirical study showing that
32
33 506 the production and on-site assembly of components have a significant impact on the resilience
34
35 507 of the PCSC. Ekanayake et al. carried out a series of studies on resilience in PCSC and developed
36
37 508 a multilevel-multicriteria mathematical model to analyze the PCSC in Hong Kong (Ekanayake et
38
39 509 al. 2021a). In addition, they also simulated the dynamic influence of supply chain vulnerabilities
40
41 510 and supply chain capabilities in PCSC indicating that on-site assembly was considered as the
42
43 511 most vulnerable stage, while anticipation as the most influential capability (Ekanayake et al.
44
45 512 2021b). In view of the urgency of improving supply chain resilience in PC, Ekanayake et
46
47 513 al.(2021c) explored the relationship between supply chain vulnerability and supply chain
48
49 514 capability and they also developed a model to evaluate supply chain capability to improve the
50
51 515 resilience of industrialized construction in high-density cities (Ekanayake et al., 2021d).

516 5.1.6 Research on supply chain intelligentization and informatization

517 With the advent of the era of Industry 4.0, a new generation of revolutionary technologies
518 in the industrial field promotes the transformation of the construction industry to
519 intelligentization. In this context, many research results have been achieved in the field of PCSC.
520 See Table 11 for research on informatization in PCSC. The research on intelligentization in PCSC
521 focuses on real-time information and prefabricated component tracking. Zhong et al. (2017) and Li et

1
2
3
4 522 al. (2018b) combined Internet of Things (IoT) and BIM to design an information platform to achieve
5 523 real-time visibility and traceability in PCSC. Xu et al. (2019) proposed a cloud-based fleet
6 524 management platform through integrating the advantages of IoT and cloud technology to address
7
8 525 the scarcity of real-time data and ineffective information sharing mechanisms. Zhao et al. (2019)
9
10 526 introduced an innovative method that incorporated Radio Frequency Identification (RFID) and Long
11
12 527 Range (LoRa) technologies, sensor networks, the BIM model and cloud computing to automatically
13
14 528 collect, analyze and display real-time information about PC components. Wang et al. (2020c)
15
16 529 developed a novel blockchain-based information management framework for the PCSC and
17
18 530 proposed a visualization system to achieve (1) information sharing management, (2) real-time
19
20 531 control of scheduling, and (3) information traceability. Luo et al. (2020) used automated data
21
22 532 collection techniques to obtain real-time information on prefabricated components in each
23
24 533 operational phase of the PCSC and identify the factors that hinder the efficiency of the PCSC. Jiang et
25
26 534 al. (2022) and Zhao et al. (2022) developed a system based on digital twin technology for real-time
27
28 535 monitoring of assembly stages on-site. In addition, Li et al. (2014) developed a software platform
29
30 536 system and integrated all members of the PC project into this platform. On this unified platform, the
31
32 537 whole PC project is under the control of supply chain management. Zhong et al. (2015) proposed the
33
34 538 architecture of an Physical Internet (PI)-enabled prefabricated housing construction which upgrades
35
36 539 and transforms the PC so that the logistics echelons could be integrated and synchronized. In order
37
38 540 to improve communication efficiency. Abedi et al. (2016) developed a system architecture and
39
40 541 prototype of context-aware cloud computing building information modeling (CACCBIM) for PCSCM.
41
42 542 Based on RFID application and multi-agent simulation, an information tracking and supply
43
44 543 mechanism of PCSC is proposed (Du et al., 2017). Wang et al. (2017) investigated the data-driven
45
46 544 mechanisms and benefits of utilizing RFID in knowledge-based PCSC. Bian and He (2017) took the
47
48 545 information flow as the breakthrough point, analyzed the whole life cycle information flow of the
49
50 546 prefabricated construction. Xu et al. (2018) proposed a cloud-based integrated IoT platform through
51
52 547 exploiting the concept of cloud asset. Wang et al. (2020e) proposed a conceptual framework of an
53
54 548 Intelligent Construction System for Prefabricated Buildings based on the Internet of Things
55
56 549 (ICSPB-IoT) to break the bottleneck of information integration and interaction in the PCSC. Li et al.
57
58 550 (2021) developed an intelligent platform based on service-oriented manners with blockchain- and
59
60 551 IoT to promote the sustainability of the PCSC. Lee and Lee (2021) developed a digital twin framework
552
553 552 for real-time logistics simulation by using IoT sensors, BIM, and GIS, which could predict potential
554
555 553 logistics risks and accurate arrival time of modules, effective supply chain coordination can be
556
557 554 achieved through reliable prediction. Aiming for environmental friendliness, Tao et al. (2018)

555 proposed a greenhouse gas emission monitoring system based on IoT technology to real-time
556 monitor emissions during the production of components.

557 5.1.7 Research on modern construction technology

558 A significant feature that distinguishes PC from traditional construction is that
559 prefabricated components are transferred to the construction site for assembly. The design and
560 on-site assembly of prefabricated components make the PCSC needs to pay more attention to
561 the design stage and assembly stage, which is different from the traditional construction supply
562 chain (Mohamed et al., 2021). The application of modern design and assembly technology is
563 conducive to promoting the development of PC and improving their supply chain management.
564 This section provides a review of research related to design and assembly technology for further
565 study of the application of modern technology in the PC.

566 Isaac et al. (2016) put forward a graph-based method, which decomposes the design into
567 non-repetitive modules, so that these modules can be easily replaced in case of any damage, and
568 optimizes the modules by applying clustering algorithm to the data of BIM tools. Said et al. (2017)
569 put forward a new model of platform optimization for exterior wall panels (EPWPO), which is solved
570 by non-dominated sorting genetic algorithm (NSGA). This model can not only find the near optimal
571 geometric and structural design of wallboard, but also minimize the production cost. Alwisy et al.
572 (2019) developed a systematic method, It utilized 2D computer-aided design (CAD) drawings to
573 automatically generate BIM and construction manufacturing BIM. Navarro-Rubio et al. (2020)
574 combined artificial neural network with finite element model to improve the design efficiency of
575 prefabricated components and found the best structural design. Chen et al. (2020b) developed an
576 optimization design program using genetic algorithm. Compared with the results of existing
577 methods, the optimization design program can find the best structural design more quickly and
578 accurately.

579 Taghaddos et al. (2018) proposed a more comprehensive method to help plan multiple mobile
580 crane operations, such as crane selection, crane location and path planning. In order to solve the
581 assembly sequence planning and optimization (ASPO) problem in PC, Building Information Modelling
582 (BIM) and Improved Genetic Algorithm (IGA) were organically combined to propose a new method
583 called BIM-IGA-based ASPO method. This method used BIM for parametric modelling, used IGA to
584 search for an optimal assembly sequence, and then used BIM again for visual simulation to further
585 test the assembly sequence. Besides, IGA, which was improved in coding mode, crossover operation
586 and mutation operation, was also used to achieve the dynamic adjustment of assembly sequence in

1
2
3
4 587 construction process (Wang et al., 2018d). Zheng et al. (2020) developed a module-detection model
5 588 based on mask regions with volatile neural network (mask r-CNN), which could automatically
6
7 589 monitor modules in the process of site construction. Li et al. (2020) developed the smart work
8
9 590 packaging (SWP)-enabled constraints optimization service, to achieve autonomous initial path
10 591 planning of crane, networked constraints classification, and adaptive decisions on path re-planning.
11
12 592 Wang et al. (2021b) proposed a novel framework that integrates the latest computer vision methods
13 593 to realize automatically monitoring construction progress of precast walls, status information
14 594 identified and collected was stored as a JavaScript object notation (JSON) format and then sent into a
15 595 corresponding building information model (BIM) to timestamp the wall components. Table 12 shows
16 596 the related research on the modern construction technology of PCSC in recent years.

597 5.1.8 Research on other topics

598 The research in PCSCM also involves other aspects. For instance, Rocha et al. (2019),
599 Kahkonen et al.(2003), Xun et al. (2019) had contributed to providing standardized PCSC
600 processes. Arashpour et al. (2017), Daget and Zhang (2019), Han et al.(2017) and others had
601 devoted themselves to studying how to make optimal decisions in different stages of the PCSC
602 to improve the efficiency of PC projects. Green et al. (2017), Zeng et al. (2018) and others
603 contributed to the integration of PCSC. Considering the impact of construction projects on the
604 environment, Du et al. (2021) discussed the key factors affecting carbon emissions and their
605 relationship from the perspective of PCSC in order to realize the carbon reduction potential of
606 prefabricated construction. In addition, Wuni and Shen (2021) studied the key determinants of
607 PCSCM success, and the results showed that design for SCM, effective communication and
608 information sharing, organizational readiness, seamless integration and coordination of PCSC,
609 early involvement of critical supply chain stakeholders and extensive supply chain planning are
610 the top five critical success determinants of effective PCSCM.

611 5.2 Summary of the discussion

612 5.2.1 Top ten articles with cited frequency

613 This section summarizes the ten most frequently cited articles in the existing research on
614 PCSC, as shown in Table 13. The research contents of these articles mainly involve risk
615 management (Li et al., 2016; Luo et al., 2019; Wang et al., 2020c), investment cost (Demiralp et
616 al., 2012; Arashpour et al., 2017) and component delivery (Zhai et al., 2016; Wang and Hu, 2017;

617 Hsu et al., 2018).

618 Li et al. (2016) and Luo et al. (2019) applied social network analysis (SNA) to identify and
619 investigate the potential network of risk factors related to stakeholders in PCSC. Wang et al.
620 (2020c) constructed a information management framework in PCSC based on blockchain to cope
621 with the risks, such as fragmentation, poor traceability, lack of real-time information and so on.
622 In order to reduce the cost of PCSC operations, Arashpour et al. (2017) proposed an
623 optimization model to improve the performance of the supply network with less investment,
624 and consideration should also be given to how the related investment costs were allocated
625 among the stakeholders (Demiralp et al., 2012). Zhai et al. (2016) presented the coordination
626 scheme to solve the problem of production lead-time value preservation in the PCSCM. To
627 further optimize the component production scheduling, Wang and Hu (2017), Hsu et al. (2018)
628 considered various stages including component manufacturing and storage in a comprehensive
629 manner, while Wang and Hu (2017) only focused on the component transportation stage and
630 Hsu et al. (2018) only focused on the assembly stage. From the materials management
631 perspective, Cus-Babic et al. (2014) discussed the information flow integration related to
632 material management in PCSC. Starting from the concept of modularity, Margherita et al. (2015)
633 investigated the concept of modularity within the Engineer-to-Order (ETO) industries (such as
634 construction and shipbuilding) by means of an explorative case study approach .

635 5.2.2 The main research methods adopted

636 This part summarizes the commonly used research methods in the field of PCSC, shown in
637 Table 14. It can be seen that mathematical modeling is widely used and generally applicable to a
638 variety of research topics. In addition, there are also definite preference on the research
639 methods used for different topics. For example, genetic algorithm is mostly used in the study on
640 scheduling and delivery in PCSC, while system dynamics and social network analysis can be
641 considered only in the research on the risk and resilience in PCSC. More obviously, RFID is
642 almost one of the most effective research methods for scholars to study the real-time state of
643 prefabricated components in PCSC.

644 5.2.3 Research trends in terms of different topics

645 As can be seen from Table 15, there are more and more publications about the topics of
646 risk, resilience and real-time information in PCSC compared to other research topics. There has
647 been a significant increase on the number of articles about risk and resilience in PCSC in the

1
2
3
4 648 latest years, which indicates that PCSC is facing severe challenges brought by uncertainty, hence
5 649 the risk management and resilience control of PCSC has received wide attention from scholars.
6
7 650 In addition, PCSC operates around various stakeholders and prefabricated components, which
8
9 651 need to go through multiple stages from design, manufacturing, transportation to on-site
10 652 assembly. This process involves complex information exchange. It can be seen from Table 15
11 653 that scholars have recognized this problem and have started to study it in early years, but the
12 654 research on informatization in PCSC has not been further expanded in recent years. However,
13 655 the efficiency of PCSC is heavily influenced by the efficiency of information sharing among all
14
15 656 participants, and therefore it is necessary to pay close attention to intelligentization and
16
17 657 informatization in PCSC continuously.

18
19
20 658 Table 6: Research on Logistics and Transportation

21 659 Table 7: Research on Inventory Planning

22 660 Table 8: Research on Supply Chain Costs

23
24 661 Table 9: Research on Project Delivery and Scheduling

25 662 Table 10: Research on Supply Chain Risk and Resiliency

26
27 663 Table 11: Research on Supply Chain Intelligentization and Informatization

28 664 Table 12: Research on Modern Construction Technology

29
30 665 Table 13: Top ten articles with cited frequency

31 666 Table 14: The main research methods adopted

32
33 667 Table 15: Research trends in terms of different topics

34
35 668

669 6. Conclusion

670 6.1 Summary

671 Based on the WoS core, 131 documents that meet the requirements are reviewed and
672 summarized in the field of PCSCM .The two main tasks of this review are (1) to conduct a visual
673 analysis on the existing literature in PCSCM to capture the overall picture of this research area,
674 and (2) to summarize the existing literature into different modules and areas of PCSCM through
675 qualitative discussion The quantitative analysis is conducted from five aspects: journal sources,
676 keywords co-occurrence, co-author analysis, authorship citation and country active. The
677 qualitative analysis discusses existing studies from seven themes: logistics and transportation,
678 inventory planning, supply chain costs, delivery and scheduling, risk and resiliency, supply chain
679 intelligentization and informatization and modern construction technology. Through above
680 analysis, this literature review comprehensively and systematically reveals the fundamental
681 venation, current research progress, trends and future directions in the field of PCSCM.

682 6.2 Implications

683 Compared to previous studies, this study is more comprehensive and integrated, as
684 reflected by the addition of the dimension related to "article authorship" in the quantitative
685 analysis and by covering all main themes in the qualitative discussion in the field of PCSCM
686 (including the most recent articles published in 2022). In addition, this paper deeply discusses
687 the the main research topics from both the specific contents and research methods adopted.
688 The findings received in this review can help scholars acquire academic knowledge, research
689 frontiers and emerging trends and explore future research directions in the field of PCSC from
690 different research perspectives . what's more, this study can help project participants to
691 understand the current operation status and existing problems of PCSC in practice and provide a
692 basis for future solutions to the difficulties faced in PCSC.

693 6.3 Future direction

- 694 ● The unqualified or defective prefabricated components will not only cause waste in
695 materials and the invested funds, delay on construction progress and even cause long-term
696 problems associated with project performance and quality, so the quality inspection of
697 precast components is the one of future research topics.
- 698 ● The logistics and transportation management in PCSC mainly focused on prefabricated
699 components in previous publications. The logistics management of construction waste
700 needs to be paid more attention to in the future research on PCSCM. Effective recovery on

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

701 construction waste can achieve a win-win situation warranting both economic and
702 environmental benefits.

703 ● Previous studies could not grasp the comprehensive supply chain risk situation and the
704 impacts of all uncertainties. Future research should identify and control the risk factors in
705 all phases of PCSC.

706 ● Advancing the informatization level in PCSC is one of the keys to improve the PC efficiency.
707 How to combine modern construction technologies with information technologies and
708 intelligent tools will be an interesting research direction.

709

Acknowledgment

This research is jointly supported by the Key Research and Development Program of Shaanxi (Grant No. 2021SF-522), the Fundamental Research Funds for the Central Universities (Grant No. 300102239621, and 300102230616) and Science and Technology Planning Program of Xi'an (Grant No. 21RKYJ0041). Their support is gratefully acknowledged. The authors would like to thank the editors, reviewers and experts for their time and constructive comments.

Reference

- Abedi, M.(2016). Integrated collaborative tools for precast supply chain management. *Scientia Iranica*, 232(2), 429-448.
- Ahmadi, H. B., Kusi-Sarpong, S., & Rezaei, J.(2017). Assessing the social sustainability of supply chains using Best Worst Method. *Resources Conservation & Recycling*, 126, 99-106.
- Ahmadian, F. F. A., Akbarnezhad, A., Rashidi, T. H., Waller, S., & Travis.(2016). Accounting for Transport Times in Planning Off-Site Shipment of Construction Materials. *Journal of construction engineering and management*, 142(1), 4015050.1.
- AlMaian, R.Y., Needy, K.L., Walsh, K.D., & Alves, T.D.L.(2015). Supplier quality management inside and outside the construction industry. *Engineering Management Journal*, 27(1), 11-22.
- Alwisy, A., Hamdan, S. B., Barkokebas, B., Bouferguene, A., & Al-Hussein, M.(2019). A BIM-based automation of design and drafting for manufacturing of wood panels for modular residential buildings. *The international journal of construction management*, 19(3), 187-205.
- Arashpour, M., Bai, Y., Aranda-Mena, G., Bab-Hadiashar, A., Hosseini, R., & Kalutara, P.(2017). Optimizing decisions in advanced manufacturing of prefabricated products: Theorizing supply chain configurations in off-site construction. *Automation in Construction*, 84(12), 146-153.
- Aria, M., and Cuccurullo, C.(2018). Bibliometrix: An R-Tool for Comprehensive Science Mapping Analysis. *Journal of Informetrics*, 11(4), 959-975.
- Bian, J. and He, Q.(2017). Research on Information Flow of Prefabricated Building Supply Chain Based on BIM. *International Conference on Construction and Real Estate Management (ICCREM)*, 131-138.
- Blanco-Mesa, F., Gil-Lafuente, A. M., & Merigo, J. M.(2017). Fuzzy decision making: A bibliometric-based review. *Journal of Intelligent and Fuzzy Systems*, 32(3), 2033-2050.
- Broadus, R. N.(1987). Toward a definition of "bibliometrics". *Scientometrics*, 12(5), 373-379.
- Chen, Q., Adey, B. T., Haas, C., & Hall, D. M.(2020a). Using look-ahead plans to improve material flow processes on construction projects when using BIM and RFID technologies. *Construction Innovation-England*, 20(3), 471-508.
- Chen, Y., Cai, K., Sheng, T., & Wu, H.(2020b). Optimum design for unbonded posttensioned precast concrete frames with damping. *The Structural Design of Tall and Special Buildings*, 29(14).
- Cheng, J., Law, K. H., Bjornsson, H., Jones, A., & Sriram, R.(2010). A service oriented framework for construction supply chain integration. *Automation in Construction*, 19(2), 245-260.
- Cus-Babic, N., Nenad, Rebolj, D., Nekrep-Perc, M., & Podbreznik, P.(2014). Supply-chain transparency within industrialized construction projects. *Computers in Industry*, 65(2),

- 345-353.
- Daget, Y. T., & Zhang, H.(2019). Decision-making model for the evaluation of industrialized housing systems in ethiopia. *Engineering Construction & Architectural Management*, 27, 296-320.
- Demiralp, G., Guven, G., & Ergen, E.(2012). Analyzing the benefits of RFID technology for cost sharing in construction supply chains: A case study on prefabricated precast components. *Automation in Construction*, 24, 120-129.
- Du, J., Sugumaran, V., & Gao, B.(2017). RFID and Multi-Agent Based Architecture for Information Sharing in Prefabricated Component Supply Chain. *Ieee Access*, 5, 4132-4139.
- Du, J., Xue, Y., Sugumaran, V. Hu, M., & Dong, P.(2022). Improved biogeography-based optimization algorithm for lean production scheduling of prefabricated components. *Engineering Construction and Architectural Management*, 35.
- Du, Q., Pang, Q., Bao, T., Guo, X, & Deng, Y.(2021). Critical factors influencing carbon emissions of prefabricated building supply chains in China. *Journal of Cleaner Production*, 280, 124398-12.
- Eck, N., and Waltman, L.(2010). Software survey: VOSviewer, a computer program for bibliometric mapping. *Scientometrics*, 84(2), 523-538.
- Ekanayake, E., Shen, G. Q., & Kumaraswamy, M. M.(2021d). A fuzzy synthetic evaluation of capabilities for improving supply chain resilience of industrialised construction: a hong kong case study. *Production Planning and Control*.18.
- Ekanayake, E., Shen, G. Q., Kumaraswamy, M. M., & Owusu, E. K.(2021a). A fuzzy synthetic evaluation of vulnerabilities affecting supply chain resilience of industrialised construction in hong kong. *Engineering Construction & Architectural Management*.
- Ekanayake, E., Shen, G. Q., Kumaraswamy, M. M., Owusu, E. K., & Abdullahi, S. (2021b). Modelling supply chain resilience in industrialized construction: a hong kong case. *Journal of Construction Engineering and Management*. 147(11), 16.
- Ekanayake, E., Shen, G. Q., MM Kumaraswamy, Owusu, E. K., & Xue, J.(2021c). Capabilities to withstand vulnerabilities and boost resilience in industrialized construction supply chains: a hong kong study. *Engineering Construction & Architectural Management*, 21.
- Ergen, E., Akinci, B., & Sacks, R.(2007). Tracking and locating components in a precast storage yard utilizing radio frequency identification technology and GPS. *Automation in Construction*, 16(3), 354-367.
- Esfahbodi, A., Zhang, Y., & Watson, G.(2016). Sustainable supply chain management in emerging economies: Trade-offs between environmental and cost performance. *International Journal of Production Economics*, 181, 350-366.
- Fang, Y. and Ng, S. T.(2019). Genetic algorithm for determining the construction logistics of precast components. *Engineering Construction and Architectural Management*, 26(10), 2289-2306.
- Feng, M , Yu, W., Wang, X., Wong, C. Y., Xu, M., & Xiao, Z.(2018). Green supply chain management and financial performance: the mediating roles of operational and environmental performance. *Business Strategy and the Environment*, 27(7), 811-824.
- Feng, T., Tai, S., Sun, C., & Man, Q.(2017). Study on cooperative mechanism of prefabricated producers based on evolutionary game theory. *Mathematical Problems in Engineering*, 2017(7), 1-6.
- Goh, M., & Goh, Y.(2019). Lean production theory-based simulation of modular construction processes. *Automation in Construction*, 101, 227-244.

- 1
2
3
4 Gosling, J., Pero, M., Schoenwitz, D., Towill, R.(2016). Cigolini, Defining and Categorizing Modules
5 in Building Projects: An International Perspective. *Journal of Construction Engineering and*
6 *Management*, 142, 11.
- 7
8 Grau, D., Zeng, L., & Xiao, Y.(2012). Automatically tracking engineered components through shipping
9 and receiving processes with passive identification technologies. *Automation in Construction*,
10 28(11), 36-44.
- 11
12 Green, M., Dowsett, R., Sexton, M., & Harty, C.(2017). Liquid integration and modern methods of
13 construction: eddies of house-building in the UK. *Proceedings of the 9th Nordic Conference*
14 *on Construction Economics and Organization*, 152-162.
- 15
16 Han, Y., Miroslaw, S., & Wang, L.(2017). A Market Equilibrium Supply Chain Model for Supporting
17 Self-Manufacturing or Outsourcing Decisions in Prefabricated Construction. *Sustainability*,
18 9(11), 18.
- 19
20 Hasim, S., Fauzi, M. A., Yusof, Z., Endut, I. R., & Ridzuan, A.(2018). The material supply chain
21 management in a construction project: A current scenario in the procurement process.
22 *International Conference on Advances in Civil Engineering and Science Technology*.
- 23
24 Hatmoko, J. U. D., Wibowo, M. A., Astuty, M. D., Arthaningtyas, D. R., & Sholeh, M. N.(2018).
25 Managing risks of precast concrete supply chain: a case study. *2nd Conference for Civil*
26 *Engineering Research Networks*, 270.
- 27
28 He, Q., Wang, G., Luo, L., Shi, Q., Xie, J., & Meng, X.(2017). Mapping the managerial areas of
29 building information modeling (bim) using scientometric analysis. *International Journal of*
30 *Project Management*, 35, 670-685.
- 31
32 Hosseini, M. R., Martek, I., Zavadskas, E. K., Aibinu, A. A., Arashpour, M., & Chileshe, N.(2018).
33 Critical evaluation of off-site construction research: A Scientometric analysis. *Automation in*
34 *Construction*, 87, 235-247.
- 35
36 Hsu, P. Y., Angeloudis, P., & Aurisicchio, M.(2018). Optimal logistics planning for modular
37 construction using two-stage stochastic programming. *Automation in Construction*, 94, 47-61.
- 38
39 Hsu, P. Y., Aurisicchio, M., & Angeloudis, P.(2017). Establishing outsourcing and supply chain plans
40 for prefabricated construction projects under uncertain productivity. *Springer, Cham*.
- 41
42 Hsu, P. Y., Aurisicchio, M., & Angeloudis, P.(2019). Risk-averse supply chain for modular
43 construction projects. *Automation in Construction*, 106, 102898.
- 44
45 Hu, Y., Sun, Z., & Wu, D.(2010). Analysis of hot topics in soil remediation research based on
46 VOSviewer. *IOP Conference Series: Earth and Environmental Science*, 300(3), 032098 (7pp).
- 47
48 Isaac, S., Bock, T., & Stoliar, Y.(2016). A methodology for the optimal modularization of building
49 design. *Automation in Construction*, 65(5), 116-124.
- 50
51 Isatto, E. L., Azambuja, M., & Formoso, C. T.(2015). The Role of Commitments in the Management of
52 Construction Make-to-Order Supply Chains. *Journal of Management in Engineering*, 31(4),
53 10.
- 54
55 Jaillon, L. and Poon, C. S.(2014). Life cycle design and prefabrication in buildings: A review and case
56 studies in Hong Kong. *Automation in Construction*.
- 57
58 Jardim-Goncalves, Sousa, Pimentao, J.P., Steiger-Garciao, Grilo, & Tadeu.(1999). Integration of
59 planning and control activities for building and construction: experiencing standards.
60 *Proceedings*, 8(1-4), 2180-2188.
- Jiang, Y. S., Li, M., Guo, D. Q., Wu, W., Zhong, R. Y., & Huang, G. Q.(2022). Digital twin-enabled smart modular integrated construction system for on-site assembly.

- 1
2
3 *Computers in Industry*, 136, 18.
- 4 Jin, R., Gao, S., Cheshmehzangi, A., & Aboagye-Nimo, E.(2018). A Holistic Review of off-site
5 Construction Literature Published between 2008 and 2018. *Journal of Cleaner Production*,
6 202, 1202-1219.
- 7
8 Jussila, A., Kiviniemi, M., & Talvitie, U.(2012). *Piloting a new information sharing method in a*
9 *construction supply chain*.
- 10
11 Kahkonen, K., Koskela, L., Leinonen, J., & Aromaa, P.(2003). Supply chain management aspects for
12 top quality industrial construction. *10th International Symposium on Construction Innovation*
13 *and Global Competitiveness*, 841-852.
- 14
15 Kamali, M., and Hewage, K.(2016). Life cycle performance of modular buildings: A critical review.
16 *Renewable & Sustainable Energy Reviews*, 62, 1171-1183.
- 17
18 Kim, K., Kim, Y. W., & Cho, H.(2020). Dynamic production scheduling model under due date
19 uncertainty in precast concrete construction. *Journal of Cleaner Production*, 257, 13.
- 20
21 Kim, S. Y. and V. T. Nguyen.(2018). A Structural model for the impact of supply chain relationship
22 traits on project performance in construction. *Production Planning & Control*, 29(2), 170-183.
- 23
24 Kim, Y. W., Han, S. H., Yi, J. S., & Chang, S. W.(2016). Supply chain cost model for prefabricated
25 construction material based on time-driven activity-based costing. *Canadian Journal of Civil*
26 *Engineering*, 43, 287-293.
- 27
28 Ko, C. H.(2013). MATERIAL TRANSSHIPMENT FOR PRECAST FABRICATION. *Journal of Civil*
29 *Engineering and Management*, 19(3), 335-347.
- 30
31 Kong, L., Li, H., Luo, H., Ding, L., & Zhang, X.(2018). Sustainable performance of just-in-time (jit)
32 management in time-dependent batch delivery scheduling of precast construction. *Journal of*
33 *Cleaner Production*, 193(aug.20), 684-701.
- 34
35 Kusi-Sarpong, S., Gupta, H., & Sarkis, J.(2019). A supply chain sustainability innovation framework
36 and evaluation methodology. *International Journal of Production Research*, 57(7),
37 1990-2008.
- 38
39 Lee, D. and Lee, S.(2021). Digital twin for supply chain coordination in modular construction. *Applied*
40 *Sciences-Basel*, 11(13), 14.
- 41
42 Lee, J., Park, M., Lee, H. S., & Hyun, H.(2019). Classification of modular building construction
43 projects based on schedule-driven approach. *Journal of Construction Engineering and*
44 *Management*, 145(5), 04019031.1-04019031.9.
- 45
46 Li, C. Z., Chen, Z., Xue, F., Kong, X. T. R., Xiao, B., Lai, X. L., & Zhao, Y. Y.(2021). A
47 blockchain- and IoT-based smart product-service system for the sustainability of
48 prefabricated housing construction. *Journal of Cleaner Production*, 286, 17.
- 49
50 Li, C. Z., Hong, J., Xue, F., Shen, G. Q., Xu, X., & Mok, M. K.(2016). Schedule risks in prefabrication
51 housing production in Hong Kong: a social network analysis. *Journal of Cleaner Production*,
52 134, 482-494.
- 53
54 Li, C. Z., Xu, X., Shen, G. Q., Fan, C., Li, X., & Hong, J.(2018a). A model for simulating schedule
55 risks in prefabrication housing production: a case study of six-day cycle assembly activities in
56 hong kong. *Journal of Cleaner Production*, 185(JUN.1), 366-381.
- 57
58 Li, C. Z., Xue, F., Li, X., Hong, J. K., & Shen, G. Q.(2018b). An Internet of Things-enabled BIM
59 platform for on-site assembly services in prefabricated construction. *Automation in*
60 *Construction*, 89, 146-161.
- 61
62 Li, C.Z., Shen, G.Q., Xu, X.X., Xue, F., Sommer, L., & Luo, L.Z.(2017). Schedule risk modeling in

- 1
2
3 prefabrication housing production. *Journal of Cleaner Production*, 153(1), 692-706.
- 4 Li, H., and Mao, Q.(2017). SD-Based Research on Industrialized Construction Supply Chain.
5 *International Conference on Construction and Real Estate Management*, 163-172.
- 6 Li, X., Chi, H. L., Wu, P., & Shen, G. Q.(2020). Smart work packaging-enabled constraint-free path
7 re-planning for tower crane in prefabricated products assembly process. *Advanced engineering*
8 *informatics*, 43(1), 101008.1-101008.16.
- 9
10 Li, Y., Qiu, K., Wei, Y., & Tao, Z.(2014). Study of Digital Lean Construction Platform for Precast
11 Components. *International Conference on Computing in Civil & Building Engineering*, 480-7.
- 12
13 Liu J and Lu M.(2018). Constraint Programming Approach to Optimizing Project Schedules under
14 Material Logistics and Crew Availability Constraints. *Journal of construction engineering and*
15 *management*, 144(7), 15.
- 16
17 Liu, J., Siu, M., & Ming, L.(2017). Modular construction system simulation incorporating off-shore
18 fabrication and multi-mode transportation. *Winter Simulation Conference*.
- 19
20 Liu, Y., Dong, J., & Shen, L.(2020a). A conceptual development framework for prefabricated
21 construction supply chain management: an integrated overview. *Sustainability*, 12,29.
- 22
23 Liu, Y., Dong, J., & Shen, L.(2020b). A Conceptual Development Framework for Prefabricated
24 Construction Supply Chain Management: An Integrated Overview. *Sustainability*, 12.
- 25
26 Luo, L. Z., Li, Z. D., Mao, C., & Shen, L. Y.(2015). Risk factors affecting practitioners' attitudes
27 toward the implementation of an industrialized building system: a case study from china.
28 *Engineering construction & architectural management*, 22, 622-643.
- 29
30 Luo, L., Jin, X., Shen, G. Q., Wang, Y. & Li, C. Z.(2020). Supply Chain Management for Prefabricated
31 Building Projects in Hong Kong. *Journal of Management in Engineering*, 36(2), 15.
- 32
33 Luo, L., Shen, G. Q., Xu, G., Liu, Y., & Wang, Y.(2019). Stakeholder-Associated Supply Chain Risks
34 and Their Interactions in a Prefabricated Building Project in Hong Kong. *Journal of*
35 *Management in Engineering*, 35(2), 94-107.
- 36
37 Maas, G., and Eekelen, B. V.(2004). The bollard - the lessons learned from an unusual example of
38 off-site construction. *Automation in Construction*, 13(1), 37-51.
- 39
40 Mangla, S. K., Luthra, S., Mishra, N., Singh, A., & Dwivedi, Y.(2018). Barriers to effective circular
41 supply chain management in a developing country context. *Production Planning and Control*,
42 29(6), 551-569.
- 43
44 Mani, V., Gunasekaran, A., & Delgado, C.(2018). Enhancing supply chain performance through
45 supplier social sustainability: An emerging economy perspective. *International Journal of*
46 *Production Economics*, 195, 259-272.
- 47
48 Margherita, P., Martin, S., & Roberto, C.(2015). Linking product modularity to supply chain
49 integration in the construction and shipbuilding industries. *International Journal of*
50 *Production Economics*, 170, 602-615.
- 51
52 María, Huertas. González-Serrano., Jones, P., & Llanos-Contrera, O.(2019). An overview of sport
53 entrepreneurship field: a bibliometric analysis of the articles published in the Web of Science.
54 *Sport in Society*, 23(1), 1-18.
- 55
56 Meng, X.(2019). Lean management in the context of construction supply chains. *International Journal*
57 *of Production Research*, 57(11), 3784-3798.
- 58
59 Mh, A., Aeee, B., Akc, D., Ias, E., & Tz, A.(2021). Modelling in off-site construction supply chain
60 management: a review and future directions for sustainable modular integrated construction.
Journal of Cleaner Production, 310, 127503.

- 1
2
3 Mojumder, A., and Singh, A.(2021). An exploratory study of the adaptation of Green Supply Chain
4 Management in Construction Industry: the case of Indian Construction Companies. *Journal of*
5 *Cleaner Production*, 295, 15.
- 6
7 Moreno-Guerrero, A. J., Gómez-García, G., López-Belmonte, J., & Rodríguez-Jiménez, C.(2020).
8 Internet addiction in the web of science database: a review of the literature with scientific
9 mapping. *International Journal of Environmental Research and Public Health*, 17(8), 27-53.
- 10
11 Naranje, V. and Swarnalatha, R.(2019). Design of tracking system for prefabricated building
12 components using RFID technology and CAD model. *Procedia Manufacturing*, 32, 928-935.
- 13
14 Navarro-Rubio, J., Pineda, P., & Navarro-Rubio, R.(2020). Efficient structural design of a prefab
15 concrete connection by using artificial neural networks. *Sustainability*, 12(19).
- 16
17 Oraee, M., Hosseini, M. R., Papadonikolaki, E., Palliyaguru, R., & Arashpour, M.(2017). Collaboration
18 in BIM-based construction networks: A bibliometric-qualitative literature review.
19 *International Journal of Project Management*, 35(7), 1288-1301.
- 20
21 Piroozfar, P., and Farts, E.(2013). Evolution of Nontraditional Methods of Construction;21st Century
22 Pragmatic Viewpoint. *Journal of Architectural Engineering*, 119-133.
- 23
24 Ps, A., and Sash, B.(2019). Development of supply chain risk management approaches for construction
25 projects: A grounded theory approach. *Computers & Industrial Engineering*, 128, 837-850.
- 26
27 Qaiser, F. H., Dev, N. K., & Shankar, R.(2019). Industry 4.0 and circular economy: Operational
28 excellence for sustainable reverse supply chain performance. *Resources Conservation and*
29 *Recycling*, 153:15.
- 30
31 Razkenari, M. A., Fenner, A. E., Woo, J., Hakim, H., & Kibert, C. J.(2018). A Systematic Review of
32 Applied Information Systems in Industrialized Construction. *Construction Research*
33 *Congress*, 101-110.
- 34
35 Ricardo, E.(2019). Improved building sustainability in seismic zones. *Revista de la Construcción*,
36 18(1), 166-177.
- 37
38 Rocha, C., Ghoz, H., & Guadanhim, S. J.(2019). A model for implementing product modularity in
39 buildings design. *Engineering Construction & Architectural Management*, 27, 680-699.
- 40
41 Rudolf, C. A., and Stefan, S.(2018). Key risks in the supply chain of large scale engineering and
42 construction projects. *Supply Chain Management*, 23(4), 336-350.
- 43
44 Said, H. M., Chalasani, T., & Logan, S.(2017). Exterior prefabricated panelized walls platform
45 optimization. *Automation in Construction*, 76, 1-13.
- 46
47 Sarkar, B., Sarkar, M., & Ganguly, B.(2021). Combined effects of carbon emission and production
48 quality improvement for fixed lifetime products in a sustainable supply chain management.
49 *International Journal of Production Economics*, 231, 14.
- 50
51 Shahbaz, M. S., Qureshi, M. A., Sohu, S., & Keerio, M. Ali.(2020). The Impacts of Operational Risks
52 in the Supply Chain of Construction Projects in Malaysia. *Tehnicky Vjesnik-Technical Gazette*,
53 27(6), 1887-1893.
- 54
55 Shukor, A., Muhammad, M. F., Khaderi, S. S., & Halil, F. M.(2016). Supply chain integration:
56 establish the appropriate challenges in improving integrated sc in an innovative approach of
57 ibs. *Environment-Behaviour Proceedings Journal*, 1(3), 79-79.
- 58
59 Si, T., Li, H. X., Lei, Z., Liu, H., & Han, S. H.(2021). A dynamic just-in-time component delivery
60 framework for off-site construction. *Advances in Civil Engineering*, 2021(1), 1-19.
- Su, H. N., and Lee, P. C.(2010). Mapping knowledge structure by keyword co-occurrence: a first look
at journal papers in Technology Foresight. *Scientometrics*, 5(1), 65-79.

- 1
2
3 Taghaddos, H., Hermann, U., & Abbasi, A. B.(2018). Automated crane planning and optimization for
4 modular construction. *Automation in Construction*, 95(11), 219-232.
- 5
6 Tao, X. Y., Mao, C., Xie, F. Y., Liu, G. W., & Xu, P. P.(2018). Greenhouse gas emission
7 monitoring system for manufacturing prefabricated components. *Automation in*
8 *Construction*, 93, 361-374.
- 9
10 Wang, C., Zhang, Q., & Zhang, W.(2020a). Corporate social responsibility, Green supply chain
11 management and firm performance: The moderating role of big-data analytics capability.
12 *Research in Transportation Business and Management*, 37(9), 10.
- 13
14 Wang, J. J., Tingley, D. D., Mayfield, M., & Wang, Y. F.(2018a). Life cycle impact comparison of
15 different concrete floor slabs considering uncertainty and sensitivity analysis. *Journal of*
16 *Cleaner Production*, 189(JUL.10), 374-385.
- 17
18 Wang, S. Q., Tang, J., Zou, Y. Q., & Zhou, Q. H.(2020d). Research on production process
19 optimization of precast concrete component factory based on value stream mapping.
20 *Engineering Construction and Architectural Management*, 27(4), 850-871.
- 21
22 Wang, S., Mursalin, Y., Lin, G., & Lin, C.(2018c). Supply chain cost prediction for prefabricated
23 construction construction under uncertainty. *Mathematical Problems in Engineering*, (1), 1-5.
- 24
25 Wang, X. T., Wang, S. L., Song, X. N., & Han, Y. L.(2020e). IoT-Based Intelligent Construction
26 System for Prefabricated Buildings: Study of Operating Mechanism and Implementation
27 in China. *Applied Sciences-Basel*, 10(18), 18.
- 28
29 Wang, Y.(2019). Research on Risk Management of Prefabricated Construction Supply Chain Based on
30 Immune Principle. *IOP Conference Series: Earth and Environmental Science*, 371, 052058
31 (052056 pp.)-052058 052056 pp.
- 32
33 Wang, Y., Yuan, Z., & Sun, C.(2018d). RESEARCH ON ASSEMBLY SEQUENCE PLANNING
34 AND OPTIMIZATION OF PRECAST CONCRETE BUILDINGS. *Journal of Civil*
35 *Engineering and Management*, 24(2), 106-115.
- 36
37 Wang, Z. J., and Hu, H.(2017). Improved precast production-scheduling model considering the whole
38 supply chain. *Journal of computing in civil engineering*, 31(4), 4017013.1.
- 39
40 Wang, Z. J., and Hu, H.(2018). Dynamic response to demand variability for precast production
41 rescheduling with multiple lines. *International Journal of Production Research*, 56(15-16),
42 5386-5401.
- 43
44 Wang, Z. J., Hu, H., & Gong, J.(2018b). Simulation based multiple disturbances evaluation in the
45 precast supply chain for improved disturbance prevention. *Journal of Cleaner Production*,
46 177(10), 232-244.
- 47
48 Wang, Z. J., Hu, H., & Zhou, W.(2017). RFID Enabled Knowledge-Based Precast Construction Supply
49 Chain. *Computer-Aided Civil and Infrastructure Engineering*, 32, 499-514.
- 50
51 Wang, Z. J., Wang, T. Y., Hu, H., Gong, J., Ren, X., & Xiao, Q. Y. (2020c). Blockchain-based
52 framework for improving supply chain traceability and information sharing in precast
53 construction. *Automation in Construction*, 111, 13.
- 54
55 Wang, Z. L., Shen, H. C., & Zuo, J.(2019a). Risks in Prefabricated Buildings in China:
56 Importance-Performance Analysis Approach. *Sustainability*, 11.
- 57
58 Wang, Z., Hu, H., Gong, J., Ma, X., & Xiong, W.(2019b). Precast supply chain management in off-site
59 construction: a critical literature review. *Journal of Cleaner Production*, 232, 1204-1217.
- 60
Wang, Z., Zhang, Q., Yang, B., Wu, T., & Fang, T.(2020b). Vision-based framework for automatic
progress monitoring of precast walls by using surveillance videos during the construction

- 1
2
3 phase. *Journal of Computing in Civil Engineering*, 35(1).
- 4 Wei, P., Gibb, A., & Dainty, A.(2012). Strategies for Integrating the Use of Off-Site Production
5 Technologies in House Building. *Journal of Construction Engineering and Management*,
6 138(11), 1331-1340.
- 7
8 Woo, C., Kim, M. G., Chung, Y., & Rho, J. J.(2016). Suppliers' communication capability and external
9 green integration for green and financial performance in korean construction industry. *Journal*
10 *of Cleaner Production*, 112(JAN.20PT.1), 483-493.
- 11
12 Wuni, I. Y. and Shen, G. Q.(2021). Exploring the critical success determinants for supply chain
13 management in modular integrated construction projects. *Smart and Sustainable Built*
14 *Environment*, 19.
- 15
16 Xu, G. Y., Li, M., Chen, C. H., & Wei, Y. C.(2018). Cloud asset-enabled integrated IoT platform
17 for lean prefabricated construction. *Automation in Construction*, 93, 123-134.
- 18
19 Xu, G. Y., Li, M., Luo, L. Z., Chen, C. H., & Huang, G. Q.(2019). Cloud-based fleet management
20 for prefabrication transportation. *Enterprise Information Systems*, 13(1), 87-106.
- 21
22 Xun, Z., Kang, L., & Zhao, Z.(2019). Construction of prefabricated construction Supply Chain
23 Operation Model Based on SCOR, The 2nd International Seminar on Computational
24 Intelligence. *Engineering and Technology*, 490.
- 25
26 Yang, H., Chung, J., Chen, Y., Pan, Y., Mei, Z., & Sun, X.(2018). Ordering strategy analysis of
27 prefabricated component manufacturer in construction supply chain. *Mathematical Problems*
28 *in Engineering*, 1-16.
- 29
30 Yuan, F.(2018). Main Obstacles to Prefabricated Construction: The Contractor's Perspective in China.
31 *International Conference on Construction and Real Estate Management*, 220-224.
- 32
33 Yue, Z., Yelin, F., Gangyan, X., & George, H.(2018). Multi-period hedging and coordination in a
34 prefabricated construction supply chain. *International Journal of Production Research*, 1-23.
- 35
36 Yungui, L., Kuining, Q., Yongbin, W., & Tao, Z.(2014). Study of digital lean construction platform for
37 precast components. *International Conference on Computing in Civil & Building Engineering*.
- 38
39 Zakaria, S. A. S., Gajendran, T., Rose, T., & Brewer, G.(2018). Contextual, structural and behavioural
40 factors influencing the adoption of industrialised building systems: a review. *Architectural*
41 *engineering and design management*.
- 42
43 Zeng, N., Liu, Y., Mao, C., & König, M.(2018). Investigating the relationship between construction
44 supply chain integration and sustainable use of material: evidence from china. *Sustainability*,
45 10(10), 17.
- 46
47 Zhai, Y., Xu, G., & Huang, G. Q.(2019). Buffer space hedging enabled production time variation
48 coordination in prefabricated construction. *Computers & Industrial Engineering*, 137(Nov.),
49 106082.1-106082.14.
- 50
51 Zhai, Y., Zhong, R. Y., & Huang, G. Q.(2018). Buffer space hedging and coordination in prefabricated
52 construction supply chain management. *International Journal of Production Economics*,
53 200(JUN.), 192-206.
- 54
55 Zhai, Y., Zhong, R. Y., Li, Z., & Huang, G.(2016). Production lead-time hedging and coordination in
56 prefabricated construction supply chain management. *International Journal of Production*
57 *Research*, 55(13-14), 3984-4002.
- 58
59 Zhang, H. and Yu, L.(2020). Dynamic transportation planning for prefabricated component supply
60 chain. *Engineering Construction and Architectural Management*, 27(9), 2553-2576.
- Zhang, H. and Yu, L.(2021). RESILIENCE-COST TRADEOFF SUPPLY CHAIN PLANNING FOR

- 1
2
3 THE PREFABRICATED CONSTRUCTION PROJECT. *Journal of Civil Engineering and*
4 *Management*, 27(1), 45-59.
- 5
6 Zhang, L., Cheng, Y., & Liang, J.(2017) Mechanism of leader-follower distribution decision of the
7 suppliers with the supply hub. *Journal of Systems & Management*, 26, 577-582.
- 8
9 Zhang, M., Guo, H., Huo, B., Zhao, X., & Huang, J.(2019). Linking supply chain quality integration
10 with mass customization and product modularity. *International Journal of Production*
11 *Economics*, 207, 227-235.
- 12
13 Zhang, M., Liu, Y., & Ji, B.(2021b). Influencing Factors of Resilience of PBSC Based on Empirical
14 Analysis. *Buildings*, 11(10), 17.
- 15
16 Zhang, W., Kang, K., & Zhong, R.(2021a). A cost evaluation model for iot-enabled prefabricated
17 construction supply chain management. *Industrial Management & Data Systems*, 121(12),
18 2738-2759.
- 19
20 Zhao, L. L., Liu, Z. S., & Mbachu, J.(2019). Development of Intelligent Prefabs Using IoT
21 Technology to Improve the Performance of Prefabricated Construction Projects. *Sensors*,
22 19(19), 30.
- 23
24 Zhao, Y. H., Cao, C. F., & Liu, Z. S.(2022). A Framework for Prefabricated Component Hoisting
25 Management Systems Based on Digital Twin Technology. *Buildings*, 12(3), 19.
- 26
27 Zheng, Z., Zhang, Z., & Pan, W.(2020). Virtual prototyping- and transfer learning-enabled module
28 detection for modular integrated construction. *Automation in Construction*, 120.
- 29
30 Zhong, R. Y., Peng, Y., Fang, J., Xu, G., Xue, F., Zou, W., & Huang G.Q.(2015). Towards physical
31 internet-enabled prefabricated housing construction in hong kong. *Ifac Papersonline*, 48(3),
32 1079-1086.
- 33
34 Zhong, R. Y., Peng, Y., Xue, F., & Fang, J.(2017). Prefabricated construction enabled by the
35 Internet-of-Things. *Automation in Construction*, 76, 59-70.
- 36
37 Zhu, J., and Liu, W.(2020). A tale of two databases: The use of Web of Science and Scopus in
38 academic papers. *Scientometrics*, 123, 321-335.
- 39
40 Zhu, R., Wang, Y., Wu, R., Meng, X., & Duan, Z.(2020). Trends in High-impact Papers in Nursing
41 Research Published from 2008 to 2018: A Web of Science-based Bibliometric Analysis.
42 *Journal of Nursing Management*, 28(5).
- 43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

Table 1: Analysis of Publication Sources (Scientific Journal Outlets): Total link strength, Number of articles, Total citations, Avg. citations, Avg. pub. Year, Avg. norm. Citations

Source	Total link strength	Number of articles	Total citations	Avg. citations	Avg. pub. year	Avg. norm. citations
<i>J of Management in Engineering</i>	23	3	106	36	2018	3.56
<i>Sustainability</i>	20	6	20	4	2018	0.62
<i>J of Cleaner Production</i>	19	12	161	15	2019	2.07
<i>Automation in Construction</i>	14	7	166	28	2017	1.93
<i>International J of Production Economics</i>	4	8	175	22	2016	2.31
<i>J of Construction Engineering and Management</i>	10	12	93	9	2018	0.95

Table 2: Analysis of Keyword Co-occurrence: including Total link strength, Occurrence, Avg. Citations, Avg. pub. Year, Avg. norm. citations

Keyword	Total link strength	Occurrence	Avg. citations	Avg. pub. year	Avg. norm. citations
Model	92	19	16	2017	1.65
Framework	84	14	9	2017	1.55
Innovation	80	14	15	2016	1.32
Integration	70	12	6	2016	0.79
Hong Kong	68	11	13	2016	1.31
Optimization	67	15	5	2017	0.80
Flexibility	62	8	3	2018	0.54
Strategy	59	9	5	2018	0.90
Uncertainty	58	9	4	2019	0.73
Technology	49	8	10	2017	1.25
Logistics	46	10	10	2016	1.40
Inventory	40	5	13	2017	2.54
Simulation	33	8	14	2016	0.95
China	32	6	37	2016	3.31
Game Theory	30	4	7	2018	0.99
Supply Chain Coordination	30	4	7	2018	0.99
Genetic Algorithm	28	4	14	2019	2.42
Japan	27	4	20	2016	1.00
Reduction	26	4	12	2018	1.52
Barriers	25	5	25	2018	2.55
Cost	23	4	3	2017	0.40
Lean Construction	23	3	2	2019	0.69
RFID	20	4	18	2017	1.45

BIM	18	4	23	2017	2.40
Dynamic Capability	18	3	4	2018	0.57
Sustainability	18	3	2	2018	0.46
Risk	17	3	2	2018	0.39
Critical Success Factors	15	3	2	2019	0.23
Information	14	3	6	2016	0.72
Interoperability	13	4	10	2016	1.76

Table 3: Analysis of Co-authorship, including total link strength, number of articles, total citations, average citations, average published years and average normalization citations

Author	Total link strength	Number of articles	Total citations	Avg. citations	Avg. pub. Year	Avg. norm. citations
Shen, Geoffrey Qiping	11	5	104	21	2018	2.75
Li, Clyde Zhengdao	9	3	84	28	2017	3.37
Xue, Fan	9	3	91	31	2016	3.19
Luo, Lizi	8	3	33	11	2018	2.25
Xu, Xiaoxiao	7	2	84	41	2016	4.56
Hu, Hao	6	6	88	15	2018	2.31
Wang, Zhaojing	6	6	88	15	2018	2.31
Xu, Gangyan	6	4	25	6	2018	1.14
Zhai, Yue	4	4	28	7	2018	0.99
Zhong, Ray Y.	4	3	33	11	2016	1.33
Arashpour, Mehrdad	2	2	24	12	2018	1.65
Bai, Yu	2	2	24	12	2018	1.65
Mao, Chao	1	2	93	47	2016	3.26
Pan, Wei	1	2	162	81	2013	4.55

Table 4: Analysis of Authorship Citation: including Title, Links, Citations, Norm. citations

Document	Title	Links	Citations	Norm. citations
Luo, Shen, Xu, Liu and Wang	Stakeholder-Associated Supply Chain Risks and Their Interactions in a Prefabricated Building Project in Hong Kong.	9	16	3.64
Li, Shen, Xu, Xue, Sommer and Luo	Schedule risk modeling in prefabrication housing production	5	17	2.12
Pan, Gibb and Dainty	Strategies for Integrating the Use of Off-Site Production Technologies in House Building	5	72	3.05
Arashpour, Bai, Aranda-mena, Bab-Hadiashar,	Optimizing decisions in advanced manufacturing of prefabricated products: Theorizing supply chain configurations in off-site construction	4	21	1.82

Hosseini and Kalutara						
Demiralp, Guven and Ergen	Analyzing the benefits of RFID technology for cost sharing in construction supply chains: A case study on prefabricated prefabricated components	4	43	2.62		
Wang and Hu	Dynamic response to demand variability for precast production rescheduling with multiple lines	3	33	5.08		
Wang, Hu and Zhou	RFID Enabled Knowledge-Based Precast Construction Supply Chain	3	21	2.62		
Zhai, Zhong, Li and Huang	Production lead-time hedging and coordination in prefabricated construction supply chain management	3	17	2.12		
Li, Hong, Xue, Shen, Xu and Mok	Schedule risks in prefabrication housing production in Hong Kong: a social network analysis	3	67	6.99		
Cus-Babic, Rebolj, Nekrep-Perc and Podbreznik	Supply-chain transparency within industrialized construction projects	3	22	2.40		
Wang, Hu and Gong	Simulation based multiple disturbances evaluation in the prefabricated supply chain for improved disturbance prevention	2	10	1.54		
Han, Skibniewski and Wang	A Market Equilibrium Supply Chain Model for Supporting Self-Manufacturing or Outsourcing Decisions in Prefabricated Construction	2	12	1.50		
Wang and Hu	Improved Precast Production–Scheduling Model Considering the Whole Supply Chain	1	18	2.25		
Kim, Han, Yi and Chang	Supply chain cost model for prefabricated building material based on time-driven activity-based costing	1	13	1.36		
Cheng, Law, Bjornsson, Jones and Sriram	A service oriented framework for construction supply chain integration	1	86	3.62		

Table 5: Analysis of Country Active: Total link strength, Number of articles, Total citations, Avg. citations, Avg. pub. Year, and Avg. norm. citations

Country	Total link strength	Number of articles	Total citations	Avg. citations	Avg. pub. year	Avg. norm. citations
China	124	44	349	9	2015	1.13
USA	56	25	356	15	2015	1.22
Australia	27	6	78	13	2016	1.02
England	20	13	191	15	2014	1.53
New Zealand	18	3	27	9	2016	1.21
Germany	13	8	103	13	2013	1.25
Italy	13	7	42	6	2013	0.54

Brazil	11	6	34	6	2018	1.00
Wales	10	4	47	12	2014	2.24
France	9	6	66	11	2013	1.69
Netherlands	8	5	28	4	2015	0.67
Sweden	6	6	122	20	2012	1.10
Canada	5	6	39	7	2016	0.71
Japan	3	5	35	7	2015	0.70

Table 6: Research on Logistics and Transportation

Title	Author	Year	Research topics	Research methods or tools
Modular Construction System Simulation Incorporating Off-Shore Fabrication and Multi-Mode Transportation	Liu, J. Y., et al.	2016	logistics management	modeling based on Simphony
Accounting for Transport Times in Planning Off-Site Shipment of Construction Materials	Ahmadian, F. F. A., et al.	2016	off-site material transport time and influence factor	case study
Optimal logistics planning for modular construction using two-stage stochastic programming	Hsu, P. Y., et al.	2018	optimizing the logistics system	two-stage stochastic programming model, case study
Sustainable multi-period reverse logistics network design and planning under uncertainty utilizing conditional value at risk (CVaR) for recycling construction and demolition waste	Rahimi, M., et al.	2018	reverse logistics network, recovery of construction waste	Two-stage stochastic programming, off-site and on-site separation
Genetic algorithm for determining the construction logistics of prefabricated components	Fang, Y., et al.	2019	logistics planning	genetic algorithms (Gas), Activity-Based Costing (ABC) method
Dynamic transportation planning for prefabricated component supply chain	Zhang, H., et al.	2020	dynamic transport planning	just-in-time (JIT), particle swarm optimization (PSO) algorithm

Table 7: Research on Inventory Planning

Title	Author	Year	Research topics	Research methods or tools
Establishing Outsourcing and Supply Chain Plans for prefabricated Construction Projects Under Uncertain Productivity	Pei-Yuan, H., et al.	2017	inventory dispatching, production planning	two-stage stochastic programming model, mixed integer linear programming model

1					
2					
3					
4	Mechanism of Leader-Follower Distribution Decision of	Zhang, L.,	2017	supplier collaborative	collaborative main-slave decision-making
5	the Suppliers with the Supply Hub	et al.		distribution	mechanism (centralized distribution center as
6					main supplier as slave)
7	Ordering Strategy Analysis of Prefabricated Component	Yang, H.	2018	ordering strategy	EOQ model, construction supply chain theory,
8	Manufacturer in Construction Supply Chain	X., et al.			order decision, Gas, Matlab
9					
10	Buffer space hedging and coordination in prefabricated	Zhai, Y.,	2018	buffer space hedging	Stackelberg games, Nash game, mathematical
11	construction supply chain management	et al.			modeling
12					
13	Optimization of reinforcement steel supply to precast	Nical, A.	2019	procurement strategy	mathematical modeling
14	concrete plants				
15	Multi-period hedging and coordination in a	Zhai, Y.,	2019	buffer space hedging	cooperative game, Nash game
16	prefabricated construction supply chain	et al.			
17					
18	Buffer space hedging enabled production time variation	Zhai, Y.,	2019	buffer space hedging	Stackelberg games, Nash game
19	coordination in prefabricated construction	et al.			
20					

Table 8: Research on Supply Chain Costs

25	Title	Author	Year	Research topics	Research methods or tools
26	Analyzing the benefits of RFID technology for cost sharing in	Demiralp,	2012	allocation of technology	cost sharing ratio, simulation
27	construction supply chains: A case study on prefabricated	G., et al.		investment cost	
28	prefabricated components			transshipment strategies,	mathematical modeling, computer
29				total material	simulation
30	Material Transshipment for Precast Fabrication	Ko, C. H.	2013	management costs	
31					
32	Supply chain cost model for prefabricated building material	Kim, Y.	2016	total supply chain costs	supply chain cost model using time-driven
33	based on time-driven activity-based costing	W., et al.			activity-based costing, sensitivity analysis
34					
35	Modularity, Lead time and Return Policy for Supply Chain in	Li, J. Z., et	2016	manufacturing cost	simultaneous-move game,
36	Mass Customization System	al.			sequential-move game and the
37					cooperative game
38	Study on Cooperative Mechanism of Prefabricated Producers	Feng, T.	2017	initial cost, partnership	evolutionary game theory
39	Based on Evolutionary Game Theory	Y., et al.			
40	Supply Chain Cost Prediction for Prefabricated Building	Wang, S.	2018	total supply chain costs	Activity-Based Costing (ABC) method
41	Construction under Uncertainty	L., et al.			
42					
43	Exploring transaction costs in the prefabricated housing	Wu, H. J.,	2019	transaction costs	Social Network Analysis (SNA),
44	supply chain in China	et al.			semi-structured interviews
45					
46	RESILIENCE-COST TRADEOFF SUPPLY CHAIN PLANNING FOR	Zhang, H.	2021	resilience cost	Multi-objective optimization model
47	THE PREFABRICATED CONSTRUCTION PROJECT	and L. Yu			
48		Zhang,			
49	A cost evaluation model for IoT-enabled prefabricated	W. N., et	2021	supply chain cost	System Dynamics Model
50	construction supply chain management	al.		assessment	
51					

Table 9: Research on Project Delivery and Scheduling

59	Title	Author	Year	Research topics	Research methods or tools
60					

1					
2					
3					
4	Improved Precast Production-Scheduling Model Considering	Wang, Z.	2017	production scheduling	genetic algorithm, case study
5	the Whole Supply Chain	J., et al.			
6	Sustainable performance of just-in-time (JIT) management in			production scheduling ,	Just-in Time (JIT) strategy,
7	time-dependent batch delivery scheduling of precast	Kong, L.	2018	environmental	batch-scheduling model
8	construction	L., et al.		performance	
9					
10	Constraint Programming Approach to Optimizing Project	Liu, J., et	2018	uncertainties in material	constraint programming-based scheduling
11	Schedules under Material Logistics and Crew Availability	al.		deliveries	optimization model
12	Constraints				
13					
14	Dynamic response to demand variability for precast	Wang, Z.	2018	dynamic production	genetic algorithm, case study
15	production rescheduling with multiple lines	J., et al.		planning, on-time delivery	
16	Classification of Modular Building Construction Projects	Lee, J., et	2019	scheduling strategies	discrete-event simulation model
17	Based on Schedule-Driven Approach	al.			
18					
19	Lean production theory-based simulation of modular	Goh, M.	2019	construction efficiency	baseline (As-Is) simulation model, Lean
20	construction processes	and Goh,		project schedule	principles
21		Y.			
22					
23	Dynamic production scheduling model under due date	Kim, T.,	2020	production scheduling	discrete-time simulation method
24	uncertainty in precast concrete construction	et al.			
25	Dynamic decision support framework for production				
26	scheduling using a combined genetic algorithm and	Du, J., et	2020	dynamic scheduling	genetic algorithm, multiagent system
27	multiagent model	al.		method	(MAS)
28					
29	Using look-ahead plans to improve material flow processes				
30	on construction projects when using BIM and RFID	Chen, Q.,	2020	lean management	RFID, BIM
31	technologies	et al.		material management	
32					
33				lean production	
34	Research on production process optimization of precast	Wang, S.	2020	prefabricated	lean production theory, value stream
35	concrete component factory based on value stream mapping	Q., et al.		components production	mapping
36					
37	Dynamic Just-in-Time Component Delivery Framework for	Si, T. G.,	2021	delivery of prefabricated	Genetic Algorithm (GA)
38	Off-Site Construction	et al.		components	
39					
40	Improved biogeography-based optimization algorithm for			production scheduling of	Improved biogeography-based
41	lean production scheduling of prefabricated components	Du, J., et	2022	prefabricated	optimization algorithm (BBO)
42		al.		components	
43					

Table 10: Research on Supply Chain Risk and Resiliency

48	Title	Author	Year	Research topics	Research methods or tools
49					
50	Schedule risks in prefabrication housing production in Hong	Li, C. Z., et	2016	schedule risk and	social network analysis (SNA)
51	Kong: a social network analysis	al.		stakeholder risk	
52					
53	Schedule risk modeling in prefabrication housing production	Li, C. Z., et	2017	schedule risks	system dynamics, Vensim software
54		al.			package, system dynamic model
55	A model for simulating schedule risks in prefabrication				system dynamics and discrete event
56	housing production: A case study of six-day cycle assembly	Li, C. Z., et	2018	schedule risks	simulation, hybrid dynamic model,
57	activities in Hong Kong	al.			Anylogic software package
58					
59					
60					

1					
2					
3	Simulation based multiple disturbances evaluation in the			the uncertainty of	
4	prefabricated supply chain for improved disturbance	Wang, Z.	2018	prefabricated supply	ARENA-based discrete event simulation,
5	prevention	J., et al.		chain	overall disturbance evaluation model
6					
7		Hatmoko,			
8	Managing risks of precast concrete supply chain: a case	J. U. D., et	2018	the risks of the supply	Supply Chain Operation Reference (SCOR),
9	study	al.		chain	questionnaire survey
10					
11	Risk-averse supply chain for modular construction projects	Hsu, P. Y.,	2019	schedule risks	mathematical modeling
12		et al.			
13					
14	Stakeholder-Associated Supply Chain Risks and Their	Luo, L. Z.,	2019	stakeholder risk	social network analysis (SNA)
15	Interactions in a Prefabricated Building Project in Hong Kong	et al.			
16					
17	Research on Risk Management of Prefabricated Construction			the risks of the supply	
18	Supply Chain Based on Immune Principle	Wang, Y.	2019	chain	Immune Principle
19					
20					
21	Influencing Factors of Resilience of PBSC Based on Empirical	Zhang, M.	2021	supply chain resilience	Structural Equation Modeling (SEM)
22	Analysis	J., et al.			
23					
24	Modeling Supply Chain Resilience in Industrialized	Ekanayak	2021	supply chain resilience	social network analysis (SNA), System
25	Construction: A Hong Kong Case	e, E., et al.			Dynamic Modeling (SDM)
26					
27	A fuzzy synthetic evaluation of capabilities for improving				
28	supply chain resilience of industrialised construction: a Hong	Ekanayak	2021	supply chain resilience	multi-stage-mathematical models, fuzzy
29	Kong case study	e, E., et al.			synthetic evaluation
30					
31	Capabilities to withstand vulnerabilities and boost resilience				
32	industrialized construction supply chains: a Hong Kong	Ekanayak	2021	supply chain resilience	Partial Least Squares Structural Equation
33	study.	e, E., et al.			Modeling
34					
35	A fuzzy synthetic evaluation of vulnerabilities affecting				
36	supply chain resilience of industrialized construction in Hong	Ekanayak	2021	supply chain resilience	multilevel-multicriteria mathematical
37	Kong	e, E., et al.			model, fuzzy synthetic evaluation

Table 11: Research on Supply Chain Intelligentization and Informatization

43	Title	Author	Year	Research topics	Research methods or tools
44	Tracking and locating components in a precast storage				
45	yard utilizing radio frequency identification	Akinci, B., et	2007	tracking prefabricated	RFID,GPS,case study
46	technology and GPS	al.		component	
47					
48	Automatically tracking engineered components				
49	through shipping and receiving processes with passive	Grau, D., et	2012	tracking prefabricated	RFID
50	identification technologies	al.		component	
51				information	
52				sharing,real-time	
53	Piloting a new information sharing method in a	Jussila, A., et	2012	information	logistics software, BIM , ERP
54	construction supply chain	al.		prefabricated	
55				construction supply	
56	Based on RFID prefabricated building component			chain	
57	design and monitoring system research	Jing, W.	2014		RFID
58					
59					
60					

1					
2					
3					
4				supply chain	software platform system(BIM, virtual
5	Study of digital lean construction platform for	Li, Y., et al.	2014	optimization	construction technology, IoT, cloud services
6	prefabricated components			management	technology, remote monitoring technology)
7					
8					
9	Towards Physical Internet-enabled Prefabricated	Zhong, R. Y.,	2015	real-time tracing,	Internet of Things (IoT), cloud techniques
10	Housing Construction in Hong Kong	et al.		real-time interactions	
11					
12	Integrated collaborative tools for prefabricated supply	Abedi, M., et	2016	prefabricated supply	Context-Aware Cloud Computing Building
13	chain management	al.		chain management	Information Modelling (CACCBIM)
14					
15				identifying	
16	A CASE OF STUDY FOR EMBEDDING RFID TAGS IN	Alonso-Calvo,	2016	prefabricated	RFID
17	PRECAST CONCRETER	R., et al.		component and its	
18				location	
19					
20	Research on Information Flow of prefabricated			whole life cycle	BIM
21	construction supply chain Based on BIM	Bian, J., et al.	2017	information flow	
22					
23	RFID and Multi-Agent Based Architecture for			information tracking	
24	Information Sharing in Prefabricated Component	Du, J., et al.	2017	and supply mechanism	RFID, multi-agent simulation
25	Supply Chain				
26					
27	RFID Enabled Knowledge-Based Precast Construction	Wang, Z. J.,	2017	benefits of RFID	
28	Supply Chain	et al.		application in supply	RFID, simulation, comparative analysis
29				chain	
30					
31	Prefabricated construction enabled by the	Zhong, R. Y.,	2017	real-time information	
32	Internet-of-Things	et al.		tracking	BIM, internet of thing (IoT)
33					
34					
35	An Internet of Things-enabled BIM platform for			real-time information	
36	on-site assembly services in prefabricated	Li, C. Z., et al.	2018	tracking	BIM, internet of thing (IoT)
37	construction				
38					
39	Greenhouse gas emission monitoring system for	Tao, X. Y., et	2018	carbon emission	internet of thing (IoT)
40	manufacturing prefabricated components	al.		monitoring	
41					
42					
43	Cloud asset-enabled integrated IoT platform for	Xu, G. Y., et	2018	material management	internet of thing (IoT)
44	lean prefabricated construction	al.			
45					
46					
47	Cloud-based fleet management for prefabrication	Xu, G. Y., et	2019	real-time information	cloud model, internet of thing (IoT)
48	transportation	al.		information sharing	
49					
50	Development of Intelligent Prefabs Using IoT				
51	Technology to Improve the Performance of	Zhao, L. L., et	2019	tracking prefabricated	RFID, Long Range (LoRa) technologies, BIM, cloud
52	Prefabricated Construction Projects	al.		component	computing
53					
54	Design of Tracking System for Prefabricated Building	Naranje, V.,	2019	tracking prefabricated	
55	Components using RFID Technology and CAD Model	et al.		component	RFID, BIM, CAD
56					
57	Blockchain-based framework for improving supply				
58	chain traceability and information sharing in precast	Wang, Z. J.,	2020	supply chain real-time	blockchain-based information management
59	construction	et al.		information	framework
60					

1					
2					
3	IoT-Based Intelligent Construction System for			information	
4	Prefabricated Buildings: Study of Operating	Wang, X. T.,	2020	integration and	internet of thing (IoT)
5	Mechanism and Implementation in China	et al.		interaction	
6					
7	Supply Chain Management for Prefabricated Building	Luo, L. Z., et	2020	supply chain real-time	automated data collection technologies
8	Projects in Hong Kong	al.		information	
9					
10	Digital Twin for Supply Chain Coordination in Modular	Lee, D. and	2021	Real-time logistics	digital twin, BIM, internet of thing (IoT)
11	Construction	Lee, S.		simulation	
12					
13	A blockchain- and IoT-based smart product-service			supply chain	
14	System for the sustainability of prefabricated housing	Li, C. Z., et al.	2021	sustainability	blockchain, internet of thing (IoT)
15	construction				
16					
17	Digital twin-enabled smart modular integrated	Jiang, Y. S., et	2022	assembly phase	digital twin
18	construction system for on-site assembly	al.		monitoring	
19					
20	A Framework for Prefabricated Component Hoisting	Zhao, Y. H.,	2022	assembly phase	digital twin
21	Management Systems Based on Digital Twin	et al		monitoring	
22	Technology.				

Table 12 Research on Modern Construction Technology

27	Title	Author	Year	Research topics	Research methods or tools
29	Methodology for the optimal modularization of building	Isaac, S., et al.	2016	prefabricated component	graph-based methodology, clustering
30	design			design	algorithm, BIM
31					
32	Exterior prefabricated panelized walls platform optimization	Said, H. M., et	2017	prefabricated component	non-dominated sorting genetic algorithm
33		al.		design	(NSGA)
34	Automated crane planning and optimization for modular	Taghaddos, H.,	2018	crane operation	mathematical and numerical algorithms
35	construction	et al.			
36					
37	RESEARCH ON ASSEMBLY SEQUENCE PLANNING AND	Wang, Y., et al.	2018	prefabricated component	BIM, Improved Genetic Algorithm (IGA)
38	OPTIMIZATION OF PRECAST CONCRETE BUILDINGS			assembly sequence	
39					
40	A BIM-based automation of design and drafting for	Alwisy, A., et	2019	shop drawing design	CAD, BIM
41	manufacturing of wood panels for modular residential	al.			
42	buildings				
43					
44	Optimum design for unbonded posttensioned precast	Chen, Y., et al.	2020	prefabricated component	Genetic Algorithm (GA)
45	concrete frames with damping			design	
46					
47	Smart work packaging-enabled constraint-free path	Li, X., et al.	2020	crane path planning	Smart Work Packaging (SWP)
48	re-planning for tower crane in prefabricated products				
49	assembly process				
50					
51	Efficient structural design of a prefab concrete connection	Navarro-Rubio,	2020	prefabricated component	Artificial Neural Networks (ANNs)
52	by using artificial neural networks	J., et al		design	
53					
54	Virtual prototyping- and transfer learning-enabled module	Zheng, Z., et al.	2020	construction monitoring	virtual prototyping, transfer-learning
55	detection for modular integrated construction				techniques, convolutional neural network
56					
57	Vision-based framework for automatic progress monitoring				
58	of precast walls by using surveillance videos during the	Wang, Z., et al.	2021	construction monitoring	computer vision methods, BIM
59	construction phase				

Table 13 Top ten articles with cited frequency

Title	Author	Year	Journal	Cited frequency
Schedule risks in prefabrication housing production in Hong Kong: a social network analysis	Li, C. Z., et al.	2016	<i>J of Cleaner Production</i>	113
Analyzing the benefits of RFID technology for cost sharing in construction supply chains: A case study on prefabricated prefabricated components.	Demiralp, G., et al.	2012	<i>Automation in Construction</i>	59
Blockchain-based framework for improving supply chain traceability and information sharing in precast construction	Wang, Z. J., et al.	2020	<i>Automation in Construction</i>	55
Stakeholder-Associated Supply Chain Risks and Their Interactions in a Prefabricated Building Project in Hong Kong	Luo, L. Z., et al.	2019	<i>J of Management in Engineering</i>	55
Optimal logistics planning for modular construction using two-stage stochastic programming	Hsu, P. Y., et al.	2018	<i>Automation in Construction</i>	42
Optimizing decisions in advanced manufacturing of prefabricated products: Theorizing supply chain configurations in off-site construction	Arashpour, M., et al.	2017	<i>Automation in Construction</i>	39
Supply-chain transparency within industrialized construction projects	Cus-Babic, N., et al.	2014	<i>Computers in Industry</i>	39
Linking product modularity to supply chain integration in the construction and shipbuilding industries	Margherita, P., et al.	2015	<i>International J of Production Economics</i>	36
Production lead-time hedging and coordination in prefabricated construction supply chain management	Zhai, Y., et al.	2017	<i>International J of Production Research</i>	35
Improved Precast Production-Scheduling Model Considering the Whole Supply Chain	Wang, Z. J. and H. Hu	2017	<i>J of Computing in Civil Engineering</i>	34

Table 14 The main research methods adopted

Topics Methods	Logistics and Transportation	Inventory Planning	Supply Chain Costs	Delivery and Scheduling	Risk and Resiliency	Real-time Information	Modern Construction Technology
Mathematical modeling	3	3	4		3		
Genetic algorithm	1			4			3
Optimization	1		1	2			
Game theory		3	2				
System dynamics			1		3		
Social network analysis			1		3		
RFID				1		6	
BIM				1	1	9	4
IoT						10	

Table 15 Research trends in terms of different topics

Topic Years	Logistics and Transportation	Inventory Planning	Supply Chain Costs	Delivery and Scheduling	Risk and Resiliency	Real-time Information	Modern Construction Technology
2007						1	
2008							
2009							
2010							
2011							
2012			1			2	
2013			1				
2014						2	
2015						1	
2016	2		2		1	2	1
2017		2	1	1	1	4	1
2018	2	2	1	3	3	3	2
2019	1	3	1	2	3	3	1
2020	1			4		2	4
2021			2	1	5	3	1
2022				1		2	
Total	6	7	9	12	13	25	10




Figure 1 Trends of publications in prefabricated construction supply chain




Figure 2 Overall framework and process of this research

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60





Figure 3: Analysis of Publication Sources (Scientific Journal Outlets)





Figure 4: Analysis of Keyword Co-occurrence

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60




Figure 5: Co-authorship Analysis




Figure 6: Authorship Citation Analysis

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60




Figure 7: Analysis of Country Active