

Cite this: *Mater. Adv.*, 2022,
3, 19Received 10th June 2021,
Accepted 18th October 2021

DOI: 10.1039/d1ma00506e

rsc.li/materials-advances

Nitrogen-rich covalent organic frameworks: a promising class of sensory materials

Himanshi Bhambri,^a Sadhika Khullar,^b Sakshi^b and Sanjay K. Mandal^{ib}*^a

Covalent organic frameworks (COFs) have emerged as highly crystalline porous organic materials and proven to be potential candidates for various interesting applications, such as gas adsorption and separation, catalysis, energy storage, and sensing. Fluorescence-based sensing has attracted significant attention due to its high selectivity, rapid response time, and real-time monitoring. Lately, luminescent COFs have been developed as sensing probes to detect various target molecules. In this review, we present a comprehensive account of the chronological development of the field of COFs starting from 2005 to date. We describe the design principles of COFs with a focus on various topologies reported, classification of their structural diversity based on thirty-two linkages and dimensionality, methods for their synthesis with examples, and the use of various characterization techniques. Interestingly, almost half of the COFs contain nitrogen-rich linkages. With a background in different processes involved in fluorescence sensing, we illustrate the potential applicability of nitrogen-rich COFs as sensors for numerous analytes, such as explosives, volatile organic molecules, pH, temperature, toxic anions, metal ions and biomolecules in different media utilizing their striking features with predesigned structures and diverse functionality.

1. Introduction

Polymers have been known for many years and are currently indispensable in daily life. The term 'polymer' was coined by

Berzelius in 1833, which was initially muddled with the concept of 'isomers'. At that time, polymers were described as two substances having a purely compositional relationship and had nothing to do with their relative sizes, building units (organic or inorganic), structures and ability to interconvert.¹ However, with the evolution of organic chemistry, the two concepts of polymerism and isomerism were set equal. Later in 1922, Straudinger introduced the term 'macromolecules' to describe large covalently bonded organic chains carrying more than 1000 atoms.² Organic polymers commonly have the

^a Department of Chemical Sciences, Indian Institute of Science Education and Research Mohali, Sector 81, Manauli PO, S.A.S. Nagar, Mohali, Punjab 140306, India. E-mail: sanjaymandal@iisermohali.ac.in

^b Department of Chemistry, Dr B R Ambedkar National Institute of Technology Jalandhar, Jalandhar, Punjab 144011, India. E-mail: khullars@nitj.ac.in

**Himanshi Bhambri**

Himanshi Bhambri was born in Punjab, India. She received her Bachelor of Science degree from Kurukshetra University, Kurukshetra in 2013, and Master of Science degree in Chemistry from Panjab University, Chandigarh. Currently, she is pursuing her PhD in Chemistry under the supervision of Prof. Sanjay Mandal. Her research mainly focuses on the design, synthesis, and applications of porous materials, such as metal and covalent organic frameworks (MOFs and COFs, respectively).

**Sadhika Khullar**

Dr Sadhika Khullar is currently an Assistant Professor in the Department of Chemistry at Dr B. R. Ambedkar National Institute of Technology Jalandhar. She obtained her Master's in Chemistry from Guru Nanak Dev University, Amritsar, and PhD in Chemistry from IISER Mohali, Punjab, India. She is recognized for her expertise in supramolecular chemistry, catalysis, smart materials, and X-ray crystallography.



drawback of being non-porous, one-dimensional mingled chains with compromised crystallinity and stability when exposed to heat and chemicals. There is little or no control over the synthesis of organic polymers, resulting in a lack of the above-mentioned properties. Although various attempts have been made to control the monomer sequence during the synthesis of polymers, which influences the macroscopic properties of these materials,³ the desired robustness and uniformity have not been achieved. Therefore, the two factors are of paramount importance, *i.e.*, synthetic control of the polymer construction and choice of the precursor molecules. Consequently, covalent organic frameworks (COFs) have emerged.

COFs are highly crystalline and porous framework materials built from purely organic monomers, which exhibit exceptional robustness and stability in a wide range of organic and inorganic solvents. The synthesis of the first COF was proposed and successfully achieved by O. M. Yaghi and co-workers in 2005 using boronic acid monomer units, in which the macromolecular framework is made up from diboronic benzene molecules.⁴ Soon after, a huge effort was made to synthesize controlled 2D and 3D porous covalent-bonded frameworks with variable functionalities and tailorable pore shapes and sizes.^{5,6} Utilizing their unique and tuneable electronic and photophysical properties based on the linkages and functionalities, this class of materials has been established as potential candidates for many applications, such as gas adsorption and separation, catalysis, energy production and storage, optoelectronics, drug delivery, and sensing.⁷⁻¹¹ However, the recent focus on their luminescent properties, which have been exploited for sensing applications, is noteworthy.

In recent years, several reviews have been published on COFs, which selectively discussed their design principle and very concise topological description, synthesis and characterization with emphasis on a particular application topic. Furthermore, only a few of these reviews included mechanistic studies for the understanding of the control over the growth of their framework

and critical steps to obtain single crystal materials. Lately, a few more reviews appeared on sensing due to the above-mentioned reasons.^{12,13} Therefore, it is necessary to compile all these topics in an elaborate manner to connect certain types of COFs to a particular application with the underlying principles discussed to achieve a structure–property–application correlation. In this review, we attempt to discuss in the following sequence: (a) the design principle with a detailed analysis of all the topologies reported for 2D and 3D COFs, (b) their classification based on thirty-two different linkages and dimensionality, (c) mechanistic details to understand the growth of their framework, (d) their synthesis with a background on all the general methods used, and (e) their characterization *via* six commonly used analytical techniques. Based on this detailed background in four different sections, we then describe their luminescence properties and the processes involved in the application of nitrogen-rich COFs, which are mainly the sensing of various analytes such as explosives, pH, VOCs and small organic molecules, toxic anions, metal ions, biomolecules and temperature.

2. Design principle

To make a pre-designable approach and set up a regular pore framework, topological delineation must be followed precisely. The fabrication of a regular net involves the placement of the C_n -reaction substrates (where 'n' is the number of reactive terminals) according to their topological connectivities and geometries, which further requires good knowledge of molecular symmetry.¹⁴ For instance, a covalent-bonded network with a honeycomb topology primarily requires a combination of planar C_3 - and C_2 -symmetric monomers,⁴ whereas a square lattice combines C_4 - and C_2 -symmetric units.¹⁵ The appropriate monomer/linker sets combine *via* strong covalently bonded linkages to reticulate into a highly ordered network under



Sakshi

Sakshi is currently a PhD Fellow at Dr B R Ambedkar National Institute of Technology, Jalandhar under the supervision of Dr Sadhika Khullar. She completed her BSc (Non-medical) in 2015 and MSc (Chemistry) in 2017, respectively, from Guru Nanak Dev University, Amritsar. Her research area includes porous materials, specifically the synthesis of coordination architectures and their application in sensing, water splitting reactions, and catalysis.



Sanjay K. Mandal

Prof. Sanjay Mandal is currently working in the department of Chemical Sciences at IISER Mohali. Prior to joining this Institute in August 2008 as one of the first faculty members, he spent over twenty years in the USA. He earned his PhD under the guidance of Professor F. Albert Cotton at Texas A&M University. His career has been equally divided in academia and industry for over three decades. His research interests span several diverse fields involving multifunctional nanomaterials, crystal engineering, organometallic chemistry, X-ray crystallography, and Six Sigma methodologies with special emphasis on heterogeneous catalysis, and energy/environment-related topics.



favourable conditions. Moreover, the plane of symmetry plays a vital role in the resulting dimensionality and nature of the framework. The systematic connection of planar organic monomers forms two-dimensional sheets, which lay on each other *via* supramolecular interactions such as π - π stacking, leading to 2D COFs. AA-stacked sheets create larger pores in comparison to AB- and ABC-stacked 2D sheets. Conversely, for an increase in the dimensionality of the framework, non-planar moieties are the appropriate choice, which yield either interpenetrated or non-interpenetrated 3D frameworks.¹⁶

2.1 Topologies of 2D COFs

The known topological designs for two-dimensional COFs include **hcb** (honeycomb), **hxl** (hexagonal), **sql** (square lattice), **kgm** (kagome), **fxt**, **kgd** (kagome-dual), **fes**, **cpi**, **bex**, **mtf**, **htb** and **tth** networks formed from C_1 , C_2 , C_3 , C_4 and C_6 -symmetric and asymmetric building units (Fig. 1). These topologies are elaborated as follows.

hcb topology. This topology is very common in 2D COFs and devised from various combinations of C_1 -asymmetric and C_2 - and C_3 -symmetric monomers. Primarily, the self-condensation of linear C_2 -symmetric moieties, mostly having nitrile and




Fig. 1 Topological design for 2D COFs guided by suitable symmetries and angularity of their planar building blocks.



boronic acid functionalities, develops hexagonal pores, forming triazine and boroxine anhydride-based frameworks, respectively.^{4,17–19} COFs with triazine-based linkages are also called covalent triazine frameworks (CTFs). CTF-1 consists of a terephthalonitrile unit (which is linear, planar and possesses 2-fold symmetry), yielding edge-connected hexagons with the triazine core located at the vertices and the aromatic strut on the edges *via* self-condensation.²⁰ Triazine-based frameworks knitted from C_2 -asymmetric monomers are also known.²¹ The same topology is obtained with the $[C_3 + C_2]$ combination having hexagonal pores within the framework. Depending on the stacking of the 2D sheets, **hcb** is comprised of the **gra** (staggered stacking) and **bnn** (eclipsed stacking) topologies.^{4,22} In addition, the combination of two planar trigonal monomers $[C_3 + C_3]$ weaves a honeycomb net with similar pores. One example is the microporous COF-6 synthesized *via* the polycondensation reaction between 2,3,6,7,10,11-hexahydroxytriphenylene (HHTP) and 1,3,5-benzenetriboronic acid (BTBA) (C_3 -units).²³ A unique six-fold interpenetrated **hcb** topology framework was obtained *via* the Schiff base reaction between tri(4-formylphenoxy)-cyanurate (TFPC) and α -aminonaphthalene, offering a star-shaped channel.²⁴

hxl topology. Another topology knitting the 2D framework is the hexagonal topology formed *via* the two-component condensation reaction between C_6 - and C_2 -symmetric functionalities having a σ_h plane, where triangular micropores are obtained.²⁵ The propeller-shaped hexabenzocoronene bearing six amino groups ($[\text{NH}_2]_6\text{HBC}$) undergoes Schiff-base condensation reaction with a linear terephthaldehyde unit $[C_6 + C_2]$ and stitches HBC-COF with supermicropores (1.2 nm).²⁶ HEX-COF is another example of the **hxl** topology, which is fabricated using the propeller-like hexaphenylbenzene core with azine linkages.

kgm topology. The kagome topology is also called hexadeltile (having hexagonal and trigonal tiling), which possesses triangular micropores and hexagonal mesopores. For the formation of a periodically arranged dual-pore **kgm** net, the planar $[C_4 + C_2]$ symmetric building units are combined.^{27,28} An appropriate example is the imine-linked binary COF in which the four-fold D_{2h} symmetric ETTA (4,4',4'',4'''-ethene(1,1,2,2-tetrayl)-tetraaniline) locks with the two-fold linear terephthaldehyde to give a kagome network. The TPE-Ph COF, which was reported in 2016, exhibits a dual-pore kagome lattice when stacked in the AA-layer having tetraphenylethene units on its vertices.²⁹ Furthermore, rhombic structures of the **kgm** topology are also formed, weaving a single-type pore with a $[C_4 + C_2]$ combination.^{30,31}

kgd topology. The kagome-dual topology represents rhombic tiling, which is a tessellation of identical rhombi (looks like diamonds) with inner angles of 60° and 120°.³² The synthesis of HAT-NTBCA-COF from the heterodromous orientation of imine linkages formed by fusing $[C_6 + C_3]$ symmetric units, *i.e.*, propeller-like hexaamino-hexaazatriphenylene ($[\text{NH}_2]_6\text{HAT}$) and triangular symmetric linker 4',4'',4'''-nitrotritolris([1,1'-biphenyl]-4-carboxaldehyde) (NTBA), gives a dual kagome net.³³ Likewise, the $[C_6 + C_3]$ combination of propeller-like hexaformyl-phenylbenzene (HFPB) and 1,3,5-tris(*p*-aminophenyl)benzene (TAPB) tailors a single-pore COF-360 framework.³⁴

sql topology. The combination of either $[C_4 + C_2]$ or $[C_4 + C_4]$ symmetric reaction substrates confers a uni-pore square lattice topology. The tetra-functional square planar C_4 unit phthalocyanine tetra(acetonide) (Pc) preferably combines with C_2 symmetric diboronic acid to stitch an upright square lattice in the Pc-PBBA COF.¹⁵ Likewise, the one-component synthesis of an azodioxy-linked POR-COF from tetrakis(arylhydroxylamine)porphyrin under a protected environment creates a square lattice with the porphyrin unit covering the vertices and azodioxy-linkages located at the edges.³⁵

fmt topology. This is a unique topology in which ternary-pore COFs are designed *via* the mixture of a bent C_4 unit and a linear C_2 symmetric unit. Notably, the V-shape of the four-fold reaction substrate is essential in developing the connectivity to obtain a three-pore framework. TP-COF-BZ and TP-COF-DAB are two examples of the **fmt** topology utilizing terphenyl-tetracarbaldehyde with benzidine and 1,4-diaminobenzene, respectively.³⁶

fes topology. Another rare topology in 2D COF materials forming a semi-regular net with one type of vertex but more than one type of face. For example, the spiroborate-linked ICOF-1 and ICOF-2 obtained *via* the condensation of $\text{B}(\text{OMe})_3$ with a C_4 -symmetric polyol moiety create the **fes** topology with dual pores.³⁷

cpi topology. The combination of a rectangular C_4 -functionalized core with a linear C_2 -symmetric ditopic core tailors the **cpi** net. The planar monomers usually fabricate the **kgm** topology and only one case is reported for the **cpi** net. Aminal-COF-1 and aminal-COF-2 were synthesized in 2019 *via* the condensation of linear piperazine and D_{2h} -symmetric tetraldehyde units.³⁸

bex topology. When a triangular C_3 symmetric core unites with a rectangular C_4 unit, the combination yields a dual-pore **bex** topology with two distinct vertex moieties. Examples of this are PT- and PY-COFs, which topologically connect pyrene-tetraniline (P) along with triazine tribenzaldehyde (T) and benzene tripicolinaldehyde (Y), respectively, as $[C_4 + C_3]$ to frame a small rectangular and a large hexagonal pore.³⁹ Likewise, TT-COF-1 and TT-COF-2 were tailored using a TPE-core rectangular C_4 with a C_3 unit.

mtf topology. This unprecedented net uses the rectangular C_4 symmetric unit with a C_3 symmetric fragment to form a voided square grid-type topology, *viz.*, **mtf**. COF-432 was reportedly knitted from 4,4',4'',4'''-ethene(1,1,2,2-tetrayl)tetraaniline (ETTA) and 1,3,5-triformylbenzene (TFB), where in the conformation of TFB, the two formyl groups form a 90° angle with the third formyl group.⁴⁰ This net is similar to the **sql** topology with the removal of 1/8 4-c nodes, giving (3, 4, 4)-connectivity.

htb topology. The newly designed **htb** topology can be represented by a hexagonal tungsten bronze diagram, which utilizes a uniquely designed building block to tessellate the network. The C_4 -functionalized monomer must have angles of ~60°, 90°, 90° and 120° to meet the connectivity requirement, an example of which was reported recently. The BITA-PDA COF uses benzimidazole-based tetraaldehyde (BITA) with a C_2 -symmetric linear phenylenediamine linker to knit the ternary-pore framework.⁴¹

tht topology. This distinctive topology tessellates the 2D COFs synthesized from three-component reactions, incorporating



complexity into their structure. Therefore, careful choice of the organic building units with an appropriate linker length and angle between the two functionalities of the same unit is necessary. Considering this, COF-346 was synthesized from a hexatopic (hexaaminophenylbenzene (HAPB)), a tetratopic (tetrakis(4-aminophenyl)ethane (ETTA)) and a tritopic (1,3,5-tri(*p*-formylphenyl)benzene (TFPB)) linker having the angles of 60°, 60° and 120°, respectively, which formed a strain-free **tth** framework.³⁴ On the contrary, if the tetratopic linker ETTA is replaced with either a porphyrin-tetraamine (having 90° angle) or a tetrakis(4-aminophenyl)pyrene (length 11.3 Å), the topology design fails to give the desired COF. This is attributed to the higher angle of the porphyrin linker and length of the pyrene-based linker in comparison to ETTA and HAPB (*ca.* 7.1 Å), which prevents the formation of a closed ring.

2.2 Topologies of 3D COFs

All the above-mentioned combinations with an appropriate planar geometry of organic monomers and suitable topological connectivities give rise to stacked 2D COF sheets. To increase the dimensionality of the framework, a deviation from planarity and implementation of geometric constraints over the building units are prominent choices.⁴² There are 15 topologies (Fig. 2)

known thus far, in which 3D COFs are tessellated, six of which use monomers with a T_d geometry, for instance, **dia** (diamond net), **ctn** (cubic- C_3N_4), **bor** (borcaite net), **pts** (platinum sulfide) net, **ljh** (Luojia Hill), **lon** (lonsdaleite) and **rra**. A few reports have been found in which the planar building units connect in such a way that they knit three-dimensional COFs, which are **srs** (SrSi₂ net), **ffc**, **tbo** (twisted boracite) and **fjh**. The former utilizes the [$C_3 + C_3$] combination, whereas the other three amalgamates the triangular C_3 unit with a C_4 symmetric monomer unit with varying geometry (rectangular or square planar). An expansion in the topological library of 3D COFs is seen when high connectivity building units (C_6 and C_8) have been reported to give **stp**, **acs**, **ceq** and **bcu** (body-centered cubic) nets. Various examples of 3D COFs with different topological designs are elaborated as follows.

dia topology. A very common topology for 3D networks is attributed to the diamond net forged from the combination of a tetrahedral-shaped C_4 building unit and a linear C_2 monomer or another T_d node.⁴³ For example, the extended 3D network of COF-300 was synthesized using tetra-(4-anilyl)methane (TAM), which is a tetrahedral unit, and terephthalaldehyde *via* a two-component polycondensation reaction, leading to the formation of the **dia** topology.⁶ COF-300 crystallizes in the body-centered




Fig. 2 Topological designs for 3D COFs guided by combining symmetrical, planar and non-planar building blocks.



tetragonal space group with a **dia-c7** net with seven-fold interpenetration. However, the first non-interpenetrated **dia** net was found in PI-COF-4, in which the imidization of tetraaminoadmantane (TAA) (a smaller-sized T_d monomer, *ca.* 3.1 Å) and pyromellitic dianhydride (PMDA) occurs.⁴⁴ Steric factors play a role in hindering the interpenetration here.

ctn and **bor** topology. The $[C_4 + C_3]$ combination of the reaction substrates gives both **ctn** and **bor** nets, which differ only in their topological densities and pore size inside the framework. The topological density is “the number of vertices per unit volume for the given embedding”. The **Bor** net is observed to be topologically less dense than the **ctn** net, with the latter being more strain free and possessing smaller pores. COF-105 and COF-108 are unified in the **ctn** and **bor** topology, giving lower densities of 0.41 and 0.17 g cm⁻³, respectively.⁴⁵ This is attributed to the different synthetic units in both COFs, given that COF-108 is formed by cross-condensation of tetra(4-dihydroxyborylphenyl)methane (TBPM) with a triangular hexahydroxytriphenylene (HHTP) unit in comparison to COF-108 formed by cross-condensation of the silane analog of TBPM and HHTP. Thus, the linker geometry does not explain the topological difference between the two.

pts topology. In the platinum sulphide-like net, a tetrahedral C_4 -symmetric unit, which replaces the sulphide ions, combines with a square planar C_4 -unit at the location of the platinum nodes to give the underlying **pts** topology design. This is more likely to exist in an interpenetrated form. 3D-Py-COF obtained from the $[C_4 + C_4]$ imine condensation reaction between tetra(*p*-aminophenyl)methane (TAPM) and tetrakis(4-formylphenyl)pyrene (TFPPy) affords a two-fold interpenetrated **pts** net with vague π - π interactions.⁴⁶

ljh topology. This is an unusual topology, which was reported recently by introducing steric factors in the monomers of the **pts** net. The very common combination of $[T_d + C_4]$ using tetra(*p*-aminophenyl)methane (TAPM) and 1,2,4,5-tetrakis(4-formylphenyl)-3,6-diphenylbenzene (TPB-Ph) formed a rare unprecedented self-penetrated **ljh** net.⁴⁷

lon topology. A rare topology representing the lonsdaleite network is woven using two T_d units. The **lon** topology usually competes with the **dia** net, which is quite commonly knitted with the $[T_d + T_d]$ combination. In 2018, single crystals of LZU-111 were obtained *via* the imine condensation of tetra-(4-anilyl)methane (TAM) and tetra(4-formylphenyl)silane (TFS), which crystallize in a chiral $P6_5$ space group with a three-fold interpenetrated **lon-b-c3** topology.⁶ Surprisingly, despite the use of achiral monomers, the 6_5 screw axis was found to be generated from an interpenetration within the network.

rra topology. With the idea of incorporating pliable building units to diversify the topological domain of covalently linked porous organic networks, a γ -cyclodextrin monomer was used to form a 3D anionic CD-COF with the **rra** net.⁴⁸ The topology was constructed by combining a 4- c T_d anionic borate node with eight hydroxyl groups of γ -cyclodextrin *via* the formation of spiroborate linkages.

srs topology. There are a few network designs that are constructed from planar building units, but higher dimensionality

is achieved. One of these nets is **srs**, representing a strontium silicide framework knitted from a $[C_3 + C_3]$ monomer combination. The first COF with the **srs** net is the anionic SiCOF-5 synthesized from the condensation of a catecholate building unit (HHTP) and tetramethoxysilane (TMOS) using the reversible Si-O chemistry.⁴⁹ Here, the TMOS unit acts as a silicon source, which *in situ* forms the dianionic octahedral $[\text{SiO}_6]^{2-}$ building unit, and hence increases the dimensionality of the whole framework. The anions are stabilized by alkali metal ions.

ffc topology. Another unusual 3D topology formed from planar monomeric units is **ffc**, which is obtained by mixing a rectangular unit and a triangular unit. The $[C_4 + C_3]$ imine condensation of ETTA with NBC yields ETTA-NBC COF (named COF-1 in the original paper), which contains two independent (3,4)-coordinated nets interwoven with each other to increase the dimensionality.⁵⁰

tbo topology. The **tbo** net represents a twisted boracite, which differs from the **ffc** net with the geometry of the C_4 symmetric unit. It uses a 4-connected square planar monomer together with a 3-connected triangular unit to yield a non-interpenetrated 3D framework with three different polyhedron sharing faces when closely packed. The truncated tetrahedron polyhedron cage shares the trigonal face with the truncated cube, which further shares an octagon face with the truncated cuboctahedron. A porphyrin-based square planar amine unit (H_2TAP) underwent $[C_4 + C_3]$ imine condensation with the tritopic nitrilotris(biphenyl)carbaldehyde (NBC) unit to form the TAP-NBC COF (named COF-1 in the original paper).⁵¹

fjh topology. The combination of trigonal-planar and square-planar moieties connected at the dihedral angles of ~ 75 – 90° resulted in an **fjh** net for COF-790, which has rarely been reported. For its synthesis, a trimethyl substituted tris(4-formylphenyl)benzene (TTFB) was chosen with 4-*c* ETTA, which provided an appropriate dihedral angle due to the position of the methyl group.⁵² A single crystal of COF-790 was obtained with the molecular formula $[(\text{TTFB})_4(\text{ETTA})_3]_{\text{imine}}$, which crystallizes in the orthorhombic *Iba*2 (No. 45) space group. It has been investigated that the additional substitution of methyl on TFPB contributes to the crystallization in the **fjh** topology.

stp topology. Recently, JUC-564 COF was synthesized using a D_{3h} -symmetric trigonal prism unit with a triptycene-based core as a 6-*c* node with a 4- c D_{2h} square-planar monomer.⁵³ The unique link angle of 60° and 120° in the respective linkers yielded the novel **stp** topology for the low-density large-pore COF. A few months later, two other triptycene-centered COFs, Trip-COF 1 and Trip-COF2, were reported with an **stp** net *via* the $[C_6 + C_4]$ combination using rigid hexagonal hexakis(4-formylphenyl)triptycene (HFPTP) with tetraamino benzene and pyrene units, respectively.⁵⁴

acs topology. The combination of a high connected trigonal prism node with a linear ditopic unit weaves the symmetry-guided design for the **acs** topology. This rare net was reported when the 3D-cage COF-1 was synthesized from a D_{3h} -symmetric cage-6-NH₂ unit and linear 2,5-dihydroxyterephthaldehyde (DHTPA).⁵⁵ Reversible structural transformation was noted between the small-pore and large-pore with the loading of DMF, although the topology remained intact.



ceq topology. Another rarely reported topology with a high coordination number is **ceq**. 3D-**ceq** net was constructed using a rigid D_{3h} -symmetric hexaformyl triptycene moiety oriented at 120° at vertical positions with a substituted triangular planar organic strut.⁵⁶ Therefore, the connectivity of the 6-c trigonal prismatic unit with three different planar monomers, *i.e.*, square planar, triangular and linear, yields **stp**, **ceq** and **acs** nets, respectively.

bcu topology. This indicates body-centered cubic connectivity from the combination of an 8-coordinated core having a link angle of $\sim 70.5^\circ$ with 2-c linear units. A polycubane BP-COF-1 was reported in which eight borophosphonic acid units join to give BP-cubes with B–O–P linkages.⁵⁷ The sp^3 -hybridised B- and P-atoms located at the cube vertices connect the next eight BP-cubes through phenyl linkers, yielding a polycubane framework with the **bcu** topology.

3. Classification of COFs

3.1 Based on their linkages

There are numerous linkages used for constructing COFs with high crystallinity, stability towards heat, chemicals and water, and enormous surface areas with sizeable pores and functionalization (Fig. 3). Topological diversity can help explain the use of these linkages. COFs with good crystallinity, exceptional stability and multiple functionalization are challenging to synthesize given that control of their growth is required (long-range order), but functionalization results in the loss of this control. Furthermore, thermal, chemical and hydrolytic stability are other challenges to overcome within a single framework. An attempt to combine different synthetic strategies to engineer the desired COFs was envisioned by Lotsch and co-workers last year.⁵⁸ It is known that by employing dynamic covalent chemistry, one can control the covalent bond formation rate. Accordingly, introducing reversible linkages within the framework of COFs causes them to be more crystalline, robust and resistant upon exposure to heat; however, their stability towards moisture and several organic and inorganic chemicals is sacrificed. For instance, the first thermally stable and ordered boroxine and boronic ester-linked COFs, namely, COF-1 and COF-5, disintegrate in the presence of water following Le Chatelier's principle. Water, as the by-product, shifts the reaction to the backward direction, limiting or preventing the formation of a COF. Recent studies have shown that to maintain the 'error-correction' and 'proofreading' during COF synthesis, a calculated amount of H_2O (~ 15 equiv.) is required to get highly crystalline COF-5 with controlled crystallite sizes.⁵ The COF would not be formed when water content is increased to 20 equiv. However, functionalizing the linkers with alkyl chains in boron-containing COFs can provide resistance to aqueous medium to some extent.⁵⁹

Further attempts have been made to increase the stability of COFs in thermal, chemical and humid environments by incorporating N-containing bonds within their framework. The various linkages containing a nitrogen heteroatom include triazine, imine, heptazine, hydrazone, aminal, phenazine, azine, squaraine, azidoxo, anhydride, indoimine, nitrile-substituted olefin, amide,

viologen, urea, and pyrimidazole, as shown Fig. 3. These N-containing linkages enrich the framework with robust reversible bonds and provide protection against different organic and inorganic chemicals and moisture. Based on a detailed study and literature comparison, it can be perceived that the COFs enriched with N-centres are highly crystalline, possess great stability and can tolerate functionalization of their framework compared to boron-based linkages (Table 1).

Linkages such as borazine, borosilicate and polycubane were obtained by introducing N, Si and P atoms in boron-rich frameworks, endowing the frameworks with exceptional crystallinity, but their chemical and hydrolytic stabilities are still lacking.^{57,60,61} Some oxygen-containing linkages have also contributed to the stability, *i.e.*, dioxin, ester and silicate-based, examples of which are shown in Table 1.^{49,62,63} To explore more traits, the chemistry of knitting a framework with two different linkages was practiced. The N-rich imine linkage was intermixed with boroxine (or boronic ester) and β -ketoenamine to enhance the crystallinity and stability.^{64,65} Furthermore, the boroxine and hydrazone linkages were taken in a single framework to overcome the chemical stability limitation and allow selective hydrolysis in the framework.⁶⁶ These COFs are known as double-stage COFs.

Lately, it has been found that incorporating reversibility during the synthesis of COFs is not the only route to attain all the required properties in one frame. Hence, combining reversible covalent bond-forming reactions with irreversible non-covalent interactions has gathered increasing attention to solve the above-mentioned problem. Remarkably, stable materials with intact crystallinity in harsh acidic, basic and aqueous conditions have been synthesized using this strategy, which can also withstand chemical functionalities tied up on the framework. These linkages are β -ketoenamine,⁶⁷ bis(imidazole),⁶⁸ benzo-bis(oxazole)⁶⁹ and thiazole⁷⁰ (Fig. 4). In these types of linkages, the pre-orientation of the building units to induce order *via* reversible linkages provides crystallinity and irreversible locking of the bonds to induce stability in the framework synergistically.

Nevertheless, the fabrication of ordered COFs solely using irreversible reactions is a very cumbersome process. However, by limiting the flexibility and reducing the degree of freedom in the building units, a kinetically controlled but crystalline framework can be obtained. One example of this was reported by Liu *et al.* in 2017, where a highly ordered 2D-CAP COF from the exceptionally rigid 2,7,13,18-tetrabromodibenzo[*a,c*]dibenzo[5,6:7,8]quinoxalino[2,3-*l*]phenazine (2-TBQP) building block was successfully engineered.⁷¹ In addition to the 2D framework, an energetically less favourable 1D-CAP was formed. The 2D polymer was formed *via* metal-surface-mediated polymerization at an elevated temperature of $\sim 250^\circ C$, where the debromination of 2-TBQP and aryl–aryl coupling reaction occurred. A similar example of an irreversible C–C coupling reaction was reported the next year, in 2018, forming highly conjugated 2D aromatic polymers, *viz.*, CAP-1 and CAP-2, at high temperature and under an inert atmosphere (Fig. 5).⁷² A few other COFs synthesized using irreversible Ullmann, Suzuki–Glaser^{73,74} and Horner–Wadsworth–Emmons reactions⁷⁵ were also reported.





Fig. 3 Types of linkages in COFs with a timeline for their discovery and progress. ^a Subclass of imine linkages, ^b subclass of hydrazone linkages and ^c falls under β -ketoenamine linkage.

3.2 Based on their dimensionality











Considering their dimensionality, COFs are categorized as 2D and 3D COFs. As explained earlier in Section 2, following the topological delineation of 2D COFs, planar building units from the diverse list of monomers are used, whereas deviation from planarity is one of the requirements to yield 3D frameworks. In this section, we focus on the chemistry involved in the formation of 2D and 3D frameworks using covalently bonded organic units.

3.2.1 2D COFs.

Upon closely monitoring the mechanism through which two-dimensional covalent organic frameworks are formed in the reaction, two forces have been found to play an essential role as follows: (1) the reversible covalent bond formation among the organic monomers and (2) the supra-molecular interactions formed among the 2D sheets. The use of dynamic covalent chemistry involves reversibility in the organic reaction by making and breaking covalent bonds, which directs



Table 1 Framework stability (thermal, chemical and water) of COFs formed by different linkages^a

Linkage	Thermal stability			Hydrolytic stability			Linkage	Thermal stability			Reason
	Framework	stability (°C)	Chemical stability	stability	Reason	Framework		stability (°C)	Chemical stability	stability	
Boronic ester	 COF-14A (ref. 59)	NR	NR	Stable for ~17 h	Hydrophobic alkyl chains	 COF-316 (ref. 62)	~400	12 M HCl for 3 days and 6 M NaOH	NR	Bond locking by irreversible nucleophilic aromatic substitution (S _N Ar)	
Borazine	 BLP-(2)H (ref. 60)	~420	NR	NR	—	 SiCOF-5 (ref. 49)	~500	Stable in acetone, CH ₂ Cl ₂ , CH ₃ , CN, MeOH, THF and in air	NR	NR	
Imine	 COF-LZU1 (ref. 121)	> 300	NR	Stable	Strong π - π interactions	 TpPa-1 (ref. 67)	~350	9 N HCl	Stable for ~7 days	Bond locking by irreversible tautomerism	
Imine	 TFPC-NDA COF (ref. 24)	400	1 M HCl and 1 M NaOH for 7 days	NR	Strong π - π interactions	 TBI-COF (ref. 68)	~400	3 NHCl and 3 N NaOH for 7 days	NR	Bond locking by cyclization followed by dehydrogenation reaction	
Hydrazone	 COF-43 (ref. 22)	~280	Stable in THF, CHCl ₃ , PhMe, MeOH	Water, unstable	Hydrolysis of framework	 BBO COF-1 (ref. 69)	350	Stable in organic solvents	Stable for 24 h	Bond locking by ring closure and oxidation reaction	

^a NR = not reported.




Fig. 4 Strategy for the synthesis of highly stable N-containing linkages by (a) reversible and (b) irreversible reactions.




Fig. 5 Schematic representation of the formation of CAP-1 and CAP-2 by irreversible C–C coupling reactions. Reproduced with permission from ref. 72, Copyright the American Chemical Society (2018).

the crystallinity of 2D sheets.⁷⁶ Accordingly, the requirement of rigid, planar and highly symmetric monomers should be fulfilled. Moreover, factors such as the choice of solvent for the reaction, temperature, effect of modulator added, degree of freedom, rate of the addition of monomers and amount of by-product in the reaction largely determine the course of the reaction and product stability.⁷⁷ The size, shape and type of pores constructed during this process can be predetermined by the topological design (*vide supra*). Once stable covalent organic sheets are formed, the supramolecular interactions come into play. The adhesion of 2D sheets one-over-the other influences the bulk properties, such as surface area, luminescence, and conductivity. For instance, strong π - π interactions between stacked COF sheets containing a pyrene moiety cause the ACQ effect (*vide infra*).

Various reversible linkages have been proposed to gain an ordered 2D sheet (discussed in Section 3.1). On the contrary, the supramolecular interactions that stick the planar sheets

together are somewhat less explored.⁷⁸ A few examples are discussed below to give insight into the different types of supramolecular interactions, depending on the geometry and orientation of the monomers.

Constructed with strong van der Waals forces. Boronic ester-linked COFs were the first COFs to be synthesized and well-studied to discover their core chemistry. These frameworks are stacked on each other with strong van der Waals forces between two robust 2D COF layers. A detailed computational study was carried out on HHTP-DPB COF, where planar and highly rigid monomers were utilized under solvothermal conditions.¹⁸ The results from molecular mechanics and density functional theory indicate slight offset stacking (~ 1.7 – 1.8 Å) of the layers, which is not feasible to determine using the common characterization methods, but can be observed by SCXRD. This offset places the boron atoms of one layer in close proximity to the O-atoms of the adjacent layer, thereby building strong dipole-dipole



interactions, which stick the 2D sheets together. The results are more accurate with density functional theory given that it precisely considers the electrostatic interactions for simulation.

Constructed with aromatic π - π stacking. The planarity of the monomers after their assembly within a framework is vital to achieve a good magnitude of certain bulk properties. An excellent example of this was reported in 2016 by Banerjee and co-workers, yielding two imine-based COFs 2,3-DhaTta and 2,3-DhaTab, *via* the combination of 2,3-dihydroxyterephthalaldehyde with triazine and phenyl-core triamine, respectively (Fig. 6).⁷⁹ During the reversible imine bond formation, it was reported that planarity of the triazine-core with respect to the peripheral phenyl rings was achieved with angles of $\sim 174^\circ$ – 179° , whereas in the case of the phenyl core, deviation from planarity with angles of $\sim 145^\circ$ – 154° was observed. Intralayer H-bond formation between the imine N and diols caused additional planarity to the 2D sheet, although there was a tilt of $\sim 134^\circ$ between the triamine and terephthalaldehyde units. Consequently, strong aromatic π - π stacking was observed in 2,3-DhaTta, forming ribbon-like structures in comparison to 2,3-DhaTab with a hollow sphere. This was evident from the BET surface area calculations with a high surface area of $1700 \text{ m}^2 \text{ g}^{-1}$ for the more planar and stacked 2,3-DhaTta, which also showed nine-times more intense PXRD reflections (100 to 001 plane) compared to the value of $413 \text{ m}^2 \text{ g}^{-1}$ for 2,3-DhaTab.

Constructed with hydrogen bonding. Some cases have been recorded where the 2D COF sheets are stacked together by

hydrogen bonding. This requires that the atoms with the ability to form hydrogen bonds be oriented in close proximity to fulfil the hydrogen-bonding conditions. As examples, six different COFs have been reported, namely TPOMe-Tab, TPOMe-PaNO₂, TPOMe-Pa1, TPOMe-BD(NO₂)₂, TPOMe-BPy and TPOMe-Azo, which were synthesized from trimethoxy-substituted benzene-tricarboxaldehyde (TPOMe) with six different diamines.⁸⁰ Except for the TPOMe-BD(NO₂)₂ COF, they all have OMe groups perpendicular to the planar COF sheets, which favourably form interlayer hydrogen bonds. In addition, the methoxy groups provide steric hindrance around them, which generates a hydrophobic environment for the framework as a whole. Hence, the COFs resist very harsh acidic (18 M conc. H₂SO₄ and 12 M conc. HCl for 7 d), basic (9 M NaOH for 1 d) and moisture conditions. The utilization of flexible monomers for the construction of hydrogen-bonded 2D COFs is a much more laborious challenge than that with planar monomers. Thus, only the urea-functionalized COFs, COF-117 and COF-118, reported by Yaghi and co-workers in 2018 give a comparative study to emphasize this point.⁸¹ The variation in their surface areas, *i.e.*, $114 \text{ m}^2 \text{ g}^{-1}$ (COF-117) and $1524 \text{ m}^2 \text{ g}^{-1}$ (COF-118), is due to the different conformations of the urea molecule. The disruption of the C–N···H bond in COF-117 is attributed to the bond rotations in the pliable units, which were confirmed by FTIR spectroscopy before and after the introduction of acetonitrile solvent guest molecules.

As discussed in the preceding paragraphs, there are numerous examples of 2D COFs with supramolecular interactions of various




Fig. 6 (a) Strategy for the formation of COFs 2,3-DhaTta and 2,3-DhaTab. (b–d) Angle between the planes of triazine and phenyl core with phenyl substituents and that with a diol moiety. Reproduced with permission from ref. 79, Copyright John Wiley and Sons (2016).



types that produce microcrystalline powders. Supramolecular interactions, which are weaker in comparison to covalent bonds, provide reversibility to the reaction, but still it is difficult to obtain single crystals of 2D COFs. A detailed analysis of this has been extensively done by various groups, elaborating various factors in controlling the crystallinity of 2D COFs (see Section 4.3).

3.2.2 3D COFs. The synthesis of 3D COFs involves the reaction of rigid, non-planar and symmetric organic monomers, forming strong covalent bonds with high bond energies ($>500 \text{ kJ mol}^{-1}$). The 3D framework is chiefly associated with covalent bonding, which is absolutely irreversible, and therefore requires input to yield crystalline products. However, despite the problems associated with the difficulty of error-correction and reticular chemistry complications, a few single crystals of 3D covalently-bonded organic networks have been successfully reported. The three different categories of 3D COFs that can be separately outlined based on the information available in the literature are presented below.

Polycrystalline. Most 3D COFs are polycrystalline solids prepared mainly *via* the solvothermal technique. To generate highly ordered 3D COFs, the reaction conditions must be monitored in a proper and regular manner. Various parameters such as choice of solvents and their optimized composition, reaction temperature and environment (vacuum, N_2 or air), time required for completion of the reaction, and amount of catalyst added are the major factors that control the reversibility of the reaction, yielding a multi-crystalline material. As mentioned in Section 3.1, the various linkages developed thus far use dynamic covalent chemistry to achieve the desired crystallinity.

The very first polycrystalline 3D COF was reported to possess a boroxine and boronic-ester linkage, which was synthesized solvothermally in 2007 by Yaghi and co-workers.⁴⁵ Subsequently, the formation of the first imine-linked 3D COF was reported in 2009 by the same group.⁸²

Since then, many of these frameworks have been reported by solely controlling the reaction conditions. Several other greener techniques have also been used to increase the uniformity and maintain high dimensionality in COFs, including mechanochemical,⁸³ microwave-assisted,⁸⁴ ionothermal,⁸⁵ devitrification⁸⁶ and linker exchange methods⁸⁷ (see Section 4.1 for details). Basically, devitrification is the process of obtaining a crystalline material from an amorphous material. CAF-1 and CAF-2 with long-range order were synthesized by heating the corresponding amorphous polyamide networks, namely PATnC and PATCnC, respectively, at 240–250 °C for 7 days in the presence of 15 meq water.⁸⁶ In addition, a 3D-to-3D COF transformation happened from COF-320 to COF-300 *via* a heterogeneous linker exchange method.⁸⁷ Initially, the 3D COF-320 net was formed solvothermally from biphenyl-4,4'-dicarbaldehyde (BPDA) and tetra-4-anilylmethane (TAM). Afterwards, COF-320 was subjected to the linker exchange process with terephthalaldehyde (TA) under solvothermal conditions, yielding COF-300. An appropriate amount of acid catalyst was required to activate the TA linker for the exchange reaction, as shown in Fig. 7a.




Fig. 7 (a) Synthesis of COF-300-to-320-X and COF-320-to-300-X. (b) Synthesis of COF-301-to-TPB-DHTP-COF-X ($X = (n1/n2) \times 100$, where $n1/n2$ is the molar ratio of the exchanging monomer to initial COF; $X = 5, 10, \text{ and } 15$). Reproduced with permission from ref. 87, Copyright the American Chemical Society (2019).

Single-crystalline. In recent years, mechanistic studies have focused on insight into improving the crystallinity of 2D COFs, while single crystals have only been obtained for 3D COFs. The first single crystal of a 3D COF was reported in 2013, namely, NPN-1, NPN-2 and NPN-3, which were synthesized *via* the oxidation of hydroxylamines, yielding tetrakis(4-nitrosophenyl)-substituted methane, silane and adamantane, and subsequent polymerization yielded large and uniform crystals of approximately 0.5 mm in size (for NPN-3).⁸⁸ In the same year, Zhang *et al.* proposed the crystal structure of the 3D imine-linked COF-320 (with size of $\sim 200 \text{ nm}$) using the rotation electron diffraction technique (Section 5.4.2). The 9-fold interpenetrated net was woven solvothermally using tetra-(4-anilyl)methane and 4,4'-biphenyldialdehyde with the **dia** topology.⁸⁹ Fortunately, large-sized single crystals ($\sim 60 \mu\text{m}$) of 3D imine-based COFs were obtained, namely COF-300 (hydrated), COF-303, LZU-79, and LZU-111 with **dia** and **lon** nets (Section 2, *vide supra*), which



were successfully diffracted using the SCXRD technique (Section 5.3.2).⁶ This propelled the expansion of single-crystal COF chemistry, emphasizing certain requirements.

Interpenetrated nets. Another remarkable feature of 3D frameworks is their interpenetrating capability to give a thermally strong and stable net. Almost all 3D COFs become tangled during their synthesis, and only a few examples have been reported with non-interpenetration (cited in Section 2). The highest interpenetration in a 3D COF was recently reported with the chiral COF-16, which forms a 11-fold interpenetrated diamondoid-network.⁹⁰ A more interesting interpenetration isomerism was witnessed by Ma *et al.* in 2018, where COF-300 was found to exist in two distinct isomers, **dia-c7** and **dia-c5**, based on its degree of interpenetration.⁹¹ The factor of aging plays a role in their synthesis given that the formation of COF-300 **dia-c5** requires a three-day solvothermal process, whereas COF-300 **dia-c7** was synthesized in 9 days with a gradual increase in temperature from 25 °C to 50 °C, and finally 120 °C for 3 days each.

3.2.3 Dimensionality exchange in COFs. As discussed above, 2D and 3D COFs are known to exist with a variety of linkages and network designs. Both have distinct synthetic routes and outstanding properties. A recent and unique report by Li *et al.* indicated that the dimensionality of COF-301 is reduced from 3D-to-2D TPB-DHTP COF by heterogeneous linker exchange (Fig. 7b).⁸⁷ This is achieved by the replacement of a C_4 -symmetric T_d -tetraamine linker by C_3 -symmetric triamine, where the **dia** net opens and changes to an **hcb** net. The noteworthy point here is that the use of the reversible imine bond formation reaction during the solvothermal synthesis of COF-301 makes ligand exchange possible. The imine bond hydrolyses in aqueous conditions, and therefore the second triamine ligand gets a chance to bind and reform the framework of lower dimensionality. Another report on switching the COF dimensionality from 2D to 3D was reported by Gao *et al.*⁹² The 2D-BPTA-COF was synthesized solvothermally using the planar building units -tetra(*p*-aminophenyl)-biphenyl (BPTA) and tetrakis-(4-formylphenyl) benzene

(TPBH) *via* [$C_4 + C_4$] imine condensation, yielding AB-stacked 2D sheets. Interestingly, by substituting the BPTA monomer with a methyl group, the two planar biphenyl rings (with an initial dihedral angle of $\sim 0^\circ$) suffer steric hinderance and become twisted, attaining a dihedral angle of 60° . Therefore, a high-dimensional COF, namely 3D-BMTA-COF, was formed from the combination of tetra(*p*-aminophenyl)-bimesitylene (BMTA) and TPBH monomer. The new framework formed had the **pts** topology with 7-fold interpenetration.

4. Synthesis

The synthesis of robust porous organic polymers *via* covalent bonds with in-built crystallinity is challenging. The comprehensive discussion in the previous sections elaborates the importance of the reversible dynamic covalent chemistry for the synthesis of COFs. COF chemistry requires thermodynamically controlled organic reactions, which help in correcting and reforming the wrong bond and proofreading each step.⁹³ Several synthetic methods have been developed to incorporate crystallinity and stability in COFs, making them potent materials for sensing applications. Recently, crystalline COF powders and films have been extensively utilized as sensory materials, which have been synthesized using various methods, as mentioned in detail below.

4.1 General synthetic methods

In this section, we discuss the various methods utilized for the synthesis of COFs and modifications for their applications. All the reported synthetic methods are different in terms of maintaining the reaction conditions, choice and amount of solvent, reaction temperature, time consumed, requirement of catalysts, and the source of energy, which helps in the formation of a particular framework in each case. A detailed comparison is shown in Table 2.

4.1.1 Solvothermal method. This is the most prevalent method for yielding crystalline bulk COF powders. In this method, a mixture of monomer units in an appropriate solvent

Table 2 Comparison of the different methods reported for the synthesis of COFs

Synthetic method	Energy source	Reaction conditions	Solvent environment	Reaction time	Product formation
Solvothermal	Thermal energy	<ul style="list-style-type: none"> High temperature and autogenous pressure High vacuum conditions 	<ul style="list-style-type: none"> High boiling solvents Non-polar solvents reduce the reaction homogeneity, which further increases time to attain thermodynamically-controlled product Freeze-pump-thaw process for proper degassing of solvents 	<ul style="list-style-type: none"> 2 to 9 days 	<ul style="list-style-type: none"> Gram-scale (comparatively high yields for 2D COFs are seen) Interpenetration reduces the %yield Depends upon the solubility and reactivity of the starting materials
Mechanochemical	Mechanical energy	<ul style="list-style-type: none"> Ambient conditions Constant grinding 	<ul style="list-style-type: none"> No or minimum solvent is required 	<ul style="list-style-type: none"> Several minutes to a few hours 	<ul style="list-style-type: none"> Good yields obtained but with lower surface areas
Microwave-assisted	Microwave radiations	<ul style="list-style-type: none"> Moderate temperature and autogenous pressure 	<ul style="list-style-type: none"> No harsh solvent conditions are required 	<ul style="list-style-type: none"> Faster compared to other methods 	<ul style="list-style-type: none"> Higher yields but with reduced surface areas
lonothermal	Thermal energy	<ul style="list-style-type: none"> Extremely high temperature conditions 	<ul style="list-style-type: none"> Ionic solids in molten form act as solvents and catalyse the reaction 	<ul style="list-style-type: none"> Prolonged reaction time required to reduce side-product formation 	<ul style="list-style-type: none"> Good yields but limited crystallinity of frameworks
Room temperature synthesis	No external energy	<ul style="list-style-type: none"> Ambient conditions Constant stirring 	<ul style="list-style-type: none"> Solvents are chosen according to solubility of the monomers 	<ul style="list-style-type: none"> Several minutes to a few hours 	<ul style="list-style-type: none"> Reduction of yields of well-defined frameworks due to solubility



combination is kept in an airtight container and sonicated and degassed *via* the freeze–pump–thaw method. The reaction mixture is then heated at high temperatures of ~ 70 – 120 °C for 2–9 days under vacuum. This helps in maintaining an appropriate environment for the reaction, achieving high crystallinity and stability in the framework. A large number of crystalline, porous and highly stable COF powders has been synthesised using this method.^{4,57,68,82} The reaction parameters such as temperature and pressure direct the reaction towards a thermodynamic output, which ensures long-range order in the framework. Moreover, the solubility of the reactants can be controlled by using a combination of solvents. The use of a modulator also plays a crucial role in introducing reversibility in the reaction.

4.1.2 Mechanochemical method. This method for the synthesis of COF powders is different from the other methods due to its greener approach. In this method, the organic monomers are placed in mortar and finely ground with a pestle for several minutes to yield highly ordered COFs. The energy required for the formation of persistent organic frameworks is provided by mechanical energy. For instance, the TpPa-COF series was constructed *via* solvent-free mechanical grinding under mild temperature conditions.⁸³ To increase the reaction rate during synthesis, liquid-assisted grinding (LAG) is carried out, which involves the addition of a trace amount of catalytic solvent to the reaction mixture.⁹⁴ This maintains the homogeneity in the reaction and mixes the reactants well to ensure monomer availability, which helps in attaining high periodicity. Other COFs with various linkages synthesized using the LAG approach are discussed in detail below.

4.1.3 Microwave-assisted method. Among the various synthetic methods, microwave-assisted COF synthesis takes the least time to complete the reaction. It accelerates the rate of the reaction to support the rapid synthesis of crystalline materials with high BET surface areas. In this method, the reactants are dissolved or dispersed in a suitable solvent mixture *via* sonication, and then sealed in a glass Pyrex tube, which has either a vacuum or N₂ environment. The sealed tube is subjected to microwave irradiation together with heating for a short period (20–60 min). The boronic ester-linked COFs MW-COF-5 and MW-COF-102 were synthesized at moderately high temperature in 20 min,⁹⁵ while a dioxin-linked TH-COF (also called COF-318) took 30 min for completion of the reaction using this approach.⁹⁶

4.1.4 Ionothermal method. In this method a mixture of monomers and ZnCl₂, sealed in a Pyrex tube, is evacuated and heated to high temperature (400 °C) for a prolonged time. At the elevated temperature, the molten salt acts as a catalyst, the excess of which is washed away with dilute HCl solution. COF powders with moderate surface areas (~ 500 – 900 m² g⁻¹) and pore volume are fabricated using this method. The first crystalline CTFs, namely CTF-1 and CTF-2, were constructed using this method.²⁰ The use of ionic liquids as a solvent for the synthesis of 3D-IL-COFs was proven to be a green synthetic approach.⁸⁵ However, the ionothermal process has some limitations, for example, (a) the monomers must have the ability to withstand harsh reaction conditions and (b) the removal of the spent ZnCl₂ is difficult, and thus its residue causes contamination of up to 5 wt%.

4.1.5 Room-temperature synthesis. Bulk powder synthesis of highly crystalline and stable COFs has also been practiced under ambient conditions. The two monomers were mixed with an appropriate solvent combination and a suitable catalyst, and then stirred at room temperature for several hours. This method is simple and easy to operate. Thus, many porous organic frameworks with improved thermal stability and high surface areas have been synthesized using this strategy, for example RT-COF-1⁹⁷ and NP@a-1.⁹⁸ COF_{2.5} was constructed *via* acid-catalysed room temperature synthesis, yielding a crystalline bulk powder with a high BET surface area of 1523 m² g⁻¹.⁹⁹

4.1.6 Interfacial method. COF thin films and nanosheets have been successfully produced using the bottom-up interfacial approach. In this strategy, the films are synthesized at narrow interfaces of liquid/liquid,¹⁰⁰ solid/vapour¹⁰¹ or liquid/air¹⁰² phases. In the liquid/liquid interfacial synthesis method, monomer **A** is dissolved in a suitable high density solvent **1** and placed as the bottom layer in the ampule. Then, a spacer layer (also called the buffer layer in MOF chemistry¹⁰³) is placed on top of it, which can either be solvent **2** of a comparatively lower density or a mixture of two solvents (**1:2**). The third layer contains monomer **B** immersed in solvent **2**. The two solvents taken must be miscible at a slow rate to form smooth and periodic thin COF films.

Alternatively, the fabrication of solid/vapour interfacial thin films is carried out over an HOPG surface. In the typical synthetic procedure, a drop of monomer **A** solution is impinged over the substrate, and then introduced in a Teflon-sealed autoclave, which contains monomer **B** with CuSO₄·5H₂O. It should be noted that both monomers are not in direct contact. The whole system is sealed and subjected to high temperature for a few hours. Precursor **B** evaporates at high temperature and comes in contact with monomer **A**, resulting in the formation of covalent bonds at the solid/vapour interface. The rate of the vapour-phase monomer dosage decides the growth of the COF.

4.1.7 Exfoliation method. The delamination of bulk materials is another way to fabricate discrete thin films, which is a top-down strategy. In this method, the 2D COF sheets stacked by π – π interactions are pushed away using different energy sources, including solvent-aided delamination, mechanical grinding, and chemical and self-exfoliation. Solvent-directed delamination is the most common approach, which introduces low boiling solvent molecules into the 2D powdered framework and the suspension is sonicated for ~ 15 – 30 min. On evaporation of the solvent, thin nanofilms with a thickness of 0.5–10 nm are obtained. COF-1,¹⁰⁴ COF-8,¹⁰⁵ COF-43¹⁰⁶ and TPA-COF¹⁰⁷ were fabricated using the solvent-assisted exfoliation approach. Solvent-free mechanical grinding of bulk COF powders has proven to be a convenient method to yield thin films with a thickness of ~ 3 – 10 nm. TpPa and TpBD COFs were synthesized by grinding the bulk material at room temperature for 0.5 h,¹⁰⁸ whereas DAAQ-ECOF was milled with steel balls in two shifts for 30 min.¹⁰⁹

In some cases, it has been observed that the COF nanofilms lose their stability in the dispersion medium after they are peeled from the bulk powder. Therefore, the chemical exfoliation approach is carried out, which provides dispersion stability to



the nanosheets. The nanosize of the thin films primarily varies with the concentration of the powder suspension. At a higher concentration, more sheets will be in proximity to form thick films. An example of this is the DaTp COF, where *N*-hexylmaleimide was used at high temperature to conduct delamination with great stability.¹¹⁰ *N*-Hexylmaleimide undergoes Diels–Alder reaction with the anthracene units in Da and increases the hydrophobic alkyl–alkyl interactions among the 2D layers. The process was well monitored by FT-IR and PXRD analysis. Post-synthetic modification by chemical delamination was also performed during the thin film synthesis of the TpASH COF, which was further exploited for drug delivery applications.¹¹¹

A few cases have been reported where self-exfoliation of the framework occurs, leading to the formation of thin nanofilms. In this case, the choice of the building units, which leads to delayering *via* internal force, is important. No external force is required for carrying out this process. Few-layered IISERP-CON1 nanofilms with a thickness of ~2–6 nm and aspect-ratio of <0.1 were fabricated using the above-mentioned technique.¹¹² Moreover, a few ionic covalent organic nanosheets (iCONs) were self-exfoliated due to the interlayer repulsions caused by the positively charged guanidinium monomeric unit, including TpTGx ($x = \text{Cl}^-$, Br^- and I^-) iCONs¹¹³ possessing 3–6 layers with a size of 2–5 nm and DATG_{Cl}iCONs¹¹⁴ possessing 13–18 layers with a size of 5–7 nm. The iCONs formed showed chemical and water stability and retained their ionic properties after self-exfoliation.

In addition to these methods, the continuous flow method^{115,116} and hydrothermal method¹¹⁷ were employed to produce direct and free-standing COF nanosheets *via* the bottom-up approach. Nanofilms of COF-5, which is the first COF reported to be formed by boronic ester linkages, with a thickness of ~70–200 nm have been successfully formed.

4.2 Reaction conditions for diverse linkages

In this section, we selected examples from Table 3 for all the linkages mentioned in Fig. 3 to discuss the reaction conditions used for their synthesis. We apologise to researchers for not being able to include their examples given that it is very difficult to present all the examples available in the literature in this review. The heart of COF chemistry is the choice of the monomers, except in few cases, where it involves only one component such as boroxine and triazine-based COFs and the complementary monomers in the two-component system form the linkages. For nitrogen-rich COFs, there are four types of monomers, namely nitriles, amines, aldehydes and hydrazones. Furthermore, there are eleven nitrile-based, forty-eight amine-based, thirteen aldehyde-based and fourteen hydrazine-based monomers used thus far. Interestingly, the distribution of amines (twenty-five diamines, nine triamines, two C_2 -symmetric tetramines, nine C_4 -symmetric tetramines, one C_2 -symmetric hexamine and three C_6 -symmetric hexamines) is less than even aldehydes (thirteen dialdehydes, fifteen trialdehydes, eleven tetra-aldehydes and one hexa-aldehyde).

B–O linkage. The synthesis of covalent organic frameworks linked with small and light atoms (B and O) was first reported in 2005 by Yaghi and co-workers.⁴ COF-1 and COF-5 were

constructed *via* the one-pot solvothermal technique, directing the formation of a six-membered planar boroxine ring and a five-membered boronic-ester ring, respectively, by polycondensation reaction. The formation of the COF-1 crystalline bulk powder involves the co-condensation of 1,4-benzenediboric acid (BDBA) at 120 °C for 72 h in a mesitylene/dioxane mixture in a sealed tube (Fig. 8). Similar reaction conditions were implemented for the bulk synthesis of COF-5 using 2,3,6,7,10,11-hexahydroxytriphenylene (HHTP) and phenyl boronic acid (PBA), involving the interaction between boronic acids and diols. Numerous microporous COFs with alkyl (*i.e.*, methyl, ethyl or propyl) functionality were also synthesized through the reaction of dialkyl-substituted derivatives of 1,2,4,5-tetrahydroxybenzene (R_2 THB) with benzene-1,3,5-triboronic acid (BTBA). A series of COF networks with various pore diameters named COF-18 Å ($R = -\text{H}$), COF-16 Å ($R = -\text{methyl}$), and COF-14 Å ($R = -\text{ethyl}$) was obtained in 95–99% yield, while COF-11 Å ($R = -\text{propyl}$) was formed in 65% yield.⁵⁹

The faster synthesis of the COF-5 powder was conducted with the microwave-assisted technique, yielding a crystalline product in 20 min at 100 °C and 200 W power.⁹⁵ The resulting framework possessed a higher BET surface area (2019 m² g⁻¹) in comparison to that obtained *via* the usual solvothermal method (1590 m² g⁻¹).

C–N linkage (triazine). Covalent triazine frameworks (CTFs) are analogs to zeolites, metal organic frameworks (MOFs), and covalent boron oxide-based frameworks (COFs) in terms of performance due to their high surface area and porosities. They are obtained *via* trimerization reaction under ionothermal conditions in the presence of molten ZnCl₂ at high temperature (400–600 °C) for 40 h. It is noteworthy that the nitrile-substituted monomers are highly soluble in molten ZnCl₂ salt, which eventually behaves as an efficient catalyst for the trimerization reaction. The reaction is adequately reversible at elevated temperatures, yielding thermally stable CTFs (above 400 °C) with aromatic and heterocyclic-based nitrile monomers. CTF-1 was synthesized *via* the trimerization of dicyanobenzene (DCB) monomer in molten ZnCl₂ with high crystallinity and a porous framework.²⁰ Extended π -conjugation in the layered CTF-2 was obtained in similar manner *via* the ionothermal condensation of the highly rigid and chemically stable 2,6-naphthalenedinitrile (NDN) monomer.¹¹⁸ Zhang *et al.* reduced the reaction time from 40 h to 1 h by using the microwave-assisted polymerization approach. CTF-type polymers, namely P1-P6 and P1M-P6M, were synthesized by employing trifluoromethanesulfonic acid (TFMS) catalyst with six different nitrile-substituted aromatic monomers at room temperature and microwave-assisted conditions, respectively.¹¹⁹ The low-temperature TFMS-catalyzed condensation has a significant advantage in that it avoids the undesirable decomposition due to carbon-hydrogen bond cleavage at high reaction temperature. Moreover, among the samples, polymers P6 and P6M exhibited the highest surface areas (1152 and 947 m² g⁻¹, respectively) due to their longest T_d -symmetric tetra-nitrile-substituted monomer. Another triazine-linked framework, namely CTF-0, was prepared under similar ionothermal conditions using 1,3,5-tricyanobenzene (TCB).¹⁹ CTF-0 possesses a higher nitrogen content



Table 3 Selected examples of the linkages with monomers used, synthetic method, topology, and surface area of COFs






Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
1	Boroxine anhydride	COF-1	 <p>BDBA HHTP</p>	Solvothermal; mesitylene/ 1,4-dioxane; 120 °C for 72 h	hcb(gra)	711 (0.6–1.2)	4
		COF-102 COF-103	 <p>BTBA HHTP</p>	Solvothermal; mesitylene/ 1,4-dioxane; 85 °C for 4 d	ctn	3472 (1.15) 4210 (1.25)	44
2	Boronic ester	COF-5	 <p>BTBA HHTP</p>	Solvothermal; mesitylene/dioxane; 120 °C for 72 h Microwave-assisted; mesitylene/ 1,4-dioxane, 100 °C, 200 W for 20 min	hcb(bnn)	1590 (2.7) 2019 (N.R.)	4 95
		COF-11 Å, COF-14 Å, COF-16 Å, COF-18 Å	 <p>BTBA HHTP</p>	Conventional; THF/CH ₃ OH (99 : 1); Refluxed under N ₂ for 72 h		105 (1.1) 805 (1.4) 753 (1.6) 1263 (1.8)	198
		COF-6, COF-8, COF-10	 <p>BTBA HHTP</p>	Solvothermal; mesitylene/ 1,4-dioxane; 85 °C for 48–120 h		980 ^b (0.64) 1400 ^a (1.87) 2080 ^b (3.41)	23



Table 3 (continued)






Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
		COF-105 COF-108	 <p>HHTP</p> <p>X = C, TBPM; X = Si, TBPS</p>	Solvothermal; mesitylene/ 1,4-dioxane; 85 °C for 4 d	ctn bor	(N.R.)	45
		Py-DBA-COF-1, Py-DBA-COF-2, Py-MV-DBA-COF	 <p>PDBA</p> <p>DBA[18]</p> <p>DBA[12]</p>	Solvothermal; mesitylene/ 1,4-dioxane (2 : 1) (v/v); 105 °C for 72 h	bnn	1392 (3.6) 1354 (4.3) 1134 (4.1)	212
3	Boro-silicate	COF-202	 <p>DBA[12]</p> <p>tBuST</p>	Solvothermal; 1,4-dioxane/ toluene (1 : 2) (v/v); 120 °C for 3 d	ctn	2690 (1.1)	61
4	Triazine	CTF-1	 <p>THBPM</p> <p>DCB</p> <p>NDN</p>	Ionothermal synthesis; Molten ZnCl ₂ ; 400 °C in a quartz ampoule for 40 h	hcb	791 (1.2)	20
		CTF-2	 <p>NDN</p>	Ionothermal synthesis; Molten ZnCl ₂ ; 400 °C in a quartz ampoule for 40 h	hcb	2255 (0.8)	118



Table 3 (continued)










Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
		P1M, P2M, P4M		Microwave; CF ₃ SO ₃ H; 110 °C for 30 min	hcb	4 (N.R.) 464 (1.5–2) 542 (2–4)	119
							
							
		CTF-0		Ionothermal Synthesis; ZnCl ₂ ; 400 °C in a quartz ampoule for 40 h	hcb	400–500 (N.R.)	19
		FCTF-1 FCTF-1–600		Ionothermal Synthesis; ZnCl ₂ ; 400 °C or 600 °C in a Pyrex ampoule for 40 h	hcb	623 (0.46, 0.54) 752 (0.46, 0.59)	120
		mCTF, PTF-550, PTF-600, PTF-650, PTF-700		Ionothermal Synthesis; Molten ZnCl ₂ ; 400 °C for mCTF; 550 °C for PTF-550; 600 °C for PTF-600; 650 °C for PTF-650 700 °C for PTF-700	hcb	1212 1419 1964 2482 (~0.7)	121
5	Triazine-imine linkage	TRITER-1		Refluxed (inert atmosphere); anhydrous DMF; 150 °C for 12 h	hcb	716 (1.7)	128
6	Imine	COF-300		Solvothermal; 1,4-dioxane/3M aq. AcOH 10:2 (v/v); 90 °C for 2 d	dia	1360 (0.72)	82
		SCOF-IC1 SCOF-LZU1		Solid/vapour interfacial; in a closed system; 150 °C for 3 h	hcb	N.R.	101



Table 3 (continued)




Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
		II-COF1	 PPDA, TFPPY, TFB	Solvothermal; 1,4-dioxane/aq. AcOH; 120 °C for 3 d	sql	2723 (1.0, 1.7, 2.3)	122
		sCOF ^{A+B} sCOF ^{C+D}	 TAPB, PPDA, TFDA	Solid/vapour interfacial; preloaded on freshly cleaved HOPG; water/THF; Heating at 140 °C for 3 h (sCOF ^{A+B}); Heating at 80 °C for 3 h (sCOF ^{C+D})	hcb	N.R.	127
		COF-LZU1	 PPDA, TFDA	Solvothermal; 1,4-dioxane/3 M aq. AcOH; 120 °C for 72 h	hcb	410 (1.2)	116



Table 3 (continued)




Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
			 <p>TAM, BDA, PPDA</p>				
			 <p>TFA, TFS</p>				
			 <p>TAM, TFBZ, TFS</p>				
		COF-300 [(TAM) ₂] _{imine} , COF-303 [(TAM)(BDA) ₂] _{imine} , LZU-79, chiral LZU-111		Solvothermal; 1,4-dioxane/6 M aq. AcOH; 120 °C for 72 h	dia (COF-300, COF-303, LZU-79) lon-b-c3 (LZU-111)	2120 (LZU-111)	6



Table 3 (continued)




Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
		LZU-306	 TPE-4NH ₂	Conventional method with modulation strategy; aniline (50 equiv.), 1,4-dioxane, AcOH; 30 °C for 25 d	pts	2056 (1.09)	16
		COF-346	 ADA-CHO HAPB ETTA	Solvothermal; DCB/ <i>n</i> -BuOH; 120 °C for 72 h	tth	1081 (1.04, 2.19)	34
		SNW-1	 Melamine Tpa	Microwave synthesis; N ₂ atmosphere; 280 W for 6 h	(N.R.)	476 (40)	232



Table 3 (continued)

Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
			<p>pyrene tetraaniline (P)</p>				
		PT-COF PY-COF	<p>Triazine tribenzaldehyde (T) X = N; A = CH</p> <p>benzene tripicolinaldehyde (Y) X = CH; A = N</p>	Solvothermal; mesitylene/1,4-dioxane (1/1); 120 °C for 3 d	bex	1791, 1220 (1.77–1.83)	39
			<p>DHTC</p> <p>AD</p> <p>BPDA</p> <p>TPDA</p> <p>TPTCA</p> <p>DAB</p> <p>BZ</p>	Solvothermal; mesitylene/1,4-dioxane (1 : 1); 120 °C for 5 d	hcb	657 (2.7)	223
		IIERP-COF7	<p>DHTC</p> <p>AD</p> <p>BPDA</p> <p>TPDA</p> <p>TPTCA</p> <p>DAB</p> <p>BZ</p>	Solvothermal; toluene/1,4-dioxane/9 M aq. AcOH; 120 °C for 3 d	kgm	478.41 (0.73, 1.18, 3.06) 46.13 (1.13, 1.38, 3.27)	207
		SIOC-COF-X (X = 1,2)		Solvothermal; DMAC/mesitylene (1 : 2); 120 °C for 3 d	ftt	302.78 (1.61, 3.18) 518.94 (2.56, 3.91)	36



Table 3 (continued)




Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
				Solvothermal; DMAc/mesitylene (5 : 15); 120 °C for 7 d	N.R.	707 (0.81, 1.38) 1617 (1.02, 1.66)	208
				Solvothermal; aniline/AcOH/1,4-dioxane; 120 °C for 5 d	hcb	34 (0.5)	225
				Solvothermal; DMAc/mesitylene (1 : 1); 120 °C for 3 d	kgd	439.9 (1.27)	33



Table 3 (continued)

Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
		COF-432		Solvothermal; chloroform/methanol/aq. acetic acid (0.6/0.4/0.2); 120 °C for 3 d	mtf	895 (0.8)	40
		BITA-PDA-COF		Solvothermal; aq. acetic acid (9 M)/1,2-DCB/ethanol (2:13:13 v/v/v); 110 °C for 5 d	htb	940 (1.0, 1.7, 3.3)	41
		Trip-COF-x (x = 1,2)		Solvothermal; 1,2-DCB/ <i>n</i> -butanol/acetic acid (8:2:1); 120 °C for 3 d	stp	1473 (1.26, 2.96, 3.99) 1624 (1.26, 2.93)	54



Table 3 (continued)

Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
				Solvothermal; 1,4-dioxane/DMAc (1/2); 6 M AcOH; 120 °C for 3 d	hcb hxl	642 (2.4) 738 (1.6)	149
				Solvothermal; toluene/1,4-dioxane (1:1); 6 M AcOH acid; 150 °C for 3 d	dia	218 (1.6)	190
				Solvothermal; mesitylene/1,4-dioxane; 6 M AcOH; 120 °C for 4 d	kgm	2140 (2.9, 1.6) 2070 (3.8, 1.7) 1000 (4.5, 1.8)	27



Table 3 (continued)






Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
		4PE-TT		Solvothermal; benzyl alcohol/mesitylene; 6 M AcOH; 120 °C for 3 d	kgm	1990 (3.3, 1.6)	27
		TPE-Por-4, TPE-Por-2		Solvothermal; 1,2-DCB/1-butanol/6 M AcOH (1.5 : 1.5 : 0.5); 120 °C for 3 d	sql	50.2 (1.03) 324.13 (1.27)	235
		TAPB-DMTP-COF		Solvothermal; 1,4-dioxane/butanol (v/v, 1 : 1); MeOH; aq. AcOH; 80 °C for 24 h	hcb	2385 (N.R.)	252
		TpBpy-COF		Solvothermal; DMAc/o-DCB/aq. AcOH; 120 °C for 72 h	hcb	1004–1226 (N.R.)	264
		3D cage COF-1		Solvothermal; 1,4-dioxane/AcOH/aniline; 120 °C for 72 h	acs	1040 (0.88, 0.56)	55



Table 3 (continued)



Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
							
		COF-790		Solvothermal; nitrobenzene/ mesitylene (3:1 v/v); 85 °C for 72 h	fjh	2650 (2)	52
							
		2,3-DhaTta 2,3-DhaTab		Solvothermal; mesitylene/ 1,4-dioxane/AcOH (1.7:0.3:0.2); 120 °C for 72 h	hcb	1700 (3.537) 413 (3.536)	79



Table 3 (continued)


Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
							
		TpOMe-Pa1 TpOMe-Pa1NO ₂ TpOMe-BD(NO ₂) ₂ TpOMe-Bpy TpOMe-Azo TpOMe-Tab		Solvothermal; PTSA (<i>p</i> -toluene sulfonic acid); 120 °C for 3 h	hcb	1164 (1.5) 615 (1.4) 913 (1.8) 2023 (2.2) 1885 (2.8) 593 (1.4)	80
		COF-320		Solvothermal; 1,4-dioxane/3 M aq. AcOH; 120 °C for 3 d	dia	1410 (0.85, 3.42)	87



Table 3 (continued)






Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
			 TAM (R)-BDA	Solvothermal; mesitylene/ <i>n</i> -BuOH/6M AcOH (5:5:1); 120 °C for 3 d	dia	631 (0.8, 1.1) 825 (1.2, 1.5)	90
		CCOF-15 CCOF-16	 (R)-BPDA				
		TpASH COF	 Tp ASH NPHS	Conventional; 4-methyl benzene sulphonic acid; Stirred at 90 °C for 12 h	hcb	500 (1.3)	111
		TpASH-NPHS	 Tp ASH NPHS	Conventional; 4-methyl benzene sulphonic acid; Stirred at 90 °C for 12 h	hcb	~100 (N.R.)	260
		TpTG _x (x = Cl ⁻ , Br ⁻ , I ⁻)	 Tp TG _x	Solvothermal; 1,4-dioxane/water; 120 °C for 72 h	hcb	267 (N.R.) 305 (N.R.) 298 (N.R.)	114



Table 3 (continued)




Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
		TFPC-NDA COF		Solvothermal; mesitylene/THF (2:1); 100 °C for 3 d	hcb	294 (0.75, 1.0, 2.1)	24
		JUC-50x (x = 8,9) JUC-509-Y (Y = Mn, Cu, Eu)		Solvothermal; mesitylene/1,4-dioxane/AcOH; 120 °C for 3 d	dia	1513 (1.3) (JUC-508) 1443 (1.2) (JUC-509)	123
		TTT-COF TTI-COF		Solvothermal; di(<i>n</i> -octyl) phthalate/triphenyl phosphate (1:1 v/v); 6M aq. acetic acid; 120 °C for 72 h	hcb	1431 (2.2) 1362 (2.3)	170



Table 3 (continued)

Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
				Solvothermal; mesitylene/ 1,4-dioxane/AcOH; 120 °C for 72 h	hcb	532 (3.7) 867 (2.9) 452 (4.1)	124
		TzDa-COF		Solvothermal; <i>o</i> -DCB/DMAC/6 M aq. AcOH; 120 °C for 3 d	hcb	709 (3.6)	222
		COF-HQ		Solvothermal; 6 M AcOH/ <i>n</i> -BuOH/ <i>o</i> -DCB (1/1, v/v); 120 °C for 3 d	hcb	302 (3.7)	234



Table 3 (continued)




Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
		TAT-COF-1 TAT-COF-2	 <p>2-CHO-TAT DAB NH₂</p> <p>2-NH₂-TAT</p>	Solvothermal; EtOH/3 M AcOH; 90 °C for 6 d	hcb	61.2 (N.R.) 1166.1 (1.48)	126
		TX-COF-2	 <p>TX-CHO</p> <p>TAPB</p>	Solvothermal; mesitylene/ 1,4-dioxane/6 M aq. AcOH; 120 °C for 72 h	hcb	1137 (2.3)	240
		TTA-DFP COF Eu,Tb@ TTA-DFP COF	 <p>TTA</p> <p>DFP</p>	Solvothermal; mesitylene/ 1,4-dioxane/6 M aq. AcOH; 90 °C for 24 h	(N.R.)	265 142 (N.R.)	266



Table 3 (continued)

Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
7	Mixed imine- β -boroxine	NTU COF-1, NTU COF-2	 BPTA	Solvothermal; α -DCB/ <i>n</i> -BuOH/AcOH; 120 °C for 7 d	Rhombic pts	1000 (1.27) 1650 (0.85)	92
			 BMTA				
7	Mixed imine- β -boroxine	NTU COF-1, NTU COF-2	 TPB-H	Solvothermal; 1,4-dioxane/ mesitylene; 120 °C for 3 d	hcb	41 (N.R.) 1619 (2.5)	64
			 FPBA				
8	Mixed imine- β -ketoenamine	NTU-BDA-HTA (2:4), NTU-BDA-DHTA (4:2)	 HTCA	Solvothermal; aq. AcOH/dioxane; 120 °C for 3 d	hcb	1289.3 (1.4) 1344.2 (1.4)	65
			 DHTA				



Table 3 (continued)





Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
9	Hydrazone	COF-42 COF-43	 <p>DETH</p> <p>TFB</p>	Solvothermal; mesitylene/ 1,4-dioxane; 120 °C for 72 h	hcb	710 (2.3) 620 (3.5)	22
		Exfoliation of COF-43	 <p>DETH</p> <p>TFPB</p>	Solvent assisted exfoliation; EtBr/K ₂ CO ₃ DMF; Heating at 90 °C for 8.5 h	hcb	N.R.	106
		Pt-COF-42	 <p>DETH</p> <p>TFB</p>	Mesitylene/1,4-dioxane/AcOH; ambient conditions for 3 d	hcb	228 (1.8)	129
		TFPPY-DETHz COF	 <p>DETH</p> <p>TFPPY</p>	Solvothermal; mesitylene/ 1,4-dioxane; 120 °C for 72 h	sql	1090 (2.1)	137



Table 3 (continued)











Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
NUS-50, NUS-51			 2,5-DHTH	Pestle & mortar; TFP; H ₂ O; 90 °C for 12 h	hcb	520 (2.56) 510 (2.51)	130
			 TFP				
COF-ASB			 BTCH	Solvothermal; AcOH/DMF; 120 °C for 72 h	hcb	357.88 (2.5)	140
			 BDA				
Bth-Dha, Bth-Dma			 BTCH	Solvothermal; mesitylene/1,4-dioxane (3:2)/Ar; 120 °C for 5 d	hcb	130 (1.9) 392 (1.7)	141
			 BDA				
TpODH, TFBODH			 BTCH	Solvothermal; mesitylene/ 1,4-dioxane; 120 °C for 3 d	hcb	835 (0.5–1.2) 94 (N.R.)	136
			 ODH				
TpODH, TFBODH			 TP		hcb		
			 TFB				



Table 3 (continued)


Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
							
		co-COF-OH		DMAC/1,2-DCB/6 M AcOH; heated in a muffle furnace at 120 °C for 72 h	hcb	998 (2.4)	139
		COF-DB, COF-DT		Solvothermal; mesitylene/ 1,4-dioxane/aq. AcOH; 120 °C for 72 h	hcb	632 (3.1) 747 (3.1)	131
		COF-Fx-H (x = 6,8,10)		Solvothermal; mesitylene/ 1,4-dioxane/6 M AcOH; 120 °C for 3 d	hcb	233 (1.1) 29 (N.R.) 23 (N.R.)	132
		<i>p</i> -COF10		Solvothermal; mesitylene/ 1,4-dioxane/6 M AcOH; 120 °C for 3 d	hcb	1839 (2.3)	133



Table 3 (continued)






Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
		Tfpa-Mth COF		Solvothermal; mesitylene/6 M AcOH; 120 °C for 3 d	hcb	130 (1.59, 2.7)	134
		Pythz COF		Solvothermal; mesitylene/1,4-dioxane/6 M AcOH; 120 °C for 5 d	Rhombic structure of kgm	1571 (2.34)	138
		XB COF		Solvothermal; mesitylene/1,4-dioxane/6 M AcOH; 120 °C for 3 d	hcb	365 (2.35)	135
		PEG _x -COF-42 (x = molecular wt. of polymer)		Interfacial layering; DTH-dimer in H ₂ O/1,4-dioxane and TB in AcOH/mesitylene; RT for 48 h	hcb	101 (for PEG ₄₀₀) and 22 (for PEG ₆₀₀)	226
10	Mixed hydrazone-boroxine	COF-OEt		Solvothermal; <i>n</i> -BuOH/ <i>o</i> -DCB; 150 °C for 3 d	Dual-pore hcb	465 (2.35)	66



Table 3 (continued)




Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
11	Aminal	AMINAL COF-1, AMINAL COF-2	 <p>Piperazine Tetraldehyde A1 Tetraldehyde A2</p>	Solvothermal (Under N ₂); For Aminal COF-1, DCI/DMSO-d ₆ ; 90 °C for 8 h. For Aminal COF-1, toluene; 120 °C for 3 d	cpi	1169 (0.52, 0.82) 1168 (0.54, 0.82)	38
12	Borazine	PAF-6 BLP-2(H)	 <p>Piperazine TazTCl BHP-2(H)</p>	Conventional THF/DIEA; 0 °C for 4 h; reflux at 90 °C Solvothermal; mesitylene/toluene; 120 °C/150 mTorr for 3 d	hcb hcb	182.7 (1.18) 1178 (0.64)	142 60
13	β-Ketoamine	DAB-TFP, DAAQ-TFP	 <p>Piperazine DAB DAAQ TFP</p>	Solvothermal; mesitylene/1,4-dioxane; 3 M AcOH; 120 °C for 3 d Microwave-assisted; mesitylene/1,4-dioxane, 3 M AcOH; 100 °C for 1 h Mechano-chemical grinding for 40 min Solvothermal; 6 M AcOH/1,4-dioxane; 120 °C for 2 d	hcb hcb hcb hcb	535 (1.25) 724.6 (1.27) 61 (N.R.) 365 (N.R.) 435 (2.0)	67 84 83 143



Table 3 (continued)






Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
		TPTh(LAG)		Liquid-assisted mechanochemical; mesitylene/1,4-dioxane; 3 M AcOH; 120 °C for 3d	hcb	~100 (N.R.)	94
		TAPB-TFP, iPr-TAPB-TFP		Solvothermal; 6 M AcOH/dioxane; 110 °C for 5 d	hcb	567 (N.R.) 756 (N.R.)	145
		TpBD(NO ₂) TpBD(NH ₂) TpBD(NHCOGH ₃) ₂		Solvothermal; mesitylene/1,4-dioxane/3 M AcOH; 120 °C for 96 h	hcb	639 (2.3, ~1.6) 643 (2.3, ~1.6) 519 (2.3, ~1.6)	146
		TP-EDDA, TP-BDDA		Solvothermal; mesitylene/1,4-dioxane/AcOH; 120 °C for 72 h, 96 h	hcb	523 (N.R.) 758 (N.R.)	147
		3D-TpBD-Me ₂		Solvothermal; mesitylene/1,4-dioxane/3 M AcOH; sonication at RT for 30 mins; 120 °C for 72 h	hcb	1022	148



Table 3 (continued)



Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
			 <p>TAPT, TDOEB, TCTAB, DMB</p>	Room temperature synthesis; AcOH/H ₂ O; 8 h	hcb	976 (1.53) 1127 (1.87) 1182 (1.95) 1435 (2.88)	150
		JUC-52x (x = 0, 1, 2, 3)	 <p>DMOB, DMTH, TFG</p>	Solvothermal; mesitylene/1,4-dioxane (3:1 v/v)/6 M AcOH; 120 °C for 7 d	hcb	923 (2.2)	144



Table 3 (continued)




Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
							
				Solvothermal; mesitylene/ 1,4-dioxane/3 M AcOH; 130 °C for 3 d	hcb	505 (1.27) 478 (1.33) 258 (3.19, 4.52) 252 (9.70)	201
				Solvothermal; DMAc/mesitylene; 120 °C for 3 d	hcb	216 (N.R.)	109



Table 3 (continued)






Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
14	Phenazine	CS-COF		Solvothermal; Ethylene glycol; 3 M aq AcOH; sonication for 15 min; 120 °C for 3 d	hcb	776 (1.6)	151
15	C-C coupling	2D-CAP		Surface-mediated polymerization; adsorption on Au(111); 250 °C	Rectangular grid net	539 (N.R.)	72
16	Azine	Py-Azine		Solvothermal; 6 M AcOH; <i>n</i> -BuOH/ <i>o</i> -DCB 120 °C for 7 d	Rhombic kgm	1210 (1.76)	152
		NUS-30 NUS-31 NUS-32		Solvothermal; 1,4-dioxane/6 M AcOH (10/1, v/v); 120 °C for 5 d	kgm	1386 (0.6, 2.96) 685 (1.26, 3.05) 249 (3.71)	209
		ACOF-1		Solvothermal; mesitylene/ 1,4-dioxane/6 M AcOH; 120 °C for 72 h	hcb	1176 (0.94)	153



Table 3 (continued)

Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
			<p>H₂N-NH₂·H₂O Hydrazine</p> <p>BHFB</p> <p>TAPA</p> <p>PMDA</p>	Solvothermal; DMF/6 M AcOH; 120 °C for 3 d	hcb	560 (N.R.)	245
17	Imide	PI-COF-1, PI-COF-2, PI-COF-3	<p>TAPA</p> <p>TAPB</p> <p>PMDA</p>	Solvothermal; NMP/mesitylene/ isoquinoline; 200 °C or 250 °C for 5–7 d	hcb	1027 (2.9) 1297 (3.3) 2346 (5.1)	156
		PI-COF-4, PI-COF-5	<p>TAA</p> <p>TAPM</p> <p>PMDA</p>	Solvothermal; NMP/mesitylene/ Isoquinoline; 160 °C for 5 d	dia	2403 (1.3) 1876 (1.0)	44



Table 3 (continued)






Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
18	Spiroborate	ICOF-1 (DMA ^{Li}), ICOF-2 (Li ⁺)		Solvothermal; (CH ₃) ₂ NH or LiOH; 120 °C for 7 d	fes	1022 (1.1) 1259 (2.2)	37
19	Amide	CD-COF-Li CD-COF-DMA CD-COF-PPZ		Microwave synthesis; mesitylene/DMF; 120 °C for 4 h	rra	760 (0.64) 934 (N.R.) 494 (N.R.)	48
20	Olefinic	2DPPV		Solvothermal; DMF; N ₂ ; NEt ₃ ; 0 °C; H ₂ O; 10 ⁻⁴ mbar; 250 °C (CAF-1) 270 °C for 3 d and (CAF-2) for 7 d	hxl dia	256 (N.R.) 354 (N.R.)	86
20	Olefinic	2DPPV		Solvothermal; <i>o</i> -DCB; 150 °C for 3 d	hcb	472 (1.6)	158
		g-C ₁₈ N ₃ , g-C ₃₃ N ₃		Solvothermal; nBuOH/ <i>o</i> -DCB; 120 °C for 72 h	hcb	1170 (1.72) 752 (1.45)	159



Table 3 (continued)







Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
		COF-701	 <p>TMTA BPDA</p>	Solvothermal; mesitylene/dioxane/CAN; CF ₃ COOH; 150 °C for 72 h	hcb	1366 (1.14)	160
		g-C ₃₄ N ₆	 <p>DCTMP TFPT</p>	Solvothermal; DMF/piperidine; 180 °C for 3 d	hcb	1003 (1.45)	161
		TP-COF	 <p>PDAN TFPT</p>	Solvothermal; dioxane/Cs ₂ CO ₃ ; 120 °C for 3 d	hcb	232 (1.2, 2.2)	200
		TFPT-BTAN-AO	 <p>TFPT BTAN</p>	Solvothermal; NH ₂ OH·HCl; o-DCB/4 M DBU (10:1 v/v); 85 °C for 24 h	hcb	803 (1.26)	256
		sp ² c-COF-1, sp ² c-COF-2, sp ² c-COF-3	 <p>PDAN, n = 1 BPDA, n = 2 TPDA, n = 3</p>	Solvothermal; 1,4-dioxane/KOH; 90, 110 °C for 3 d and o-DCB/MeOH; 120 °C for 3 d, respectively	sql	613 (~2.0) 322 (~2.0) 737 (~2.0)	202
21	Dioxin	COF-316, COF-318	 <p>TFPN HHTP</p>	Solvothermal; 1,4-dioxane/Et ₃ N; 120 °C for 3 d	hcb	557 (1.2) 576 (1.5)	62



Table 3 (continued)








Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
22	Bis(imidazole)	MPC-TFPN (M = Ni/Co/Zn)	 <p>TFPN</p> <p>OHPM</p>	Solvothermal; DMAc/mesitylene/Et ₃ N; 150 °C for 3 d	sql	252.4 (for Ni) ~200 (for Co/Zn)	171
22		TPDAB	 <p>DAB</p> <p>TP</p>	Solvothermal; mesitylene/ 1,4-dioxane/6 M AcOH/120 °C for 72 h	(N.R.)	319 (1.3–1.8)	162
23		TBICOF	 <p>TAB</p> <p>TFPC</p>	Solvothermal; mesitylene/NMP/ dioxane; 120 °C for 3 d	hcb	1424 (2.5)	68
23	Benzo-bis(oxazole)	BBO-COF-1, BBO-COF-2	 <p>DABD</p> <p>SA</p>	Conventional; DMF; -15 °C; 3 h; RT; 1 eqv NaCN; 130 °C for 4 d	hcb	891 (1.34) 1106 (1.84)	69
		TPT-DAHQ	 <p>TFPB</p> <p>TPT-3CHO</p>	Solvothermal; DMF; 120 °C for 3 d	hcb	1855 (2.3)	164
24	Squaraine	CuP-SQ	 <p>DABD</p> <p>TAP-CuP</p>	Solvothermal; DMF; 120 °C for 3 d	hcb	1855 (2.3)	164
24		CuP-SQ	 <p>SA</p> <p>TAP-CuP</p>	Solvothermal; <i>o</i> -DCB/ <i>tr</i> -BuOH; 85 °C for 7 d	sql	539 (2.1)	155



Table 3 (continued)





Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
25	Silicate	SiCOF-5	 <p>HHTP TMOS</p>	Solvothermal; MeOH; 180 °C for 4 d	srs	370 (~ 3)	49
		SiCOF-Li SiCOF-Na SiCOF-K	 <p>DMTHA TMOS</p>	Solvothermal; anhy. MeOH; SiO ₂ or TMOS; 180 °C for 4 d	hcb	1153, 1276, 1067 (0.6, 1.35)	165
26	Oxazole and thiazole	LZU-192 (oxazole), COF-921 (thiazole)	 <p>TFPpy PPDA XH 2HCl X = O, S</p>	Solvothermal; DCB/BuOH; 6 M AcOH; 120 °C for 4 d and DMF/H ₂ O; 85 °C for 1 d	sql	1770 (2.049) 1550 (2.121)	70
27	Azodioxy	POR-COF	 <p>pAHAP</p>	Room temperature; THF; stirred for 12 h	sql	447 (1.95)	35



Table 3 (continued)





Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
28	Urea	NPN-1, NPN-2, NPN-3 COF-117 COF-118	 <p>TNPM, X = C, TNPS, X = Si, TNPAD, X = Adamantane</p> <p>TFP</p> <p>BDU</p> <p>DMBDU</p>	Mesitylene/ethanol (3 : 2); Celite-supported Ag ₂ CO ₃ ; stirred for 5 min at RT; left undisturbed for 48 h	dia	(N.R.)	88
		Pyurea COF	 <p>PDU</p> <p>Py</p> <p>DMBDU</p>	Solvothermal; NMP/1,2,4-trichlorobenzene (TCB)/6 M aq. AcOH; 85 °C for 3 d	hcb	114 1524 (~2.5)	81
			 <p>PDU</p> <p>Py</p> <p>DMBDU</p>	Solvothermal; 6 M AcOH/NMP; 120 °C for 5 d	Rhombic structure of kgm	1016 (1.48)	138
29	Viologen	HS HT COGF	 <p>BDNBPpyCl</p> <p>TAPB</p>	Solvothermal; EtOH/H ₂ O; 120 °C for 3 d; or microwave-assisted; 2.45 GHz at 100 °C for 2 h	hcb	12 (HS) 35 (HS) (N.R.)	166



Table 3 (continued)






Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
		COP ²⁺	 HCMPCTP 2 Cl [⊖]  2 Cl [⊖] 	Microwave-assisted; ACN; 2.45 GHz; 89 °C for 1 h	(N.R.)	(N.R.)	167
		COP-1 ²⁺ , COP-2 ²⁺	 pTNC4A 2 Cl [⊖]	Solvothermal; DMF; 150 °C for 24 h	(N.R.)	17.9 (N.R.) 51.8 (N.R.)	169
	PV-COF		 ZS AP	Microwave; EtOH/H ₂ O; 90 °C for 2 h	sql	38.2 (2.3)	168



Table 3 (continued)







Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
30	Ester	COF-119, COF-120, COF-121, COF-122		Solvothermal; anhy. dioxane/ 1,8-diazabicyclo [5.4.0] undec-7-ene; 150 °C (COF-119 to 121) or 160 °C (COF-122) for 3 d	Kgm (for COF-119) hcb (for COF- 120/121/122)	2092 (2.99, 1.79) 1255 (2.52) 908 (2.99) 664 (2.272, 4.367)	63
							
30	Ester	COF-119, COF-120, COF-121, COF-122		Solvothermal; THF/TEA; 60 °C; 3 d	hcb	583 (1.7–1.8)	265
							



Table 3 (continued)

Entry	Linkage	COF	Monomers used	Synthesis method	Topology	SA ^a (pore size) m ² g ⁻¹ (nm)	Ref.
31	Pyrimidazole	LZU-56x x = 1–8	 R', R'' = H, Me, OMe, Cl, Br	Solvothermal; DCB; PTSA-H ₂ O; EtOH/mesitylene; 120 °C for 5 d	(N.R.)	321 (1.2) 340 (1.2, 1.8) 554 (1.1) 540 (1.2) 110 (2.7) 87 (2.7) 137 (2.7) 400 (2.7)	172
32	Poly-cubane	BP-COF-1, BP-COF-2, BP-COF-3, BP-COF-4, BP-COF-5	 TICPN DCB BPA-1 BPA-2 BPA-3 BPA-4 BPA-5	Solvothermal; DMSO/toluene; 120 °C for 3 d (BP-COF-1 to BP-COF-3) and 100 °C for 3 d (BP-COF-4 and BP-COF-5)	bcu	519 (0.6) 485.69 (0.54) 655.75 (0.58) 632.08 (0.6) 621.65 (0.93)	57

^a Surface area (SA) by BET except those marked with b. ^b Langmuir surface area. N.R. = not reported.






Fig. 8 Synthesis of boroxine-linked COF-1 via the self-condensation of 1,4-benzenediboronic acid. Adapted from ref. 4, Copyright The American Association for the Advancement of Science (2005).

inside its framework with more cross-linked density in comparison to CTF-1, and therefore, is more thermally stable up to 600 °C under an O₂ atmosphere.

The other covalent triazine frameworks synthesized using the ionothermal technique include FCTF-1, FCTF-1-600, *m*-CTF and PTF-series.^{120,121} The FCTF series involves the inclusion of fluorine atoms in the framework, which improved the network stability and increased the number of ultramicropores (<0.5 nm). Alternatively, the *m*-CTF and PTF-series were subjected to molten ZnCl₂ at different temperatures, *i.e.*, 400 °C for the *m*-CTF series and 550–700 °C for the PTF series, with 1,3,5-tricyanobenzene (TCB) precursor.

C=N linkage (imine). An imine bond is a dynamic covalent bond, which is usually synthesized *via* a reversible Schiff-base condensation reaction between amines and aldehydes. The imine-linked porous frameworks are N-rich and have higher thermal, chemical and hydrolytic (in some cases) stability compared to boron-containing frameworks. Imine-linked crystalline COF powders have been synthesized *via* solvothermal, mechanochemical, ionothermal and room-temperature synthesis. The first imine-linked 3D COF was formed in 2009 *via* the solvothermal condensation of a *T_d*-symmetric tetra-(4-anilyl)methane (TMA) with the linear terephthaldehyde (BDA), as shown in Fig. 9a.⁸² Single crystals of COF-300 were obtained nine years later for structure determination by the single-crystal X-ray diffraction (SCXRD) technique (*vide infra*).⁶ The representation of COF-300 is [(TAM)(BDA)₂]_{imine} with seven-fold interpenetration. Also, the highly crystalline 2DILCOF-1 was synthesized at 120 °C *via* the condensation reaction between 1,3,6,8-tetrakis(*p*-formylphenyl)pyrene (TFPPy) and *p*-phenylenediamine (PDA) in 1,4-dioxane in the presence of aqueous acetic acid over 3 days (Fig. 9b).¹²² This COF had a larger surface area than that of the 3D imine-linked IL COF-1 (refer to Section 5.6).

The other COF powders with imine-linkages fabricated *via* the solvothermal technique include TFPC-NDA COF,²⁴ JUC-508, JUC-509, and JUC-509-Y (Y = Mn, Cu and Eu),¹²³ and some single-crystal COFs include COF-303, LZU-79 and LZU-111 with **dia** and **lon** networks.⁶ The modulator-directed imine formation reaction was conducted, which increased the state of reversibility and provided a chance for error-correction. Aniline is a mono-functional molecule that hinders nucleation and promotes crystal growth. Two other single crystalline COFs, *viz.*,

COF-303 and LZU-79, were synthesized solvothermally *via* the reticular strategy and possessed very highly interpenetrated **dia-c7** and **dia-c10** topology, respectively. Alternatively, the combination of two *T_d*-symmetric monomers tailored the LZU-111 COF with the distinct **lon-b-c3** topology (*vide supra*, Section 2.2).

A series of unique semi-flexible and flexible imine-linked 2D COFs, namely CON, CONN and CONNCO, was solvothermally synthesized with high crystallinity and stability in water and at different pH (Fig. 10).¹²⁴ The N-rich frameworks act as an efficient ON-OFF pH-responsive proton scavenger (further discussed in Section 6.2.2).

High temperature-autogenous pressure conditions successfully worked for the synthesis of highly luminescent active, crystalline and stable COFs, namely the COF-N, COF-NN (Fig. 11a) and TAT-COF series (Fig. 11b).^{125,126} These 2D frameworks were well explored for the fluorescence-based detection of small volatile organic molecules.

Furthermore, several imine-linked covalent organic thin films and nanosheets have also been fabricated using the exfoliation, interfacial and continuous flow methods. Surface COFs, namely SCOF-IC1 and SCOF-LZU1¹⁰¹ and single-layered sCOF (A + B) and sCOF (C + D),¹²⁷ were constructed *via* solid/vapour interfacial synthesis.

The formation of single-layered sCOF (A + B) and (C + D) requires control of the conformation of the precursor during the reaction. Highly rigid, aromatic monomers were chosen to construct single-layered films at ambient conditions, whereas more flexibility of aliphatic monomers requires ultra-high vacuum (UHV) conditions after impinging on the Au(111) surface.

A unique method of continuous flow was employed for the synthesis of COF-LZU-1 from 1,3,5-triformylbenzene (TFB) and *p*-phenylenediamine (PPDA).¹¹⁶ The stock solution of both monomers was separately formed in a mixture of dioxane and acetic acid, and then injected together in a flow reactor at a rate of 20 μL/min under ambient conditions, yielding a bright yellow product.

Mixed triazine-imine (C=N) linkage. The only example in this category is TRITER-1, which was synthesized *via* a one-pot polycondensation reaction between 4-aminobenzonitrile and terephthalic acid in the presence of triflic acid.¹²⁸ The reaction mixture was refluxed at 150 °C for 12 h in the high boiling-point solvent, DMF. Initially, the *in situ* synthesis of 1,3,5-tris-(4-aminophenyl)triazine (TAPT) was conducted using a nitrile-substituted unit supported by acid-catalyzed trimerization. Subsequently, it underwent a Schiff base condensation reaction, yielding mixed triazine-imine linkages. This framework is N-rich, thermally stable, and possesses a high surface area and supermicropores (1.5 nm).

Mixed imine-boroxine or boronic ester (C=N and B-O) linkage. Binary NTU-COF-1 and ternary NTU-COF-2 involve the formation of two types of covalent bonds (C–N and B–O).⁶⁴ The orthogonal reaction strategy to construct NTU-COF-1 involves the use of 4-formylphenylboronic acid (FPBA) and 1,3,5-tris(4-aminophenyl)-benzene (TAPB). The bifunctional FPBA unit contains a boronic acid group on one end, which is easily converted into a boroxine ring under high thermal conditions, and an aldehydic






Fig. 9 (a) Synthesis of COF-300 and (b) 2D ILCOF-1. Reproduced with permission from: (a) ref. 6, Copyright The American Association for the Advancement of Science (2018) and (b) ref. 122, Copyright John Wiley and Sons (2013).

group on the other end, generating an imine-linkage. Both reactions are compatible and do not interfere with each other to carry out feasible orthogonal reactions. Similarly, NTU-COF-2 utilizes three different monomers, TAPB, FPBA and HHTP, in 1,4-dioxane solvent. Therefore, solvothermal conditions are employed for the synthesis of mixed imine–boroxine linked COFs, *i.e.*, heating at 120 °C for 72 h for both NTU-COF-1 and NTU-COF-2.

Hydrazone (C=N–NH₂) linkage. A large number of covalently-bonded frameworks with hydrazone-linked monomeric units has been reported thus far. These frameworks are either formed as crystalline bulk powders and/or few-layered thin films. The first hydrazone-linked COFs were reported in 2011, which are mesoporous crystalline COF-42 and COF-43 constructed by the reversible dehydration reaction of 2,5-diethoxyterephthalohydrazide (DETH) and 1,3,5-triformylbenzene (TFB) or 1,3,5-tris(4-formylphenyl)benzene (TFPB) in the presence aqueous

acetic acid and a mesitylene/1,4-dioxane mixture in a flame-sealed tube at 120 °C for 72 h, respectively.²² Both COFs were collected as a pale-yellow microcrystalline powder. The few-layered COF-43 was obtained one year later by employing the solvent-assisted exfoliation technique and solid/vapour interfacial method.¹⁰⁶ The appropriate choice of solvent yields COF-layered sheets with high aspect ratios. In addition to solvothermal conditions, the room-temperature synthesis of COF-42, COF-43 and Pr-COF-42 was performed in 2017 with the same monomers, DETH (propyl substituted for Pr-COF-42) and TFB.¹²⁹ The monomers were suspended in a 1,4-dioxane/mesitylene mixture in the presence of 6 M aq AcOH catalyst and then left undisturbed for 3 days. Highly crystalline frameworks were obtained, particularly COF-42 with 72% yield, which was found to be comparable to that synthesized under solvothermal conditions.

Lately, various other COFs have been fabricated with the hydrazone linkage using the solvothermal technique, such as






Fig. 10 Synthesis of CON, CONN, and CONNCO from highly flexible and semi-flexible linkages. Dotted lines indicate various possible conformers due to flexibility and semi-flexibility of linkers. Reproduced with permission from ref. 124, Copyright the American Chemical Society (2021).

NUS-50,¹³⁰ NUS-51,¹³⁰ COF-DB,¹³¹ COF-DT,¹³¹ COF-Fx-H,¹³² *p*-COF₁₀,¹³³ TFPA-Mth COF,¹³⁴ and XB-COF,¹³⁵ all of which are made from ditopic aromatic hydrazine and tritopic aldehydic units. Although the synthesis of the two hydrazone-based COFs, NUS-50 and NUS-51 (NUS = National University of Singapore), involved the use of water as the solvent, the products were obtained in good yields and high purity, exemplifying the good use of water in place of toxic organic solvents. The incorporation of Co(II) in these COFs resulted in good Lewis acid catalytic activity. The stable and fluorescent active TFPA-Mth COF was prepared *via* the Schiff-base solvothermal condensation of tris-(4-formylphenyl) amine (Tfpa) with a hydrazide-based chiral monomer (Mth) at 120 °C for 72 h. The two above-mentioned COFs were proven to be potential candidates for metal ion sensing (*vide infra*). In addition, flexible dihydrazine units have been used together with a trialdehyde monomer to give TPODH and TFPODH COFs *via* the imine condensation of oxalyl dihydrazide (ODH) and 1,3,5-triformylphloroglucinol (Tp) or 1,3,5-triformylbenzene (TFB) at 120 °C for 72 h, respectively.¹³⁶

Alternatively, the combination of a ditopic aromatic hydrazine with a tetratopic pyrene-based aldehydic unit under solvothermal conditions afforded TFPPy-DETHz COF in 2018 and Pythz-COF in 2021. The TFPPy-DETHz COF was obtained in

86% *via* the condensation reaction of 1,3,6,8-tetrakis(4-formylphenyl)pyrene (TFPPy) and 2,5-diethoxyterephthalohydrazide (DETH) in a mixture of mesitylene and dioxane with acetic acid at 120 °C for 72 h.¹³⁷ Usually COFs having a hydrazone linkages display poor luminescence behavior (similar to an imine linkage) given that the N-atoms of the linkage cause fluorescence quenching. However, scissoring the N–H bond in the N-site of the hydrazone moiety generates an N[−] anion, which shows improved light-emitting activity. Another pyrene-based COF, Pythz-COF, possesses high surface area and good crystallinity and exhibits excellent water sensing and adsorption behavior.¹³⁸ To synthesize Pythz-COF, a Pyrex tube charged with 1,3,6, 8-tetrakis(*p*-formylphenyl)pyrene (Py) and terephthalic dihydrazide in a mixture of mesitylene/dioxane (2:1, v/v) with acetic acid as a catalyst was sonicated for 10 min, degassed, and then sealed under vacuum and heated at 120 °C for 5 d.

In 2019, the mixed linkers amine-*co*-COF-OH and amine-*co*-COF-H were tailored with different amounts of 2,5-bis(2-(dimethylamino)ethoxy)-terephthalohydrazide (DtATH) with DETH and trialdehydes TFG/TFB, respectively.¹³⁹ The synthesis was conducted under solvothermal conditions at 120 °C for 72 h, yielding amine-rich frameworks for CO₂ sorption studies. It was found that with an increase in the content of the amine-functionalized monomer






Fig. 11 (a) Synthesis of 2D imine-linked COF-N and COF-NN. (b) Structures of TAT model compound and its aldehyde and amine derivatives and synthesis of TAT-COF-1 and TAT-COF-2. Reproduced and adapted with permission from: (a) ref. 125, Copyright the American Chemical Society (2020) and (b) ref. 126, Copyright The Royal Society of Chemistry (2015).

DtATH, the BET surface area of both COFs was reduced by more than 50%, leading to a decrease in their CO₂ uptake capacity.

A few other hydrazone-linked COFs have been reported combining trihydrazine units with dialdehyde monomers, *i.e.*, COF-ASB, Bth-Dha and Bth-Dma. The usual solvothermal condensation was employed for their synthesis, where the monomers of both the frameworks were heated at 120 °C for 3–5 days. The highly crystalline COF-ASB was prepared *via* the reaction

between benzene-1,3,5-tricarbohydrazide (BTCH) and benzene-1,4-dicarboxaldehyde (BDA) for 3 d.¹⁴⁰ The COF possesses high thermal and chemical stability. Its composite with Ru nanoparticles (Ru@COF-ASB) promotes the synthesis of imines from amines and alcohols in solvent-free aerobic conditions.

Two other thermally and chemically stable COFs, Bth-Dha and Bth-Dma, were synthesized *via* the reaction between benzene-1,3,5-tricarbohydrazide (Bth) and 2,5-dihydroxyterephthalaldehyde (Dha)



or 2,5-dimethoxyterephthaldehyde (Dma), respectively, for 5 d.¹⁴¹ Bth-Dma COF contains O,N,O'-chelating sites, which tend to bind Fe(III) ions selectively, acting as a potent sensor.

Mixed hydrazone-boroxine (C=N-NH₂, B-O) linkage. A rare example in this category is the dual-pore COF-OEt, which was solvothermally fabricated using 3,5-diformylphenylboronic acid (DFPBA) and 2,5-diethoxyterephthalohydrazide (DETH) monomers.⁶⁶ At elevated temperature, the boronic acid condensed to form a boroxine ring with the simultaneous formation of the hydrazone linkage. The framework was then subjected to hydrolysis to synthesize nanotubes with free -OH groups.

Aminal (-C(NR₂)(NR₂)- linkage) (R = H, Alkyl). Very few examples have been reported in the literature with an aminal linkage. The design and fabrication of these crystalline materials is still challenging due to the extreme changes in the stereochemistry of their structure during the condensation reaction. The first aminal COF was reported in 2011, namely PAF-6, which was prepared from cyanuric chloride and piperazine.¹⁴² Recently, COFs, namely AMINAL COF-1 and AMINAL COF-2, were synthesized *via* the solvothermal condensation of piperazine and tetraaldehydes A1 and A2 with D_{2h}-symmetry, respectively, at 120 °C for 3 days in sealed tubes.³⁸

β-Ketoenamine (-C=O, -NH₂) linkage. The COF chemistry that combine reversible and irreversible reactions involves the formation of a β-ketoenamine linkage. Solvothermal conditions were employed with the monomers 1,3,5-triformylphloroglucinol (Tp) and *p*-phenylenediamine (Pa-1) or 2,5-dimethyl-*p*-phenylenediamine (Pa-2) to yield TpPa-1 and TpPa-2 COF powders, respectively.⁶⁷ A well-sonicated concoction of monomers in dioxane/mesitylene was added to a Pyrex tube and subjected to prolonged heating at 120 °C for 72 h. The detailed chemistry and stability aspects of TpPa-1 are mentioned in Section 3.1.

Similarly, the 2D DAAQ-TFP COF was tailored using 2,6-diaminoanthraquinone (DAAQ) and 1,3,5-triformylphloroglucinol (TFP) monomers in two different solvents, *i.e.*, 1,4-dioxane and *N,N*-dimethylacetamide.¹⁴³ The reaction temperature of the glass ampoule containing the reaction mixtures varied with the choice of solvent, *i.e.*, dioxane-solvated mixture was heated at 120 °C, yielding ~60–70% product, while that with DMA was carried out at 90 °C for 2 days, yielding ~70–85% product.

In 2016, the highly luminescent and semi-flexible COF-JLU4 was reported from the solvothermal condensation of 2,5-dimethoxyterephthalohydrazide with triformylphloroglucinol (Fig. 12).¹⁴⁴ The COF initially forms hydrazone bonding with further bonding in the β-ketoenamine linkage due to the hydroxyl-substituted trialdehyde group. The N-rich framework possessed exceptional chemical and moisture stability and was the first to be utilized as an efficient pH sensor (Section 6.2.2).

Likewise, many β-ketoenamine-linked frameworks have been constructed using high temperature-autogenous pressure conditions, such as, TAPB-TFP COF, *i*Pr-TAPB-TFP COF,¹⁴⁵ nitro-substituted TpBD(NO₂) COF,¹⁴⁶ highly unsaturated TP-EDDA and TP-BDDA COFs,¹⁴⁷ and methyl substituted 3D-TpBD-Me₂ COF.¹⁴⁸ The synthesis of these COFs involves the use of a solvent combination of 1,4-dioxane/mesitylene with a catalytic amount of AcOH in the temperature range of ~110–120 °C for 72–96 h.

As shown in Fig. 13, Das *et al.* reported the construction of two COFs, TpBDH and TfpBDH, *via* the solvothermal reaction of 1,3,5-triformylphloroglucinol (Tp) and 1,3,5-tris(4-formylphenyl)benzene (Tfp), respectively, with pyromellitic-*N,N'*-bisaminoimide (BDH).¹⁴⁹ These COFs show moderate chemosensor ability due to their π-stacked 2D layers, which leads to poor electron mobility and unavailability of space for the guest analytes to interact. Thus, nanosheets of TpBDH and TfpBDH




Fig. 12 Synthesis of β-ketoenamine-based COF-JLU4 and its structural packing. Reproduced with permission from ref. 144, Copyright The Royal Society of Chemistry (2016).






Fig. 13 (a) Schematic representation of the synthesis of TpBDH and TfpBDH [one unit of the space filling model of TpBDH and TfpBDH is shown in the inset of the chemical drawing model]. (b and c) Experimental PXRD patterns (blue) compared with simulated pattern (eclipsed; black) and Pawley refined difference between experimental and calculated data (red) [inset models show the eclipsed AA and staggered ABC stacking of consecutive 2D layers of TpBDH and TfpBDH, respectively]. (d) Schematic representation of COFs to CONs formation. Reproduced with permission from ref. 149, Copyright The Royal Society of Chemistry (2015).

CONs were obtained by exfoliating the respective bulk powders in the liquid phase using isopropyl alcohol at room temperature. AFM analysis confirmed the thickness of the nanosheets of ~ 1.5 – 5.1 nm with ~ 5 – 15 layers stacked together (see Section 5.4.3). Consequently, the BET surface areas of TpBDH and TfpBDH-COFs to CONs were reduced from 642 and 738 to 270 and 112 $\text{m}^2 \text{g}^{-1}$, respectively. The two CONs exhibit a rare turn-on explosive sensing capability in comparison to their bulk materials (see Section 6.2.1).

The rapid, solvent-free, room temperature synthesis of TpPa-1 (MC), TpPa-2 (MC) and TpBD (MC) COFs was performed *via* the mechanochemical (MC) grinding method. The monomers 1,3,5-triformylphloroglucinol (Tp) and *p*-phenylenediamine (Pa-1), 2,5-dimethyl-*p*-phenylenediamine (Pa-2), or benzidine (BD) were placed in a mortar and finely ground with a pestle for 40–45 min.⁸³ A visible color change was observed at the time intervals of 5, 15 and 40 min, showing light-yellow, bright orange and dark-red colors, indicating extended π -conjugation, respectively (Section 6.1.1).

A hydrazone-linked TpTh COF underwent β -ketoenamine formation by using 1,3,5-triformylphloroglucinol (Tp) and terephthalic dihydrazide (Th) *via* enol-to-keto tautomerism under LAG conditions.⁹⁴ The monomers, solvent mixture (1,4-dioxane and mesitylene) and 3 M AcOH catalyst were placed in a stainless steel jar with a 7 mm steel ball and milled for 90 min. A yellow

powder with high crystallinity and stability was obtained in $\sim 78\%$ yield.

A distinct method for the construction of highly crystalline micro and mesoporous COFs was performed using the Michael addition-elimination reaction in the aqueous phase under ambient conditions. The JUC-52 x (JUC = Jilin University China, $x = 0$ – 3) COF series with a pore size in the range of 1.59–2.92 nm was constructed.¹⁵⁰ In a typical synthesis, a C_3 -symmetric 1,3,5-tris(3-dimethylamino-1-oxoprop-2-en-yl)benzene (TDOEB) unit was combined with four different amines, two of which are C_3 -symmetric 1,3,5-tris(4-aminophenyl)triazine (TAPT) and 1,3,5-tricarboxylic acid-tris(4-amino-phenyl-amide)benzene (TCTAB) and the other two are C_2 -symmetric linkers, 2,5-dimethyl-1,4-benzenediamine (DMB) and 3,3'-dimethoxybenzidine (DMOB). The by-product of the reaction is dimethylamine, which further reacts with acetic acid used in the reaction to give dimethylamine acetate and dimethylacetamide, benefitting the formation of COFs with high crystallinity, porosity at high reaction rate (30 min), good yields ($\sim 93\%$) and scalable capability (up to 5.0 g). Furthermore, the Fe(II)-loaded JUC-521 was efficiently exploited for the degradation of toxic pollutants in aqueous medium using the Fenton reaction.

Mixed imine- β -ketoenamine (C=N, C=O) linkage. The synthesis of COFs with mixed imine- β -ketoenamine linkages requires solvothermal conditions to form reversible Schiff bases and irreversible tautomerism, giving a β -ketoenamine linkage. Last year, three different COFs, namely NTU-BDA-HTA, NTU-BDA-DHTA, and NTU-BDA-THTA, were formed, which differ from each other in the linkage ratio due to different number of hydroxyl groups in the trialdehyde monomer unit.⁶⁵ The first two COFs, as their name suggest, use mono- and di-hydroxy benzene-1,3,5-tricarbaldehyde (HTA and DHTA), which form an imine to β -ketoenamine ratio of 4:2 and 2:4, respectively. In contrast, the third COF, *viz.* NTU-BDA-DHTA, uses tri-hydroxy benzene-1,3,5-tricarbaldehyde (THTA) with benzene-1,4-diamine (BDA) having only β -ketoenamine linkages (linkage ratio = 0:6). Facilitating the framework with more stable β -ketoenamine linkages enhances the COF stability and makes the framework efficient for photocatalytic activity.

Borazine (B-N) linkage. The use of borazine as a precursor for the construction of porous materials is rare given that their synthesis is challenging. Compounds containing a B-N bond, resembling boron nitride (BN) are generally accessible only at high temperature and pressure conditions. The first borazine-linked crystalline COF, BLP-2(H),⁶⁰ was synthesized *via* the thermal decomposition of 1,3,5-(*p*-aminophenyl)-benzene-borane (APBB) in a mixture of mesitylene/toluene in a sealed tube at 120 °C/150 mTorr for 72 h.

Phenazine linkage. CS-COF is a conjugated microporous polymer, which was efficiently synthesized under solvothermal conditions.¹⁵¹ In a Pyrex tube charged with triphenylene hexamine (TPHA) chloride and *tert*-butyl-pyrenetetraone (PT), a mixture of ethylene glycol and aq. AcOH acid was added and sonicated for 15 min at room temperature. The tube was then placed in an autoclave at 120 °C for 72 h to allow the ring fusion reaction, forming phenazine-linkages and the product was isolated in an appreciable amount (~ 86 – 90%).





Fig. 14 Synthesis of azine-linked ANCOF, where the star marks represent the recognition sites for the selective detection of DCNA and 4-NA. Reproduced with permission from ref. 154, Copyright the American Chemical Society (2020).

Azine linkage. The first COF with an azine-linkage was synthesized in 2013. The Py-azine COF was obtained from the prolonged solvothermal condensation of hydrazine with 1,3,6,8-tetrakis(4-formylphenyl)pyrene (TFPPy) in a solvent mixture of *o*-DCB/*n*-BuOH with AcOH catalyst at 120 °C for 7 d.¹⁵² Another 2D azine-linked ACOF-1 was prepared under similar conditions *via* the condensation of hydrazine hydrate and 1,3,5-triformylbenzene for 3 d.¹⁵³

Recently, using the solvothermal approach, a highly luminescent azine-linked framework, namely ANCOF, was constructed from tri(4-formylphenoxy)cyanurate (TFPC) and hydrazine monohydrate (Fig. 14).¹⁵⁴ The framework is rich in nitrogen and with a high π -electron density to detect some electron-deficient species (*vide infra*).

Squaraine linkage. A CuP-SQ COF was synthesized *via* the solvothermal condensation reaction of squaric acid (SA) and copper(II) 5,10,15,20-tetrakis(4-aminophenyl)porphyrin (TAP-CuP) in the presence of a mixture *o*-dichlorobenzene/*n*-butanol at 85 °C for 7 d.¹⁵⁵ The resulting framework possesses planar squaraine units, forming a zigzagged N-rich conjugated COF skeleton.

Azodioxy linkage. The formation of an azidoxy bond involves the dimerization of nitroso units, which is a reversible reaction. Therefore, azidoxy-linked COFs require nitroso-functionalized monomeric units. Three of these frameworks have been reported, namely NPN-1, NPN-2 and NPN-3, which gave beautiful single-crystals (see Sections 3.2.2 and 5.4).⁸⁸ For their synthesis, a solution of either tetrakis[4-(hydroxylamino)phenyl]methane, silane or adamantane was mixed with $\text{Ag}_2\text{CO}_3/\text{Celite}$ in a solvent mixture of benzene or mesitylene/ethanol, mesitylene/methanol and mesitylene/ethanol/THF and stirred for 5 min under ambient conditions and left undisturbed for 48 h to 1 week. Also, the room temperature synthesis of azidoxy-linked POR-COF was reported using the highly conductive N-rich porphyrin core (Fig. 15).³⁵ The hydroxylamine-substituted protected porphyrin monomer was converted into the nitroso derivative *in situ* in the presence of tetrabutylammonium fluoride (TBAF) and THF solvent, followed by polymerization to give the desired COF.

Imide linkage. The polyimide (PI) COF series, PI-COF- x ($x = 1-5$), was constructed in 2014 and 2015 *via* an imidization reaction under solvothermal conditions. PI-COF-1, PI-COF-2 and PI-COF-3 are 2D frameworks constructed using pyromellitic




Fig. 15 Synthesis of azodioxy-linked porphyrin-based covalent organic framework (POR-COF). Reproduced with permission from ref. 35, Copyright The Royal Society of Chemistry (2016).



dianhydride (PMDA) with tris(4-aminophenyl)amine (TAPA, 7 Å), 1,3,5-tris(4-aminophenyl)benzene (TAPB, 9 Å) or 1,3,5-tris[4-amino(1,1-biphenyl-4-yl)]benzene (TABPB, 13 Å) in a mixture of N-methyl-2-pyrrolidone (NMP), mesitylene and isoquinoline, respectively.¹⁵⁶ The reaction mixture was heated at 200–250 °C for 5–7 d, yielding the **hcb** net from the [C₃ + C₂] combination. Conversely, the 3D porous frameworks PI-COF-4 and PI-COF-5 were synthesized using pyromellitic dianhydride (PMDA) and a tetrahedral building block 1,3,5,7-tetraaminoadamantane (TAA) or tetra(4-aminophenyl)methane (TAPM), respectively, at 160 °C for 5 d.⁴⁴ Surprisingly, the former 3D framework with an adamantane core was free from interpenetration possibly due to the steric bulk around the short imide-linked arms, whereas PI-COF-5 was weaved in a four-fold interpenetrated **dia** net.

Spiroborate linkage. Ionic covalent organic frameworks (ICOFs) with boron as the anionic center was prepared through the formation of a spiroborate linkage.^{37,157} These ICOFs, namely ICOF-1 and ICOF-2, contain a permanent immobilized ionic center, which allows the transportation of DMA⁺ and Li⁺ ions. An inert N₂ environment was maintained for their synthesis, where an octahydroxy-substituted macrocycle and trimethoxy borane in DMF were heated at 120 °C for 7 d. ICOF-1 utilizes dimethylamine, whereas ICOF-2 uses LiOH as the cationic source.

Olefinic (–C=C–) linkage. An olefin-linked 2D conjugated COF, namely 2DPPV, was synthesized by the Knoevenagel polycondensation reaction of 1,3,5-tris(4-formylphenyl)benzene (TFPB) and 1,4-phenylene diacetonitrile (DCB) in a sealed Pyrex tube containing Cs₂CO₃ and *o*-dichlorobenzene and heated at 150 °C for 72 h.¹⁵⁸ Recently, two triazine-cored unsubstituted olefinic-linked COFs, g-C₁₈N₃-COF and g-C₃₃N₃-COF, were synthesized *via* the solvothermal reaction of 2,4,6-trimethyl-1,3,5-triazine (TMTA) with a C₂-symmetric linear aldehyde monomer, 1,4-diformylbenzene (DFB), and C₃-symmetric trigonal aldehyde precursor, 1,3,5-tris(4-formylphenyl)-benzene (TFPB), respectively, at 120 °C for 2 h.¹⁵⁹ The solvent combination of *o*-dichlorobenzene/*n*-butanol was employed for both frameworks with KOH and EtONa reagents in the respective mixtures. A very common honeycomb topology is knitted for both the COFs. Similarly, solvothermal conditions were used to construct olefinic-bonded COF-701¹⁶⁰ *via* the aldol condensation of 2,4,6-trimethyl-1,3,5-triazine (TMT) and 4,4'-biphenyldicarbaldehyde (BPDA) and g-C₃₄N₆-COF¹⁶¹ *via* the Knoevenagel condensation of 3,5-dicyano-2,4,6-trimethylpyridine and 1,3,5-tris(4-formylphenyl)triazine.

Benzimidazole linkage. The first semi-crystalline benzimidazole-based TpDAB COF was synthesized *via* the solvothermal Schiff base condensation of 1,3,5-triformylphloroglucinol (Tp) and 3,3'-diaminobenzidine (DAB).¹⁶² The extended π -conjugation system is responsible for its electronic and ionic conductivity, which facilitate the movement of ions within the micropores of the porous framework and make it a promising candidate for energy storage. Benzimidazole-linked polymers (BILPs) have attracted increasing interest in the scientific community due to the easy formation of the imidazole ring unit *via* the condensation of an amine and an aldehyde. A highly crystalline and fully conjugated COF, hcc-COF, was reported in 2019, using a light-promoted synthesis method.¹⁶³ The monomers 1,2,4,5-tetraminobenzene

tetrahydrochloride (TAB) and hexaketocyclohexane octahydrate were sealed in a quartz vial together with mesitylene/methanol solvents and purged with Ar followed by the addition of distilled water and AcOH catalyst. The mixture was sonicated for different intervals and irradiated with sunlight at wavelengths in the range of 200–2500 nm to produce the bulk powder of hcc-COF. The same reactants were sonicated in NMP/mesitylene/chloroform with AcOH catalyst and irradiated with solar light for 1 h to yield 3.8 nm-thick hcc-COF thin films. Therefore, a new method was used to synthesize the benzimidazole-linked framework in the bulk and thin film forms, which were significantly characterized using various techniques (see Section 5). Another triazine-based benz-bis(imidazole)-linked COF, namely TBICOF, was synthesized *via* the solvothermal polycondensation reaction of tri(4-formylphenoxy)cyanurate (TFPC), 1,2,4,5-tetraminobenzene tetrahydrochloride (TAB) and imidazole in a mixture of mesitylene/N-methyl-2-pyrrolidone/dioxane at 120 °C for 72 h.⁶⁸ The benzimidazole-connected frameworks are rich in nitrogen and possess extraordinary thermal and chemical stabilities due to the irreversible bond locking by cyclization (see Section 3.1).

Benzo-bis(oxazole) linkage. This linkage is another example of an exceptionally stable linkage built over both reversible and irreversible reaction pathways (see Section 3.1). Two of these COFs, namely BBO-COF 1 and BBO-COF 2, were obtained *via* the reaction of 1,3,5-triformylbenzene (TFB) and 1,3,5-tris(4-formylphenyl)benzene (TFPB), respectively, with 2,5-diamino-1,4-benzenediol dihydrochloride (DABD) in two steps as follows: (1) the monomers were stirred in DMF at –15 °C for 3 h for the formation of a phenolic imine-linked intermediate and (2) the addition of methanolic solution of NaCN and heating at 130 °C for 4 d in an aerobic environment.⁶⁹ The framework exhibited a high surface area, and exceptionally high thermal, chemical and water stability. Recently, a triazine-cored benzo-bis(oxazole)-linked TPT-DAHQ COF was constructed *via* the one-pot [3+2] solvothermal condensation of 2,4,6-tris(4-formylphenyl)triazine (TPT-3CHO) and 2,5-diaminohydroquinone dihydrochloride (DAHQ-2HCl) in the presence of DMF at 120 °C for 3 days.¹⁶⁴ The time-dependent study showed the growth of ribbon-like crystallites into microtubes at intervals of 12, 24 and 48 h (see Section 5.4). The framework is rich in nitrogen atoms, which makes it efficient for energy storage and sensing applications.

Amide (HN–C=O) linkage. Two polyamide-based COFs, CAF-1 and CAF-2, were synthesized under very harsh solvothermal conditions *via* the devitrification method (Section 3.2.2).⁸⁶ The amorphous monomers, polyamide(1,3,5-tricarboxybenzene-*net-trans*-1,4-cyclohexanediamine) (PATnC) (for CAF-1) and polyamide(4,4',4'',4'''-tetra(carboxyphenyl) methane-*net-trans*-1,4-cyclohexanediamine)(PATnC) (for CAF-2), were dried under vacuum to remove the moisture content and kept at 250 °C in a pressure reactor for 3 d (CAF-1), and 240 °C in an oven for 7 d (CAF-2).

Silicate linkage. The one-pot self-assembly method was employed for the formation of silicate organic frameworks based on a hexacoordinated SiO₆²⁻ moiety. Examples are the anionic SiCOF with alkali metal ions (M = Li, Na, and K) named SiCOF M₂[Si(C₁₆H₁₀O₄)_{1.5}].¹⁶⁵ The monomers 9,10-dimethyl-2,3,6,7-tetrahydroxyanthracene (DMTHA) and tetramethyl orthosilicate (TMOS)



in the presence of a suitable alkali-metal methoxide base were added to a Teflon-lined vessel and kept at 180 °C for 4 d, yielding up to 97% product.

Viologen linkage. Viologen-based linkages contain charged 4,4'-bipyridinium moieties, which are widely used due to their rich redox chemistry. These linkages exhibit three redox states, which can be accessed electrochemically and also vary from hydrophilic to hydrophobic in nature. Due to this feature, these materials are promising candidates to adsorb multiple dyes with different polarities. The first viologen-based COF was reported in 2017 in the form of hollow spheres (HS) or hollow tubes (HT), which were prepared by the Zincke reaction between 1,1'-bis(2,4-dinitrophenyl)-[4,4'-bipyridine]-1,1'-diium dichloride (BDB) and 1,3,5-tris(4-aminophenyl)benzene (TAPB), in different solvents.¹⁶⁶ The amorphous materials, HS and HT, were prepared in ethanol:water (4 : 1) and dioxane, respectively, by employing the solvothermal method for 3 d or using the microwave technique for 2 h. In addition, a free-standing crystalline covalent organic gel framework (COGF) was made in a mixture of ethanol and water *via* microwave irradiation. The formation of hollow spheres and tubes was confirmed and observed using various microscopic characterization techniques (*vide infra*).

In another viologen-linked dicationic-COF, COP⁺⁺, the hexatopic cyclophosphazene core was combined with CH₃CN under the microwave-assisted Menshutkin reaction.¹⁶⁷ This framework was well exploited for the adsorption of dyes with varying polarities. The polarity of COP⁺⁺ was varied by reducing it from the dicationic form to the radical cationic form (COP^{•+}), both of which are hydrophilic and match the polarities of fluorescein (neutral) and rhodamine B (cationic) dyes. However, COP⁺⁺ adsorbs fluorescein dye more selectively by up to 90%. The neutral framework COP⁰ exhibits a hydrophobic nature and efficiently adsorbs Nile red up to 85%.

Two porphyrin-based viologen-linked COFs, Zn-PV-COF and Red-PV-COF, were synthesized under microwave conditions, heating at 90 °C for 2 h.¹⁶⁸ The Zincke reaction occurs between the amino-derivative of porphyrin and Zincke salt in an ethanol/water solvent mixture to give PV-COF. This COF was further metallated with zinc ions in a methanol/chloroform mixture at 50 °C for 24 h to yield Zn-PV-COF. Conversely, neutral Red-PV-COF was obtained *via* the stirring of PV-COF at room temperature for 15 min, where its bipyridinium units were chemically reduced using cobaltocene. The azo-bridged viologen- and calix[4]arene-based cationic covalent organic polymers (COPs) denoted as COP1⁺⁺ and COP2⁺⁺, respectively, were prepared by the formation of a diazo linkage between a nitro derivative of calix[4]arene (pTNC4A) and two different viologen-containing diamines in the presence of a strong base in a Schlenk tube at 150 °C for 1 d.¹⁶⁹

Oxazole and thiazole linkage. Two new covalently bonded frameworks with oxazole and thiazole-connected units were constructed *via* the linker exchange method under solvothermal conditions. The imine-linked ILCOF-1 was employed as the precursor and added to 2,5-diaminobenzene-1,4-dithiol dihydrochloride (DAHQ-2HCl) or 2,5-diaminohydroquinone dihydrochloride (DAHD-2HCl) to give COF-921 and LZU-192, respectively. These two COFs required slightly different reaction conditions, *i.e.*, for

COF-921: DMF/water in 75 : 25 at 85 °C for 1 day, and for LZU-192 : 85 : 15 DMF/water at 85 °C for 2 days.⁷⁰ The frameworks are rich in N, O and S-heteroatoms, rigid and exhibit enhanced thermal, chemical stability under harsh acidic and basic conditions. Another thiazole-linked TTT COF was synthesized using post-synthetic locking of an imine-linked TTI-COF under very harsh thermal conditions.¹⁷⁰ The activated TTI-COF and molten sulphur (S₈) were heated at 155 °C for 3 h. The reaction mixture was well-mixed given that sulphur attains minimum viscosity at this temperature. Subsequently, the harsh thermal environment of 350 °C was provided for another 3 h, and then the mixture was left to cool to room temperature. The extra sulphur was removed by Soxhlet extraction with a toluene/THF mixture for 24 h. The imine bond locking by thiazole-ring formation enhanced the stability and robustness in the framework.

Urea-based linkage. The flexible urea-based linkage was established in COF-117 and COF-118 from the solvothermal imine-condensation of 1,3,5-triformylphloroglucinol (TFP) and 1,4-phenylenediurea (BDU) or 1,1'-(3,3'-dimethyl-[1,1'-biphenyl]-4,4'-diyl)diurea (DMBDU) in NMP/trichlorobenzene and 6 M aq AcOH at 85 °C for 3 d.⁸¹ The major challenge in the construction of these frameworks is the various conformations of the linkers due to their low C–N rotational energies, which is easily overcome under high temperature reaction conditions (*vide supra*, Section 3.2.1).

This year, harsher conditions with prolonged time were employed for the synthesis of a urea-linked Pyurea COF.¹³⁸ The monomers 1,4-phenylenediurea and 1,3,6, 8-tetrakis(*p*-formylphenyl)pyrene (Py) were taken in a Pyrex tube with NMP/AcOH (6M) in a ratio of 1 : 0.1 and sonicated for 10 min, degassed, and then sealed under vacuum and heated at 120 °C for 5 d.

Dioxin linkage. In 2018, two 2D COFs, COF-316 and COF-318, were synthesized under solvothermal conditions in which the triangular monomer 2,3,6,7,10,11-hexahydroxytriphenylene (HHTP) combines with either the linear tetrafluorophthalonitrile (TFPN) or 2,3,5,6-tetrafluoro-4-pyridinecarbonitrile (TFPC) in 1,4-dioxane/triethylamine and dioxane/mesitylene/trimethylamine, respectively, at 120 °C for 3 d.⁶² The fluorine atoms on the nitrile monomers are electron-withdrawing moieties, which tend to increase the extent of nucleophilic attack by the hydroxyl group of HHTP, resulting in a nucleophilic aromatic substitution (S_NAr) reaction. An appropriate basic environment is required to carry out the reversible nucleophilic attack, which is followed by irreversible ring closure, directing the linkers toward a rigid and long-range ordered framework.

Later, the microwave-assisted nucleophilic substitution reaction was also employed to synthesize COF-318 (here, named TH-COF).⁹⁶ Both monomers, HHTP and TFPC, were placed in an ampoule and sealed with a solvent mixture of dioxane/mesitylene/triethylamine and treated with microwave heating at 70 °C for 30 min, giving 71% yield. Its surface area of 1254 m² g⁻¹ is much higher than that synthesized under solvothermal conditions (576 m² g⁻¹).

A series of dioxin-linked metallophthalocyanine COFs, MPC-TFPN COF (M = Ni, Co, and Zn), was prepared using reticular chemistry.¹⁷¹ The Et₃N-catalysed nucleophilic substitution reaction occurs between 2,3,9,10,16,17,23,24-octahydroxyphthalocyaninato metal (MPC-8OH; M = Ni, Co, and Zn) and tetrafluorophthalonitrile (TFPN)



in DMA/mesitylene placed at 150 °C for 3 d. The framework possesses high thermal stability (~ 400 in N_2 and ~ 300 in O_2 environment) and chemical stability (in common organic solvents and conc. acid/base conditions), which are attributed to the rigid metalophthalocyanine units.

Ester (O=C–O–) linkage. An ester is a rarely exploited linkage in COF chemistry. A solvothermal synthetic method was used to construct a series of ester-linked COFs, COF-119, COF-120, COF-121 and COF-122.⁶³ Here, the *trans*-esterification reaction takes place between the hydroxyl-functionalised tri- or tetra-topic units and ditopic 2-pyridinyl aromatic carboxylates. The reaction between di(pyridin-2-yl) terephthalate (DPT) and tetrakis(4-hydroxyphenyl)ethylene (THPE) or 1,3,5-tris(4-hydroxyphenyl)benzene (THPB) yields COF-119 with the **kgm** topology and COF-120 with **hcb** topology, respectively, in the presence of DBU/dioxane at 150 °C for 3 d. Furthermore, the reticulated COF-121 was obtained by reacting THPB with di(pyridin-2-yl) [1,1'-biphenyl]-4,4'-dicarboxylate (DPBP). To further explore the reticulation of COF-122, triol- and methyl-substituted dicarboxylates with extended arms were used under similar reaction conditions, yielding the **hcb** net with a high surface area.

Pyrimidazole linkage. The synthesis of the pyrimidazole-based linkage within a framework requires the solvothermal Groebke–Blackburn–Bienaymé (GBB) reaction based on isocyanide chemistry. A series of pyrimidazole-based COFs named LZU-56x ($x = 1$ to 8) and synthesized *via* the reaction between the derivatives of aminopyridine, 1,3,5-tris(3-fluoro-4-formylphenyl)benzene (TFFPB) and 1,3,5-tris(4-isocyanophenyl)benzene (TICB).¹⁷² The *p*-toluenesulfonic acid monohydrate (PTSA-H₂O) catalyst was added to an ethanol/mesitylene solvent mixture (for LZU-561) in a glass tube, subjected to freeze–pump–thaw cycles, and then heated at 120 °C for 5 d. The optimized solvent conditions with different substituents on the aminopyridine unit give high-order frameworks. By switching the tritopic isocyanide unit to the ditopic diisocyanobenzene, LZU-564 to LZU-568 were fabricated with different solvent combinations.

Polycubane linkage. A rare polycubane-linked COF uses boron-phosphoric acid-based (BPA) linkages, which after subjecting to harsh solvothermal conditions formed cubes and rods.⁵⁷ BP-COF-1 was synthesized by dissolving BPA-1 in a mixture of DMSO/toluene with methylphosphonic acid and sealing in a Pyrex tube, and then heating at 120 °C for 3 d (Fig. 16). It should be noted that the formation of the body-centered cubic (**bcc**) BP-COF-1 was unsuccessful with the polycondensation of diboronic and diphosphonic acid monomers. The thermal conditions for BP-COF-4 and BP-COF-5 were 100 °C for 3 d, which use different linkers, BPA-4 and BPA-5. To synthesize BP-COF-6, a Pyrex tube was loaded with BPA-1, conc. HCl, and DMSO/toluene and kept in a programmable oven at 120 °C for 5 d. This is the first example of a COF with a very high content of connecting networks (see Section 2.2).

4.3 Mechanistic studies for the synthesis of COFs

In the aforementioned sections, it can be seen that there is a large number of linkages from which highly crystalline COFs are obtained when the monomers are employed under suitable




Fig. 16 Synthesis of BP-COF-1. Reproduced and adapted with permission from ref. 57, Copyright The American Association for the Advancement of Science (2020).

reaction methods and conditions. However, very few reports elaborate on the mechanistic pathways to describe how these monomers combine to give long-range orders and what factors affect the crystalline growth. In this section, we emphasize the mechanistic details of two widely explored linkages, *i.e.*, boronic ester and imine, formed with different synthetic methods under different conditions.

4.3.1 COFs with boronic ester linkages. In-depth insight into the formation of COFs *via* boronic ester linkages was gained in the past five years by Dichtel and co-workers. It was observed for a long time that the formation of COFs is a heterogeneous process, where the monomers and organic polymer co-precipitate, yielding a framework with certain limitations, such as limited/low crystallinity, framework stability, and surface area. Thus, to overcome these shortcomings, the COF synthetic conditions were investigated by Smith *et al.* in 2014, where they reported a more efficient method for the synthesis of boronic ester-linked COF-5 under high temperature homogeneous conditions.⁵ It was concluded that by starting the reaction from a homogeneous mixture of HHTP and PBBA, COF-5 was more crystalline with a higher BET surface area (~ 2000 m² g⁻¹) in comparison to that previously reported in the literature (see Table 3, entry 2). Homogeneity of the starting mixture was gained by adding the liquid additive MeOH (~ 15 equiv. of HHTP) and increasing the amount of dioxane in the solvent mixture. The turbidity experiments depicted that after heating the reaction mixture to 90 °C within a 2 min induction period, a precipitate begin to appear, yielding 75% COF product after 20 h reaction time. The additional kinetic studies indicate that the formation rate of COF-5 is second order with respect to [diol] and [boronic acid], but has an inverse second- and first-order dependence on the concentration of MeOH and TCAT, respectively. TCAT, as a uni-functional catechol-based modulator, competes with the diol monomer HHTP to slow down the polymer formation time; therefore, increasing the rate of COF formation.

The next year, another study was published by the same group focusing on the rate of framework growth and nucleation and factors inducing moisture stability in the product.¹⁷³ It has been elucidated that the rate-determining step in the boronic ester-linked COF formation reactions is not the formation of the C₂O₂B ring, namely, the 2D intermolecular stacking path



occurs when growth of already existing micro-crystallite COFs predominates. Furthermore, factors such as controlled temperature (60–90 °C), aromaticity of monomers (pyrene vs benzene-core), amount of competitor (TCAT) used in the beginning or during the reaction, and quantity of liquid additives (MeOH and H₂O) are the deciding factors influencing the crystallinity and stability of the COF.

The effect of modulator on the microwave-assisted synthesis of COF-5 was closely studied by Bein and co-workers in 2016 using the functionalized truncated boronic acids, MPBA and CPBA.¹⁷⁴ The reaction mixture was sealed in a microwave tube and heated to 100 °C at 300 W power. The report showed that with 10% modulation (HHTP : BDBA : modulator = 2 : 2.70 : 0.6), the reaction time increased by 30 min, forming a large number of crystallite domains with sizes of 60 and 56 nm for MPBA and CPBA, respectively. Moreover, the highest XRD intensity and BET surface area were obtained under these conditions, *i.e.*, 2100 m² g⁻¹, which is ~35% greater than that of the unmodulated COF-5. Further studies done by Dichtel's group revealed that the use of nitrile-containing co-solvents help in stabilizing the colloidal suspension for over a month.¹⁷⁵ This promotes the growth of 2D COFs by inhibiting the particle aggregation, ameliorating the quality of its single crystals. Later, in a follow-up paper published in 2018 by the same group, it was proven that control of the crystallite size was achieved *via* the rate of monomer addition after stabilizing the COF colloidal suspension.¹⁷⁶ The SAXS/WAXS studies showed that with the slow addition of the monomer (0.1 equiv. h⁻¹), the crystallinity of the framework

increased, suppressing the nucleation process, which contradicts the results of fast monomer addition (1.0 equiv. h⁻¹). These studies provide a way to overcome the crystallite growth and nucleation issues for knitting boronic ester-linked COFs.

Based on the summary of the above-discussed information, a comprehensive mechanism for the formation of a COF with boronic ester linkages under either high temperature or microwave-assisted conditions is thoroughly displayed in Fig. 17A.

During the formation of COF-5 from HHTP and PDBA, the monomers initially combine to give oligomers in step *a*, which then stack reversibly in step *b*. During this stage, an addition of diol or boronic acid-mimicking modulators controls the growth by slackening the reaction. On proceeding further, either the oligomeric sheets stack together forming metastable layers, or one sheet acts a base for template polymerization. Consequently, each stage gives COF crystallites through step *c*, which require further treatments to get the desired product. Control of the various aforementioned factors in the early stages helps to build the crystallites at this stage. By recovering these crystallites, a multi-crystalline precipitate is obtained *via* step *d*, whereas treating them with suitable stabilizing agents yields single crystals by preventing nucleation (step *e*). This can occur when the monomers are slowly added at this point. On the contrary, the fast addition of the monomer yields new crystallite particles *via* nucleation, and thus single crystal growth is prevented.

4.3.2 COFs with imine linkages. After boronic ester bonds, the imine linkages are widely explored to weave a long list of single crystalline, water-stable COFs. The Schiff base imine




Fig. 17 Mechanism for the formation of (A) 2D boronic ester-linked and (B) imine-linked COFs proposed by analyzing the information from the detailed mechanistic studies. Adapted from ref. 5, 173–177, 180 and 182.



condensation reactions are very fast, and therefore, pose difficulty in building crystalline 2D frameworks from amorphous organic polymers. Reports have shown that these linkages are extensively formed under solvothermal conditions, where thermodynamic equilibrium is achieved in a few days, yielding the desired uniformity. Similar but distinctive in-depth studies were performed by Smith *et al.* in 2016 to understand the mechanism of imine-linked 2D COFs, using TAPB and PDA as monomers in particular.¹⁷⁷ Accordingly, a homogeneous solution of reactants with an optimized dioxane/mesitylene ratio (4:1 v/v) was heated to 70 °C for 5 days. The glacial acetic acid catalyst and H₂O content were maintained for the minimum quantity to be ≥ 1 M and 3.3 M, respectively, which was required to initiate crystallinity within the framework and attain higher yields. Additionally, the BET surface area of the initial amorphous solid was found to be 18 m² g⁻¹, which further increased to 287 m² g⁻¹ over a period of two days. This supports the observation that the amorphous-to-crystalline imine COF transformation is a two-step process, *i.e.*, fast polymerization of soluble monomers to an amorphous organic polymer at elevated temperature followed by the imine exchange process, which increases the tendency of error-correction.

A big step was taken by Yaghi and co-workers by judiciously adding a suitable amine-based modulator to obtain 3D imine-linked COFs. The widely used modulator is aniline, which is a monofunctional mimic of the diamine monomer and competes in the COF formation reaction. Consequently, large-size crystals of good quality grow by inhibiting nucleation. By following the aniline modulation process, large single crystals (size in parentheses) of COF-300 (~60 μm), COF-303 (~15 μm), LZU-79 (~100 μm) and LZU-111 (~50 μm) were obtained.⁶ In all cases, good-quality crystals were obtained under solvothermal conditions when the aniline modulator concentration varied from 15–80 equiv. The other amine and aldehyde-based modulators used for knitting prolonged 2D and 3D COF nets include propylamine, 2-aminopyridine, benzaldehyde, and 2,4,6-trimethylbenzaldehyde.^{178–180}

A few months ago, the mechanochemical synthetic approach for the synthesis of imine-linked COFs was deeply studied to understand its mechanistic pathway. Four different COFs, *viz.*, COF-LZU1, TbBd-COF, IISERP-COF4 and N-COF, were constructed by liquid-assisted mechanochemical milling of their respective monomers in an X-ray transparent PMMA milling jar. It was evidently shown that by controlling the ratio of liquid additive (dioxane with respect to the reactants) and providing a catalyst suitable for Schiff base formation, very high crystallinity of the framework could be achieved by this method. With this approach, the limited surface area is also enhanced to a good extent when Sc(OTf)₃ was utilized for catalyzing the reaction.¹⁸¹ The drawbacks of the COF activation process were also reported last year, where the collapse of imine-linked frameworks was reported during high-vacuum activation. The solution to this problem was provided by activating the fragile frameworks with N₂ or supercritical CO₂ flow activation using an ultrahigh-pressure reactor.¹⁸²

Fig. 17B shows the summarized mechanism, which presents insight into obtaining single crystals of 2D imine-linked COFs *via* the use of an aniline modulator in large excess (step a),

giving the desired product in 30–80 days. However, a polycrystalline material can be obtained in a few hours by using amorphous COF sheets as a precursor (step c), which can be produced within seconds from the monomers (step b).

5. Structural characterization

5.1 Fourier-transform infrared (FTIR) spectroscopy

This technique is a very basic and widely used technique to detect the functional groups present in any organic system. Almost all organic polymers, particularly COFs, have been characterized using this method due to its easy accessibility and user-friendly approach. This technique can be easily operated and analyzed to obtain subtle results about the functional groups present in materials. It is mostly used to help determine the completion of reactions for covalent organic frameworks, *i.e.*, in the case of Schiff-base imine condensation, the disappearance of the peaks corresponding to an amine and an aldehyde near 3500–3300 and 1690 cm⁻¹, respectively, indicates that the reaction is complete. An example for this is COF_{DAAQ-BTA-3DG}, which was synthesized *via* the combination of a ditopic amine unit and a tritopic aldehyde unit.¹⁸³ The fully formed product was witnessed by the appearance of a new C–N stretching peak (~1331 cm⁻¹) and the absence of the strong carbonyl stretching frequency near 1695 cm⁻¹ (Fig. 18). This framework was well characterized using other techniques for the confirmation of its synthesis (*vide infra*).




Fig. 18 (a) Structures of DAAQ and BTA monomers and COF_{DAAQ-BTA-3DG} and (b) their characterization using FT-IR spectroscopy. Reproduced with permission from ref. 183, Copyright the American Chemical Society (2015).






Fig. 19 Condensation reactions of boronic acids used to produce extended COF structures of (a) COF-1 and (c) COF-5. FTIR spectra highlighting the characteristic boron functional group bands of (b) COF-1 and (d) COF-5. Reproduced with permission from ref. 4, Copyright The American Association for the Advancement of Science (2005). Asterisks indicate spinning side-band peaks.

Moreover, as mentioned in Section 4.2, triazine-linked COFs can also be monitored using the FTIR technique by noting the disappearance of the C–N stretching frequency for nitriles and appearance of a peak corresponding to imines. The formation of CTF-1 was studied at different reaction times and various reaction temperatures. The intense carbonitrile peak at 2218 cm^{-1} disappeared, which clearly indicated the successful occurrence of the trimerization reaction. This was further supported by the emergence of a strong absorption peak at 1352 cm^{-1} , corresponding to the formation of a triazine ring.²⁰

The boron-containing frameworks have also been well characterized using FTIR spectroscopy. COF-1 and COF-5 (Fig. 19a and c) are linked by boroxine- and boronic ester-linkages, respectively. The FTIR peak at 711 cm^{-1} increased with respect to the (B_3O_3) boroxine ring (Fig. 19b), whereas the peak at 1026 cm^{-1} corresponds to the boronic ester ring B–C stretching frequency (Fig. 19d).⁴ Moreover, the B–O stretching frequencies in both cases can be seen at 1378 and 1342 cm^{-1} for COF-1 and at 1347 and 1332 cm^{-1} for COF-5.

Similarly, the synthesis of borazine-linked COFs was monitored by the appearance of the B–N stretching frequency near 1500 cm^{-1} and strong attenuation of the N–H and B–H frequencies, as shown for BLP-2(H) in Fig. 20.⁶⁰

Considering that COFs are known to form numerous linkages, the formation of these linkages through various reversible reactions has been monitored using FTIR analysis. One of these distinctive linkages is the azidoxy-linked framework, where the nitroso-functionalized monomers dimerize to form a *trans*-azidoxy bond. The POR-COF was constructed using a protected tetraakis(aryl hydroxylamine)porphyrin unit *via* room temperature




Fig. 20 Structure of BLP-2(H) together with its monomer and its characterization using FT-IR spectroscopy. Reproduced with permission from ref. 60, Copyright The Royal Society of Chemistry (2012).

synthesis (see Section 4.2).³⁵ According to the FT-IR spectrum, it was observed that with the propagation of dimer formation, the peaks at 1735 cm^{-1} for the C=O stretching and $2950\text{--}2850\text{ cm}^{-1}$






Fig. 21 FT-IR spectra of (a) azido-linked POR-COF and its monomer with its magnified spectrum (b), (c) TAPT-DAHQ COF and its monomers DAHQ·2HCl and TAPT-3CHO and (d) BP-COF-1 and its monomer BPA-1. Reproduced with permission from: (a and b) ref. 35, Copyright The Royal Society of Chemistry (2016); (c) ref. 164, Copyright John Wiley and Sons (2019) and (d) ref. 57, Copyright The American Association for the Advancement of Science (2020).

for the C-H stretching disappeared (Fig. 21a and b). Moreover, a new peak at around 1283 cm⁻¹ for N=N stretching was seen, representing completion of the reaction.

Likewise, the formation of benz-bis(oxazole) was monitored, where the FTIR spectra of the monomers and the product were simultaneously plotted and compared. In Fig. 21c, it can be seen that the peaks corresponding to C=N (1608 cm⁻¹), C=C (1583–1517 cm⁻¹) and C=O (1706 cm⁻¹) for the TAPT-3CHO monomer and that for C=N bending (1352 cm⁻¹), C=C (1555 cm⁻¹), C=O (1190 cm⁻¹) and phenolic -OH and NH₃Cl (~3200 cm⁻¹) for the DAHQ·2HCl monomer disappeared during the reaction, whereas peaks for C=N (1613 cm⁻¹) and C=O (1117 cm⁻¹) appear. This is attributed to the formation of a benzobisoxazole ring.¹⁶⁴

The synthesis of the highly connected BP-COF-1 using BP-1 was also studied using FTIR spectroscopy (Fig. 21d). The broad peak corresponding to free -OH groups and sharp P=O stretching in the monomer unit were attenuated completely after completion of the reaction.⁵⁷

Monitoring the formation of the β-ketoenamine linkage using FT-IR was reported in 2015, which compared the fabrication of the TpBDH COF from 1,3,5-triformylphloroglucinol (Tp) and pyromellitic-*N,N'*-bisaminoimide (BDH) units (Fig. 22).¹⁴⁹ The appearance of peaks at 1583 and 1273 cm⁻¹ correspond to the C=C and C-N stretching, respectively, which match that of




Fig. 22 FT-IR spectra of TpBDH COF with its monomers, Tp and BDH, and the reference compounds. Reproduced and adapted with permission from ref. 149, Copyright The Royal Society of Chemistry (2015).

the reference compound. Conversely, the monomer peaks for N-H and C=O stretching are fully attenuated in the product.

Monitoring thin film synthesis from bulk COFs. COF thin films have been proven to be emerging candidates for sensing applications. Their synthesis from the bulk powder demands






Fig. 23 FT-IR spectra of (a) DaTp COF and its monomers, Tp and Da and (b) DaTp-CON with *N*-hexylmaleimide. Reproduced with permission from ref. 110, Copyright John Wiley and Sons (2016).

the choice of solvents and other conditions, as mentioned in Section 4.1. FT-IR spectroscopy is employed as the first tool to validate the powder-to-film conversion. For example, the β -ketoamine-linked DaTp COF was exfoliated chemically to yield DaTp-CON sheets using *N*-hexylmaleimide at 160° for 24 h.¹¹⁰ Initially, the synthesis of DaTp COF was confirmed by comparing its stretching frequencies with the monomers, 2,6-diaminoanthracene (Da) and 2,4,6-triformylphloroglucinol (Tp) (Fig. 23a). The complete disappearance of the peaks at 3388, 3317 and 3206 cm^{-1} , corresponding to the NH_2 group in Da and that at 1627 cm^{-1} for the $-\text{CHO}$ group in Tp, and the characteristic $\text{C}=\text{C}$ and $\text{C}=\text{N}$ peaks at 1590 and 1270 cm^{-1} for the bulk COF confirmed the reaction progress. Afterwards, the exfoliated DaTp-CON showed some additional stretching frequency bands at 2937, 2857 and 1695 cm^{-1} , corresponding to the $\text{C}-\text{H}$ and $\text{C}=\text{O}$ groups from the alkyl chain and imide unit of *N*-hexylmaleimide (Fig. 23b).

Monitoring linkage transformation via post-synthetic modification. Post-synthetic modification of covalent organic frameworks is an emerging field, which has improved the applicability of these materials for numerous applications, one of which is sensing. Imine-linked COFs, *viz.* TPB-TP-COF (1) and 4PE-1P-COF (2), were subjected to post-synthetic modification *via* oxidation of the imine to amide linkages using mild reaction conditions of




Fig. 24 FT-IR spectra of imine-linked (a) TPB-TP COF (1) and (b) 4PE-1P-COF (2) in red with their oxidized products amide-linked (a) TPB-TP COF (1') and (b) 4PE-1P-COF (2') in blue. Reproduced with permission from ref. 184, Copyright the American Chemical Society (2016).

$\text{NaClO}_2/2\text{-methyl-2-butene}/1,4\text{-dioxane}$ with AcOH catalyst and left to stand at room temperature for 2 days.¹⁸⁴ The amide-linked frameworks were denoted as (1') and (2'), respectively. The appearance of FTIR stretching peaks at 1651 cm^{-1} (for 1') and 1654 cm^{-1} (for 2') with respect to the amide ($\text{C}=\text{O}$) group and disappearance of the $\text{C}=\text{N}$ imine stretching peaks at $\sim 1622 \text{ cm}^{-1}$ (for 1' and 2') support the linker transformation process (Fig. 24).

A similar study was done to strengthen the imine linked TTI-COF by post-synthetic modification to form the thiazole-linked TTT-COF at high thermal conditions (*vide* Section 4.2).¹⁷⁰ The disappearance of the peak at 1627 cm^{-1} corresponds to the $\text{C}=\text{N}$ imine stretching in TTI-COF and the emergence of a new $\text{C}=\text{N}$ stretching for the thiazole ring can be seen at 1609 cm^{-1} .

As exemplified above, this is the foremost and a very basic tool that can be used in different aspects for functional group analysis in a framework.

5.2 Solid-state magic angle spinning (ss-MAS) nuclear magnetic resonance (NMR) spectroscopy

Covalently-bonded organic polymers are usually insoluble in common solvents, which make their analysis difficult using the NMR technique given that it requires high solubility of the sample in deuterated solvents. Therefore, magic-angle spinning of the solid-state sample is done at an angle 54.74° with respect to the magnetic field during NMR analysis. This technique is used for monitoring the formation of COFs by comparing the NMR peaks of the polymer with their respective monomers. The first set of COFs was comprised of B, C, O and N-atoms, where ^{11}B , ^{13}C and ^{15}N NMR spectroscopy were utilized to corroborate the framework structure. Recently, ^{31}P and ^{29}Si NMR spectroscopy were exploited for their characterization with the incorporation of P and Si atoms in the linkages. ss-MAS NMR was first implemented for COF-1 and COF-5 to study the completion of their reaction. The ^{11}B -MAS NMR spectra for both COFs do not match that of the monomer benzenediboronic acid (BDDBA) and totally matches with their model compounds. This indicates the formation of the boroxine ring in COF-1 and boronic ester in COF-5 (Fig. 25a and b), respectively.⁴

^{13}C and ^{15}N CP-MAS NMR spectra were used to detect the formation of the triazine ring in a covalent triazine framework, *viz.* CTF-0. ^{13}C NMR indicated three major peaks at $\delta = 167$,






Fig. 25 ^{11}B magic-angle spinning NMR spectra of (top) COF, (middle) model compound and (bottom) BDBA for (a) COF-1 and (b) COF-5. Reproduced and adapted. ^{13}C CP-MAS solid-state NMR (c) and ^{15}N CP-MAS solid-state NMR (d) of CTF-0. (e) Overlay of the ^{11}B solid-state (ss) NMR spectra of BP-COF-1, a molecular boro-phosphonate model compound and BPA-1. (f) ^{31}P and ^{13}C NMR spectra of BP-COF-1. Me, methyl. Asterisks denote spinning sidebands. Reproduced with permission from: (a and b) ref. 4, Copyright The American Association for the Advancement of Science (2005); (c and d) ref. 19, Copyright the American Chemical Society (2013) and (e and f) ref. 57, Copyright The American Association for the Advancement of Science (2020).

136 and 114 ppm, which correspond to the three sp^2 carbons (the deshielded peak for the triazine ring and other two for the phenyl ring) and no peak was observed at $\delta = 110$ ppm, ruling out the possibility of any residual CN group from the monomer unit (Fig. 25c and d).¹⁹ In addition, the ^{15}N ssNMR spectrum helped to identify the triazine moiety, with a peak observed at -121 ppm for the triazine-ring N-atom.

Similarly, ^{11}B -MAS NMR spectroscopy was used to validate the complete utilization of monomers in the polycubane-based BP-COF-1 (Fig. 25e).⁵⁷ The single doublet of the framework near 0 ppm for the COF is consistent with the model compound, whereas this peak was not observed for sp^2 -hybridised boron in the monomer BPA-1. Moreover, ^{31}P and ^{13}C ssNMR spectroscopy were also used to confirm the reaction (Fig. 25f). The ^{31}P NMR spectrum of BP-COF-1 showed two peaks at 6.9 and 21.1 ppm,

indicating the presence of two distinct phosphorous atoms in the framework. The less intense peak at 21.1 ppm represents the methylphosphates present at the crystallite edges, whereas the more shielded NMR signal at 6.9 ppm represents the $\text{C}_{\text{Ar}}\text{-P}$ unit. Conversely, the ^{13}C CP-MAS NMR spectrum displays peaks in the aromatic region between 151.6 and 125.8 ppm, which correspond to the aromatic carbon bonded to the boron and phosphorus atoms, respectively.

Silicon-containing frameworks have been synthesized to incorporate ionic nature in COFs (see Section 4.2). Therefore, for their characterization, ^{29}Si CP-MAS ssNMR spectroscopy has been exploited. The synthesis of an anionic SiCOF was validated using ^{29}Si NMR spectroscopy, which showed a single peak at -143 ppm, corresponding to the hexacoordinated Si-atom in the framework.¹⁶⁵ However, no peak for the TMOS monomer at






Fig. 26 X-ray analysis of (a) COF-1 and (b) COF-5 with the observed pattern in black, the refined profile in red, and the difference plot in blue (observed minus refined profiles). The bottom trace is the calculated PXRD pattern from *Cerius*.² Experimental (black) and refined (red) PXRD patterns of (c) aminal-COF-1 and (d) aminal-COF-2. Difference plot between the experimental and refined PXRD patterns (grey) and simulated PXRD patterns for eclipsed (blue) and staggered (pink) structures. Inset is the perspective and top views of the structural representation of both COFs in eclipsed stacking. Reproduced with permission from: (a and b) ref. 4, Copyright The American Association for the Advancement of Science (2005) and (c and d) ref. 38, Copyright the American Chemical Society (2019).

–79 ppm was seen. Considering that the COF was anionic and stabilized by Li^+ and Na^+ ions, the rarely utilized ^7Li and ^{23}Na -MAS NMR spectra were recorded, showing peaks at –1 ppm for SiCOF-Li and –24 ppm for SiCOF-Na, respectively. This is a unique example of the use of Na and Li NMR spectroscopy.

5.3 X-ray diffraction (XRD)

As mentioned above, COFs are synthesized in the form of small crystallites/powders, highly ordered thin films and small single crystals. Therefore, X-ray diffraction is an extensively exploited analytical technique used to elucidate the crystallographic structure of these materials. The powders and films are characterized using PXRD (small/wide angle X-ray diffraction) supported by theoretically simulated peaks, whereas single crystals with good mosaic structures are characterized using the SCXRD technique.

5.3.1 Powder X-ray diffraction (PXRD) supported by theoretical simulations. Generally, the synthetic techniques applied to produce COFs yield fine powders, which are diffracted using the PXRD technique. The intense and sharp diffraction peaks fulfilling Bragg's law indicate high order of crystallinity in the

frameworks. In addition, a simulated study is conducted on the framework using different basis sets and hybrid functionals, which generate the simulated pattern and structure of the COFs. Various important parameters of the porous organic framework such as atom-coordinates, unit cell parameters, space group, interlayer distance and the type of stacking for 2D COFs, degree of interpenetration in 3D COFs, framework packing, and pore shape and size can be determined using this technique. Moreover, this method also indicates the homogeneity of the sample, which can also be confirmed by microscopic techniques (vide Section 5.4).

Structure determination. The first highly crystalline COFs were the boron-containing COF-1 and COF-5, which were characterized by PXRD, giving sharp peaks corresponding to different $(h\ k\ l)$ planes, as shown in Fig. 26a and b, respectively.⁴ To confirm these planes, the extended structures of both frameworks were modelled and their simulated powder patterns were calculated. The simulated patterns were found to be well fitted with the experimental patterns, indicating the formation of staggered AB stacked and eclipsed AA stacked frameworks for COF-1 and COF-5 with the hexagonal lattice



space groups of $P6_3/mmc$ and $P6/mmm$, respectively. The honeycomb framework sets in the **gra** and **bnn** network with and interlayer spacing of 3.328 and 3.460 Å for COF-1 and COF-5, respectively.

Aminal-linked COFs, *viz.* aminal-1 and aminal-2, diffract to give very sharp and intense peaks, corresponding to the (100), (010) and (110) facets, which match well with the simulated patterns with fairly low fitting parameters (Fig. 26c and d),




Fig. 27 Structural analysis of ANCOF: (left) experimental PXRD pattern (blue), simulated PXRD pattern (cyan), and its fit by Pawley refinement (red) with a minimum difference (black line). (right) Structures of ANCOF obtained from the Rietveld refinement; AB stacking is shown in cyan and pink color. Reproduced with permission from ref. 154, Copyright the American Chemical Society (2020).

respectively.³⁸ Both frameworks show eclipsed (AA) stacking in the triclinic $P1$ space group with the rarely fabricated 2D **cp1** topology (*vide supra*, Section 2.1). It was observed that the two COFs possess piperazine units, which exist in the chair-form, resulting in an increase in the interlayer distance (beyond 6 Å) and reduction in aromatic π - π interactions.

Similarly, a nitrogen-rich azine-linked COF with triazine cores, namely ANCOF, showed very sharp and intense diffraction peaks in small/wide angle PXRD, which are consistent with the simulated pattern calculated using the Pawley and Rietveld refinement methods with good profile-fitting values.¹⁵⁴ The framework was set in the triclinic $P\bar{1}$ space group with an AB-type interpenetrated arrangement, as shown in Fig. 27. The interlayer separation was calculated to be 4.5 Å.

The two imine-linked COFs, 2,3-DhaTta and 2,3-DhaTab, were found to have the AA stacked pattern (Fig. 28b and c), respectively.⁷⁹ As mentioned in Section 3.2.1, the strong π - π interactions of 2,3-DhaTta COF due to its planar building units were clearly depicted from its high intensity (100)/(001) peak ratio of 46.21 in comparison to that of the 2,3-DhaTab COF, which is 5.01 (Fig. 28a and d), respectively. The simulated results showed the greater π - π stacking energy of -1634.2 kJ mol⁻¹ for the former COF in comparison to that of the latter of -1578.6 kJ mol⁻¹. The deviation from planarity of the phenyl-core 2,3-DhaTab COF possibly indicates the improper growth of the material along the c-axis, which disrupts the proper stacking and yields bent crystallites with a lower BET surface area.




Fig. 28 Mechanism for the formation of ribbon (a) and hollow sphere (d) for CPP 2,3-DhaTta, and 2,3-DhaTab, respectively. PXRD patterns of as-synthesized (b) 2,3-DhaTta and (c) 2,3-DhaTab (black) compared with the eclipsed (red) and staggered (blue); eclipsed (left) and staggered (right) stacking models shown in the inset. Reproduced and adapted with permission from ref. 79, Copyright John Wiley and Sons (2016).



Optimization of synthetic conditions. It was discussed in the previous sections (particularly, Section 4) that optimization of the reaction conditions for the synthesis of COFs with prolonged periodicity, in-built thermal, chemical and water stability and functionalization is a very tedious task. A large number of factors must be thoroughly considered during their synthesis, which makes the process laborious and time-consuming. However, the utilization of appropriate characterization techniques to monitor the reaction progress under different conditions must be considered to save time and gain a better understanding. This case was observed when the TFPC-NDA COF was synthesized under two different reaction conditions (Fig. 29a).²⁴ The use of an acid catalyst to activate the aldehydic functional group under

solvothermal conditions has been done for long time, but in this rarely seen case, the COF was synthesized without the use of the AcOH catalyst. The PXRD pattern showed intense peaks when the acid was not used as a catalyst during the solvothermal synthesis, whereas very broad peaks were observed when the synthesis was conducted with acid, indicating the amorphous nature of the COF. Furthermore, the COF was utilized for VOC and TNP sensing (see Section 6.2) and its stability in each application was validated using the PXRD technique, as discussed further below.

Additionally, a few *in situ* PXRD experiments have been performed to understand the formation of the framework. This '*in situ*' approach is beneficial to check the reaction requirements to obtain a particular framework from amorphous organic




Fig. 29 (a) PXRD patterns of TFPC-NDACOF prepared without an acid and its analogue prepared in the presence of an acid. (b) WAX patterns of TFPC-NDACOF before and after immersion in 1 M NaOH and 1 M HCl for 7 days (inset: 2D WAX images). (c and d) WAX patterns showing that the crystallinity of TFPC-NDACOF was maintained after the absorption of different electron-withdrawing and electron-donating aromatic VOCs, respectively. Variable-temperature powder diffraction patterns of TFPC-NDA COF upon (e) heating from -100 °C to 350 °C and (f) cooling to 25 °C. Reproduced with permission from ref. 24, Copyright The Royal Society of Chemistry (2018).



polymers. For instance, during the study of the mechanochemical synthesis of four COFs, *i.e.*, COF-LZU1, TbBd-COF, IISERP-COF4 and N-COF (*vide supra*, Section 4.3), the *in situ* time-resolved synchrotron PXRD studies revealed the appearance of the first peak corresponding to the 100 plane in 3, 10, 10 and 4 min, respectively.¹⁸¹ Moreover, during the course of the reaction, the peaks intensified and reached the highest value after a certain time. At this time, the peak intensity matched that from the *ex situ* PXRD measurements. Additionally, the *ex situ* PXRD data of the COF-LZU1 intermediate, which crystallizes in the triclinic $P\bar{1}$ space group, revealed that there is one triple imine unit and one-half dioxane molecule in the asymmetric unit.

Stability confirmation. For their use in various applications, COFs must be stable in different conditions. Particularly, in the case of sensing, their stability in the presence of different analytes is necessary to avoid collapse of the framework. A large number of systems can act as analytes, such as nitro-rich explosives, metal ions and anions, acids, bases, small molecules such as ammonia, and various organic solvents. Besides, the stability of the framework at different temperatures can also be investigated using the variable-temperature PXRD (VT-PXRD) technique.

Several examples of this have been reported in the literature, two of which are the β -ketoamine-linked TpPa-1 and TpPa-2 COFs. Their exceptionally high thermal, water and chemical stability were confirmed by the PXRD technique, as shown in Fig. 30.⁶⁷ Other analytic methods such as FESEM, BET and TGA analysis help in getting more detailed information regarding the retention of morphology, high surface areas before and after treatment with different environments and the decomposition temperature, respectively (*vide infra*).

Another example, continuing from the previous subsection, is TFPC-NDA COF, which is a semi-flexible COF synthesized from 1,3,5-tri(4-formylphenoxy)cyanurate (TFPC) and naphthalene diamine (NDA). The COF was highly stable in various acid/basic conditions (1 M HCl and 1 M NaOH solutions for 7 days) based on its wide angle PXRD patterns (Fig. 29b).²⁴ The 2D WAX image showed the first diffraction peak from the WAX pattern. This highly stable COF was exploited for sensing different analytes, in which its stability was checked. The intact WAX patterns of the COF in different electron-poor and electron-rich (Fig. 29c and d) aromatic analytes confirmed its chemical stability, respectively. In addition, the thermal stability of the COF in a broad temperature range of 350 °C to −100 °C was also verified using VTPXRD (Fig. 29e), where ramping up or down the temperature from both extremes did not disrupt its framework integrity (Fig. 29f).

5.3.2 Single crystal X-ray diffraction (SCXRD). This is a very useful technique for structure determination in inorganic, organic and organometallic chemistry. It has been widely exploited for the structure determination of various discrete, inorganic polymeric compounds including metal-organic frameworks,¹⁸⁵ but very less explored for crystalline organic polymers. The building mechanism of 2D and 3D COFs is highly complex and requires attentive efforts to obtain a suitable single crystal for this study. However, some success has been achieved in the case of three-dimensional

frameworks, as mentioned in Section 3.2.2. In this section, we briefly discuss the use of the SCXRD technique for three examples.

In 2013, the first examples of single-crystalline azidoxy-linked frameworks were reported, *viz.* NPN-1, NPN-2 and NPN-3, by Beaudoin *et al.* The crystals were grown in different solvents, yielding a good mosaic with a size of ~ 10 nm.⁸⁸ Both NPN-1 and NPN-2 crystallized in the tetragonal space group $P4b2$, knitting four-fold-interpenetration along *c*-axis, whereas NPN-3 crystallized in the $P4_2/n$ with six-fold-entanglement. All three frameworks exhibited the **dia** topology, in which the two T_4 -nodes are at a distance of 12.26, 12.76 and 15.39 Å from each other for the methane, silane and adamantane-core tetranitroso unit. This is ascribed to the long C-Si bond in NPN-2 compared to the C-C bond in NPN-1. Moreover, the adamantane-core is bigger, and thus the framework could afford six-fold interpenetration.

As mentioned earlier, the first imine-linked COF, COF-300, was analyzed by the PXRD technique and its simulated pattern to obtain its structural information in 2009. It was determined that the framework was crystallized in the tetragonal $I4_1/a$ space group with the **dia-c5**, topology which does not obey the formula for the degree of interpenetration, *i.e.*, $N = 2a/c$, where '*a*' and '*c*' are the cell parameters for the tetragonal lattice. Recently, it was found from the SCXRD data of the 3D COF-300 that the framework is seven-fold interpenetrated (**dia-c7**) with unit cell parameters of $a = b = 28.280$ Å and $c = 10.079$ Å, which is in accordance with the formula (Fig. 31).⁶ The possible explanation for this is the aging effect, which increased the degree of interpenetration during its synthesis (*vide supra*, Section 3.2.2).

Besides COF-300, single crystals of the imine-linked 3D COF-303, LZU-79 and LZU-111 were also obtained and diffracted. It must be noted that the symmetry, topological view and degree of interpenetration in COF-300 and COF-303 are identical with a slight difference in imine connectivity, which could not be detectable using the PXRD technique. Therefore, the use of the SCXRD method is essential here.

The COF LZU-79 was reticulated from COF-300, in which the terephthaldehyde unit was replaced by the longer 4,7-bis(4-formylbenzyl)-1*H*-benzimidazole (BFBZ). LZU-79 crystallizes in the $P4_2/n$ space group with a high degree of entanglement (**dia-c10**). Moreover, large-sized crystals of a new chiral imine-linked LZU-111 COF with a size of ~ 60 μm were grown using aniline as the modulator. This chiral COF crystallizes in the $P6_5$ space group and exhibits a different topology, *i.e.*, **lon-b-c3** (*vide supra*, Section 2.1)

For a single crystal to be successfully diffracted, the required size is ~ 0.5 mm or larger. However, due to very little success in obtaining appropriately sized single-crystal COFs, the XRD technique has not been efficiently utilized in this area. Accordingly, the rotation electron diffraction method is employed when the single crystal size varies from nano- to micrometers. The RED technique is further discussed in Section 5.4.2.

5.4 Microscopic techniques

A very important and widely used characterization technique for the analysis of COFs is electron microscopy, which uses a negatively charged electron beam in place of a light source.






Fig. 30 PXRD patterns of TpPa-1 (left) and TpPa-2 (right) in boiling water, 9 N HCl and 9 N NaOH, showing their stability. Reproduced with permission from ref. 67. Copyright the American Chemical Society (2012).

This technique gives detailed information about the properties of materials such as surface morphology, phase and bulk purity, reproducibility, and elemental mapping.

5.4.1 Field emission scanning electron microscopy (FESEM).

This is a sophisticated microscopic technique, which aids in discovering the morphologies of COFs and analyzing the elements present in them. It also helps in determining the reproducibility and phase purity of samples. Almost all porous-organic frameworks are scanned by the FESEM technique and have been reported to possess distinct and eye-catching morphologies. The various surface structures (shown in Fig. 32) obtained for porous organic frameworks include spherical (a),¹⁸⁶ hollow tubes (b),¹⁸⁷

rods (c),¹⁴¹ flower like (d),⁶⁸ fibre like (e),¹⁸⁸ thin sheets/films (f),¹⁸⁸ and flakes. Unique morphologies showing trepan-like (g)¹³⁸ (known as sea cucumber) and bouquet-like (h)¹⁸⁹ structures have also been reported recently.

The homogeneity of the bulk sample and reaction completion can be confirmed using the FESEM technique, as shown in Fig. 32i.⁵⁷ The first synthesized boroxine and boronic ester-linked COFs, COF-1 and COF-5, showed an aggregated platelet-like morphology (Fig. 33).⁴ The framework can have different particle sizes, varying from a few microns (μm) to nanometers (nm). Highly magnified electron images can be obtained using the TEM technique, as discussed in Section 5.4.2.






Fig. 31 Optical microscopy images of single-crystalline COFs obtained in the presence of aniline. Reproduced with permission from ref. 6, Copyright The American Association for the Advancement of Science (2018).




Fig. 32 FESEM images showing different surface morphologies of COFs. Reproduced with permission from: (a) ref. 186, Copyright the American Chemical Society (2019); (b) ref. 187, Copyright John Wiley and Sons (2018); (c) ref. 141, Copyright the American Chemical Society (2019); (d) ref. 68, Copyright the American Chemical Society (2019); (e and f) ref. 188, Copyright Elsevier (2019). (g) ref. 138, Copyright The Royal Society of Chemistry (2021); (h) ref. 189, Copyright the American Chemical Society (2017) and (i) ref. 57, Copyright The American Association for the Advancement of Science (2020).

The stability of the framework is another factor that can be confirmed by checking the morphological stability of the material. In 2012, Banerjee and co-workers tested the chemical and water stability of two β -ketoenamine-linked frameworks, TpPa-1 and TpPa-2, using the FESEM method.⁶⁷ As can be seen in the inset of Fig. 30 (left), there was no change in the morphology of TpPa-1. Both frameworks possess flower-like surface structures, which are possibly formed by aggregated gobs of petals. For TpPa-1, each petal is 1–3 μm long, 70–150 nm wide and 30–40 nm thick in size.




Fig. 33 FESEM images of bulk COF-1 (a) and COF-5 (b). Reproduced with permission from ref. 4, Copyright The American Association for the Advancement of Science (2005).

The petals are thicker and wider for TpPa-2. The electron images confirmed the stability of the COF in boiling water, 9 N HCl and 9N NaOH for 7 days.

COFs exhibit sharp FESEM images, showing very interesting surface morphologies. Recently, this technique has been used to gain insight into the formation of different micro and nanostructures by conducting COF synthesis time-dependent studies. In 2019, the self-assembly of the hollow shuttle-shaped TPE-TAP-COF was studied at different intervals.¹⁹⁰ The fully grown shuttle-like morphology of the COF was synthesized in 5 days; therefore, the generation of its microstructure was gradually studied after 1, 2, 3, 4 and 5 day intervals (Fig. 34a). It can be observed from the FESEM images that after 1 day, a small nanospherical assembly was present, which further agglomerated into nanorods on 2 d. These rods were about 100 nm in diameter and a few microns long. After the third day, the nanorods roughly assembled to yield a dense microcapsule. Further on days 4 and 5, the surface of the microcapsule became smoother and hollow cavities began to form inside the shuttle, which was confirmed by the TEM images (Fig. 34b). A pictorial representation of the self-assembly is depicted in Fig. 34c.

Moreover, the FESEM images of various microcrystals of NPN-1, NPN-2, NPN-3, COF-300, COF-303, LZU-59 and LZU-111 were measured, which revealed the formation of single-crystalline COFs.^{6,88}

Energy-dispersive X-ray spectroscopy (known as EDX/EDS/EDXS/XEDS) is another analytical technique that accompanies electron microscopy, which is widely used for elemental analysis of the sample. To verify the elements present in the covalently-bonded organic porous framework, chemical characterization is performed, which mostly gives the electronic image with the % of elements present in it and their mapping. An example of this is COF-SO₃H and [NH₄]⁺[COF-SO₃⁻], where their SEM images and EDX mapping are shown in Fig. 34d.¹⁹¹

A few years ago, the effect of different synthetic methods on the surface morphology of the framework was studied. Banerjee and co-workers reported three distinct morphologies for the TpPa-1 COF under three different synthetic conditions.^{67,83,84} The dark-red COF possessed a flower-like, graphene-sheet like and ball-like surface when synthesized under solvothermal, mechanochemical and microwave irradiation conditions (Fig. 35). The flower-shaped morphology resulted from the aggregation of the sheet-like petals, which were 70–150 nm wide and 30–40 nm thick. The time and conditions required to form this distinct






Fig. 34 (a) FESEM and (b) TEM images of TPE-TAP-COF recorded at different intervals. (c) Mechanism for the formation of COF hollow microspheres. (d) FESEM images (top) and EDS mapping (bottom) results of COF-SO₃H (left) and [NH₄]⁺[COF-SO₃⁻] (right). Reproduced with permission from: (a–c) ref. 190, Copyright The Royal Society of Chemistry (2019) and (d) ref. 191, Copyright 2019 Creative Commons CC by license.




Fig. 35 Pictorial representation of TpPa-1 COF synthesized using triformylphloroglucinol (Tp) and phenylenediamine (Pa), acquiring three different morphologies under different reaction conditions. Reproduced and adapted from ref. 67, Copyright the American Chemical Society (2012); ref. 83, Copyright the American Chemical Society (2013) and ref. 84, Copyright The Royal Society of Chemistry (2015).

morphology were provided *via* the thermodynamically supported solvothermal method. However, when the framework was constructed by constant grinding, the 2D sheets tended to delaminate by breaking the supramolecular stacking forces. This can be seen when graphene-like layered sheets were formed

instead of a flower. For the ball-like morphology with a rough surface, the diameter of each ball was ~ 30 nm, which is consistent with the thickness of the flower petals formed during the solvothermal synthesis.

Similarly, Shinde *et al.* observed that two distinct surface patterns in TpBpy COF existed when the Tp and Bpy monomers were subjected to (a) solvothermal (120 °C, 72 h) and (b) mechanochemical (30 Hz, 90 min) conditions, respectively.¹⁹² In the high temperature vacuum environment, the small COF crystallites (100–300 nm wide) agglomerated to form fine thread-like shapes, which interweave. Conversely, the framework obtained *via* the mechanochemical approach formed sheets of smaller dimensions due to exfoliation by constant grinding.

5.4.2 Transmission electron microscopy (TEM). This is a highly exploited electron microscopic technique, which helps in determining the morphology of COFs on the nanometer scale, very close to the atomic level. The main difference between the TEM and FESEM techniques is that the latter scans image by detecting the electrons reflected from the sample surface, whereas the former utilizes the transmitted electrons, which pass through the sample to give a highly magnified image. Moreover, high-resolution TEM images (below 20 nm scale) can be obtained from this technique, which give very detailed and highly magnified surface structures. For example, various COFs with HRTEM images of different morphologies, nanospheres (a),¹⁸⁶ hollow tubes (b and c),¹⁹³ nanofilm (d),¹⁸⁸ trepan like (e)¹³⁸ and bouquet like (f)¹⁸⁹ are shown in Fig. 36.






Fig. 36 TEM images showing different surface morphologies. Reproduced with permission from: (a) ref. 186, Copyright the American Chemical Society (2019); (b) ref. 187, Copyright John Wiley and Sons (2018); (c) ref. 193, Copyright The Royal Society of Chemistry (2015); (d) ref. 188, Copyright Elsevier (2019); (e) ref. 138, Copyright The Royal Society of Chemistry (2021) and (f) ref. 189, Copyright the American Chemical Society (2017).

A distinctive surface morphology fabricated from a flower-like surface *via* the self-assembly of nanosheets was reported by Das *et al.* in 2019. The bis(imidazole)-linked TBICOF, which was solvothermally synthesized (*vide supra*), sets in a uniformly ordered porous hexagonal arrangement, which could be observed by HRTEM (Fig. 37).⁶⁸ During the course of the 3 day reaction, the nanosheets combine, forming a ring-like assembly, and set in a microfloral morphology with an average diameter of 150–200 nm and height of 12–15 nm. STEM (scanning transmission electron microscopy) images of the microflower surface were also taken, in which the electron beam is focussed at a wider angle and scans through the sample.

Previously, it was mentioned that acquiring crystallinity in a framework endowed with stability and functionalization is very complex. However, this technique helps to monitor the




Fig. 38 HR-TEM images of Fe_3O_4 @polyimine (a) and Fe_3O_4 @COF(TpBD) (b). Reproduced with permission from ref. 194, Copyright John Wiley and Sons (2016).

amorphous and crystalline nature by scanning in-depth electron images of the framework. Wang and co-workers reported an example of this, in which the amorphous-to-crystalline transformation of an Fe_3O_4 -templated polyimine COF (a) into Fe_3O_4 @COF(TpBD) (b) was carried out solvothermally. The HRTEM images were taken to record the reorganization of the disordered framework into well-defined and ordered microspheres (Fig. 38).¹⁹⁴

The growth of microstructures from nanoparticles can be well studied by TEM and HRTEM images. An example of this is shown in Section 5.4.1, Fig. 34b. Recently, the formation of hollow tubes of the TPT-DAHQ COF with sponge-like shells, which occurred *via* aggregation, self-assembly and Ostwald ripening of the COF, was examined (Fig. 39).¹⁶⁴ The solvothermally synthesized COF (see Section 4.2) investigated *via* a time-dependent study, where the reaction was quenched after 12, 24 and 48 h to obtain the high-resolution image. It was observed that after 12 h, very small ribbon-like nanocrystallites of about 40–50 nm width aggregated, which correspond to the π - π stacked 2D COF sheets. Maintaining high-temperature conditions for 24 h, the minute planar crystallites assemble to form dense tubules whose walls were formed by the aggregation of the ribbon-like nanocrystallites. After 48 h, an exceptional




Fig. 37 (a) FESEM image focusing on the microflower areas in TBICOF; (b) STEM image of TBICOF; (c) TEM image of TBICOF depicting microflowers; and (d–f) HRTEM images of TBICOF. Reproduced with permission from ref. 68, Copyright the American Chemical Society (2019).






Fig. 39 (a) Expected mechanism for the formation of the hollow microtubular TPT-DAHQ COF having sponge-like shells. (b) TEM images of the hollow microtubular TPT-DAHQ COF having sponge-like shells, measured after reaction times of 12, 24, and 48 h. Reproduced with permission from ref. 164, Copyright John Wiley and Sons (2019).

phenomenon of the Ostwald ripening process occurred, by which the crystallites present inside the hollow tubules migrated towards the outer surface to reduce their surface energy. This destroyed the tubules, and hollow microtubes were formed with rough crystallites located on their surface. At the end of the reaction after 72 h, the ribbon-like crystallites present on the outer surface of the microtubes displays a smooth sponge-like surface. The resulting tubules had an average length of 7.4 μm and average diameter of 1 μm . The average values for the outer and inner diameters of the tubules were 0.90 and 0.53 μm , respectively.

In addition to images, the bulk phase purity of powdered frameworks has also been studied using selected area electron diffraction (SAED). This technique is beneficial to observe the diffraction spots, and thus gives information about the order of the framework. Moreover, using fast Fourier transformation (FFT), the d-spacing between the two planes can be closely measured. Consequently, the high and low-angle grain boundaries can be identified, providing that the framework has exceptionally high crystallinity, stability and rigidity. This type of study was performed by Lotsch and co-workers on TTT-COF and TTI-COF.¹⁷⁰ Besides, phenomena such as twinning, or some framework defects can also be detected.

It is well known that TEM usually produces flat 2D images, which lack some features compared to FESEM, given that a 3D image of the sample can be obtained. However, a crucial study using 3D diffraction tomography (3D-EDT) can also be conducted using the TEM technique (Fig. 40). 3D-EDT is basically an extension of the regular TEM, in which the sample is rotated or tilted at different angles around its center to obtain a three-dimensional image. An example of this was reported in 2016 by Yaghi and co-workers using a rare woven COF, COF-505.¹⁹⁵

The FESEM and TEM images showed that spheres with a diameter of 2 μm were formed through the agglomeration of small crystallites with a size of ~ 200 nm. The 3D-EDT data was obtained by tilting the sample and the electron beam in the range of -41.3° to $+69.1^\circ$ with a beam-tilt step of 0.2° . According to the acquired tomography data, the C-centred orthorhombic




Fig. 40 Morphology and electron microscopy studies of COF-505. (a) Crystallites aggregated on a crystalline sphere observed by SEM. (b) TEM image of a single sub-mm crystal used for 3D-EDT. (c) 2D projection of the reconstructed reciprocal lattice of COF-505 obtained at 298 K from a set of 3D-EDT data. (d) HRTEM image of COF-505 taken with the [1–10] incidence. (e) 2D projected potential map obtained by imposing pgg plane group symmetry. (f) Reconstructed 3D electrostatic potential map (threshold, 0.8). Reproduced with permission from ref. 195, Copyright The American Association for the Advancement of Science (2016).

lattice was constructed with cell parameters of $a = 18.9 \text{ \AA}$, $b = 21.3 \text{ \AA}$, $c = 30.8 \text{ \AA}$, and $V = 12399 \text{ \AA}^3$.

A rarely used technique for the structure determination of COFs using the TEM analytical method is 3D rotation electron diffraction (RED). In this technique, the fairly small-sized single-crystalline imine-linked COF-320 was evenly spread on a carbon-coated Cu grid *via* the drop-casting method. Thereafter, the 3D-RED data was collected in SAED mode at 298 K with the diameter of the chosen aperture greater than the crystal size. The ED images were taken by tilting the crystal base in the range of -35.00° to $+25.10^\circ$ with a beam-tilt step of 0.4° . The data was processed and detailed structural information was obtained, indicating the tetragonal $I42d$ space group with the **dia-c9** topology (Fig. 41a).⁸⁹ The image of the reconstructed reciprocal lattice from 3D-RED data is shown in Fig. 41b-d.

5.4.3 Atomic force microscopy (AFM). Besides the aforementioned microscopic methods, AFM is used to obtain a more precise three-dimensional profile of the sample to clearly view its surface roughness and height. AFM scans the image of a micrometer square area with a depth of field of 10–20 μm . COFs exist in the form of 2D-layers stacked on each other or in the interpenetrated 3D form (*vide supra*). Therefore, the height-profile image is essential to check the number of layers stacked. One example is the hcc-COF thin film, where the AFM image showed the stacking of nine layers with a height of ~ 3.8 nm (Fig. 42a).¹⁶³ Likewise, the AFM height-profile image revealed the rough surface of the COF_{DAAQ-BTA-3DG} composite in comparison to graphene, with the average size 50–100 nm (Fig. 42b and c), respectively.¹⁸³ Bare graphene is nearly flat and featureless when observed *via* microscopy. Fig. 42d depicts the scratched surface of the COF_{DAAQ-BTA-3DG} film, showing a thickness of ~ 185 nm. Fig. 42e and f show the AFM images and the height profiles






Fig. 41 Morphology and electron diffraction of COF-320. (a) SEM image of the aggregation of crystallites. (b) 3D reciprocal lattice of COF-320 reconstructed from the RED data collected from a crystal of $1.0 \times 0.5 \times 0.2 \mu\text{m}^3$ (inset). (c) $(h0l)$ and (d) $(hk0)$ slices cut from the reconstructed reciprocal lattice. Reproduced with permission from ref. 89, Copyright the American Chemical Society (2013).

of two covalent organic nanosheets, namely TpBDH and TfpBDH CONs, which were efficiently used as turn-on sensors (*vide infra*).¹⁴⁹

5.5 X-ray photoelectron spectroscopy (XPS)

This technique is employed to determine the composition of elements, which helps in characterizing the bulk structure of materials. COFs are composed of light elements, such as B, C, N, O, S, P and Si, and thus the peaks in an XPS spectrum, which gives a plot of the number of electrons vs binding energy, directly indicate the identity and amount of an element present in the framework. The XPS peaks also display the subshell (1s, 2s, 2p, 3s, etc.) from which the electron is ejected when the X-ray beam falls on it. In addition, the bonding between the two monomer units can also be determined using this spectroscopic technique. A few N-rich frameworks characterized by this method are discussed below.

Triazine-linked frameworks. The CTF-1 framework contains only C and N-atoms, for which the XPS spectra show two peaks each for C1s and N1s nuclei (Fig. 43).¹²⁰ The C1s element exhibits two peaks having binding energy values of 284.6 eV and 286.2 eV, which are assigned to aromatic sp^2 -carbon and the triazine-ring carbon, respectively. Conversely, the N1s XPS spectrum displays two signals with binding energy values of 398.8 eV and 400.2 eV, respectively, where the former is assigned to the nitrogen of the triazine core and the latter to the N-atom from the nitrile moiety that remained in the uncondensed form. Relative to CTF-1, the CTF-1-600 framework shows a similar XPS spectrum with a small contribution




Fig. 42 AFM image and height profile of (a) hcc-COF film (scale bar = 1 μm), (b and c) $\text{COF}_{\text{DAAQ-BTA-3DG}}$ composite and the corresponding section profile, (d) scratched $\text{COF}_{\text{DAAQ-BTA-3DG}}$ composite and the corresponding section profile, (e) TfpBDH-CONs and (f) TpBDH-CONs with the corresponding height profiles below (the height profiles filled in red and green colour were measured along the corresponding tracks inside the circle shown in the AFM images). Reproduced and adapted with permission from: (a) ref. 163, Copyright 2019 reprinted under the terms of Creative Commons Attribution 4.0 International license; (b–d) ref. 183, Copyright the American Chemical Society (2015) and (e and f) ref. 149, Copyright The Royal Society of Chemistry (2015).

due to C1s at (288.0 eV) of low intensity. This peak corresponds to the carbon-atom from the $-\text{COO}$ group, which is observed due to the partial oxidation and dissociation of the framework at high temperature. Moreover, the intensity of the XPS peaks in the N1s spectrum for CTF-1-600 was observed to be high for the nitrile N-atom from the cyano group.

By introducing electron-withdrawing fluorine atoms in the CTF-1 moiety, the degree of polymerization was reduced. This was confirmed by the XPS spectra of FCTF-1 (fluorinated CTF-1), where the peak intensity of the uncondensed N-atom at 400.5 eV increased significantly in comparison to that at 398.8 eV, which was originally assigned to the triazine nitrogen. Furthermore, the chemical nature of the C and F atoms was also explained using this technique given that the C1s spectrum can be deconvoluted into four peaks as follows: two usual peaks at 284.6 eV (for aromatic sp^2 -C) and 286.2 eV (triazine-ring carbon) and two arising from F-substitution at 287.8 eV






Fig. 43 (a) Structures of CTF-1 and FCTF-1. (b–d) C1s, N1s and F1s XPS spectra of triazine-linked COFs, CTF-1, CTF-1-600 and FCTF-1, respectively. Reproduced with permission from ref. 120, Copyright The Royal Society of Chemistry (2013).

(semi-ionic C–F bond) and 289.1 eV (covalent C–F bond). In the F1s spectrum, two signals assigned to partial-ionic (687.8 eV) and covalent C–F bonds (689.2 eV) were observed. In the N1s XPS spectrum, FCTF-1 COF displays more striking peaks of nitrile in comparison to CTF-1, which clearly indicates that the fluorine-substituted precursor reduces the degree of polymerization in the framework.

Later, in 2015, the conversion of the triazine-linked framework from a lower *m*-CTF net to higher dimensional PTF net was reported, and the transformation was witnessed by the deconvoluted XPS N1s spectral peaks.¹²¹ The *m*-CTF net displays the two basic C1s peaks and one N1s peak at ~284.4, ~286.3 and ~398 eV, respectively, where the latter peak suggests the existence of only one type of pyridyl nitrogen in the triazine ring. Conversely, the 3D porous triazine framework, namely PTF, that was synthesized at an elevated temperature showed two extra peaks in the N1s XPS spectrum, which were assigned to pyrrolic nitrogen at ~399.5 eV and quaternary nitrogen at ~400.8 eV.

Imine-linked frameworks. In the XPS spectra of frameworks containing imine linkages, two major peaks can be observed, one near 285 eV, corresponding to the imine-carbon in the C1s spectrum, and the other for its N-atom near 398 eV in the N1s spectrum. This method supports the formation of imine-bonded frameworks using the Schiff base condensation reaction. However, sometimes an additional peak for the unreacted amine monomer can be seen in the N1s XPS spectrum. An example of this is SCOF-LZU-1, which was synthesized *via* the interfacial method using a combination of a trialdehyde and diamine.

The XPS spectra of SCOF-LZU-1 depict the standard peaks for the carbon and nitrogen atoms of the imine bond in the C1s

and N1s spectra at 285.1 and 398.6 eV, respectively (Fig. 44a). In addition, an extra peak in both the spectra was observed at 284.4 eV for the SCOF backbone and HOPG substrate and at 399.7 eV for the nitrogen from the unreacted diamine unit.¹⁰¹

Hydrazone-linked frameworks. The highly luminescent Bth-Dma COF contains free O- and N-donor atoms, which provide free chelating sites for binding metal ions (*vide supra*). The selective binding of Fe(III) ions in these sites was monitored using the N1s spectrum (Fig. 44b). A shift in the binding energy value from 400.1 to 400.6 eV indicates of Fe³⁺ binding in the chelating site. Moreover, the Fe2p spectrum could be deconvoluted into two peaks at 711.4 and 724.8 eV, which are attributed to the Fe2p_{3/2} and Fe2p_{1/2} binding energies, respectively, confirming the binding Fe(III) ions in the Bth-Dma COF system.¹⁴¹

This year, a similar example was reported, where XPS measurement verified the Fe(III) ion sensing by the Tfpa-Mth COF, forming Tfpa-Mth COF@Fe³⁺.¹³⁴ Before the sensing experiment, the Tfpa-Mth COF exhibited two peaks at 401.17 and 400.17 eV for C–N (unreacted Tfpa and Mth) and C=N (imine bond), respectively, in its N1s XPS spectrum. There was a decrease in the binding energy values after binding to the Fe³⁺ ions (400.88 and 399.90 eV), suggesting the successful fixation of Fe³⁺ ions to the wall of the pores. Moreover, the O1s XPS spectrum of the COFs also showed the BE values of 531.40 and 531.11 eV before and after the sensing experiment, respectively, which support the detection of Fe ions. In the Fe2p spectrum, the characteristic signals at 712.01 and 725.07 eV were assigned to the binding energies of Fe 2p_{3/2} and Fe 2p_{1/2}, respectively.

For COF-DB and COF-DT, three intense peaks were observed in their C1s, O1s and N1s spectra, which were comprised of






Fig. 44 (a) C1s and N1s XPS spectra of imine-linked SCOF-LZU-1. (b) N1s and Fe2p XPS spectra of hydrazone-linked Bth-Dma and Bth-Dma@Fe³⁺ COFs. Reproduced with permission from: (a) ref. 101, Copyright the American Chemical Society (2013) and (b) ref. 141, Copyright the American Chemical Society (2019).

multiple signals depicted from the high-resolution XPS spectra. It was observed that C1s and O1s show similar binding energy values for both COFs. Conversely, the N1s spectra showed peaks at 399.2 and 398.4 eV, which indicate the presence of a C–N=C center corresponding to the picoline and the triazine-cores for COF-DB and COF-DT, respectively.¹³¹

Olefinic-linked frameworks. The formation of a Csp²–Csp² bonding linkage using various organic reactions was well explored and discussed in the previous sections. Its characterization to obtain structural information was supported by XPS. For example, the 2DPPV COF was formed *via* the Knoevenagel condensation and its formed structure was compared to its monomers to validate its synthesis. The C1s XPS spectrum depicts two peaks at around 284.5 ± 0.1 and 286.0 ± 0.5 eV, which are ascribed to the sp²-hybridised aromatic carbon and the substituted cyano carbon, respectively.¹⁵⁸ Additionally, the N1s spectrum could be deconvoluted, exhibiting the binding energy at 398.0 ± 0.1 eV for the nitrogen of the cyano group (Fig. 45a and b).




Fig. 45 (a) C1s and (b) N1s XPS spectra of 2DPPV COF. Reproduced with permission from ref. 158, Copyright The Royal Society of Chemistry (2016).

Other linkages. For the aminal-linkage in aminal-COF-1 and aminal COF-2, the strong peaks for C1s and N1s near 398 and 284 eV are attributed to their framework, which is rich in C and N atoms, whereas the very low intensity of O1s just above 500 eV proves that almost negligible aldehydic monomer was left.³⁸

To gain insight into the chemical structure of the metal ions in the dioxin-linked Ni/Co/ZnPc-TFPN COF (Fig. 46),¹⁷¹ the XPS of NiPc-TFPN COF was considered. It showed peaks at 855.7 eV for Ni2p_{3/2} and 873.0 eV for Ni2p_{1/2} in the Ni2p XPS spectrum. This corresponds to the +2 oxidation state of Ni. Similarly, the Co2p and Zn2p XPS spectra are also indicative of divalent metal ions.

5.6 Gas sorption

Porous frameworks have been known for a long time and proven to be potent candidates for a number of applications. Covalently bonded organic frameworks exhibit large surface areas with multiple types of micro-, meso- and macropores, which are tailored by maintaining their topology (*vide supra*). The surface area, pore volume and pore size of these porous materials can be calculated from the gas adsorption–desorption isotherms using the multi-layered Brunauer–Emmett–Teller (BET) adsorption method. There are six different types of adsorption isotherms, as shown in Fig. 47,¹⁹⁶ which are classified as type I to VI and reveal information about the nature of sorption, type of pores depending on their size, adsorption capacity, *etc.* The isotherms are obtained *via* the physical adsorption of inert and non-polar gases (N₂ and Ar) in the pores of the material. The type I isotherm is specifically exhibited by microporous materials (pore size < 2 nm), indicating limited gas uptake due to monolayer adsorption. It is specifically






Fig. 46 Survey scan and high-resolution XPS profiles of (a) NiPc-TFPN COF, (b) CoPc-TFPN COF and (c) ZnPc-TFPN COF. Reproduced with permission from ref. 171, Copyright John Wiley and Sons (2021).

attributed to the physisorption of nitrogen or argon on porous solids.

The type II and type III isotherms are particularly associated with non-porous or microporous materials, where the size of their pores is > 50 nm. The type II sorption curve reveals the unrestricted mono- and multi-layered adsorption of inert gas over the surface, whereas the type III isotherm is restricted to only multi-layer adsorption. The type IV and V isotherms represent a hysteresis loop, where multilayer adsorption occurs on the mesoporous surface (pore size 2–50 nm), suggesting the presence of mesopores in the material. The type VI isotherm

suggests stepwise multilayer adsorption on an enormously homogeneous non-porous solid surface.

Various interesting examples of highly porous COFs with different linkages are discussed in this section, indicating their BET surface areas, number of pores, size and volume and the effect of functionalization.

It is very interesting to note that the highest BET surface area reported in COF chemistry is for the boronic ester-linked DBA-3D COF-1 with a value of $5083 \text{ m}^2 \text{ g}^{-1}$. Its surface area was reduced down to $4763 \text{ m}^2 \text{ g}^{-1}$ upon metallation of its framework.¹⁹⁷

A distinctive example for the effect of alkyl chain length in boronic ester-linked COFs, namely COF-18 Å ($R = \text{H}$), COF-16 Å ($R = \text{Me}$), COF-14 Å ($R = \text{Et}$) and COF-11 Å ($R = n\text{-Pr}$), on the BET surface is shown in Fig. 48a.¹⁹⁸ For an increase in the chain length from COF-18 Å to COF-11 Å, the surface area is drastically reduced, having S_{BET} values of 1263, 753, 805 and $105 \text{ m}^2 \text{ g}^{-1}$, respectively, based on the type-I N_2 gas adsorption isotherms at 77 K. The pore diameter decreased from 18 Å to 11 Å, as denoted by the name of the COF. It must be noted that the ethyl-substituted framework exhibits a slightly greater surface area in comparison to the methyl-substituted COF due to the rotation of the ethyl group, which provides a large surface area to adsorb nitrogen. A similar trend was observed for pore volume.

The triazine-linked CTF series, *viz.* CTF-1, CTF-1-600, FCTF-1 and FCTF-1-600, was analyzed *via* Ar sorption isotherms at 87 K to study the effect of temperature conditions on their surface area (Fig. 48b).¹²⁰ Both CTF-1 and FCTF-1 exhibited type-I sorption isotherms, with the microporous cumulative surface area of 461 and $623 \text{ m}^2 \text{ g}^{-1}$, respectively. According to non-local density-functional theory (NLDFT), it was found that CTF-1 exhibits a pore size of 0.5 nm, whereas FCTF-1 has two pores, 0.46 and 0.54 nm. On increasing the reaction temperature from 400 to 600 °C for the synthesis of CTF-1-600, a type IV sorption isotherm was observed, indicating that mesopores, was obtained with a surprisingly low surface area of $\sim 157 \text{ m}^2 \text{ g}^{-1}$. However, FCTF-1-600 showed a type I isotherm with a surface area of $752 \text{ m}^2 \text{ g}^{-1}$. The reduced pore size ~ 0.59 nm for FCTF-1-600 is possibly due to the F-atom substitutions in its framework.




Fig. 47 Different types of BET adsorption isotherms. Reproduced and adapted from ref. 196 (no permission required), Copyright IUPAC (2015).






Fig. 48 Adsorption isotherm of (a) boronic ester-linked COFs, COF-18 Å, COF-16 Å, COF-14 Å and COF-11 Å, (b) triazine-linked COFs, CTF-1, CTF-1-600, FCTF-1 and FCTF-1-600 and (c) imine-linked COFs, 2,3-DhaTta and 2,3-DhaTab with their pore size distribution (d). Reproduced with permission from: (a) ref. 198, Copyright John Wiley and Sons (2008); (b) ref. 120, Copyright The Royal Society of Chemistry (2013) and (c and d) ref. 79, Copyright John Wiley and Sons (2016).

This technique has also been utilized to monitor the significant changes within the framework caused due by different structural packing. On example was reported for the imine-linked 2,3-DhaTta and 2,3-DhaTab COFs (Fig. 48c and d), respectively. These two frameworks are different in terms of the π - π packing among the 2D layers (see Section 3.2.1). Specifically, 2,3-DhaTta contains planar triazine-cored linker units, which create high crystallinity and high BET surface area in the framework. Its N_2 adsorption isotherm depicts a type-IV curve, indicating a mesoporous framework with a surface area of $\sim 1700 \text{ m}^2 \text{ g}^{-1}$. Conversely, 2,3-DhaTab possesses a low surface area of $\sim 413 \text{ m}^2 \text{ g}^{-1}$, which is attributed to its reduced planarity and crystallinity because of its twisted phenyl-cores. This was further confirmed by the PXRD technique (vide Section 5.3.1). Moreover, a time-dependent study was conducted on both frameworks at 12, 24, 36, 48 and 72 h, showing the framework building.⁷⁹

The study of gas sorption and BET surface area is also helpful to support dimensionality changes and the extent of interpenetration. The pair 2D ILCOF-1 and 3D-ILCOF-1,

which use planar C_4 -symmetric and non-planar T_d -symmetric aldehyde monomers, respectively, is a great example. According to the Ar sorption isotherm, ILCOF-1 has a type IV curve with a sharp uptake in the range of $P/P_0 = 0.05$ – 0.15 , indicating the mesoporous nature of this material, whereas the N_2 isotherm of the 3D framework depicts uptake below $P/P_0 = 0.1$, indicating its microporous cavities (Fig. 49a and b), respectively. Their BET surface areas are 2723 and $517 \text{ m}^2 \text{ g}^{-1}$ with a pore volume of 1.21 and $0.36 \text{ cm}^3 \text{ g}^{-1}$, respectively, which was calculated using the NLDFT method. The reason for the drastic reduction in the various surface parameters is the high degree of interpenetration in 3D-ILCOF-1. Moreover, the two isostructural COFs, 3D-ILCOF-2 and 3D-ILCOF-3, show a slightly higher adsorption uptake in comparison to 3D-ILCOF-1.^{85,122}

The hydrazone- and urea-based COFs, Pythz and Pyurea COF, display quite different N_2 sorption behaviours at 77 K (Fig. 49c).¹³⁸ In the case of the Pythz COF, a distinctive combination of type I and II isotherms was observed, indicating its both micro and mesoporous nature. Conversely, the Pyurea COF shows a type I






Fig. 49 Adsorption isotherms of imine-linked COFs (a) ILCOF-1 and (b) 3D-ILCOF-1/2/3, and (c) hydrazone-linked Pythz-COF and Pyurea-COF with their pore-size distribution curves (d and e). Reproduced with permission from: (a) ref. 122, Copyright John Wiley and Sons (2013); (b) ref. 85, Copyright the American Chemical Society (2018) and (c–e) ref. 138, Copyright The Royal Society of Chemistry (2021).

adsorption isotherm, indicating its purely microporous structure. The BET surface area/pore volume of these frameworks were 1571/1.21 and 1016/0.53 $\text{m}^2 \text{g}^{-1}/\text{cm}^3 \text{g}^{-1}$, respectively. By using NLDFT calculations, the pore size distribution confirmed two pore sizes (2.34 and 1.36 nm) for Pythz COF and one pore size (1.48 nm) for the Pyurea COF (Fig. 49d and e), respectively.

Two COFs, aminal-COF-1 and aminal-COF-2, show similar a surface area of $\sim 1168 \text{ m}^2 \text{g}^{-1}$ but different pore volumes of 0.65 and 0.89 $\text{cm}^3 \text{g}^{-1}$, respectively, at $P/P_0 = 0.99$. By using quenched solid-state density functional theory (QSDFT), the calculated pore size distributions (Fig. 50) show that both COFs have two types of micropores, *i.e.*, at 5.2 and 8.2 for aminal-COF-1 and 5.4 and 8.2 for aminal-COF-2 (Fig. 50).³⁸

It has been seen that by reticulation of the framework, the specific surface areas and pore dimensions change. This can be numerically compared by the BET surface area and pore sizes of the different COFs shown in Table 3.

5.7 Thermogravimetric analysis (TGA)

One of the major reasons for the development of COFs is to generate rigid and robust materials that can withstand high thermal conditions. TGA is used to detect the maximum temperature up to which the polymer is stable, where the percentage weight loss of the framework over a certain temperature range ($\sim 30\text{--}600 \text{ }^\circ\text{C}$) is calculated. This also provides an indication for the presence of solvent molecules used during the synthesis and/or any residual unreacted monomers within the framework lattice. Accordingly, the as-synthesized COF sample is fully activated at high temperature ($\sim 100\text{--}120 \text{ }^\circ\text{C}$) under vacuum, and then subjected to TGA analysis under N_2 environment.




Fig. 50 Adsorption isotherm of (a) aminal-COF-1 and (c) aminal-COF-2 with their pore-size distribution using QSDFT (b and d), respectively. Reproduced with permission from ref. 38, Copyright the American Chemical Society (2019).

The triazine-connected crystalline framework show very high thermal stability in the presence of air. For example, CTF-0 is relatively more stable than CTF-1 up to $600 \text{ }^\circ\text{C}$, which indicates the rich nitrogen content and good cross linking density in CTF-0 compared to CTF-1.¹⁹ It should be noted that only triazine-based COFs exhibit impressive thermal stability in realistic conditions, *i.e.*, in the presence of an oxygen atmosphere. For all other linkages, the TGA is recorded under an inert atmosphere of N_2 gas due to their low stability.



Both activated β -ketoenamine-linked TpPa-1 and TpPa-2 are thermally stable up to 350 °C, indicating the absence of guest molecules within their pores. However, with a further increase in temperature, there is a large weight loss (TpPa-1: 40% and TpPa-2: 50%), which is attributed to their structural decomposition.⁶⁷

The TGA analysis of hydrazone-linked COFs, such as NUS-50 and NUS-51, showed their thermal stability up to 350 °C.¹³⁰ The amination-linked COFs, namely amination COF-1 and amination COF-2, are comparatively less thermally stable. Their TGA data revealed virtually no weight loss up to 200 °C, and only 10% weight loss was observed at around 320 °C.³⁸

The stability changes during post-synthetic modification of the robust organic framework can also be monitored using this technique. The COF TpBD(NO₂)₂ upon reduction to form TpBD(NH₂)₂ showed a similar weight loss profile (weight loss was observed at 450 °C, suggesting the decomposition of the framework), indicating that there were no distinct structural changes.¹⁴⁶ The TGA analysis of COF-701 shows no significant weight loss before 400 °C under a nitrogen atmosphere, proving its exceptional stability.¹⁶⁰ A rare example of the highly crystalline imine-linked 2D ILCOF-1, which remains stable up to 400 °C even under aerobic conditions, was also reported.¹²²

The above-mentioned characterization techniques are greatly helpful to discover the attractive properties of the N-rich frameworks and guide their use for suitable and potential applications.

6. Luminescence and sensing

6.1 Luminescence

In this section, we introduce and discuss a few phenomena that are essential to describe the luminescence properties of COFs and explain their mechanism of action in various applications in Section 6.2.

6.1.1 Increased π -conjugation. According to the basic spectroscopic knowledge, it is known that by increasing the length of a π -conjugated system, the energy gap between the valence and conduction band is lowered, leading to more redshifted π - π^* transitions ($\Delta\lambda$ higher, ΔE lower). This further affects the fluorescence emission efficiency (Φ_f) of the conjugated system, which is directly proportional to the length of the conjugated system.¹⁹⁹ Nevertheless, COFs have been explored as highly fluorescent materials by joining strongly emissive monomers and extending their conjugation *via* different linkages (*vide supra*). This effect was studied by Zhao *et al.*, where a highly conjugated TP-COF was constructed *via* the [$C_3 + C_2$] combination of 2,4,6-tris(4-formylphenyl)-1,3,5-triazine (TFPT) and 2,2'-(1,4-phenylene)diacetonitrile (PDAN).²⁰⁰ It was observed that there was a reduction in energy gap going from the model compound (TFPT + phenylene acetonitrile) to TP-COF, which led to both a red-shifted absorbance and emission maximum from 355 and 506 nm to 410 and 543 nm, respectively. This is solely ascribed to the extended π -conjugation during the formation of the framework.

Furthermore, when the number of consecutive phenyl rings increases within a unit, it loses planarity, giving rise to an anomalous trend. For instance, Peregichka and co-workers

reported two different COFs, namely 3PD and 3BD, synthesized from a combination of a tritopic-*b*-ketoenol and two different aromatic amine units, *i.e.*, phenylenediamine (PD) and biphenyldiamine (BD).²⁰¹ The calculated band gap for the less *p*-conjugated COF system, 3PD, is 2.03 eV, which, on the contrary, increased to 2.19 eV when the conjugation within the framework increased, *i.e.*, in 3BD COF. This is attributed to the loss of planarity between the phenyl rings of the linker BD.

A similar example was reported by Jiang *et al.*, examining the details of π -conjugation and its effect on the luminescent properties of COF materials.²⁰² A pyrene-containing C_4 -symmetric monomer unit, tetraformylphenylpyrene (TFFPy), was used to synthesize three sp^2 -carbon conjugated 2D-COFs, *viz.*, sp^2 c-COF, sp^2 c-COF-2 and sp^2 c-COF-3, *via* their combination with C_2 -symmetric phenyl, biphenyl and triphenylacetonitrile units (PDAN, BPDAN and TPDAN), respectively. In accordance with the theory, there was a bathochromic shift ($\Delta\lambda$ higher) in the emission spectra of TFFPy and three COFs as the monomer emits blue light, whereas the COFs emit in the bright red region (orange, bright yellow, dull and yellow). Conversely, the absorbance and emission spectra of sp^2 c-COF-2 and sp^2 c-COF-3 were more blue-shifted despite their higher conjugated frameworks. This is due to the deplanarization of the monomeric unit when more phenyl rings are incorporated within one row. Therefore, a hypsochromic shift was seen, corresponding to a high transition energy band gap.

6.1.2 Aggregation-induced emission (AIE). The study of luminescence not only includes insight about radiative emission, where knowledge of the non-radiative emission pathways can also be gained. These pathways can be examined under different conditions such as molecular aggregation, their steric environment and solvent surroundings. Several moieties have been reported to be luminescent active but do not show any FL emission in a particular environment, as shown in Fig. 51. One of the radiationless pathways is aggregation-caused quenching (ACQ), in which the quenched luminescence is attributed to the tendency of molecules to aggregate. A typical example of the ACQ effect is the perylene molecule, which shows strong luminescence when diluted with THF solvent.²⁰³ However, upon the addition of a solvent in which it is much less soluble, particularly water, their molecules form excimers *via* π - π interactions, leading to a well-packed structure. Consequently, the luminescence is weakened or completely quenched. On the contrary, the tetraphenylethene (TPE) molecule inhibits the luminescence properties in the dilute




Fig. 51 Selected examples of commonly used fluorophore units that show the AIE effect.



state but emits when its molecules aggregate.^{204,205} In the dilute state, the four phenyl rings of TPE undergo dynamic rotations against the static olefinic double bond, causing thermal dissipation of energy *via* a non-radiative pathway. When the concentration of TPE molecules is high, they aggregate and restrict intramolecular rotations (RIR), showing a strong emissive property. This process is called aggregation-induced emission (AIE). These molecules are called AIE luminogens, or simply AIEgens (terminologically, “luminophores” are the emissive chromophores, whereas “luminogens” are the non-emissive chromophores that emit under particular conditions, such as upon aggregation).

The AIE effect has been observed in covalent organic frameworks incorporating AIEgens as monomeric units. Since the COF layers are stacked on each other *via* non-covalent interlayer π -interactions, the fluorescent moieties present within the framework form excimers, leading to the dissipation of energy *via* a non-radiative pathway. This eventually restricts the luminescence in COFs due to the ACQ effect. To turn off this process, aggregation-induced emission (AIE) becomes functional, where a radiative emission competes with the faster non-radiative process to impede intramolecular rotations (RIR), vibrations (RIV) and molecular motions (RIM).

On coating the 3D-TPE-COF, which was reported by Ding *et al.*, on a regular blue LED, bright white light was emitted, which makes the COF a white light-emitting diode (WLED).²⁰⁶ The photoluminescence properties of the TPE monomer were studied when it was incorporated inside the framework. It was observed that the model compound of TPE-COF exhibited very weak yellow-green emission with a low photoluminescent quantum yield (*ca.* 6.6%), whereas the COF itself emitted bright yellow light ($\lambda_{\text{max}} = 543 \text{ nm}$) with a much higher quantum yield (*ca.* 20%). This is due to the restricted intramolecular rotation (RIR) of the phenyl ring rotators alongside the olefinic bond in TPE when placed in the rigid skeletal three-dimensional framework.

Likewise, the 2D TPE-Ph-COF contains a similar TPE-based core, which shows strong luminescence emission in its aggregated state. A boronic ester-linked COF was reported by Jiang and co-workers in 2016, elaborating the emission of bright blue color at 500 nm when excited at 390 nm (Fig. 52). The small COF

crystallites from a well-defined belt-like shape with an average size of 4 μm , the formation of which was monitored by time-dependent morphology growth.²⁹

Other examples of COFs containing TPE AIEgens are SIOC-COF- x ($x = 1, 2, 5, \text{ and } 6$),^{207,208} 4PE- x P-COF ($x = 1, 2, \text{ and } 3$) and 4PE-TT²⁷ NUS 30-32²⁰⁹ and COF-DHTA, DETA and DBTA, where the terephthalaldehyde unit is substituted with hydroxyl, ethoxy and butoxy groups, respectively.²¹⁰

The pyrene moiety has also attracted extensive attention as an AIEgen when utilized as a monomer in COFs. For instance, Jiang and co-workers reported HHTP-PDBA-COF constructed *via* the $[C_3 + C_2]$ polycondensation of hexahydroxytriphenylene (HHTP) and pyrenediboric acid (PDBA).²¹¹ A strong emission at 474 nm from the pyrene moieties was observed when packed in an eclipsed fashion. One year later, the same group synthesized 2D polypyrene sheets named PPy-COF *via* the self-condensation of PDBA under solvothermal conditions.¹⁷ Due to the layer alignment of the pyrene units in the framework, excimer formation occurred, leading to a strong luminescence emission at 484 nm.

Later, Crowe *et al.* reported Py-DBA-COF-1 and Py-DBA-COF-2, which were synthesized *via* the condensation reaction of two different dehydrobenzoannulene units, DBA[12] and DBA[18], with pyrenediboric acid, respectively.²¹² The DBA[12] and [18] units are planar, π -conjugated emissive macrocycles, where 12 and 18 indicate the number of carbon atoms within their triangular pores. A mixed variant COF using DBA[12] and [18] and PDBA was also synthesized, namely Py-MV-DBA-COF. It was found that the AIE effect of the DBA units resulted in a strong emission property for all the COFs. However, a huge red-shifted emission was observed for COF-1 (530 nm) and the mixed variant COF (528 nm) with respect to COF-2 (483 nm), which is ascribed to the fact that the DBA[12] unit embedded in the framework shows symmetry-forbidden transitions in its ground-state. This leads to the dominant excited-state properties of Py-DBA-COF-1 and Py-MV-DBA-COF.

A few more pyrene-containing COFs possessing the AIE effect have been reported in the literature, *viz.*, A-TEBPY-COF, A-TENPY-COF, A-TEPPY-COF,²¹³ 3D-Py-COF,⁴⁶ Car-ETTA-COF, TFFPy-ETTA COF,²¹⁴ COF-JLU-2 x ($x = 3, 4, 5$),²¹⁵ Per-Py-COF.²¹⁶




Fig. 52 (a) Structure of TPE-Ph-COF with kgm topology. (b) Fluorescence spectra of the TPE model compound (black) and the TPE-Ph COF (blue). Fluorescence microscopy images of TPE-Ph COF samples prepared at different reaction times of (c) 3 days, (d) 10 days, (e) 20 days, and (f) 30 days (inset image showing an enlarged view of the belts). Reproduced with permission from ref. 29, Copyright the American Chemical Society (2016).






Fig. 53 Selected examples of commonly used ESIPT fluorophore units.

6.1.3 Excited-state intramolecular proton transfer process (ESIPT). This has been extensively studied in molecules containing proton donor and acceptor moieties in close proximity to each other. This mechanism was first discovered in salicylic acid and its derivative methyl salicylate by Weller in 1955.²¹⁷ Since then, numerous studies have been performed and the importance of ESIPT in showing luminescence has been exploited.²¹⁸ Certain fluorophores have been reported in the literature to exhibit the ESIPT mechanism, such as 2-hydroxyphenyl-substituted benzimidazol (HBI), benzoxazole (HBO) and benzothiazole (HBT) derivatives, quinoline and anthraquinone derivatives, and benzophenone derivatives, as shown in Fig. 53.

Recently, various COFs have been reported in which free $-OH$ and $-NH_2$ groups are present near the proton acceptor sites, such as imine or triazine linkages or $C=O$ groups, which leads to intramolecular hydrogen-bond interactions and turns on the ESIPT process. The monomeric units exploited to make highly luminescent COFs following the ESIPT mechanism are shown in Fig. 54.

This photochemical switching process involves four states, *i.e.*, electronic ground state and first excited state of enol and keto forms, denoted by $E(S_0)$ and $K(S_0)$ and $E^*(S_1)$ and $K^*(S_1)$, respectively. The enol form of the ESIPT fluorophore is seen at the $E(S_0)$ level, which after photon absorption gets excited to the $E^*(S_1)$ level. At this stage, there is an increase in the acidic character in the H-bond donor moiety and basicity in the H-bond acceptor site, which causes an extremely rapid ESIPT transition from the excited enol to keto form at the rate of $\sim 10^{12} \text{ s}^{-1}$. After radiative decay from this stage ($K^*(S_1)$ to $K(S_0)$), a reverse proton transfer (RPT) possibly happens, giving




Fig. 54 C_2 - and C_3 -Symmetric monomer units for establishing ESIPT the mechanism in COFs.




Fig. 55 General mechanism showing the dual-enol and keto emission in the excited-state intramolecular proton transfer (ESIPT) process in COFs.

the original enol form. A detailed scheme of this process is shown in Fig. 55.

The ESIPT mechanism has been widely studied with a large variety of organic and inorganic molecules and polymers.^{218–222} During this study, it has been found that the surrounding environment of these materials highly affects their luminescence property. For instance, polar solvents form additional hydrogen bonds with the molecules in their enolic form, competing with the intramolecular hydrogen-bond formation. This ceases the ESIPT pathway from the enol to keto form, hence inhibiting the process. Thus, organic solvents have been largely used as a medium to produce and examine the luminescence caused by the excited-state intramolecular proton transfer mechanism.²¹⁸

An example of a COF (IISERP-COF-7) showing dual-emission through the ESIPT mechanism was reported by Halder *et al.* (Fig. 56).²²³ It was found to be a white-light emitter in various solvents. The free $-OH$ groups on the C_3 -unit form intramolecular hydrogen-bonding with the $-CH=N-$ linkages and strong enol–keto tautomerism was observed. The appropriate geometry of the $-OH$ group and its orientation towards the imine linkage turns on the ESIPT mechanism.

However, this dual-emission is highly disturbed by polar N-donor (pyridine, picoline, and acetonitrile) and O-donor (THF, dioxane, methanol and ethanol) solvents. It has been observed that highly basic N-donor solvents help in proton transfer from the enolic to keto form, whereas the enol form predominates when O-donor solvents are employed as the medium. In the latter case, the phenolic hydrogens of the resorcinol moiety are sandwiched between the O-atom of the solvent and phenolic oxygen.

The combination of an ESIPT and ICT system responsible for dual-emissive covalent organic frameworks was reported by Yan and co-workers.²²² The TzDa-COF contains a triazine docking site and an intramolecular hydrogen-bonding site. Upon excitation at 365 and 425 nm in an ethylacetate solution, the TzDa COF exhibits fluorescence emissions at 500 and 590 nm. The phenomenon of ICT was observed in the Tz moiety, where charge transfer






Fig. 56 (a) Dispersions of the monomers and COF suspended in NMP pictured under a UV lamp. (b) COF dispersion in different solvents placed under a UV lamp. Codes: 1, THF; 2, dioxane; 3, glyoxal; 4, pyridine; 5, DMA; 6, NMP; 7, ethanol; 8, formamide; 9, picoline; and 10, DMF. (c) Proposed schematic representation of keto-enol tautomerism in the resorcinol unit of the COF (top). The repeating unit of the COF transforms from the keto to enol form and vice versa through a polarizable transition state (bottom). (d) (i) Proton abstraction mechanism in pyridine, which stabilizes the keto-form; (ii) hydrogen bonding by THF stabilizes the enol-form; and (iii) polarized NMP stabilizing the intermediate keto-enol form. Reproduced with permission from ref. 224, Copyright the American Chemical Society (2018).

from the donor phenyl group and electron-deficient triazine center occurs, showing an emission at 500 nm. The emission at 590 nm corresponds to the ESIPT effect due to the presence of a proton donor $-OH$ group and a proton acceptor $-CH=N-$ bond in the Da moiety. Moreover, the effect of aqueous medium on the dual-luminescence emission made the TzDa-COF capable of sensing trace water molecules in organic solvents. It was observed that an increase in water content from 0.6 to 3.2 wt% blocked the ICT process by forming additional hydrogen bonding between the water and triazine nitrogens. Conversely, the increased interactions of the water molecules with the Da moiety change its excited-state form and increase the corresponding luminescence intensity at 590 nm.

A unique example was reported by Loh and co-workers, where they exploited the inter and intralayer hydrogen bonding in 2D stacked COF sheets to induce emissive properties in the framework.²²⁴ For this, a hydrazone-based non-emissive building unit with various functionalities substituted on it was employed, named 2,5-disubstituted terephthalohydrazide (DHZDR, R = Me, All, and Pr). It was proposed that due to the free intramolecular bond rotations, the monomeric units do not emit. The moiety binds with different trialdehydes, such as benzene-1,3,5-tricarboxaldehyde (Tf) and tri(4-formylphenyl)-benzene (TFPB), leading to the formation of 2D COFs with face-to-face stacked sheets, which tend to form interlayer hydrogen bonds between the free $-NH$ groups of the hydrazide moiety in one layer with $C-O-C$ sites in the other layer. Thus, the monomers cease their rotational motion, leading to strong

quenching *via* the AIE-effect. Moreover, the ESIPT mechanism was also seen in the framework where dual-emission is caused by intralayer hydrogen bond formation between the $-NH$ and imine linkage located at the proximal ends. Thus, both single- and dual-emission can be seen within a molecule *via* two different mechanisms.

In this context, COFs such as COF-4-OH²²⁵ and PEG-COF-42²²⁶ show significant dual-emission by rapid intramolecular proton transfer from the enolic excited state to the ketonic excited state and have been explored for the ESIPT mechanism. Close proximity of the proton donor and acceptor sites, solvent environment, *etc.*, are essential factors that make the ESIPT process possible.

This aforementioned knowledge has pushed the sensing-based study of covalent organic frameworks forward and these materials have been widely exploited to detect various analytes, such as nitroaromatic explosives, various toxic anions and metal ions, volatile small molecules such as organic or inorganic solvents, and biosensing. In this field, it is exciting when COFs are utilized to sense different pH in aqueous media and for thermal sensing.

6.1.4 Photo-induced electron and energy transfer (PET). This is a process in which an electronically excited molecule passes its energy to another molecule. The excited molecule shows significant luminescence property and is called a fluorophore, and the other molecule is a quencher. Fig. 57 represents a schematic of the PET process in electron-rich/poor donor species. In the initial step, the ground-state fluorophore molecule (F)






Fig. 57 Electron transfer (a) and energy transfer (b) quenching of a chromophore in the excited state. (c) Intramolecular charge transfer (ICT) mechanism.

absorbs energy from photons and upon irradiation gets excited to a higher electronic state, F^* . When the excited-state fluorophore (F^*) comes in close proximity with electron-rich or electron-poor quenchers, electron transfer occurs, which leads to FL quenching in the system (shown in Fig. 57a and b). For this, the frontier orbital energies of the fluorophore and the quencher should be similar. On the contrary, the energy transfer mechanism for the FL quenching of a fluorophore does not involve any electron transfer from the excited electronic state F^* . Rather, the excited state energy is transferred to the quencher whose LUMO must have lower energy values with respect to the excited state F^* . Fig. 57c depicts the energy transfer process.

6.1.5 Intramolecular charge transfer (ICT). This charge transfer process involves the transfer of electronic charge from electron-donating species to the electron-accepting species (Fig. 57c). When both moieties lie inside the sample molecule, charge transfer occurs through a π -electron bridge, which is called intramolecular charge transfer (ICT). The charge transfer is affected by the solvent polarity and quenched in the presence of analytes, which act as an FL quencher. A polar solvent tends to stabilize the charge separation in an excited fluorophore. Conversely, the quencher can act as a donor or an acceptor depending on its electron-rich and electron-deficient nature.

6.1.6 Förster resonance electron transfer (FRET). Another very important process in fluorescence spectroscopy is Förster (or fluorescence) resonance energy transfer (FRET). According to FRET, when a fluorophore (called donor D) molecule and a quencher (called acceptor A) molecule couple through a dipole-dipole interaction at a Förster distance in the range of 15–60 Å, there is an overlap between the emission spectrum of the fluorophore and the absorption spectrum of the quencher. This process does not involve the emission of light by the donor, which is further reabsorbed.²²⁷ The spectral overlap is shown in Fig. 58. The shorter the distance between the two species, the greater the interaction between them. The extent of energy transfer, $\kappa_T(r)$, is given by the following equation:

$$\kappa_T(r) = \frac{1}{\tau_D} \left(\frac{R_0}{r} \right)^6$$




Fig. 58 Spectral overlap of donor emission and acceptor absorption.

where r is the distance between the fluorescent donor (D) and quencher/acceptor (A), R_0 is the Förster distance and τ_D is the lifetime of the donor in the absence of energy transfer.

This mechanism is widely seen in fluorescent-active COFs, and the potential candidates for sensing various analytes are described in the next sub-section.

6.2 Sensing

6.2.1 Explosive sensing. With the advancement in science, the discovery of various hazardous compounds has resulted in many international and world wars being won. However, these nitro-based compounds such as TNP, TNT, RDX and explosive D pose a great threat to the ecosystem, human health and national/international security due to their blasting nature.^{228,229} For some time, porous materials proven to be promising candidates to detect these explosive compounds in various media, particularly water.²³⁰ COFs are one of the emerging candidates among these materials due to their potential and high emissive properties, large surface areas, pore size and pore volume, long-range order and thermal and chemical stability.²³¹

In 2012, the first melamine-based porous organic framework, SNW-1, was efficiently synthesized by W. Zhang *et al.* from terephthaldehyde (TA) and melamine (MA) using the microwave-assisted technique.²³² The synthesized nanoparticles possessed a highly cross-linked covalent-bonded network with a



particle size of 20–50 nm and BET surface area of $476 \text{ m}^2 \text{ g}^{-1}$. Due to its nano size, quite high porosity and significant emissive properties, the material was rapidly responsive for the selective detection of nitroaromatic explosives in THF-water (10% v/v) at ppb levels. The framework, being electron-rich, senses π -acidic nitroaromatics such as 2,4,6-trinitrophenol (TNP), 2,4,6-trinitrophenylmethyl nitramine (tertyl), 2,4-dinitrotoluene (DNT), 2,4,6-trinitrotoluene (TNT), 4-nitrotoluene (NT), nitrobenzene (NB) and tends to exhibit strong quenching by the photo-induced electron transfer (PET) mechanism. TNP resulted in the highest fluorescence quenching ($>80\%$) in the solution phase with a very low detection limit (*ca.* 11.5 ppb). In addition to PET, the formation of a Meisenheimer complex resulting from hydrogen bonding between the phenolic group of TNP and the secondary amine linkages of SNW-1 caused the quenching. This was confirmed by the blue shift from 261 nm to 244 nm in the absorbance peak of the SNW-1 nanoparticles in the presence of TNP. Moreover, a detailed time-dependent vapour phase sensing experiment was conducted for DNT with a detection limit down to 9.8 ppb. The authors also tested common organic solvents such as dimethylformamide, dimethylsulfoxide, ethanol, acetonitrile, acetone, and benzene, where no significant effect on the emission intensity of the SNW-1 NPs was observed. The utility of this COF for sensing applications gave a great push to exploit COFs in this direction.

The next year, Jiang *et al.* reported a nitrogen-rich 2D azine-linked COF with the pyrene-core monomer TFPPy (see Section 4.2).¹⁵² The chemically robust azine linkage in the Py-azine COF was unaffected in various polar and non-polar organic solvents and did not get destroyed even in inorganic acid and base such as aqueous HCl and NaOH, respectively. Moreover, the intense emitting property of the COF originates from the extended conjugation *via* azine linkages between the monomers and from the pyrene fluorescent tag. Therefore, the Py-azine COF was used as a distinctive chemosensing detector for various nitrobenzene derivatives such as 2,4,6-trinitrophenol (TNP), 2,4-dinitrophenol (DNP), 2,4-dinitrotoluene (DNT), 2-nitrophenol

(NP), and 2-nitrotoluene (NT). Turn-off sensing up to 69% fluorescence quenching was observed for TNP with a detection limit of 70 ppm, whereas other analytes quenched only around 13%. The hydrogen-bonding interactions between the TNP analyte and the azine units, which serve as the open docking sites at the framework edges, lead to a reduction in the emission intensity of the Py-azine COF.

Eventually, numerous COFs have been reported with electron-rich and fluorescent moieties, leading to the detection of nitroaromatic explosives, which are electron-deficient. Thus, a turn-off sensing is seen due to the electron transfer process. A unique example of turn-off and turn-on was reported in 2015 utilizing COF thin films, which enhanced the phenomenon of chemical sensing in comparison to bulk COFs. Two frameworks, TpbDH and TfpBDH, were explored for sensing applications in the bulk and exfoliated form, namely TpbDH and TfpBDH-CONs (Fig. 59).¹⁴⁹

TpbDH-COFs and CONs do not show PL activity due to the restricted π -conjugation arising from enol-keto tautomerism. Conversely, there are no free OH groups present in TfpBDH-COFs and CONs, which limit their tautomerism, and therefore, they exhibit high FL intensity. Various nitroaromatics, such as TNP, TNT, 2-NP, DNT and DNP, were detected using CONs in both solution and dispersed phase showing quite opposite trends. In the solution phase, the FL intensity of TfpCON is quenched by 63% with TNP (detection limit of $5.4 \times 10^{-5} \text{ M}$), which is attributed to the electronic charge transfer from the π -acidic analyte (the picrate anion) to the rich electron cloud of the protonated nanosheet. On the contrary, 'turn-on' sensing behaviour was observed when the weak blue emission of a TfpBDH-CON-coated paper strip changed to a bright-yellow color upon the addition of TNP analyte. This was caused by the proton transfer from the phenolic group of the TNP analyte to the basic nitrogen atom of the imine linkage in the solid CONs.

A similar example of a polyimide covalent organic nanosheet was reported by Zhang *et al.*²³³ PI-CONs were comparatively more emissive than PI-COFs, which were synthesized *via* ultrasonic




Fig. 59 (a) Turn off sensing (PL quenching) and (b) degree of fluorescence quenching of TfpBDH-CONs with different nitro analytes. (c) Photoluminescent spectra of bulk TfpBDH and TfpBDHCONs. (d) Photoluminescent spectra showing turn on (PL enhancement) of bulk TfpBDH-CONs and with TNP. (e) Photoluminescence enhancement plots of different analytes [$5.4 \times 10^{-3} \text{ M}$] with TfpBDH-CONs. Reproduced with permission from ref. 149, Copyright The Royal Society of Chemistry (2015).



delamination. The nanosheet exhibited high quenching of TNP with 64% FL quenching and limit of detection 0.25 μM . The mechanistic explanation indicates electron transfer between the protonated PI-CONs and TNP^- , which was supported by theoretical calculations using DFT functional and the B3LYP basis set, where upon its addition, the inner filter effect (IFE) could be seen. The IFE occurs when there is re-absorption of the emitted light by the quencher. The evident spectral overlap between the absorption spectrum of TNP and the emission spectrum of PI-CONs confirms this quenching phenomenon.

As presented in the previous sections, the controlled and systematic choice of the monomers and reaction conditions leads to a framework with the desired topology and dimensionality. A two-fold interpenetrated 3D-PY-COF emits yellow-green luminescence when dispersed in DMF and excited at $\lambda_{\text{ex}} = 408 \text{ nm}$. The elevated FL intensity of the COF originates from the imine-functionalized pyrene moieties in its framework.⁴⁶ The titration experiments evidently showed the selective and sensitive detection of TNP (up to 75%) in DMF with a detection limit of 20 ppm. This was the first 3D-COF proven to be a potential candidate for sensing NACs.

Recently, Das *et al.* also reported a nitrogen-rich dual-functionalized 2D COF, which was formed from triazine-based trialdehyde (tri(4-formylphenoxy)cyanurate) and electron-rich naphthalene diamine monomers.²⁴ A unique six-fold interpenetrated framework was obtained, where the ABC stacked sheets gave rise to a star-like topology. The entangled hexagonal honeycomb sheets reduced the BET surface area (*ca.* 294 $\text{m}^2 \text{g}^{-1}$), sculpting a triple-pore framework (*ca.* 0.75 nm, 1 nm and 2.1 nm) corresponding to micro and mesopores. This multifaceted COF was utilized for (1) the detection of trace amounts of TNP in water due to the presence of π -electron-rich naphthalene moieties, (2) separation of benzene and cyclohexane using the π -acidic triazine moiety and (3) decoding of volatile organic compounds. Being highly emissive and chemically stable in aqueous media, the COF selectively detected the electron-deficient trinitrophenol up to the lower limit of 68 ppb with a K_{sv} value 30-times higher than that for the other NACs. Further improvisation

was reported for the ultrafast real-time detection of NACs through instant spot *via* paper strips. A significant color change from blue to green for the FL quenching by TNP was observed, making the COF very handy. This 'turn-off' sensing is attributed to the energy transfer from the framework to TNP analyte and photo-induced electron transfer from the LUMO of the COF to the low-lying conduction band of TNP. In addition, the H-bonded interactions between the N- and O-functionalities and -OH group of TNP contributed 90% quenching.

Last year, another luminescent COF (namely ANCOF) was synthesized by Das *et al.* for the water-based sensing of nitroaromatic explosives and amines such as dichloronitroaniline (DCNA), 4-nitroaniline (4-NA), 2,4-dinitroaniline (DNA), 3-nitroaniline (3-NA), 2-nitroaniline (2-NA), aniline (AN), 4-nitrotoluene (4-NT), ethylene diamine (EDA), triethylamine (TEA), 1,2-diaminobenzene (DAB) and *N,N*-dimethyl-*p*-phenylenediamine (DMPD).¹⁵⁴ The appended π -electron rich sites in the framework act as recognition sites for the selective detection of dichloran (other name for DCNA) and 4-NA in water/MeOH (Fig. 60). More than 80% quenching with a large bathochromic shift in the FL intensity of ANCOF (*ca.* 21 nm and 19 nm) and lower limit of detection (*ca.* 142 ppb and 89 ppb) for DCNA and 4-NA, respectively, was observed. The mechanistic insight showed the presence of resonance energy transfer, photo-induced electron transfer (PET) and distinctive H-bonding interactions between the triazine moiety and Cl atom in DCNA and amine hydrogens in 4-NA. In addition, the lifetime measurements shed light on the static quenching mechanism at lower analyte concentrations, while the dynamic quenching mechanism occurs at higher concentrations. Moreover, the two-fold interpenetration of the framework with the ABAB arrangement yielded a beautiful marigold-like microfloral morphology.

6.2.2 pH sensing. The utility of nitrogen-rich luminescent COFs for developing pH-sensing systems is an upcoming and barely explored area. Very few examples of COF-based fluorescent pH sensors have been reported in the literature. In 2016, the β -ketoamine-based COF-JLU4 was the first to be explored as a pH-responsive material.¹⁴⁴ The crystalline 2D framework




Fig. 60 (a) Percentage of fluorescence quenching obtained for different analytes at room temperature. (b) (top to bottom) Response of ANCOF in the presence of various amines by UV illumination, and (c) fluorescence microscopy images: response of ANCOF in the presence of various amine-analytes in the FITC region. Paper strips coated with ANCOF and different concentrations of (d) DCNA and (e) 4-NA. Reproduced with permission from ref. 154, Copyright American Chemical Society (2020).






Fig. 61 (a) Electronic absorption (in water: black line and in the solid state: red line) and fluorescence spectra (in water: blue line and in the solid state: green line) of COF-JLU4. (b) pH-Dependent fluorescence of COF-JLU4 in aqueous solution with pH ranging from 0.9–13.0 measured under excitation at 334 nm. (c) Photoluminescent intensity of COF-JLU4 at 428 nm in aqueous solutions with different pH values. (d) Deprotonation and protonation processes of the COF-JLU4 framework in acidic and basic media. Reproduced with permission from ref. 144, Copyright The Royal Society of Chemistry (2016).

showed excellent hydrolytic stability and wettability, a high BET surface area of $923 \text{ m}^2 \text{ g}^{-1}$, large-sized pores with free NH groups, and good emissive properties. This makes it a pH-dependent fluorescence-responsive material for a wide range of pH in aqueous medium. It was observed that COF-JLU4 exhibited the strongest fluorescent intensity in the most acidic conditions (Fig. 61). Going from pH 9.0 to 13.0 in the more basic region, the fluorescence intensity decreased gradually with the deprotonation of the NH-groups present in the framework. Over the pH of 9.0 to 4.5, not much change was observed in the luminescence intensity, but there was a blue-shift in the emission peak at acidic pH 3.6. When the pH was below 3.6, the protonation of the NH-groups led to an enhancement of the peak at 428 nm. This optical response of COF-JLU4 in a broad pH range is reversible and makes the COF a recyclable and reusable fluorescent pH-sensor.

Another COF reported for colorimetric pH sensing contained a pH-sensitive fluorescent chemical group, 8-hydroxyquinoline (HQ).²³⁴ COF-HQ was solvothermally synthesized by Chen *et al.* from the HQ-substituted terephthaldehyde monomer and TAPB, yielding a quite low surface area and semi-occupied pores. This HQ-functionalized framework possesses good acidic and hydrolytic stability, and thus exhibits high luminescent intensity, which is strongly correlated with the pH of the aqueous medium. Unlike COF-JLU4, the fluorescence intensity of COF-HQ is completely quenched in a highly acidic medium at pH = 1.0 due to the protonation of the 4-hydroxyquinoline group inside the pores. Conversely, when the pH is raised to 5.0, the HQ grafted inside the framework gets deprotonated, leading to a gradual increase in the emission intensity. This has a good linear relationship with the correlation coefficient of $R^2 = 0.979$.

COF-HQ acts as a colorimetric-based pH sensor as its color turns black when the luminescence is quenched and intensifies to dark orange under basic conditions at pH ≥ 5.0 .

Recently, two porphyrin-based COFs were utilized as colorimetric pH-responsive materials in the pH range of 0 to 7.0. TPE-Por-4 and TPE-Por-2 were distinctively constructed under solvothermal conditions.²³⁵ Between them, the highly crystalline TPE-Por-4 displays enhanced luminescence intensity due to (1) aggregation-induced emission (AIE) by the non-planar TPE chromophore, (2) the adequate layer spacing among the AB stacked COF, leading to the restriction of its intramolecular rotation (RIR), which enhances its FL emission, and (3) loose stacking and weak π - π interaction because the twisted TPE prevents FL quenching. Furthermore, colorimetric pH-responsive studies were conducted, showing a bathochromic shift ($\sim 15 \text{ nm}$) and hyperchromic shift of the emission peak from 2.01 to 4.15 nm. This is due to the more protonated N-atoms inside the porphyrin rings at a high hydrogen ion concentration, which destroys the π -electron-conjugated double-bond system, leading to fluorescence quenching. The TPE-Por-4 COF showed an obvious color change from dark red to bright green below pH 2.0, but no marked change above this value was seen.

Working in this direction, Das *et al.* reported the synthesis of three nitrogen-rich flexible COFs namely CON, CONN, and CONNCO (*vide supra*, Section 4.2) for sensing different acidic and basic environments.¹²⁴ These flexible COFs are pH-stable, possess very high BET surface areas ($867 \text{ m}^2 \text{ g}^{-1}$) and pore size (4.2 \AA for CONNCO), and have imine, amide, and hydrazide linkages, which provide inter and intramolecular H-bonding among their stacked layers. These flexible COFs were utilized as reversible fluorescent ON-OFF pH sensing materials (Fig. 62). For CON, the luminescent intensity increases, and a sharp blue shift ($\sim 50 \text{ nm}$) was observed from pH 1.0 to 13.0. In highly basic conditions, the deprotonation of the N-atom leads to electron transfer towards the π -acidic triazine moiety, and hence a wavelength shift is observed in this region. On the contrary, CONN shows the opposite trend, exhibiting turn ON sensing from basic to acidic medium. This is due to the emergence of extra intramolecular H-bonding in acidic conditions together with the prior intermolecular H-bonding between the carbonyl O and NH groups. Conversely, CONNCO exhibits the highest luminescent intensity at pH 4.0 and shows moderate quenching at high acidic and basic conditions. Under these conditions, the intramolecular H-bonding for CONNCO is destroyed, allowing intramolecular rotation, and the emission is quenched. From pH 7.0 to 4.0, the protonation of the N-atoms in the hydrazide linkage dominate the intramolecular H-bonding, resulting in restriction of intramolecular rotations (RIR). The lifetime studies showed a dynamic process at basic pH for CON and at acidic pH for CONN, whereas at both conditions for CONNCO. The good agreement with the R^2 values, *i.e.*, 0.982 and 0.984 in the polynomial fitting, and 0.999 in the linear fit for CON, CONN, and CONNCO, respectively, confirms the good correlation.

6.2.3. VOCs and small molecules. Recently, the potential of COFs as sensing probes has been explored for the detection of volatile organic and solvent molecules such as ammonia,^{29,236}






Fig. 62 pH-Dependent fluorescence spectra of (a) CON, (b) CONN, and (c) CONNCO in aqueous solution with pH ranging from 1 to 13. Relative fluorescence intensity of (d) CON, (e) CONN and (f) CONNCO at different pH. Reproduced with permission from ref. 124, Copyright the American Chemical Society (2021).

formaldehyde,^{237,238} arene,¹²⁶ and HCl vapours,^{239,240} unsaturated aromatic volatile molecules²⁴ and various protic and aprotic solvents.^{125,241} Several pesticides have also been detected using highly luminescent covalent organic frameworks.²³⁴

In 2016, Dalapati and co-workers reported the synthesis of TPE-Ph-COF, which is highly emissive due to aggregate-induced emission.²⁹ The COF was synthesized *via* the solvothermal condensation of tetraphenylethene boronic acid (TPEBA) and 1,2,4,5-tetrahydroxybenzene (THB), developing boronate linkages. This COF was highly crystalline with a BET surface area of 962 m² g⁻¹, forming a dual-pore **kgm** net having pore sizes of 1.3 and 2.6 nm. This material was utilized for the detection of ammonia molecules, which showed rapid quenching response in the organic solvents toluene and cyclohexane. It was explained that the Lewis acidic boronate linkages form acid-base interactions with the Lewis basic ammonia molecules, turning off the bright blue luminescence of the COF.

Xie *et al.* studied and reported the fluorescence properties of the highly crystalline TAT-COF-2.¹²⁶ This 2D COF was synthesized from the C₃-symmetric trialdehyde and triamine derivative of triazatruxene (TAT), forming imine-linkages. The topological [C₃ + C₃] connectivity weaves the COF with a high BET surface area and pore size of 1166.1 m² g⁻¹ and 1.48 nm, respectively. Various electron-rich and electron-deficient arenes were successfully sensed using the strong electron-donating abilities of the TAT building unit (Fig. 63). It was found that the FL intensity was enhanced when an ethanolic suspension of TAT-COF-2 was diluted with electron-rich arenes such as toluene, chlorobenzene, *o*-dichlorobenzene, mesitylene, bromobenzene, 1,2-dimethylbenzene, pyridine, and some solvents such as *N*-methylpyrrolidone, tetrahydrofuran, ether,

triethylamine, dimethylformamide, ethyl acetate, dimethylacetylamine, dimethyl sulfoxide, hexane and chloroform. On the contrary, significant fluorescence turn-off was seen upon dilution with nitrobenzene, 2-nitrotoluene, methanol, water, *n*-butanol, tetraethylene glycol, dioxane and phenol solution, which are electron-deficient species. Among them, total quenching was achieved upon the addition of 5 drops of nitrobenzene, while ~60% enhancement was seen with toluene and mesitylene. The phenomenon of electron transfer was responsible for the whole quenching and enhancement of the emission peak.

Another truxene-based crystalline COF, Tx-COF-2, was reported recently by Nailwal *et al.*, which was utilized for sensing vapor and solid-phase HCl.²⁴⁰ The framework, being highly stable in 12 M HCl, was exposed to HCl vapor in a 1,4-dioxane suspension. An evident rapid color change from yellow to bright orange was seen, attributing to the protonation of the imine linkages in the framework, showing fast fluorescence enhancement. The detection limit was found to be as low as 4.5 nmol L⁻¹, which is the best reported value for the detection of HCl vapor to date. The reversibility of the framework was noted up to 10 cycles using ammonia vapor with recovery of the framework using triethylamine when the pH is maintained at 7.

N-Rich frameworks with high emissive properties and crystallinity were reported by Mandal and co-workers in 2018.²⁴ A dual-functionalized COF was proven to be potent for sensing various tropospheric VOCs such as benzene, toluene, *o*-, *m*-, *p*-xylene, mesitylene, chloro-, bromo-, iodo-benzene, anisole and cyanobenzene. VOCs have great affinity towards electron-deficient centers, making the COF suitable for VOC sensing. The results showed that the host-guest charge transfer causes the formation of an exciplex,






Fig. 63 (a) UV-Vis adsorption of TAT-COF-2, (b) fluorescence of TATCOF-2 suspended in ethanol at different densities; 100 mg TAT-COF-2 suspended in 1 mL ethanol and diluted with (c) ethanol, (d) nitrobenzene, with the calculated detection limit of about 10 mM; (e) acetonitrile and (f) chlorobenzene, with the calculated detection limit of about 198 mM. Reproduced with permission from ref. 126, Copyright The Royal Society of Chemistry (2015).

changing the FL intensity and emission wavelength in each case. COF-mesitylene showed the maximum emission intensity at 381 nm with a high quantum yield (*ca.* 0.083) and long average lifetime (*ca.* 3.89 ns), which was blue-shifted in comparison to other electron-donating VOCs. Conversely, there was a red-shift in the emission wavelength of the COF when benzene was substituted with a heavy atom, *viz.*, iodobenzene, with an increase in its average lifetime. Moreover, the same triazine core was utilized to sense and separate aromatic benzene (Bz) molecules from the non-aromatic cyclohexane (Cy) domain. A red shift in the luminescence intensity of the COF was observed when immersed in benzene with quantum yields of 0.06/0.042 and average lifetimes of 3.47/4.02 ns (Bz/Cy), respectively. This is ascribed to the very strong interactions between the electron-rich Bz and electron-deficient triazine core in the framework.

In recent years, it has been explored that covalent organic frameworks provide a site for hydrogen bond interactions with molecules having carbonyl groups. This led to the sensing of small molecules such as formaldehyde, where the electronegative oxygen atom from the carbonyl group forms hydrogen bonds with the aromatic hydrogens present in the framework. Hao and co-workers investigated the effect of the luminescent properties of the HHTP-DPB COF before and after sensing formaldehyde molecules.²³⁷ It was observed that the FL intensity of the HHTP-DPB COF was rapidly quenched after the incremental addition of formaldehyde. Employing the quantum chemical approach, DFT

AND TDDFT methods, it was determined that the H-bonding is enhanced in the S_1 state, leading to a diminished energy gap between G. S. and E. S. by 0.54 eV after the interaction of formaldehyde and the COF. This was further confirmed by calculation of the H-bond lengths, IR spectra of the donor and acceptor groups and NMR chemical shifts for the framework hydrogens involved in H-bonding in the S_0 and S_1 states. Also, the FL rate coefficients for the COF and HCHO@COF were 1.22×10^4 and $4.13 \times 10^3 \text{ s}^{-1}$, respectively, indicating that the FL intensity weakened after the addition of the analyte.

Similar studies were carried out with TT-COF reported by Hussain *et al.*²³⁸ The noncovalent interactions between the thienothiophene-based COF and formaldehyde were investigated using DFT and TDDFT computational tools, which are indicative of strengthened H-bonding and weakened emission intensity after mixing. The FL rate constants for the simulated TT-COF and its complex with HCHO are 1.16×10^8 and $1.45 \times 10^3 \text{ s}^{-1}$, respectively, strongly indicating the quenching effect. Furthermore, the reduction in band gap between the S_1 and T_1 states (1.00 to 0.32 eV) indicates the possibility of a radiationless ISC process as the reason for quenching.

Recently, Mandal and co-workers reported two highly crystalline, luminescent and chemically stable COFs, COF-N and COF-NN, decorated with molecular docking sites for solvatochromic decoding of volatile solvent molecules (VSMs).¹²⁵ The COFs possess pore sizes of 2.7 and 3.06 nm, respectively, with moderate BET surface areas, and thus, the structurally small molecules were deciphered by these materials. On immersing the two COFs in different VSMs with varying polarities such as alcoholic (MeOH, EtOH, 1-PrOH, 2-PrOH, 1-BuOH, 2-BuOH and *t*-BuOH), chlorinated (DCE, CHCl_3 , and CH_2Cl_2) and some aprotic solvents (acetone, acetonitrile, THF, dioxane, EtOAc, DMF, DMA and DMSO), a remarkable color change together with a change in wavelength and emission intensity was noted (Fig. 64). The interactions between the COFs and VSMs were examined using polarity parameters such as Reichardt's, Kamlet-Taft's and Gutmann's parameters. The results showed that the singlet energies are in good luminescence correlation with Reichardt's parameters for COF-N and that with Gutmann's parameters for COF-NN. Moreover, the presence of an extra amine functionality in the COF-NN framework contributed to the electron donation and enhanced the H-bonding interactions with the VSMs.

6.2.4 Toxic anions. The sensing of toxic acidic radicals in various solvents has been practiced for some time. N-rich COFs have been extensively utilized for this purpose due to their porous nature, exceptional stability and availability of reversible proton donor/acceptor sites in their framework.

Considering that pyrene-core organic moieties have been widely explored for AIE in covalent organic frameworks, they have also been utilized for turn-on sensing of anionic molecules. An efficient but weakly luminescent N-rich TFPPy-DETHz COF was fabricated through hydrazone bridges and emitted low green-yellow FL intensity due to the ACQ effect (vide Section 6.1.2).¹³⁷ The luminescent intensity of the COF was enhanced by 3.8-fold that of its original intensity after the addition of a THF solution of tetrabutylammonium fluoride to it. On the






Fig. 64 Emission spectra of COF-N and COF-NN in different (a and e) alcoholic, (b and f) chlorinated, and (c and g) aprotic VSMs (0.25 mg in 2 mL). (d and h) Solvatochromic behavior of COF-N and COF-NN in the presence different VSMs (top row: under visible light and bottom row: UV illumination). Reproduced with permission from ref. 125. Copyright the American Chemical Society (2020).

contrary, other halogen and nitrate ions did not have any effect on the weakly luminescent framework. This was ascribed to the strong acid–base reaction between the F^- ions and N–H units of the hydrazone linkages, which led to deprotonation of these units. However, reversible protonation of N[−] anions can be successfully carried out by adding triflic acid (TFA) to the system. It must be noted that the TFPPY-DETHz COF was the first report of anion sensing using a porous organic framework.

Common oxidizing agents, such as CrO_4^{2-} , $Cr_2O_7^{2-}$ and MnO_4^- , are widely used in laboratories and industry, which pose a threat to the environment and mankind. Therefore, it is essential to monitor and sense these anions using efficient and

easy to handle probes, such as porous organic polymers. Li and co-workers developed the 3D stable and luminescent COF-TT, which exhibited high sensitivity towards the detection of CrO_4^{2-} , $Cr_2O_7^{2-}$ and MnO_4^- ions *via* a turn-off sensing phenomenon (Fig. 65a).²⁴² The COF-TT framework contains a flexible core synthesized from bis(tetraoxacalix[2]arene[2]triazine) and the rigid tetra(paminophenyl)methane. When anions interact with the framework in aqueous medium, a strong competitive energy transfer process occurs, which was validated by UV-Vis spectroscopy. The spectral overlap of the adsorption band of COF-TT with the wide range absorption bands of the three anions supports the quenching mechanism. With up to 0.8 mM






Fig. 65 (a) Fluorescence intensities of COF-TT for different anions. (b) % quenching of DATGCl-iCONs upon the addition of different anions. Reproduced with permission from: (a) ref. 242, Copyright The Royal Society of Chemistry (2019) and (b) ref. 114, Copyright the American Chemical Society (2020).

(for CrO₄²⁻ and Cr₂O₇²⁻) and 0.7 mM (for MnO₄⁻) anionic concentration, the framework completely lost its luminescent property. This makes COF-TT an excellent anion sensor with a detection limit of 3.43×10^{-4} M (for CrO₄²⁻ and Cr₂O₇²⁻) and 3.20×10^{-4} M (for MnO₄⁻).

Another strategy for anion sensing is by incorporating an ionic linker as a monomeric unit to synthesize ionic frameworks. Recently, triguanidinium chloride (TG_{Cl}) was utilized as an anion acceptor linker, which was combined with a fluorescent-active dimethoxyterephthaldehyde (Da) unit to give ionic covalent organic nanosheets, namely DATG_{Cl}-iCONs, *via* self-exfoliation in methanol (Fig. 65b).¹¹⁴ The addition of F⁻ to the cationic sensor caused great fluorescence quenching with a detection limit of 5 ppb level. A unique property of the guanidinium linker is its ability to donate a proton (in the presence of F⁻ ions) and abstract it again (by adding HCl). The appropriate basic nature of the F⁻ ions in the framework environment leads to the abstraction of a proton, which gives rise to turn-off sensing. Moreover, the further addition of HCl supplies enough H⁺ to bind the guanidinium unit and regain its fluorescent property. According to the theoretical studies, it was found that the quenched luminescence of DATG_{Cl}-iCONs occurs *via* the photo-induced electron transfer mechanism, which was supported by time-resolved fluorescence spectroscopy, showing dynamic quenching. The turn-off/on sensing was repeated successfully for up to five cycles with minimum loss of the sensor.

6.2.5 Metal ions. The increasing amount of metal ions in water bodies poses a huge threat to the ecosystem and mankind. This global concern has attracted great attention toward the development of novel strategies for monitoring and detecting heavy metal ions.^{243,244} The first example in this direction was reported in 2016, where an azine-linked COF, namely COF-JLU3,

was explored to detect Cu²⁺ ions in THF medium.²⁴⁵ This COF exhibits strong luminescence at 601 nm in the orange-red region upon excitation at 424 nm (Fig. 66a). The framework contains high porosity, surface area and rich hetero-atom content, such as N and O, which act as Lewis basic sites for ion sensing. Among the various metal nitrates, Cu²⁺ ions were selectively detected, and the FL intensity of the framework was reduced to 18.3% when 2.0 equivalents of Cu(NO₃)₂ was dispersed with COF-JLU3 in THF solution. The selective detection of cuprous ions is ascribed to the partly filled d-orbitals in comparison to alkaline metals (with no d-subshells) and d¹⁰ transition metal ions. Among Fe³⁺, Co²⁺ and Cu²⁺ ions, the highest selectivity of the framework was found with Cu²⁺ ions with the detection limit of 0.31 μM and Stern–Volmer constant of 3.8×10^4 M. The Lewis acid–base interactions are mainly responsible for this quenching due to photo-induced electron transfer (PET) from the COF to metal ion. The time-resolved lifetime measurements indicated the FL lifetime for COF-JLU3 was reduced from 1.5 ns to 0.7 ns when dispersed with 2×10^{-4} M Cu²⁺ nitrate solution.

Other COFs for the efficient sensing of Cu²⁺ ions are Q-graphene (QG)-grafted COF,²⁴⁶ which detects up to 0.5 nM, and nitrogen-rich CTF²⁴⁷ with a detection limit of 0.05 μg L⁻¹.

Bipyridine-based COF nanosheets (Tp-Bpy NSSs) exhibit a structure with regular pores and abundant N-based moieties, which act as active sites for the detection of Hg²⁺ ions.²⁴⁸ The Tp-Bpy nanosheets were prepared *via* ultrasonic exfoliation, on which Au nanoparticles were loaded to form the AuNPs@Tp-Bpy nanocomposite. The affinity between gold and mercury suggests the high selectivity of AuNPs@Tp-Bpy towards Hg²⁺ ions with a detection limit of 0.33 nM. The framework was enriched with nitrogen, which provides ultra-affinity for Au nanoparticles, and therefore, it provides an excellent platform to detect Hg²⁺ with good selectivity and sensitivity in real-life sensing applications.

In addition, COF-LZU8 was also utilized for sensing Hg²⁺ with a very low detection limit of 25.0 ppb.²⁴⁹ Recently, COFs have been explored to make quantum dots, which exhibit high luminescent properties for metal ion analyte sensing. The CTF-based N-doped quantum dots (CTFQDs) detected Hg²⁺ ions up to a limit of 0.23 μM (Fig. 66b).²⁵⁰

The highly fluorescent AH-COF, which was synthesized using hydroxyl functionalized 2,5-diallyl-3,6-dihydroxyterephthalohydrazide and 1,3,5-benzenetricarboxaldehyde, was utilized for selective and rapid Hg²⁺ ion sensing (Fig. 66c).²⁵¹ This COF possesses exceptional luminescent properties due to its excited-state intramolecular proton transfer (ESIPT) and increased π-conjugation. According to the simulated PXRD showing its eclipsed packed structure, one unit cell exhibits six reacting receptor sites, which consist of allyl and hydroxyl groups. The Hg²⁺ ions firstly bind to the hydroxyl groups, forming an Hg-containing five-membered ring, blocking the ESIPT mechanism from occurring, which finally quenches the FL intensity of the framework.

For the detection of toxic lead ions in aqueous media, a novel electrochemical sensor, named TAPB-DMTP-COF, was utilized.²⁵² This COF was formed *via* the imine condensation



of 1,3,5-tris(4-aminophenyl)benzene (TAPB) and 2,5-dimethoxy terephthaldehyde (DMTP). Lead ions were attached to the surface of TAPBDMTP-COF *via* the formation of a complex with its amine moiety. This sensor exhibited a broad linear range, ultra-stability, low detection limit and great sensitivity towards Pb^{2+} ions due to its large active sites and surface area. The wide surface area of these electrochemical sensors will provide an excellent platform in environmental monitoring and clinical diagnostic applications.

A series of imine-linked COFs, namely TaTa, DhaTab, TRITER-1 and TzDa, was utilized for the detection of Fe^{3+} ions in DMF/ H_2O (9 : 1, v/v) medium. The luminescent-active N-rich frameworks underwent strong PL quenching due to the absorption competition quenching effect of Fe^{3+} ions, with the highest quenching coefficient for DhaTab ($1.0 \times 10^5 \text{ M}^{-1}$, LOD = $0.12 \mu\text{M}$) followed by TaTa ($1.4 \times 10^4 \text{ M}^{-1}$), TRITER-1 ($5.6 \times 10^3 \text{ M}^{-1}$) and TzDa ($3.3 \times 10^3 \text{ M}^{-1}$). Moreover, a slight increase in the luminescent intensity of all four COF sensors was observed due to their strong interactions with Al^{3+} ions.²⁵³ In the following year, a new hydrazone-linked Bth-Dma COF was employed as a sensor to detect Fe^{3+} ions *via* the selective coordination of these ions with the O,N,O'-chelating sites on the pores of the framework (*vide supra*, Section 4.2).¹⁴¹ Switch-off quenching was reported with an LoD value of $0.17 \mu\text{M}$. Additionally, neither the presence of anions (Cl^- , Br^- , NO_3^- and OAc^-) nor change in pH from 4 to 10 caused a change in the quenching profile of the COF (Fig. 66d). To support the electron and energy transfer quenching mechanism,

XPS was used, which showed a decrease in the binding energy values for Bth-Dma and Bth-Dma@ Fe^{3+} (see Section 5.5). Later, Asadi *et al.* synthesised benzimidazole-linked COFs, *viz.* COF-BI-1 and COF-BI-2, which were conventionally synthesized using pyromellitic dianhydride (PMDA)/Perlin-tetracarboxylic anhydride (PTCA), 5-aminoisophthalic acid and 3,3'-diaminobenzidine, showing significant fluorescent quenching with the incremental addition of an Fe^{3+} ion solution to COF-BI-1 in THF and COF-BI-2 in DMF up to a limit of $1.3 \mu\text{M}$.²⁵⁴

An evident fluorescence “turn-on” mechanism was reported by Qiu and co-workers, where the PL intensity of the water-stable covalent organic nanosheets Bpy-NSs was enhanced with the incremental addition of Al^{3+} ions among several monovalent (Li^+ , Na^+ , K^+ , and Ag^+), divalent (Zn^{2+} , Mn^{2+} , Cd^{2+} , Cu^{2+} , Mn^{2+} , Ni^{2+} , Co^{2+} , Pb^{2+} , Ba^{2+} , and Ca^{2+}) and trivalent (Cr^{3+} and Fe^{3+}) metal ions in aqueous media.²⁵⁵ The photoluminescence intensity of the N-rich Bpy-NSs nanosheets was limited due to extensive energy dissipation by their bipyridine (Bpy) moieties, leading to photoinduced electron transfer to the phloroglucinol centres. However, the addition of Al^{3+} ions resulted in the formation of a strong Lewis acid–base coordination complex with the Bpy-core, in which the electrons occupy the lowest energy orbital, preventing the PET process. The detection limit for Al^{3+} ions was as low as $0.33 \mu\text{M}$.

The olefin-linked TFPT-BTAN-AO COF was formed *via* Knoevenagel condensation followed by post-synthetic modification through amidoximation by treating it with excess $\text{NH}_2\text{OH}\cdot\text{HCl}$ at




Fig. 66 (a) Luminescence spectra of COF-JLU3 in THF suspension containing different concentrations of Cu^{2+} (0 to $2 \times 10^{-4} \text{ M}$), $\lambda_{\text{ex}} = 400 \text{ nm}$. The inset shows the corresponding images of COF-JLU3 under UV irradiation at 365 nm before and after titration with Cu^{2+} ions. (b) Fluorescence emission spectra of CTFQD in aqueous solution at different concentrations of Hg^{2+} . (c) Fluorescence titration of AH-COF in the acetonitrile upon treatment with Hg^{2+} . (d) Fluorescence emission spectra of Bth-Dma COF at various concentrations of Fe^{3+} ions. Reproduced with permission from: (a) ref. 245, Copyright The Royal Society of Chemistry (2016); (b) ref. 250, Copyright The Royal Society of Chemistry (2017); (c) ref. 251, Copyright Elsevier (2020) and (d) ref. 141, Copyright the American Chemical Society (2019).






Fig. 67 Turn-on fluorescent sensor for the detection of biomolecules. Reproduced with permission from ref. 257, Copyright The Royal Society of Chemistry (2017).

85 °C for 24 h.²⁵⁶ This made the framework rich in –OH and –NH₂ functional groups and the material was utilized to detect uranium ions in aqueous medium. The UO₂²⁺ units reversibly bind to the N and O atoms of the amino and the hydroxyl groups, respectively, and the COF detects uranium ions up to 6.7 nM with an ultra-fast response time of 2 s. The UO₂²⁺@TFPT-BTAN-AO COF could be regenerated when dispersed in 1 M Na₂CO₃ aqueous solution as it has >95% elution efficiency for up to 6 cycles.

6.2.6 Bioanalytes. Functionalized porous COFs behave as potent biosensors if they contain the biological receptor elements and mimic biological species for their sensing in a suitable environment.

In 2017, Li *et al.* reported a biosensor, named TpTta-COF, which was solvothermally synthesized using 4,4',4''-(1,3,5-triazine-2,4,6-triyl)trianiline (Tta) and 1,3,5-triformylphloroglucinol (Tp) units.²⁵⁷ Initially, the COF was tagged with an FAM-labeled probe, which was adsorbed on its surface and inside its pores *via* H-bonding and π - π stacking interactions (Fig. 67). The carboxyfluorescein in the FAM probe shows very strong luminescence, which was quenched upon contact with COF (acceptor) *via* fluorescence resonance energy transfer (FRET). The probe (5'-FAM-TCG CTA ACC TGT TCA TCG TAG-3') was uniquely designed to be complementary to the target DNA analyte (5'-CTA CGA TGA ACA GGT TAG CGA-3'). After the DNA analyte comes in contact with the COF quenched FAM-labeled probe, the formation of double-stranded DNA occurs, resulting in complete detachment of the probe from the framework. The rapid formation and detachment process resulted in the turn-on sensing of DNA with the limit of 3.7 nM.

Peng *et al.* reported the synthesis of imine-based covalent organic nanosheets (NS), TPA-COF NSs, *via* the chemical exfoliation of TPA-COF, which was previously synthesized using tris(4-formylphenyl)amine (TFPA) and tris(4-aminophenyl)amine (TAPA)




Fig. 68 (a) Schematic representation of a TPA-COF NS-based fluorescence sensor to detect DNA. (b) Fluorescence spectra recorded with different conditions: (I) H1 + H2; (II) H1 + H2 + T + TPA-COF NSs; (III) H1 + T + TPA-COF NSs; and (IV) H1 + H2 + TPA-COF NSs. Reproduced with permission from ref. 107, Copyright the American Chemical Society (2017).

under solvothermal conditions.¹⁰⁷ The ultrathin NSs were well exploited for the highly selective and sensitive 'switch-on' sensing of DMA molecules, which mechanistically takes place exactly like the previous example in Fig. 67. Initially, two types of hairpin-like DNA probes, denoted as H1 and H2, were fabricated, one of which was FL tagged, and then allowed to adsorb on the TPA-COF nanosheets *via* π - π stacking (Fig. 68). This led to fluorescence quenching, which was again revived by the hybridization chain reaction (HCR) between the two probes on the surface of the NSs. A long double-stranded DNA (dsDNA) was formed and detached from the NSs due to the weaker p-p interactions. Furthermore, the fluorescence intensity was enhanced by increasing the concentration of the targeted DNA up to 1 nM and a good linear relation was achieved. The LoD value for DNA in this case was found to be very low, *i.e.*, 20 pM.

Myocardial infarction is a life-threatening cardiovascular disease, which can be prevented by the early detection of the biomarker cardiac troponin I (cTnI). In this direction, Zhang *et al.* reported an electrochemical immunosensor decorated with gold nanoparticles, TiO₂-PPy (TiO₂-PPy-Au).²⁵⁸ This material was efficiently employed to detect cTnI quantitatively through the signal amplification strategy (Fig. 69). Initially, TiO₂-PPy-Au was decorated with primary antibodies (AB₁) on a GCE electrode. Conversely, the Au NP-decorated COF was subjected to secondary antibodies (AB₂) and toluidine blue (TB) aromatic dye *via* its amino-groups. The two units then behave as a sandwich-type electrochemical sensor for cTnI analyte. The proposed technique displayed a linear range from 0.5 pg mL⁻¹ to 10.0 ng mL⁻¹ together with a low detection limit of 0.17 pg mL⁻¹.

In 2018, Wang *et al.* synthesized a porphyrin-based Fe-COF, which was utilized as a peroxidase mimic.²⁵⁹ The COF undergoes




Fig. 69 (a) Process for the detection of antibiotics with COF-1. (b) Procedure for the preparation of the TB-Au-COFs-Ab₂ labels. (c) Schematic illustration of the sandwich-type electrochemical immunosensor. Reproduced with permission from: (a) ref. 262, Copyright the American Chemical Society (2020) and (b) ref. 258, Copyright Elsevier (2018).



colorimetric sensing of H₂O₂ and glucose molecules up to very low detection limit of 1.1 and 1.0 μM, respectively. The mechanism of the biosensing experiment involved the oxidation of the chromogenic substrate TMB in the presence of H₂O₂, where the peroxidase-mimetic Fe-porphyrin-COF captures OH radicals upon its decomposition. This was supported by observing the color change from colorless (for TMB) to blue (for oxTMB). After this, the framework was utilized for the detection of glucose. By combining the COF with glucose oxidase (GOx), the glucose molecules were oxidized to gluconic acid with high sensitivity and selectivity.

Recently, COFs have been utilized to detect H₂S gas in living cells, tumor tissues, *etc.* to diagnose neurodegenerative diseases. The COF TpASH was formed *via* the Schiff-base condensation of 1,3,5-triformylphloroglucinol (Tp) and the PTSA salt of 4-aminosalicylhydrazide (ASH), which was then tagged with a fluorescent probe *via* post-synthetic modification.¹¹¹ The phenolic groups in TpASH were first alkylated by glycidol (Glc) on which a 4-amino-1,8-naphthalimide derivative (NPHS) was anchored. This functionalized TpASH-NPHS framework was then exfoliated chemically to yield active nanosheets for the detection of H₂S.²⁶⁰ In the presence of H₂S, the azide units present on the NPHS-modified nanoprobe were reduced to amino group, causing an enhancement in the fluorescent emission with a detection limit of 0.11 μM. In addition, the TpASH-NPHS fluorescent nanoprobe was employed to detect and image the H₂S in deep tumor tissues, HeLa and HepG2, and in a cirrhotic liver.

Furthermore, chiral COFs (CCOFs) have been proven to be promising candidates for the enantioselective recognition of chiral molecules due to the presence of chiral-functionalized crown ether units in their framework.²⁶¹ Crown ethers contain free electron pairs, and thus have the ability to form complexes with ammonium ions, binding them through H-bonds. The formation of an adduct between the immobilized crown ether and protonated amines increases the interlayer spacing among the CCOF layers by weakening the π-π interactions among them. This causes a change in fluorescent intensity.

In terms of food safety, the detection of antibiotics is necessary and provides insight in various food detection fields. Recently, attempts have been made in this direction. The green synthesis of a polyimide COF, named COF-1, was reported, showing very high luminescence at 530 nm ($\lambda_{\text{ex}} = 369 \text{ nm}$) in DMF, which is attributed to its perylene core and triazine monomeric units. Significant FL quenching was observed in the presence of the antibiotics ofloxacin and tetracycline, with a detection limit of 0.002 and 0.0065 mM, respectively, as shown in Fig. 69a.²⁶²

It is well known that antibiotics consist of various aromatic units, particularly, benzene ring units. Examples of these antibiotics are ampicillin (AMP) and enrofloxacin (ENR), which were effectively sensed by the novel pyrene-core Py-M-COF.²⁶³ This COF was constructed using melamine and TFPPy units, possessing a nanosheet-like structure, which is rich in functional groups such as amino, keto, imino and olefin groups. This enabled the framework to act as a good charge carrying probe. Moreover, the very high FL intensity of this framework is

attributed to the presence of Py cores and extended π-conjugation. The COF behaves as an electrochemical aptasensor as it was first anchored with aptamers *via* π-π stacking and electrostatic interactions. The ENR aptamers sense ENR molecules, and the AMP aptamers detect ANP molecules. There was an observable change in the confirmation and flexibility of the aptamer during the detection of AMP, whereas the ENR aptamer folded upon binding ENR. Extremely low detection limits for both antibiotics were calculated, *i.e.*, 6.07 and 0.04 fg mL⁻¹ (S/N = 3) for ENR and AMP, respectively.

6.2.7 Thermosensors. One of the essential but least explored field is the utility of COFs as thermosensors. Considering that temperature is a crucial parameter for many scientific domains, its detection by easily accessible materials is of great demand. Accordingly, Ln-grafted imine-linked COFs have been explored as temperature sensory materials. The incorporation of Ln³⁺ ions in the binding sites of COFs helps in their sensitization, provide well-separated sharp luminescent peaks, increased luminescence decay and high quantum yield values.

Voort and co-workers attempted the synthesis of the first TpBpy-COF grafted with various lanthanides (Ln³⁺ = Eu³⁺, Tb³⁺, Eu³⁺-Tb³⁺, and Dy³⁺) to serve as a heat detecting material in different temperature ranges.²⁶⁴ Initially, the TpBpy COF was synthesized solvothermally from triformylfluoroglucinol (Tp) and 2,2'-bipyridine-5,5'-diamine (Bpy), which was then implanted with different Ln³⁺ ions using Ln(acac)₃(H₂O)₂ and LnCl₃. Among them, Eu, the Eu/Tb- and Dy-grafted systems were successfully employed as ratiometric thermometers in the temperature range of 10–360 K for the former two and 280–440 K for the latter (Fig. 70). In the Eu³⁺-sensitized TpBpy-COF (labelled 1), the sharp FL peak corresponding to 610 nm (λ_{max}) with respect to the ⁵D₀ → ⁷F₂ transition gradually decreased with an increase in temperature, whereas no significant change was found for the Tb³⁺-grafted COF (labelled 2), corresponding to the ⁵D₄ → ⁷F₅ transition at the emission maximum of 548 nm. This is ascribed by the absence of Tb³⁺-to-ligand back energy transfer due to the fact that the ⁵D₄-acceptor band lies above the donor triplet level of the TpBpy ligand, which is present for the former case. In the mixed ion-grafted COF (labelled 5) with an Eu³⁺: Tb³⁺ ratio of 80:20, a similar trend was observed given that the Tb³⁺-to- Eu³⁺ energy transfer is not possible due to the long distance between the ions. Therefore, Tb³⁺ did not show any quenching effect with an increase in temperature. A visible color change from orange-red to green for 5 was observed when the temperature was increased from 60 K to 360 K. The results are highly convincing, with a thermal sensitivity of 1.403% K⁻¹ (160 K) and error bar of ~1 K above 110 K. Moreover, the Dy³⁺ hybrid TpBpy COF also showed strong luminescence (482 nm, ⁴F_{9/2} → ⁶H_{15/2} transition), which was gradually quenched with an increase in temperature from 280–440 K.

In 2020, another PP-TzDa COF was synthesized, which senses thermal changes in its environment without using Ln³⁺ ions.²⁶⁵ The PP-TzDa COF was obtained by mixing tri(4-aminophenyl)triazine and 2,5-dihydroxyterephthalaldehyde as monomers, followed by post-synthetic modification with the chloro-derivative






Fig. 70 (a) Schematic representation of TpBpy and TpBpy-Ln_acac COF materials. Emission map of (b) Tb³⁺-grafted and (c) Eu³⁺: Tb³⁺ (80 : 20)-grafted TpBy COF recorded at 10–360 K and (d) Dy³⁺-grafted TpBy COF at 280–480 K. Reproduced with permission from ref. 264, Copyright John Wiley and Sons (2020).

of 2-phenylpropionic acid. The highly emissive COF exhibits luminescence due to (a) extended π -conjugation and (b) ESIPT causing dual-emission (530 and 597 nm) due to the presence of $-\text{OH}$ groups, which further react during PSM. The emission maximum at 597 nm is sharply quenched in the temperature range of 20–100 °C in DMF with a δT higher than 0.1 °C and maximum temperature sensitivity of 0.95% per °C (Fig. 71).

According to the above-mentioned experiments, Ln³⁺-COF hybrids have been proven to be a new and emerging class of porous materials that can be exploited as luminescent thermometers. This year, another 4f-3d-grafted COF was reported, in which the TTA-DFP COF was grafted with Eu³⁺, Tb³⁺, Cu²⁺ and Ni²⁺ ions.²⁶⁶ Subsequently, this COF was subjected to Eu(tfac)₃·2H₂O or Tb(tfac)₃·2H₂O and Cu(OAc)₂ one at a time, forming the Eu,Tb@TTA-DFPCOF@Cu material. It was further used for dual-ion thermometry application in the temperature range of 0–120 °C and 20–90 °C in toluene medium before and after

co-grafting with Cu²⁺ ions, respectively. Interestingly, it was found that the Eu,Tb@TTA-DFP COF, before Cu²⁺-grafting, undergoes emission quenching with thermal sensitivity of 4.1% °C at 42 °C. Conversely, with the Cu-grafted Eu,Tb@TTA-DFP COF, there was an increase in emission intensity and good thermal uncertainty of $\delta T < 0.37$ °C in the range of 20–90 °C was observed. Being embedded with Cu²⁺/Ln³⁺ ions, this material was synchronously used as a thermometer and catalyst for the Glaser reaction.

7. Concluding remarks and future perspectives

In this review, we described the growth of COFs, starting from 2005 to date, to illustrate how this field has grown tremendously and attracted the attention of scientists at the global level. Recapitulating the main points, we briefly explained how the






Fig. 71 (left) Synthetic route to PP-TzDa. (right) Fluorescence emission spectra of PP-TzDa in DMF ($\lambda_{\text{ex}} = 460 \text{ nm}$) at 20–100 °C. Reproduced with permission from ref. 265, Copyright Elsevier (2020).

choice of monomer, oriented at a particular angle with an appropriate geometry, tailors various networks with a number of topologies. Consequently, this affects various properties of the framework such as formation of highly ordered structures, its stability towards heat, chemical exposure and moisture, surface areas and pore size. The tremendous efforts in establishing various linkages to build the featured COF were explained in this review. The classification of COFs in 2D and 3D nets was thoroughly explained in the different sections. Additionally, the effect of stacking forces on the construction of 2D COFs and the property of interpenetration in 3D COFs were elaborated with various examples. We also described the various synthetic methodologies such as room temperature, hydro-/solvothermal, microwave, ionothermal, mechanochemical, interfacial and exfoliation methods adopted for these materials. Various analytical methods including FTIR, SS NMR, PXRD, SEM/TEM, XPS, BET and TGA have been efficiently exploited to characterize and monitor the formation of the framework. The structure modeling of most COFs is done with the help of PXRD data, which helps in predicting and establishing the application of these materials. Incorporating N-rich linkages has promoted these frameworks to act as materials for the sensing of explosives, volatile organic compounds, metal ions, toxic anions, bioanalytes, temperature, pH and many more with high sensitivity and selectivity. The detection of these analytes follows several mechanisms, such as ES IPT, AIE/ACQ, PET, ICT and FRET, which were discussed in detail.

Nevertheless, there is a lot to be explored for COFs. Specifically, the three major areas further described below can provide tremendous scope for future research.

(a) Framework construction

There are many 2D and 3D frameworks reported thus far from the simplest and commonly found networks (**hcb** and **dia**) to the rarely obtained topologies (**thh** and **bcu**). Considering that the majority of COFs in the literature chose the $[C_3 + C_2]$ or $[C_3 + C_3]$ combined **hcb** net and $[C_4 + C_2]$ or $[C_4 + C_4]$ combined **dia** net, it is necessary to explore high connectivity for both 2D and 3D COFs, respectively. As a new theme, exploring discrete molecular cages as building units can provide an interesting perspective to inflate the growth of porous networks.

(b) New strategies for synthesis

Since the solvothermal approach for the formation of first COF was carried out in 2005, this synthetic method has been largely exploited to tailor the desired framework. However, method uses harsh temperature and vacuum conditions together with the choice of non-green solvents to direct the COF reaction at the laboratory scale. Furthermore, strategic planning and vision are required to understand the formation and growth of suitable single crystals. Therefore, the following aspects need special attention:

(i) There is a dire need for the large-scale synthesis of robust frameworks using greener solvents. It must be noted that the high-scale production requires ambient reaction conditions.

(ii) The mechanistic work to establish a road map has been well done for 2D COFs forming boroxine and imine linkages with a few examples explaining the supramolecular interactions between the sheets. However, a more optimized and general method is needed for their synthesis. Henceforth, similar studies should be carried out for other widely explored linkages for a better understanding of the formation of COFs.

(iii) There are only a few single crystal structures known for 3D COF materials to date. Getting insight into the structure and establishing a structure–property relationship will open many other applications for these materials. Therefore, more efforts are needed to grow single crystals of these materials.

(iv) Finally, the post-synthetic modification of COFs is still a challenge with only a few examples known. This area can be explored further to increase the performance of COFs.

(c) Sensing aspect

Compared to other porous and highly stable materials for sensing applications, COFs are less explored for a number of reasons, as stated below. Therefore, finding proper solutions to these issues will definitely bring extraordinary results for showing the usefulness of one of the best porous materials to date.

(i) It has been observed that N-rich COF nanosheets are more efficient towards sensing applications in comparison to bulk powders. However, very few COFs have been reported, which use limited synthetic methods. This area has a lot of



scope in the formation of well-dispersed nanosheets for several real-time sensing applications.

(ii) Most COFs/CONs are studied for their chemical and thermal stability with a few examples of moisture stability. However, to utilize these materials for real-life applications, their stability towards moisture is of utmost importance. Thus, the design strategies have to be improved to generate materials with this property. For sensing applications, most of the experiments are done using organic solvents. However, for real-life applications, the functioning of sensors in water must be considered.

(iv) The regeneration and reusability of a sensor are always desirable. Thus, to maximize the efficiency of COFs as sensory materials, their regeneration and reusability should also be investigated.

(v) The utilization of COFs for temperature, pH, anion and biomolecule sensing is underexplored. Furthermore, biocompatibility of COFs still needs to be determined for their use in the sensing of bioanalytes.

Abbreviations

ABN	4-Aminobenzonitrile	DMPO	5,5-Dimethyl-1-pyrroline <i>N</i> -oxide
ACN	Acetonitrile	DMTH	2,5-Dimethoxyterephthalohydrazide
APPO	3-Anilino-1-phenyl-2-propen-1-one	DMTHA	9,10-Dimethyl-2,3,6,7-tetrahydroxyanthracene
BATH	2,5-Bis(allyloxy)terephthalohydrazide	DNB	3,3'-Dinitrobenzidine
BDA	Benzene-1,4-diamine	DNP	2,4-Dinitrophenol
BDB	1,1'-Bis(2,4-dinitrophenyl)-[4,4'-bipyridine]-1,1'-diium dichloride	DPBF	1,3-Diphenylisobenzofuran
BDBA	1,4-Benzenediboronic acid	DPBP	Di(pyridin-2-yl) [1,1'-biphenyl]-4,4'-dicarboxylate
BET	Brunauer–Emmett–Teller	DPPO	3-(Dimethylamino)-1-phenyl-2-propen-1-one
BFBZ	4,7-Bis(4-formylbenzyl)-1 <i>H</i> -benzimidazole	DPT	Di(pyridin-2-yl) terephthalate
BPDA	4,4'-Biphenyldicarbaldehyde	DPTH	2,5-Bis(prop-2-yn-1-yloxy)terephthalohydrazide
BP DAN	2,2'-(Biphenyl-4,4'-diyl)diacetoneitrile	Et ₃ N	Triethylamine
BTCA	1,3,5-Benzenetricarboxaldehyde	FPBA	4-Formylphenylboronic acid
BTCH	Benzene-1,3,5-tricarbohydrazide	FTIR	Fourier Transform Infrared Spectroscopy
BTTPA	5,5',5''-(Benzene-1,3,5-triyl)tripicolinaldehyde	HHTP	2,3,6,7,10,11-Hexadhydroxytriphenylene
CC	Cyanuric chloride	HOPG	Highly oriented pyrolytic graphite
CHDA	<i>trans</i> -1,4-Cyclohexyldiamine	HTA	2-Hydroxybenzene-1,3,5-tricarbaldehyde
DAB	3,3'-Diaminobenzidine	iPrTAPB	1,3,5-Tris(4'-amino-3',5'-isopropylphenyl)benzene
DABD	2,5-Diamino-1,4-benzenediol dihydrochloride	MOP	Microporous organic polymers
DAHQ-2HCl	2,5-Diaminohydroquinone dihydrochloride	MTAB	4,4',4'',4'''-Methanetetrayltetrabenzoic acid
DBU	1,8-Diazabicyclo[5.4.0]undec-7-ene	NMP	<i>N</i> -Methyl-2-pyrrolidinone
DCTMP	3,5-Dicyano-2,4,6-trimethylpyridine	NP	2-Nitrophenol
DCTSP	3,5-Dicyano-2,4,6-tristyrylpyridine	NT	2-Nitrotoluene
DETHz	2,5-Diethoxyterephthalohydrazide	ODH	Oxalyldihydrazide
DFPBA	3,5-Diformylphenylboronic acid	OHPM	2,3,9,10,16,17,23,24-Octahydroxyphthalocyaninato metal
Dha	2,5-Dihydroxyterephthalaldehyde	PATCnC	Polyamide(4,4',4'',4'''-tetra(carboxyphenyl)methane- <i>net-trans</i> -1,4-cyclohexanediamine)
DHTA	2,4-Dihydroxybenzene-1,3,5-tricarbaldehyde	PDA	Phenylenediamine
2,3-DHTH	2,3-Dihydroxyterephthalohydrazide	PDAN	2,2'-(1,4-Phenylene)diacetoneitrile
2,5-DHTH	2,5-Dihydroxyterephthalohydrazide	PMDA	Pyromellitic dianhydride
DMA	Dimethyl acetamide	PMMA	Polymethylmethacrylate
Dma	2,5-Dimethoxyterephthalaldehyde	PT	<i>tert</i> -Butyl pyrene-tetraone
DMB	2,5-Dimethyl-1,4-benzenediamine	PTFE	Polytetrafluoroethylene
DMOB	3,3'-Dimethoxybenzidine	PXRD	Powder X-ray diffractometry
		SEM	Scanning electron microscopy
		TAA	1,3,5,7-Tetraaminoadamantane
		TAB	1,2,4,5-Tetraminobenzene
		TABPB	1,3,5-Tris[4-amino(1,1-biphenyl-4-yl)]benzene
		TA	Terephthaldehyde
		TAP	5,10,15,20-Tetrakis(4-aminophenyl)porphyrin
		TAPA	Tris(4-aminophenyl)amine
		TAPB	1,3,5-Tris(4'-aminophenyl)benzene
		TAPM	Tetra(4-aminophenyl)methane
		TAPT	1,3,5-Tris(4-aminophenyl)triazine
		TATP	Triacetone triperoxide
		TATTA	4,4',4''-(1,3,5-Triazine-2,4,6-triyl)tribenzaldehyde
		TCB	1,3,5-Tricyanobenzene
		TCTAB	1,3,5-Tricarboxylic acid-tris(4-amino-phenylamide)benzene
		TDOEB	1,3,5-Tris(3-dimethylamino-1-oxoprop-2-en-yl)benzene
		TEM	Transmission electron microscopy
		TFB	1,3,5-Triformylbenzene



TFFPB	1,3,5-Tris(3-fluoro-4-formyl phenyl)benzene
TFM	Tetrakis(4-formylphenyl)methane
TFMS	Trifluoromethanesulfonic acid
TFP	1,3,5-Triformylphloroglucinol
Tfpa	Tris(4-formylphenyl)amine
TFFPB	1,3,5-Tris(4'-formylphenyl)benzene
TFPC	2,3,5,6-Tetrafluoro-4-pyridinecarbonitrile
TFPC	Tri(4-formylphenoxy)cyanurate
TFPN	Tetrafluorophthalonitrile
TFPPy	1,3,6,8-Tetrakis(4-formylphenyl)pyrene
TFPT	1,3,5-Tris(4-formyl-phenyl)triazine
THA	Terephthalohydrazide
THAT	4,6-Trihydroxybenzene-1,3,5-tricarbaldehyde
THPB	1,3,5-Tris(4-hydroxyphenyl)benzene
THPE	Tetrakis(4-hydroxyphenyl)ethylene
Thz	Terephthalicdihydrazide
TICPB	1,3,5-Tris(4-isocyanophenyl)benzene
TGA	Thermogravimetric Analysis
TMA	Trimesic acid
TMEDA	Tetramethylethylenediamine
TMOS	Tetramethylorthosilicate
TMSCN	Trimethylsilyl cyanide
TMTA	2,4,6-Trimethyl-1,3,5-triazine
TNP	2,4,6-Trinitrophenol
Tp	1,3,5-Triformylphloroglucinol
TPDAN	2,2'-([1,1':4',1''-Terphenyl]-4,4''-diyl)diacetonitrile
TPHA	Triphenylene hexamine
TPT-3CHO	2,4,6-Tris(4-formylphenyl)triazine
TST	2,4,6-Tri((E)-styryl)-1,3,5-triazine
XPS	X-ray photoelectron spectroscopy

Author contributions

All authors contributed to the organization and writing of this manuscript. Its final version was approved by all authors.

Note after first publication

This article replaces the version published on 23rd November 2021, which contained errors in Table 3.

Conflicts of interest

There are no conflicts to declare.

Acknowledgements

H. B. is grateful to the UGC of India for a research fellowship. Sakshi is grateful to MHRD, India for a research fellowship.

Notes and references

1 W. B. Jensen, *J. Chem. Educ.*, 2008, **85**, 624.

- H. Staudinger and J. Fritsch, *Helv. Chim. Acta*, 1922, **5**, 785–806.
- J.-F. Lutz, M. Ouchi, D. R. Liu and M. Sawamoto, *Science*, 2013, **341**, 1238149.
- A. P. Cote, A. I. Benin, N. W. Ockwig, M. O'Keeffe, A. J. Matzger and O. M. Yaghi, *Science*, 2005, **310**, 1166–1170.
- B. J. Smith and W. R. Dichtel, *J. Am. Chem. Soc.*, 2014, **136**, 8783–8789.
- T. Ma, E. A. Kapustin, S. X. Yin, L. Liang, Z. Zhou, J. Niu, L.-H. Li, Y. Wang, J. Su, J. Li, X. Wang, W. D. Wang, W. Wang, J. Sun and O. M. Yaghi, *Science*, 2018, **361**, 48–52.
- B. C. Patra, S. Khilari, R. N. Manna, S. Mondal, D. Pradhan, A. Pradhan and A. Bhaumik, *ACS Catal.*, 2017, **7**, 6120–6127.
- J. Guo and D. Jiang, *ACS Cent. Sci.*, 2020, **6**, 869–879.
- K. Zhang, K. O. Kirlikovali, R. S. Varma, Z. Jin, H. W. Jang, O. K. Farha and M. Shokouhimehr, *ACS Appl. Mater. Interfaces*, 2020, **12**, 27821–27852.
- W. Wang, V. S. Kale, Z. Cao, S. Kandambeth, W. Zhang, J. Ming, P. T. Parvatkar, E. Abou-Hamad, O. Shekhah, L. Cavallo, M. Eddaoudi and H. N. Alshareef, *ACS Energy Lett.*, 2020, **5**, 2256–2264.
- Y. Song, Q. Sun, B. Aguila and S. Ma, *Adv. Sci.*, 2019, **6**, 1801410.
- X. Liu, D. Huang, C. Lai, G. Zeng, L. Qin, H. Wang, H. Yi, B. Li, S. Liu, M. Zhang, R. Deng, Y. Fu, L. Li, W. Xue and S. Chen, *Chem. Soc. Rev.*, 2019, **48**, 5266–5302.
- T. Skorjanc, D. Shetty and M. Valant, *ACS Sens.*, 2021, **6**, 1461–1481.
- X. Chen, K. Geng, R. Liu, K. T. Tan, Y. Gong, Z. Li, S. Tao, Q. Jiang and D. Jiang, *Angew. Chem., Int. Ed.*, 2020, **59**, 5050–5091.
- E. L. Spitler and W. R. Dichtel, *Nat. Chem.*, 2010, **2**, 672–677.
- L. Liang, Y. Qiu, W. D. Wang, J. Han, Y. Luo, W. Yu, G. Yin, Z. Wang, L. Zhang, J. Ni, J. Niu, J. Sun, T. Ma and W. Wang, *Angew. Chem., Int. Ed.*, 2020, **59**, 17991–17995.
- S. Wan, J. Guo, J. Kim, H. Ihee and D. Jiang, *Angew. Chem., Int. Ed.*, 2009, **48**, 5439–5442.
- E. L. Spitler, B. T. Koo, J. L. Novotney, J. W. Colson, F. J. Uribe-Romo, G. D. Gutierrez, P. Clancy and W. R. Dichtel, *J. Am. Chem. Soc.*, 2011, **133**, 19416–19421.
- P. Katekomol, J. Roeser, M. Bojdys, J. Weber and A. Thomas, *Chem. Mater.*, 2013, **25**, 1542–1548.
- P. Kuhn, M. Antonietti and A. Thomas, *Angew. Chem., Int. Ed.*, 2008, **47**, 3450–3453.
- W. Huang, J. Byun, I. Rörich, C. Ramanan, P. W. M. Blom, H. Lu, D. Wang, L. Caire da Silva, R. Li, L. Wang, K. Landfester and K. A. I. Zhang, *Angew. Chem., Int. Ed.*, 2018, **57**, 8316–8320.
- F. J. Uribe-Romo, C. J. Doonan, H. Furukawa, K. Oisaki and O. M. Yaghi, *J. Am. Chem. Soc.*, 2011, **133**, 11478–11481.
- A. P. Côté, H. M. El-Kaderi, H. Furukawa, J. R. Hunt and O. M. Yaghi, *J. Am. Chem. Soc.*, 2007, **129**, 12914–12915.
- P. Das and S. K. Mandal, *J. Mater. Chem. A*, 2018, **6**, 16246–16256.
- S.-Q. Xu, T.-G. Zhan, Q. Wen, Z.-F. Pang and X. Zhao, *ACS Macro Lett.*, 2016, **5**, 99–102.
- S. Dalapati, M. Addicoat, S. Jin, T. Sakurai, J. Gao, H. Xu, S. Irle, S. Seki and D. Jiang, *Nat. Commun.*, 2015, **6**, 7786.



- 27 L. Ascherl, T. Sick, J. T. Margraf, S. H. Lapidus, M. Calik, C. Hettstedt, K. Karaghiosoff, M. Döblinger, T. Clark, K. W. Chapman, F. Auras and T. Bein, *Nat. Chem.*, 2016, **8**, 310–316.
- 28 T.-Y. Zhou, S.-Q. Xu, Q. Wen, Z.-F. Pang and X. Zhao, *J. Am. Chem. Soc.*, 2014, **136**, 15885–15888.
- 29 S. Dalapati, E. Jin, M. Addicoat, T. Heine and D. Jiang, *J. Am. Chem. Soc.*, 2016, **138**, 5797–5800.
- 30 Y. Wu, H. Xu, X. Chen, J. Gao and D. Jiang, *Chem. Commun.*, 2015, **51**, 10096–10098.
- 31 L. Wang, C. Zeng, H. Xu, P. Yin, D. Chen, J. Deng, M. Li, N. Zheng, C. Gu and Y. Ma, *Chem. Sci.*, 2019, **10**, 1023–1028.
- 32 A. Cuevas, I. Viera, M. H. Torre, E. Kremer, S. B. Etcheverry and E. J. Baran, *Afinidad*, 1999, **56**, 263–265.
- 33 S.-Q. Xu, R.-R. Liang, T.-G. Zhan, Q.-Y. Qi and X. Zhao, *Chem. Commun.*, 2017, **53**, 2431–2434.
- 34 B. Zhang, H. Mao, R. Matheu, J. A. Reimer, S. A. Alshimri, S. Alshihri and O. M. Yaghi, *J. Am. Chem. Soc.*, 2019, **141**, 11420–11424.
- 35 B. Nath, W.-H. Li, J.-H. Huang, G.-E. Wang, Z. Fu, M.-S. Yao and G. Xu, *CrystEngComm*, 2016, **18**, 4259–4263.
- 36 C. Qian, Q.-Y. Qi, G.-F. Jiang, F.-Z. Cui, Y. Tian and X. Zhao, *J. Am. Chem. Soc.*, 2017, **139**, 6736–6743.
- 37 Y. Du, H. Yang, J. M. Whiteley, S. Wan, Y. Jin, S.-H. Lee and W. Zhang, *Angew. Chem., Int. Ed.*, 2016, **55**, 1737–1741.
- 38 S.-Y. Jiang, S.-X. Gan, X. Zhang, H. Li, Q.-Y. Qi, F.-Z. Cui, J. Lu and X. Zhao, *J. Am. Chem. Soc.*, 2019, **141**, 14981–14986.
- 39 T. Banerjee, F. Haase, S. Trenker, B. P. Biswal, G. Savasci, V. Duppel, I. Moudrakovski, C. Ochsenfeld and B. V. Lotsch, *Nat. Commun.*, 2019, **10**, 2689.
- 40 H. L. Nguyen, N. Hanikel, S. J. Lyle, C. Zhu, D. M. Proserpio and O. M. Yaghi, *J. Am. Chem. Soc.*, 2020, **142**, 2218–2221.
- 41 S.-L. Cai, Z.-H. He, X.-L. Li, K. Zhang, S.-R. Zheng, J. Fan, Y. Liu and W.-G. Zhang, *Chem. Commun.*, 2019, **55**, 13454–13457.
- 42 X. Guan, F. Chen, Q. Fang and S. Qiu, *Chem. Soc. Rev.*, 2020, **49**, 1357–1384.
- 43 C. Bonneau, O. Delgado-Friedrichs, M. O’Keeffe and O. M. Yaghi, *Acta Crystallogr., Sect. A: Found. Crystallogr.*, 2004, **60**, 517–520.
- 44 Q. Fang, J. Wang, S. Gu, R. B. Kaspar, Z. Zhuang, J. Zheng, H. Guo, S. Qiu and Y. Yan, *J. Am. Chem. Soc.*, 2015, **137**, 8352–8355.
- 45 H. M. El-Kaderi, J. R. Hunt, J. L. Mendoza-Cortes, A. P. Cote, R. E. Taylor, M. O’Keeffe and O. M. Yaghi, *Science*, 2007, **316**, 268–272.
- 46 G. Lin, H. Ding, D. Yuan, B. Wang and C. Wang, *J. Am. Chem. Soc.*, 2016, **138**, 3302–3305.
- 47 Y. Xie, J. Li, C. Lin, B. Gui, C. Ji, D. Yuan, J. Sun and C. Wang, *J. Am. Chem. Soc.*, 2021, **143**, 7279–7284.
- 48 Y. Zhang, J. Duan, D. Ma, P. Li, S. Li, H. Li, J. Zhou, X. Ma, X. Feng and B. Wang, *Angew. Chem., Int. Ed.*, 2017, **56**, 16313–16317.
- 49 O. Yahiaoui, A. N. Fitch, F. Hoffmann, M. Fröba, A. Thomas and J. Roeser, *J. Am. Chem. Soc.*, 2018, **140**, 5330–5333.
- 50 X. Kang, X. Wu, X. Han, C. Yuan, Y. Liu and Y. Cui, *Chem. Sci.*, 2020, **11**, 1494–1502.
- 51 X. Kang, X. Han, C. Yuan, C. Cheng, Y. Liu and Y. Cui, *J. Am. Chem. Soc.*, 2020, **142**, 16346–16356.
- 52 H. L. Nguyen, C. Gropp, Y. Ma, C. Zhu and O. M. Yaghi, *J. Am. Chem. Soc.*, 2020, **142**, 20335–20339.
- 53 H. Li, J. Ding, X. Guan, F. Chen, C. Li, L. Zhu, M. Xue, D. Yuan, V. Valtchev, Y. Yan, S. Qiu and Q. Fang, *J. Am. Chem. Soc.*, 2020, **142**, 13334–13338.
- 54 Y. Wang, C. Wu, W. Sun, Q. Pan, W. Hao, H. Liu, J. Sun, Z. Li, J. Sun and Y. Zhao, *Mater. Chem. Front.*, 2021, **5**, 944–949.
- 55 Q. Zhu, X. Wang, R. Clowes, P. Cui, L. Chen, M. A. Little and A. I. Cooper, *J. Am. Chem. Soc.*, 2020, **142**, 16842–16848.
- 56 Z. Li, L. Sheng, H. Wang, X. Wang, M. Li, Y. Xu, H. Cui, H. Zhang, H. Liang, H. Xu and X. He, *J. Am. Chem. Soc.*, 2021, **143**, 92–96.
- 57 C. Gropp, T. Ma, N. Hanikel and O. M. Yaghi, *Science*, 2020, **370**, eabd6406.
- 58 F. Haase and B. V. Lotsch, *Chem. Soc. Rev.*, 2020, **49**, 8469–8500.
- 59 L. M. Lanni, R. W. Tilford, M. Bharathy and J. J. Lavigne, *J. Am. Chem. Soc.*, 2011, **133**, 13975–13983.
- 60 K. T. Jackson, T. E. Reich and H. M. El-Kaderi, *Chem. Commun.*, 2012, **48**, 8823.
- 61 J. R. Hunt, C. J. Doonan, J. D. LeVangie, A. P. Côté and O. M. Yaghi, *J. Am. Chem. Soc.*, 2008, **130**, 11872–11873.
- 62 B. Zhang, M. Wei, H. Mao, X. Pei, S. A. Alshimri, J. A. Reimer and O. M. Yaghi, *J. Am. Chem. Soc.*, 2018, **140**, 12715–12719.
- 63 C. Zhao, H. Lyu, Z. Ji, C. Zhu and O. M. Yaghi, *J. Am. Chem. Soc.*, 2020, **142**, 14450–14454.
- 64 Y. Zeng, R. Zou, Z. Luo, H. Zhang, X. Yao, X. Ma, R. Zou and Y. Zhao, *J. Am. Chem. Soc.*, 2015, **137**, 1020–1023.
- 65 H. Wang, C. Qian, J. Liu, Y. Zeng, D. Wang, W. Zhou, L. Gu, H. Wu, G. Liu and Y. Zhao, *J. Am. Chem. Soc.*, 2020, **142**, 4862–4871.
- 66 R.-R. Liang, R.-H. A, S.-Q. Xu, Q.-Y. Qi and X. Zhao, *J. Am. Chem. Soc.*, 2020, **142**, 70–74.
- 67 S. Kandambeth, A. Mallick, B. Lukose, M. V. Mane, T. Heine and R. Banerjee, *J. Am. Chem. Soc.*, 2012, **134**, 19524–19527.
- 68 P. Das and S. K. Mandal, *Chem. Mater.*, 2019, **31**, 1584–1596.
- 69 D. A. Pyles, J. W. Crowe, L. A. Baldwin and P. L. McGrier, *ACS Macro Lett.*, 2016, **5**, 1055–1058.
- 70 P. J. Waller, Y. S. AlFaraj, C. S. Diercks, N. N. Jarennattananon and O. M. Yaghi, *J. Am. Chem. Soc.*, 2018, **140**, 9099–9103.
- 71 W. Liu, X. Luo, Y. Bao, Y. P. Liu, G.-H. Ning, I. Abdelwahab, L. Li, C. T. Nai, Z. G. Hu, D. Zhao, B. Liu, S. Y. Quek and K. P. Loh, *Nat. Chem.*, 2017, **9**, 563–570.
- 72 W. Liu, M. Ulaganathan, I. Abdelwahab, X. Luo, Z. Chen, S. J. Rong Tan, X. Wang, Y. Liu, D. Geng, Y. Bao, J. Chen and K. P. Loh, *ACS Nano*, 2018, **12**, 852–860.
- 73 D. Zhou, X. Tan, H. Wu, L. Tian and M. Li, *Angew. Chem., Int. Ed.*, 2019, **58**, 1376–1381.
- 74 S. Wu, M. Li, H. Phan, D. Wang, T. S. Heng, J. Ding, Z. Lu and J. Wu, *Angew. Chem., Int. Ed.*, 2018, **57**, 8007–8011.



- 75 D. L. Paoletto, S. Xu, M. Borrelli, M. Addicoat, B. P. Biswal, S. Paasch, A. Dianat, H. Thomas, R. Berger, S. Reineke, E. Brunner, G. Cuniberti, M. Richter and X. Feng, *Angew. Chem., Int. Ed.*, 2020, **59**, 23620–23625.
- 76 J. Hu, S. K. Gupta, J. Ozdemir and M. H. Beyzavi, *ACS Appl. Nano Mater.*, 2020, **3**, 6239–6269.
- 77 L. Bourda, C. Krishnaraj, P. Van Der Voort and K. Van Hecke, *Mater. Adv.*, 2021, **2**, 2811–2845.
- 78 S. B. Alahakoon, S. D. Diwakara, C. M. Thompson and R. A. Smaldone, *Chem. Soc. Rev.*, 2020, **49**, 1344–1356.
- 79 A. Halder, S. Kandambeth, B. P. Biswal, G. Kaur, N. C. Roy, M. Addicoat, J. K. Salunke, S. Banerjee, K. Vanka, T. Heine, S. Verma and R. Banerjee, *Angew. Chem., Int. Ed.*, 2016, **55**, 7806–7810.
- 80 A. Halder, S. Karak, M. Addicoat, S. Bera, A. Chakraborty, S. H. Kunjattu, P. Pachfule, T. Heine and R. Banerjee, *Angew. Chem., Int. Ed.*, 2018, **57**, 5797–5802.
- 81 C. Zhao, C. S. Diercks, C. Zhu, N. Hanikel, X. Pei and O. M. Yaghi, *J. Am. Chem. Soc.*, 2018, **140**, 16438–16441.
- 82 F. J. Uribe-Romo, J. R. Hunt, H. Furukawa, C. Klöck, M. O’Keeffe and O. M. Yaghi, *J. Am. Chem. Soc.*, 2009, **131**, 4570–4571.
- 83 B. P. Biswal, S. Chandra, S. Kandambeth, B. Lukose, T. Heine and R. Banerjee, *J. Am. Chem. Soc.*, 2013, **135**, 5328–5331.
- 84 H. Wei, S. Chai, N. Hu, Z. Yang, L. Wei and L. Wang, *Chem. Commun.*, 2015, **51**, 12178–12181.
- 85 X. Guan, Y. Ma, H. Li, Y. Yusran, M. Xue, Q. Fang, Y. Yan, V. Valtchev and S. Qiu, *J. Am. Chem. Soc.*, 2018, **140**, 4494–4498.
- 86 D. Stewart, D. Antypov, M. S. Dyer, M. J. Pitcher, A. P. Katsoulidis, P. A. Chater, F. Blanc and M. J. Rosseinsky, *Nat. Commun.*, 2017, **8**, 1102.
- 87 Z. Li, X. Ding, Y. Feng, W. Feng and B.-H. Han, *Macromolecules*, 2019, **52**, 1257–1265.
- 88 D. Beaudoin, T. Maris and J. D. Wuest, *Nat. Chem.*, 2013, **5**, 830–834.
- 89 Y.-B. Zhang, J. Su, H. Furukawa, Y. Yun, F. Gándara, A. Duong, X. Zou and O. M. Yaghi, *J. Am. Chem. Soc.*, 2013, **135**, 16336–16339.
- 90 B. Hou, S. Yang, K. Yang, X. Han, X. Tang, Y. Liu, J. Jiang and Y. Cui, *Angew. Chem.*, 2021, **133**, 6151–6158.
- 91 T. Ma, J. Li, J. Niu, L. Zhang, A. S. Etman, C. Lin, D. Shi, P. Chen, L.-H. Li, X. Du, J. Sun and W. Wang, *J. Am. Chem. Soc.*, 2018, **140**, 6763–6766.
- 92 C. Gao, J. Li, S. Yin, J. Sun and C. Wang, *J. Am. Chem. Soc.*, 2020, **142**, 3718–3723.
- 93 L. Zhu and Y.-B. Zhang, *Molecules*, 2017, **22**, 1149.
- 94 G. Das, D. Balaji Shinde, S. Kandambeth, B. P. Biswal and R. Banerjee, *Chem. Commun.*, 2014, **50**, 12615–12618.
- 95 N. L. Campbell, R. Clowes, L. K. Ritchie and A. I. Cooper, *Chem. Mater.*, 2009, **21**, 204–206.
- 96 W. Ji, Y.-S. Guo, H.-M. Xie, X. Wang, X. Jiang and D.-S. Guo, *J. Hazard. Mater.*, 2020, **397**, 122793.
- 97 A. de la Peña Ruigómez, D. Rodríguez-San-Miguel, K. C. Stylianou, M. Cavallini, D. Gentili, F. Liscio, S. Milita, O. M. Roscioni, M. L. Ruiz-González, C. Carbonell, D. MasPOCH, R. Mas-Ballesté, J. L. Segura and F. Zamora, *Chem. – Eur. J.*, 2015, **21**, 10666–10670.
- 98 D. Rodríguez-San-Miguel, A. Yazdi, V. Guillerme, J. Pérez-Carvajal, V. Puentes, D. MasPOCH and F. Zamora, *Chem. – Eur. J.*, 2017, **23**, 8623–8627.
- 99 T. Shiraki, G. Kim and N. Nakashima, *Chem. Lett.*, 2015, **44**, 1488–1490.
- 100 K. Dey, M. Pal, K. C. Rout, S. Kunjattu, H. A. Das, R. Mukherjee, U. K. Kharul and R. Banerjee, *J. Am. Chem. Soc.*, 2017, **139**, 13083–13091.
- 101 X.-H. Liu, C.-Z. Guan, S.-Y. Ding, W. Wang, H.-J. Yan, D. Wang and L.-J. Wan, *J. Am. Chem. Soc.*, 2013, **135**, 10470–10474.
- 102 J. I. Feldblyum, C. H. McCreery, S. C. Andrews, T. Kurosawa, E. J. G. Santos, V. Duong, L. Fang, A. L. Ayzner and Z. Bao, *Chem. Commun.*, 2015, **51**, 13894–13897.
- 103 A. Gogia, P. Das and S. K. Mandal, *ACS Appl. Mater. Interfaces*, 2020, **12**, 46107–46118.
- 104 G. Li, K. Zhang and T. Tsuru, *ACS Appl. Mater. Interfaces*, 2017, **9**, 8433–8436.
- 105 I. Berlanga, M. L. Ruiz-González, J. M. González-Calbet, J. L. G. Fierro, R. Mas-Ballesté and F. Zamora, *Small*, 2011, **7**, 1207–1211.
- 106 D. N. Bunck and W. R. Dichtel, *J. Am. Chem. Soc.*, 2013, **135**, 14952–14955.
- 107 Y. Peng, Y. Huang, Y. Zhu, B. Chen, L. Wang, Z. Lai, Z. Zhang, M. Zhao, C. Tan, N. Yang, F. Shao, Y. Han and H. Zhang, *J. Am. Chem. Soc.*, 2017, **139**, 8698–8704.
- 108 S. Chandra, S. Kandambeth, B. P. Biswal, B. Lukose, S. M. Kunjir, M. Chaudhary, R. Babarao, T. Heine and R. Banerjee, *J. Am. Chem. Soc.*, 2013, **135**, 17853–17861.
- 109 S. Wang, Q. Wang, P. Shao, Y. Han, X. Gao, L. Ma, S. Yuan, X. Ma, J. Zhou, X. Feng and B. Wang, *J. Am. Chem. Soc.*, 2017, **139**, 4258–4261.
- 110 M. A. Khayum, S. Kandambeth, S. Mitra, S. B. Nair, A. Das, S. S. Nagane, R. Mukherjee and R. Banerjee, *Angew. Chem., Int. Ed.*, 2016, **55**, 15604–15608.
- 111 S. Mitra, H. S. Sasmal, T. Kundu, S. Kandambeth, K. Illath, D. Díaz Díaz and R. Banerjee, *J. Am. Chem. Soc.*, 2017, **139**, 4513–4520.
- 112 S. Haldar, K. Roy, S. Nandi, D. Chakraborty, D. Puthusseri, Y. Gawli, S. Ogale and R. Vaidhyanathan, *Adv. Energy Mater.*, 2018, **8**, 1702170.
- 113 S. Mitra, S. Kandambeth, B. P. Biswal, A. Khayum, M. C. K. Choudhury, M. Mehta, G. Kaur, S. Banerjee, A. Prabhune, S. Verma, S. Roy, U. K. Kharul and R. Banerjee, *J. Am. Chem. Soc.*, 2016, **138**, 2823–2828.
- 114 H. Singh, M. Devi, N. Jena, M. M. Iqbal, Y. Nailwal, A. De Sarkar and S. K. Pal, *ACS Appl. Mater. Interfaces*, 2020, **12**, 13248–13255.
- 115 R. P. Bisbey, C. R. DeBlase, B. J. Smith and W. R. Dichtel, *J. Am. Chem. Soc.*, 2016, **138**, 11433–11436.
- 116 Y. Peng, W. K. Wong, Z. Hu, Y. Cheng, D. Yuan, S. A. Khan and D. Zhao, *Chem. Mater.*, 2016, **28**, 5095–5101.
- 117 J. W. Colson, A. R. Woll, A. Mukherjee, M. P. Levendorf, E. L. Spitzer, V. B. Shields, M. G. Spencer, J. Park and W. R. Dichtel, *Science*, 2011, **332**, 228–231.
- 118 M. J. Bojdys, J. Jeromenok, A. Thomas and M. Antonietti, *Adv. Mater.*, 2010, **22**, 2202–2205.



- 119 S. Ren, M. J. Bojdys, R. Dawson, A. Laybourn, Y. Z. Khimiyak, D. J. Adams and A. I. Cooper, *Adv. Mater.*, 2012, **24**, 2357–2361.
- 120 Y. Zhao, K. X. Yao, B. Teng, T. Zhang and Y. Han, *Energy Environ. Sci.*, 2013, **6**, 3684.
- 121 L. Hao, J. Ning, B. Luo, B. Wang, Y. Zhang, Z. Tang, J. Yang, A. Thomas and L. Zhi, *J. Am. Chem. Soc.*, 2015, **137**, 219–225.
- 122 M. G. Rabbani, A. K. Sekizkardes, Z. Kahveci, T. E. Reich, R. Ding and H. M. El-Kaderi, *Chem. – Eur. J.*, 2013, **19**, 3324–3328.
- 123 S. Yan, X. Guan, H. Li, D. Li, M. Xue, Y. Yan, V. Valtchev, S. Qiu and Q. Fang, *J. Am. Chem. Soc.*, 2019, **141**, 2920–2924.
- 124 P. Das and S. K. Mandal, *ACS Appl. Mater. Interfaces*, 2021, **13**, 14160–14168.
- 125 P. Das, G. Chakraborty, S. Tyagi and S. K. Mandal, *ACS Appl. Mater. Interfaces*, 2020, **12**, 52527–52537.
- 126 Y.-F. Xie, S.-Y. Ding, J.-M. Liu, W. Wang and Q.-Y. Zheng, *J. Mater. Chem. C*, 2015, **3**, 10066–10069.
- 127 J.-Y. Yue, X.-H. Liu, B. Sun and D. Wang, *Chem. Commun.*, 2015, **51**, 14318–14321.
- 128 R. Gomes, P. Bhanja and A. Bhaumik, *Chem. Commun.*, 2015, **51**, 10050–10053.
- 129 S.-Y. Ding, X.-H. Cui, J. Feng, G. Lu and W. Wang, *Chem. Commun.*, 2017, **53**, 11956–11959.
- 130 T. Kundu, J. Wang, Y. Cheng, Y. Du, Y. Qian, G. Liu and D. Zhao, *Dalton Trans.*, 2018, **47**, 13824–13829.
- 131 C. Qian, W. Zhou, J. Qiao, D. Wang, X. Li, W. L. Teo, X. Shi, H. Wu, J. Di, H. Wang, G. Liu, L. Gu, J. Liu, L. Feng, Y. Liu, S. Y. Quek, K. P. Loh and Y. Zhao, *J. Am. Chem. Soc.*, 2020, **142**, 18138–18149.
- 132 X. Wu, Y. Hong, B. Xu, Y. Nishiyama, W. Jiang, J. Zhu, G. Zhang, S. Kitagawa and S. Horike, *J. Am. Chem. Soc.*, 2020, **142**, 14357–14364.
- 133 K. Gottschling, G. Savasci, H. Vignolo-González, S. Schmidt, P. Mauker, T. Banerjee, P. Rovó, C. Ochsenfeld and B. V. Lotsch, *J. Am. Chem. Soc.*, 2020, **142**, 12146–12156.
- 134 D.-M. Li, S.-Y. Zhang, J.-Y. Wan, W.-Q. Zhang, Y.-L. Yan, X.-H. Tang, S.-R. Zheng, S.-L. Cai and W.-G. Zhang, *CrysrEngComm*, 2021, **23**, 3594–3601.
- 135 Y. Lu, Y. Liang, Y. Zhao, M. Xia, X. Liu, T. Shen, L. Feng, N. Yuan and Q. Chen, *ACS Appl. Mater. Interfaces*, 2021, **13**, 1644–1650.
- 136 Y. Li, C. Wang, S. Ma, H. Zhang, J. Ou, Y. Wei and M. Ye, *ACS Appl. Mater. Interfaces*, 2019, **11**, 11706–11714.
- 137 Z. Li, N. Huang, K. H. Lee, Y. Feng, S. Tao, Q. Jiang, Y. Nagao, S. Irle and D. Jiang, *J. Am. Chem. Soc.*, 2018, **140**, 12374–12377.
- 138 S. Jiang, L. Meng, W. Ma, G. Pan, W. Zhang, Y. Zou, L. Liu, B. Xu and W. Tian, *Mater. Chem. Front.*, 2021, **5**, 4193–4201.
- 139 K. Gottschling, L. Stegbauer, G. Savasci, N. A. Prisco, Z. J. Berkson, C. Ochsenfeld, B. F. Chmelka and B. V. Lotsch, *Chem. Mater.*, 2019, **31**, 1946–1955.
- 140 G. J. Chen, X. B. Li, C. C. Zhao, H. C. Ma, J. L. Kan, Y. Bin Xin, C. X. Chen and Y. Bin Dong, *Inorg. Chem.*, 2018, **57**, 2678–2685.
- 141 G. Chen, H. H. Lan, S. L. Cai, B. Sun, X. Le Li, Z. H. He, S. R. Zheng, J. Fan, Y. Liu and W. G. Zhang, *ACS Appl. Mater. Interfaces*, 2019, **11**, 12830–12837.
- 142 H. Zhao, Z. Jin, H. Su, X. Jing, F. Sun and G. Zhu, *Chem. Commun.*, 2011, **47**, 6389.
- 143 C. R. DeBlase, K. E. Silberstein, T.-T. Truong, H. D. Abruña and W. R. Dichtel, *J. Am. Chem. Soc.*, 2013, **135**, 16821–16824.
- 144 Y. Zhang, X. Shen, X. Feng, H. Xia, Y. Mu and X. Liu, *Chem. Commun.*, 2016, **52**, 11088–11091.
- 145 D. Kaleeswaran, P. Vishnoi and R. Murugavel, *J. Mater. Chem. C*, 2015, **3**, 7159–7171.
- 146 M. S. Lohse, T. Stassin, G. Naudin, S. Wuttke, R. Ameloot, D. De Vos, D. D. Medina and T. Bein, *Chem. Mater.*, 2016, **28**, 626–631.
- 147 P. Pachfule, A. Acharjya, J. Roeser, T. Langenhahn, M. Schwarze, R. Schomäcker, A. Thomas and J. Schmidt, *J. Am. Chem. Soc.*, 2018, **140**, 1423–1427.
- 148 M. Zhang, L. Li, Q. Lin, M. Tang, Y. Wu and C. Ke, *J. Am. Chem. Soc.*, 2019, **141**, 5154–5158.
- 149 G. Das, B. P. Biswal, S. Kandambeth, V. Venkatesh, G. Kaur, M. Addicoat, T. Heine, S. Verma and R. Banerjee, *Chem. Sci.*, 2015, **6**, 3931–3939.
- 150 Y. Liu, Y. Wang, H. Li, X. Guan, L. Zhu, M. Xue, Y. Yan, V. Valtchev, S. Qiu and Q. Fang, *Chem. Sci.*, 2019, **10**, 10815–10820.
- 151 J. Guo, Y. Xu, S. Jin, L. Chen, T. Kaji, Y. Honsho, M. A. Addicoat, J. Kim, A. Saeki, H. Ihee, S. Seki, S. Irle, M. Hiramoto, J. Gao and D. Jiang, *Nat. Commun.*, 2013, **4**, 2736.
- 152 S. Dalapati, S. Jin, J. Gao, Y. Xu, A. Nagai and D. Jiang, *J. Am. Chem. Soc.*, 2013, **135**, 17310–17313.
- 153 Z. Li, X. Feng, Y. Zou, Y. Zhang, H. Xia, X. Liu and Y. Mu, *Chem. Commun.*, 2014, **50**, 13825–13828.
- 154 P. Das, G. Chakraborty and S. K. Mandal, *ACS Appl. Mater. Interfaces*, 2020, **12**, 10224–10232.
- 155 A. Nagai, X. Chen, X. Feng, X. Ding, Z. Guo and D. Jiang, *Angew. Chem., Int. Ed.*, 2013, **52**, 3770–3774.
- 156 Q. Fang, Z. Zhuang, S. Gu, R. B. Kaspar, J. Zheng, J. Wang, S. Qiu and Y. Yan, *Nat. Commun.*, 2014, **5**, 4503.
- 157 K. M. Gupta, K. Zhang and J. Jiang, *Ind. Eng. Chem. Res.*, 2018, **57**, 6477–6482.
- 158 X. Zhuang, W. Zhao, F. Zhang, Y. Cao, F. Liu, S. Bi and X. Feng, *Polym. Chem.*, 2016, **7**, 4176–4181.
- 159 S. Wei, F. Zhang, W. Zhang, P. Qiang, K. Yu, X. Fu, D. Wu, S. Bi and F. Zhang, *J. Am. Chem. Soc.*, 2019, **141**, 14272–14279.
- 160 H. Lyu, C. S. Diercks, C. Zhu and O. M. Yaghi, *J. Am. Chem. Soc.*, 2019, **141**, 6848–6852.
- 161 J. Xu, Y. He, S. Bi, M. Wang, P. Yang, D. Wu, J. Wang and F. Zhang, *Angew. Chem., Int. Ed.*, 2019, **58**, 12065–12069.
- 162 B. C. Patra, S. Khilari, L. Satyanarayana, D. Pradhan and A. Bhaumik, *Chem. Commun.*, 2016, **52**, 7592–7595.
- 163 S. Kim and H. C. Choi, *Commun. Chem.*, 2019, **2**, 60.
- 164 A. F. M. El-Mahdy, Y. Hung, T. H. Mansoure, H. Yu, T. Chen and S. Kuo, *Chem. – Asian J.*, 2019, **14**, 1429–1435.
- 165 J. Roeser, D. Prill, M. J. Bojdys, P. Fayon, A. Trewin, A. N. Fitch, M. U. Schmidt and A. Thomas, *Nat. Chem.*, 2017, **9**, 977–982.
- 166 G. Das, T. Skorjanc, S. K. Sharma, F. Gándara, M. Lusi, D. S. Shankar Rao, S. Vimala, S. Krishna Prasad, J. Raya, D. S. Han, R. Jagannathan, J.-C. Olsen and A. Trabolsi, *J. Am. Chem. Soc.*, 2017, **139**, 9558–9565.



- 167 G. Das, T. Skorjanc, T. Prakasam, S. Nuryyeva, J.-C. Olsen and A. Trabolsi, *RSC Adv.*, 2017, **7**, 3594–3598.
- 168 T. Skorjanc, D. Shetty, F. Gándara, L. Ali, J. Raya, G. Das, M. A. Olson and A. Trabolsi, *Chem. Sci.*, 2020, **11**, 845–850.
- 169 T. Skorjanc, D. Shetty, S. K. Sharma, J. Raya, H. Traboulsi, D. S. Han, J. Lalla, R. Newlon, R. Jagannathan, S. Kirmizialtin, J.-C. Olsen and A. Trabolsi, *Chem. – Eur. J.*, 2018, **24**, 8648–8655.
- 170 F. Haase, E. Troschke, G. Savasci, T. Banerjee, V. Duppel, S. Dörfler, M. M. J. Grundei, A. M. Burow, C. Ochsenfeld, S. Kaskel and B. V. Lotsch, *Nat. Commun.*, 2018, **9**, 2600.
- 171 M. Lu, M. Zhang, C.-G. Liu, J. Liu, L. Shang, M. Wang, J. Chang, S. Li and Y. Lan, *Angew. Chem., Int. Ed.*, 2021, **60**, 4864–4871.
- 172 J. Liu, T. Yang, Z.-P. Wang, P.-L. Wang, J. Feng, S.-Y. Ding and W. Wang, *J. Am. Chem. Soc.*, 2020, **142**, 20956–20961.
- 173 B. J. Smith, N. Hwang, A. D. Chavez, J. L. Novotney and W. R. Dichtel, *Chem. Commun.*, 2015, **51**, 7532–7535.
- 174 M. Calik, T. Sick, M. Dogru, M. Döblinger, S. Datz, H. Budde, A. Hart Schuh, F. Auras and T. Bein, *J. Am. Chem. Soc.*, 2016, **138**, 1234–1239.
- 175 B. J. Smith, L. R. Parent, A. C. Overholts, P. A. Beaucage, R. P. Bisbey, A. D. Chavez, N. Hwang, C. Parl, A. M. Evans, N. C. Gianneschi and W. R. Dichtel, *J. Am. Chem. Soc.*, 2016, **138**, 1234–1239.
- 176 A. M. Evans, L. R. Parent, N. C. Flanders, R. P. Bisbey, E. Vitaku, M. S. Kirschner, R. D. Schaller, L. X. Chen, N. C. Gianneschi and W. R. Dichtel, *Science*, 2018, **361**, 52–57.
- 177 B. J. Smith, A. C. Overholts, N. Hwang and W. R. Dichtel, *Chem. Commun.*, 2016, **52**, 3690–3693.
- 178 W. Zhao, J. Qiao, T. Ning and X. Liu, *Chin. J. Polym. Sci.*, 2018, **36**, 1–7.
- 179 D. Zhu, L. B. Alemany, W. Guo and R. Verduso, *Polym. Chem.*, 2020, **11**, 4464–4468.
- 180 W. Liu, X. Li, C. Wang, H. Pan, W. Liu, K. Wang, Q. Zeng, R. Wang and J. Jiang, *J. Am. Chem. Soc.*, 2019, **141**, 17431–17440.
- 181 S. T. Emmerling, L. S. Germann, P. A. Julien, J. Moudra, M. Etter, T. Frišćić, R. E. Dinnebier and B. V. Lotsch, *Chem*, 2021, **7**, 1639–1652.
- 182 C. H. Feriante, S. Jhulki, A. M. Evans, R. R. Dasari, K. Slicker, W. R. Dichtel and S. R. Marder, *Adv. Mater.*, 2020, **32**, 1905776.
- 183 Z. Zha, L. Xu, Z. Wang, X. Li, Q. Pan, P. Hu and S. Lei, *ACS Appl. Mater. Interfaces*, 2015, **7**, 17837–17843.
- 184 P. J. Waller, S. J. Lyle, T. M. Osborn Popp, C. S. Diercks, J. A. Reimer and O. M. Yaghi, *J. Am. Chem. Soc.*, 2016, **138**, 15519–15522.
- 185 M. Herrmann, P. B. Kempa, H. Fietzek, T. Altenburg, A. Polyzoidis, C. G. Piscopo and S. Löbbecke, *Chem. Ing. Tech.*, 2016, **88**, 967–970.
- 186 W. Ma, Q. Zheng, Y. He, G. Li, W. Guo, Z. Lin and L. Zhang, *J. Am. Chem. Soc.*, 2019, **141**, 18271–18277.
- 187 B. Gole, V. Stepanenko, S. Rager, M. Grüne, D. D. Medina, T. Bein, F. Würthner and F. Beuerle, *Angew. Chem., Int. Ed.*, 2018, **57**, 846–850.
- 188 S. Wang, Z. Zhang, H. Zhang, A. G. Rajan, N. Xu, Y. Yang, Y. Zeng, P. Liu, X. Zhang, Q. Mao, Y. He, J. Zhao, B.-G. Li, M. S. Strano and W.-J. Wang, *Matter*, 2019, **1**, 1592–1605.
- 189 S. He, T. Zeng, S. Wang, H. Niu and Y. Cai, *ACS Appl. Mater. Interfaces*, 2017, **9**, 2959–2965.
- 190 Z. Lu, Y. Liu, X. Liu, S. Lu, Y. Li, S. Yang, Y. Qin, L. Zheng and H. Zhang, *J. Mater. Chem. B*, 2019, **7**, 1469–1474.
- 191 X. H. Xiong, Z. W. Yu, L. Le Gong, Y. Tao, Z. Gao, L. Wang, W. H. Yin, L. X. Yang and F. Luo, *Adv. Sci.*, 2019, **6**, 1900547.
- 192 D. B. Shinde, H. B. Aiyappa, M. Bhadra, B. P. Biswal, P. Wadge, S. Kandambeth, B. Garai, T. Kundu, S. Kurungot and R. Banerjee, *J. Am. Chem. Soc.*, 2016, **4**, 2682–2690.
- 193 P. Pachfule, S. Kandambeth, A. Mallick and R. Banerjee, *Chem. Commun.*, 2015, **51**, 11717–11720.
- 194 J. Tan, S. Namuangruk, W. Kong, N. Kungwan, J. Guo and C. Wang, *Angew. Chem., Int. Ed.*, 2016, **55**, 13979–13984.
- 195 Y. Liu, Y. Ma, Y. Zhao, X. Sun, F. Gandara, H. Furukawa, Z. Liu, H. Zhu, C. Zhu, K. Suenaga, P. Oleynikov, A. S. Alshammari, X. Zhang, O. Terasaki and O. M. Yaghi, *Science*, 2016, **351**, 365–369.
- 196 M. Thommes, K. Kaneko, A. V. Neimark, J. P. Olivier, F. Rodriguez-Reinoso, J. Rouquerol and K. S. W. Sing, *Pure Appl. Chem.*, 2015, **87**, 1051–1069.
- 197 L. A. Baldwin, J. W. Crowe, D. A. Pyles and P. L. McGrier, *J. Am. Chem. Soc.*, 2016, **138**, 15134–15137.
- 198 R. W. Tilford, S. J. Mugavero, P. J. Pellechia and J. J. Lavigne, *Adv. Mater.*, 2008, **20**, 2741–2746.
- 199 Y. Yamaguchi, Y. Matsubara, T. Ochi, T. Wakamiya and Z. Yoshida, *J. Am. Chem. Soc.*, 2008, **130**, 16442.
- 200 Y. Zhao, H. Liu, C. Wu, Z. Zhang, Q. Pan, F. Hu, R. Wang, P. Li, X. Huang and Z. Li, *Angew. Chem., Int. Ed.*, 2019, **58**, 5376–5381.
- 201 M. R. Rao, Y. Fang, S. De Feyter and D. F. Perepichka, *J. Am. Chem. Soc.*, 2017, **139**, 2421–2427.
- 202 E. Jin, J. Li, K. Geng, Q. Jiang, H. Xu, Q. Xu and D. Jiang, *Nat. Commun.*, 2018, **9**, 4143.
- 203 Y. Hong, J. W. Y. Lam and B. Z. Tang, *Chem. Soc. Rev.*, 2011, **40**, 5361.
- 204 J. Mei, Y. Hong, J. W. Y. Lam, A. Qin, Y. Tang and B. Z. Tang, *Adv. Mater.*, 2014, **26**, 5429–5479.
- 205 Z. Chi, X. Zhang, B. Xu, X. Zhou, C. Ma, Y. Zhang, S. Liu and J. Xu, *Chem. Soc. Rev.*, 2012, **41**, 3878–3896.
- 206 H. Ding, J. Li, G. Xie, G. Lin, R. Chen, Z. Peng, C. Yang, B. Wang, J. Sun and C. Wang, *Nat. Commun.*, 2018, **9**, 5234.
- 207 Z.-F. Pang, S.-Q. Xu, T.-Y. Zhou, R.-R. Liang, T.-G. Zhan and X. Zhao, *J. Am. Chem. Soc.*, 2016, **138**, 4710–4713.
- 208 Y. Tian, S.-Q. Xu, C. Qian, Z.-F. Pang, G.-F. Jiang and X. Zhao, *Chem. Commun.*, 2016, **52**, 11704–11707.
- 209 J. Dong, X. Li, S. B. Peh, Y. Di Yuan, Y. Wang, D. Ji, S. Peng, G. Liu, S. Ying, D. Yuan, J. Jiang, S. Ramakrishna and D. Zhao, *Chem. Mater.*, 2019, **31**, 146–160.
- 210 Z.-F. Pang, T.-Y. Zhou, R.-R. Liang, Q.-Y. Qi and X. Zhao, *Chem. Sci.*, 2017, **8**, 3866–3870.
- 211 S. Wan, J. Guo, J. Kim, H. Ihee and D. Jiang, *Angew. Chem., Int. Ed.*, 2008, **47**, 8826–8830.
- 212 J. W. Crowe, L. A. Baldwin and P. L. McGrier, *J. Am. Chem. Soc.*, 2016, **138**, 10120–10123.
- 213 L. Stegbauer, S. Zech, G. Savasci, T. Banerjee, F. Podjaski, K. Schwinghammer, C. Ochsenfeld and B. V. Lotsch, *Adv. Energy Mater.*, 2018, **8**, 1703278.



- 214 M. G. Mohamed, C.-C. Lee, A. F. M. EL-Mahdy, J. Lüder, M.-H. Yu, Z. Li, Z. Zhu, C.-C. Chueh and S.-W. Kuo, *J. Mater. Chem. A*, 2020, **8**, 11448–11459.
- 215 Z. Li, S. Han, C. Li, P. Shao, H. Xia, H. Li, X. Chen, X. Feng and X. Liu, *J. Mater. Chem. A*, 2020, **8**, 8706–8715.
- 216 L. Ascherl, E. W. Evans, J. Gorman, S. Orsborne, D. Bessinger, T. Bein, R. H. Friend and F. Auras, *J. Am. Chem. Soc.*, 2019, **141**, 15693–15699.
- 217 A. Weller, *Naturwissenschaften*, 1955, **42**, 175–176.
- 218 L. Chen, P. Fu, H. Wang and M. Pan, *Adv. Opt. Mater.*, 2021, 2001952.
- 219 R. Ali, R. C. Gupta, S. K. Dwivedi and A. Misra, *New J. Chem.*, 2018, **42**, 11746–11754.
- 220 B. P. R. Aradhyula, R. V. Ranga Naidu Chinta, K. Dhanunjayarao and K. Venkatasubbaiah, *RSC Adv.*, 2020, **10**, 13149–13154.
- 221 K. Sakai, S. Takahashi, A. Kobayashi, T. Akutagawa, T. Nakamura, M. Dosen, M. Kato and U. Nagashima, *Dalton Trans.*, 2010, **39**, 1989.
- 222 H.-L. Qian, C. Dai, C.-X. Yang and X.-P. Yan, *ACS Appl. Mater. Interfaces*, 2017, **9**, 24999–25005.
- 223 H.-Q. Yin, F. Yin and X.-B. Yin, *Chem. Sci.*, 2019, **10**, 11103–11109.
- 224 S. Haldar, D. Chakraborty, B. Roy, G. Banappanavar, K. Rinku, D. Mullangi, P. Hazra, D. Kabra and R. Vaidhyanathan, *J. Am. Chem. Soc.*, 2018, **140**, 13367–13374.
- 225 X. Li, Q. Gao, J. Wang, Y. Chen, Z.-H. Chen, H.-S. Xu, W. Tang, K. Leng, G.-H. Ning, J. Wu, Q.-H. Xu, S. Y. Quek, Y. Lu and K. P. Loh, *Nat. Commun.*, 2018, **9**, 2335.
- 226 X. Guo, T. Mao, Z. Wang, P. Cheng, Y. Chen, S. Ma and Z. Zhang, *ACS Cent. Sci.*, 2020, **6**, 787–794.
- 227 J. R. Lakowicz, *Principles of Fluorescence Spectroscopy*, Springer, New York, USA, 3rd edn, 2006.
- 228 R. Gomes and A. Bhaumik, *RSC Adv.*, 2016, **6**, 28047–28054.
- 229 J. F. Wyman, M. P. Serve, D. W. Hobson, L. H. Lee and D. “E” Uddin, *J. Toxicol. Environ. Health*, 1992, **37**, 313–327.
- 230 A. Dutta, A. Singh, X. Wang, A. Kumar and J. Liu, *CryscEngComm*, 2020, **22**, 7736–7781.
- 231 M. S. Lohse and T. Bein, *Adv. Funct. Mater.*, 2018, **28**, 1705553.
- 232 W. Zhang, L.-G. Qiu, Y.-P. Yuan, A.-J. Xie, Y.-H. Shen and J.-F. Zhu, *J. Hazard. Mater.*, 2012, **221–222**, 147–154.
- 233 C. Zhang, S. Zhang, Y. Yan, F. Xia, A. Huang and Y. Xian, *ACS Appl. Mater. Interfaces*, 2017, **9**, 13415–13421.
- 234 L. Chen, L. He, F. Ma, W. Liu, Y. Wang, M. A. Silver, L. Chen, L. Zhu, D. Gui, J. Diwu, Z. Chai and S. Wang, *ACS Appl. Mater. Interfaces*, 2018, **10**, 15364–15368.
- 235 X. Wu, X. Zhang, Y. Li, B. Wang, Y. Li and L. Chen, *J. Mater. Sci.*, 2021, **56**, 2717–2724.
- 236 Y. Yang, Z. Zhao, Y. Yan, G. Li and C. Hao, *New J. Chem.*, 2019, **43**, 9274–9279.
- 237 Y. Wang, Z. Zhao, G. Li, Y. Yan and C. Hao, *J. Mol. Model.*, 2018, **24**, 153.
- 238 M. Hussain, X. Song, S. Shah and C. Hao, *Spectrochim. Acta, Part A*, 2020, **224**, 117432.
- 239 F.-Z. Cui, J.-J. Xie, S.-Y. Jiang, S.-X. Gan, D.-L. Ma, R.-R. Liang, G.-F. Jiang and X. Zhao, *Chem. Commun.*, 2019, **55**, 4550–4553.
- 240 Y. Nailwal, A. D. D. Wonanke, M. A. Addicoat and S. K. Pal, *Macromolecules*, 2021, **53**, 6595–6604.
- 241 Y. Liu, X. Yan, H.-S. Lu, W.-D. Zhang, Y.-X. Shi and Z.-G. Gu, *Sens. Actuators, B*, 2020, **323**, 128708.
- 242 M. Li, Z. Cui, S. Pang, L. Meng, D. Ma, Y. Li, Z. Shi and S. Feng, *J. Mater. Chem. C*, 2019, **7**, 11919–11925.
- 243 D. Huang, X. Liu, C. Lai, L. Qin, C. Zhang, H. Yi, G. Zeng, B. Li, R. Deng, S. Liu and Y. Zhang, *Microchim. Acta*, 2019, **186**, 31.
- 244 J. Zhang, X. Sun and J. Wu, *Appl. Sci.*, 2019, **9**, 489.
- 245 Z. Li, Y. Zhang, H. Xia, Y. Mu and X. Liu, *Chem. Commun.*, 2016, **52**, 6613–6616.
- 246 Y. Cai, Y. Jiang, L. Feng, Y. Hua, H. Liu, C. Fan, M. Yin, S. Li, X. Lv and H. Wang, *Anal. Chim. Acta*, 2019, **1057**, 88–97.
- 247 Y. Xiong, L. Su, X. He, Z. Duan, Z. Zhang, Z. Chen, W. Xie, D. Zhu and Y. Luo, *Sens. Actuators, B*, 2017, **253**, 384–391.
- 248 W.-R. Cui, C.-R. Zhang, W. Jiang, R.-P. Liang, S.-H. Wen, D. Peng and J.-D. Qiu, *ACS Sustainable Chem. Eng.*, 2019, **7**, 9408–9415.
- 249 S.-Y. Ding, M. Dong, Y.-W. Wang, Y.-T. Chen, H.-Z. Wang, C.-Y. Su and W. Wang, *J. Am. Chem. Soc.*, 2016, **138**, 3031–3037.
- 250 Y. Zhu, M. Qiao, W. Peng, Y. Li, G. Zhang, F. Zhang, Y. Li and X. Fan, *J. Mater. Chem. A*, 2017, **5**, 9272–9278.
- 251 Y. Yu, G. Li, J. Liu and D. Yuan, *Chem. Eng. J.*, 2020, **401**, 126139.
- 252 T. Zhang, C. Gao, W. Huang, Y. Chen, Y. Wang and J. Wang, *Talanta*, 2018, **188**, 578–583.
- 253 L.-L. Wang, C.-X. Yang and X.-P. Yan, *Sci. China: Chem.*, 2018, **61**, 1470–1474.
- 254 P. Asadi, M. Falsafin and M. Dinari, *J. Mol. Struct.*, 2021, **1227**, 129546.
- 255 W.-R. Cui, C.-R. Zhang, W. Jiang, R.-P. Liang and J.-D. Qiu, *ACS Appl. Nano Mater.*, 2019, **2**, 5342–5349.
- 256 W.-R. Cui, C.-R. Zhang, W. Jiang, F.-F. Li, R.-P. Liang, J. Liu and J.-D. Qiu, *Nat. Commun.*, 2020, **11**, 436.
- 257 W. Li, C.-X. Yang and X.-P. Yan, *Chem. Commun.*, 2017, **53**, 11469–11471.
- 258 T. Zhang, N. Ma, A. Ali, Q. Wei, D. Wu and X. Ren, *Biosens. Bioelectron.*, 2018, **119**, 176–181.
- 259 J. Wang, X. Yang, T. Wei, J. Bao, Q. Zhu and Z. Dai, *ACS Appl. Bio Mater.*, 2018, **1**, 382–388.
- 260 P. Wang, F. Zhou, C. Zhang, S.-Y. Yin, L. Teng, L. Chen, X.-X. Hu, H.-W. Liu, X. Yin and X.-B. Zhang, *Chem. Sci.*, 2018, **9**, 8402–8408.
- 261 X. Wu, X. Han, Q. Xu, Y. Liu, C. Yuan, S. Yang, Y. Liu, J. Jiang and Y. Cui, *J. Am. Chem. Soc.*, 2019, **141**, 7081–7089.
- 262 N. Zhao, J.-M. Liu, F.-E. Yang, S.-W. Lv, J. Wang and S. Wang, *ACS Appl. Bio Mater.*, 2021, **4**, 995–1002.
- 263 M. Wang, M. Hu, J. Liu, C. Guo, D. Peng, Q. Jia, L. He, Z. Zhang and M. Du, *Biosens. Bioelectron.*, 2019, **132**, 8–16.
- 264 A. M. Kaczmarek, Y. Liu, M. K. Kaczmarek, H. Liu, F. Artizzu, L. D. Carlos and P. Van Der Voort, *Angew. Chem., Int. Ed.*, 2020, **59**, 1932–1940.
- 265 M. Huang, J. Chong, C. Hu and Y. Yang, *Inorg. Chem. Commun.*, 2020, **119**, 108094.
- 266 A. M. Kaczmarek, H. S. Jena, C. Krishnaraj, H. Rijckaert, S. K. P. Veerapandian, A. Meijerink and P. Van Der Voort, *Angew. Chem., Int. Ed.*, 2021, **60**, 3727–3736.

