



# To what extent could water isotopic measurements help us understand model biases in the water cycle over Western Siberia

V. Gryazin<sup>1,2</sup>, C. Risi<sup>3</sup>, J. Jouzel<sup>1</sup>, N. Kurita<sup>4</sup>, J. Worden<sup>5</sup>, C. Frankenberg<sup>5</sup>, V. Bastrikov<sup>1,2,6</sup>, K. Gribanov<sup>2</sup>, and O. Stukova<sup>2</sup>

<sup>1</sup>Laboratoire des Sciences du Climat et de l'Environnement (LSCE/IPSL CEA-CNRS-UVSQ), CEA Saclay, Gif-sur-Yvette, France

<sup>2</sup>Institute of Natural Science, Ural Federal University, Ekaterinburg, Russia

<sup>3</sup>Laboratoire de Météorologie Dynamique, Institut Pierre Simon Laplace, Centre National de la Recherche Scientifique, Paris, France

<sup>4</sup>Graduate School of Environmental Studies, Nagoya University Furo-cho, Chikusa-ku, Nagoya, Japan

<sup>5</sup>Jet Propulsion Laboratory, California Institute of Technology, Pasadena, California, USA

<sup>6</sup>Institute of Industrial Ecology UB RAS, Ekaterinburg, Russia

Correspondence to: V. Gryazin (victor.gryazin@gmail.com)

Received: 14 December 2013 – Published in Atmos. Chem. Phys. Discuss.: 20 February 2014

Revised: 26 July 2014 – Accepted: 21 August 2014 – Published: 17 September 2014

**Abstract.** We evaluate the isotopic composition of water vapor and precipitation simulated by the LMDZ (Laboratoire de Météorologie Dynamique-Zoom) GCM (General Circulation Model) over Siberia using several data sets: TES (Tropospheric Emission Spectrometer) and GOSAT (Greenhouse gases Observing SATellite) satellite observations of tropospheric water vapor, GNIP (Global Network for Isotopes in Precipitation) and SNIP (Siberian Network for Isotopes in Precipitation) precipitation networks, and daily, in situ measurements of water vapor and precipitation at the Kourovka site in Western Siberia. LMDZ captures the spatial, seasonal and daily variations reasonably well, but it underestimates humidity ( $q$ ) in summer and overestimates  $\delta D$  in the vapor and precipitation in all seasons. The performance of LMDZ is put in the context of other isotopic models from the SWING2 (Stable Water Intercomparison Group phase 2) models. There is significant spread among models in the simulation of  $\delta D$ , and of the  $\delta D$ - $q$  relationship. This confirms that  $\delta D$  brings additional information compared to  $q$  only. We specifically investigate the added value of water isotopic measurements to interpret the warm and dry bias featured by most GCMs over mid and high latitude continents in summer. The analysis of the slopes in  $\delta D$ - $q$  diagrams and of processes controlling  $\delta D$  and  $q$  variations suggests that the cause of the dry bias could be either a problem in the

large-scale advection transporting too much dry and warm air from the south, or too strong boundary-layer mixing. However,  $\delta D$ - $q$  diagrams using the available data do not tell the full story. Additional measurements would be needed, or a more sophisticated theoretical framework would need to be developed.

## 1 Introduction

General circulation models (GCMs) have persistent and systematic biases in the representation of modern climate and its associated water cycle (Meehl et al., 2007). One example of these biases is the systematic warm and dry bias over mid latitude continental regions in summer, which is evident especially in the Great Plains of the United States and in Central and Eastern Europe (Kittel et al., 1997; Cattiaux et al., 2013). This bias may reflect a misrepresentation of the water cycle, land-surface feedbacks (Moberg and Jones, 2004; Bellprat et al., 2013), or cloud feedbacks (Boé, 2013; Cattiaux et al., 2013). This misrepresentation casts some doubts on the climate projections simulated for these regions. In particular, there is evidence for a link between the dry and warm bias in mid-latitude continents in summer for present-day and future projections of evapotranspiration (Boé and Terray, 2008) and

temperature extremes (Boberg and Christensen, 2012; Christensen and Boberg, 2012). Credible climate projections thus require a correct simulation of the present-day climate, water cycle, and associated processes.

Several approaches have been proposed to investigate the persistent warm and dry bias over mid-latitude continents in summer. Sensitivity tests on the model physics have shown that biases can be reduced by improving parameterizations or tuning parameters related to the representation of soil processes (Polcher et al., 1996; Cheruy et al., 2013). Experiments performed running GCMs in forecast mode with a realistic initialization of meteorological variables have also suggested that the bias is associated with land-surface interactions (Klein et al., 2006). Here, we investigate to what extent comparing the simulated water stable isotopic composition of water vapor to measurements can help us diagnose the source of model biases over continental regions in summer.

The water molecule has several isotopologues. The most common isotopologue is  $\text{H}_2^{16}\text{O}$  (hereafter called  $\text{H}_2\text{O}$ ), but heavier isotopologues are also found:  $\text{HD}^{16}\text{O}$  (hereafter called HDO, with D standing for deuterium) and  $\text{H}_2^{18}\text{O}$ . The water vapor isotopic composition (e.g., the concentration in HDO and  $\text{H}_2^{18}\text{O}$  with respect to  $\text{H}_2\text{O}$ ) is affected during phase changes and conserved during transport. Therefore, the water vapor composition records the various evaporation and condensation processes undergone within an air parcel throughout its history. For example, oceanic evaporation and continental evapotranspiration leave different imprints on the water vapor composition (Salati et al., 1979; Gat and Matsui, 1991; Risi et al., 2013; Simonin et al., 2013). Water vapor and subsequent precipitation is further affected by large-scale circulation (Frankenberg et al., 2009; Galewsky and Hurley, 2010) and convective and cloud processes (Bony et al., 2008; Risi et al., 2008; Yoshimura et al., 2010). In turn, water vapor isotopic measurements can help diagnose biases in the way models simulate the water cycle. For example, isotopic measurements have been used to understand systematic biases in the precipitation frequency in the tropics (Lee et al., 2009) and in subtropical tropospheric humidity (Risi et al., 2012a; Risi et al., 2012b). If biases in evapotranspiration, in large-scale moisture transport or in cloud processes contribute to the dry and warm model biases over continental regions in summer, then water isotopic measurements may help diagnose them.

Before we can operationally use water isotopic measurements to diagnose causes of model biases, the first step is to understand what controls the water isotopic composition. In this paper, we focus on this first step, and give insight on how water isotopic measurements could be used for model evaluation. With this aim, we exploit a new set of continuous isotopic measurements in low-level atmospheric water vapor and precipitation at Kourovka (70 km northwest from Ekaterinburg) near the western boundary of Western Siberia. This data set is complemented by satellite measurements (Worden

et al., 2007; Frankenberg et al., 2013) and compared with existing isotopic GCMs. In particular, using the LMDZ (Laboratoire de Météorologie Dynamique-Zoom) GCM (Risi et al., 2010c), processes controlling water isotopic composition are investigated and sources of model–data mismatches are discussed.

In Sect. 2, data sets and models are described. In Sect. 3, the LMDZ GCM is evaluated against satellite and precipitation network data and its performance is put in a broader context through comparison with other GCMs. The ability of LMDZ to represent the water cycle is evaluated in Sect. 4 using continuous measurements of water isotopic composition in Kourovka. In Sect. 5, physical processes controlling water vapor and precipitation composition are investigated. We discuss the results and conclude in Sect. 6.

## 2 Data and methods

### 2.1 Isotopic definitions

Isotope ratios are commonly reported relative to a standard in  $\delta$ -notation:

$$\delta = (R_{\text{sample}} / R_{\text{standard}} - 1) \cdot 1000,$$

where the standard used is Vienna Standard Mean Ocean Water (VSMOW),  $\delta$  represents either  $\delta D$  or  $\delta^{18}\text{O}$  expressed in ‰, and  $R$  is the ratio of HDO or of  $\text{H}_2^{18}\text{O}$  to  $\text{H}_2\text{O}$ .

Deuterium excess is defined with respect to the global meteoric water line (GMWL,  $\delta D = 8 \cdot \delta^{18}\text{O} + 10\text{‰}$ ) (Dansgaard, 1964):  $d \text{ excess} = \delta D - 8 \cdot \delta^{18}\text{O}$ . Values that fall on the GMWL have a  $d$  excess of 10‰ by definition. Since equilibrium Rayleigh condensation processes roughly follow the GMWL slope of 8, deviations in  $d$  excess can provide information about the environmental conditions during non-equilibrium processes.

### 2.2 Model simulations

#### 2.2.1 LMDZ model and simulations

The dynamical equations of the GCM LMDZ are discretized in a latitude–longitude grid, with a resolution of  $2.5^\circ \times 3.75^\circ$  and 39 vertical levels. The time step for the resolution of the dynamical equations is 1 min. We use the fourth version of LMDZ (called LMDZ4) which was used for CMIP3 (Coupled Model Intercomparison Project Phase 3, Meehl et al. (2007) feeding the fourth IPCC (International Panel on Climate Change) report. The physical package is described in detail by Hourdin et al. (2006) and called every 30 min. Each grid cell is divided into four sub-surfaces: ocean, land, ice sheet and sea ice.

To ensure a realistic large-scale circulation and daily variability, horizontal winds at each vertical level are nudged by ECMWF reanalyses (Uppala et al., 2005).

**Table 1.** List of sensitivity tests using the LMDZ-ORCHIDEE model.

Simulation name	Parameter change	Isotopic fractionation during bare soil evaporation
OR	none	yes
ORnofrac	none	no
ORrveg	The stomatal resistant is divided by 5	yes
ORhumcste	The characteristic depth of the root profile is multiplied by 4	yes
ORDpu	The soil reservoir capacity is divided by 2.	yes
ORBaresoil	The bare soil fraction as a function of leaf area index is calculated using d'Orgeval (2006) rather than Ducoudré et al. (1993), which leads to an increase in the bare soil fraction.	yes

**Table 2.** List of the SWING2 models used in this study, their respective expended names and references for isotopic implementation and simulations. Whether the winds are nudged by reanalyses or not (“free”) is also indicated.

GCM	Expended name	Reference	Nudged or free
GISS Model	Goddard Institute for Space Studies	Schmidt et al. (2007)	both
ECHAM4	European Centre Hamburg Model	Hoffmann et al. (1998)	nudged
LMDZ4	Laboratoire de Météorologie Dynamique-Zoom version 4	Risi et al. (2010c)	both
GSM	Global Spectral Model	Yoshimura et al. (2008)	nudged
CAM2	Community Atmospheric Model version 2	Lee et al. (2007)	free
HadAM	Hadley Centre Atmospheric Model	Tindall et al. (2009)	free
MIROC	Model for Interdisciplinary Research On Climate	Kurita et al. (2011)	free

Isotopologues of water ( $\text{H}_2^{16}\text{O}$ ,  $\text{H}_2^{18}\text{O}$  and HDO) are transported and passively mixed by the large-scale advection and various air mass fluxes. Fractionation is considered during condensation into droplets and ice crystals, ocean evaporation and evaporation of rain drops (Bony et al., 2008). The isotope-enabled version of the GCM LMDZ is described in detail by Risi et al. (2010c).

### 2.2.2 Representation of the land surface

The land surface in LMDZ is represented as a simple bucket model. Land surface evaporation is calculated as a single flux, represents all components of evapotranspiration. No distinction is made between transpiration, bare soil evaporation, or evaporation of water intercepted by the canopy. For water isotopes, we assume that transpiration is the dominant component of evapotranspiration (e.g., Williams et al., 2004; Jasechko et al., 2013). This approximation is especially reasonable in Siberia (Iijima et al., 2014). No fractionation is associated with transpiration (Washburn and Smith, 1934; Barnes and Allison, 1988). Thus we neglect fractionation during evapotranspiration, as in most GCMs (e.g., Hoffmann et al., 1998).

To quantify the impact of neglecting fractionating evaporation, we use a few additional simulations in which LMDZ is coupled with a more sophisticated, state-of-the-art land-surface scheme called ORCHIDEE (Organising Carbon and

Hydrology in Dynamic Ecosystems, Ducoudré et al., 1993; Krinner et al., 2005) enabled with water isotopes (Risi, 2009; Risi et al., 2013). We do not use these LMDZ-ORCHIDEE simulations in the core of the paper because these simulations are available for the year 2006 only (after sufficient spin-up in perpetual 2006 conditions). Using LMDZ-ORCHIDEE, we compare simulations in which fractionation during bare soil evaporation is activated or disabled.

The representation of land surface is much simpler than in current coupled models used for CMIP3 (Meehl et al., 2007) or CMIP5 (Taylor et al., 2012). Therefore, some of the conclusions reached in this paper regarding the role of land surface processes might be model-dependent and specific to GCMs with very simple land surface schemes. To check to what extent our results are sensitive to the representation of the land surface, we perform different sensitivity tests on land surface parameters, as listed in Table 1. These sensitivity tests were described in Risi et al. (2013) and were shown to result in large differences in evapotranspiration and in  $\delta D$  variability (Risi et al., 2013).

### 2.2.3 SWING2 models and simulations

To put LMDZ results into a broader context, we compare with other isotopic GCM simulations archived in the SWING2 (Stable Water INtercomparison Group phase 2) database (<http://people.su.se/~cstur/SWING2/>). We use nine

simulations from seven models (listed in Table 2). Some simulations are nudged by reanalyses and some others are not. More details about these SWING2 simulations can be found in Risi et al. (2012b). We use all available years (between 10 and 30) to calculate climatological averages. The choice of the time period used for the climatological average has a very small impact since all models have at least 20 years available over the past few decades.

## 2.3 Observational data sets

### 2.3.1 Water vapor measurements at Kourovka

The measurements of atmospheric surface water vapor isotopic composition are performed by the Picarro isotopic analyzer L2130-i based on wavelength-scanned cavity ring down spectroscopy (WS-CRDS). This instrument was installed in the Kourovka astronomical observatory (57.037° N, 59.547° E, 300 m above sea level). The observatory is located 70 km northwest of Ekaterinburg in a forest region. Air is sampled at 8 m height. The instrument has provided continuous measurements of specific humidity ( $q$ ),  $\delta D$  and  $\delta^{18}\text{O}$  since 1 April 2012, and we use data up to the end of 2012.

The instrumental uncertainty is conservatively estimated to be 1.4‰ for  $\delta D$  and 0.23‰ for  $\delta^{18}\text{O}$ , respectively (Steen-Larsen et al., 2013). However, at low humidity levels (<1500 ppmv) the instrument reveals a strong increase in uncertainty estimated to be 5.6‰ for  $\delta D$  and 0.92‰ for  $\delta^{18}\text{O}$  at 1000–1500 ppmv and 11.2‰ for  $\delta D$  and 1.84‰ for  $\delta^{18}\text{O}$  at 500–1000 ppmv (Bastrikov et al., 2014). The measurements below 500 ppmv are considered to be beyond the instrument measuring capabilities and are not used in the analysis.

From June 2012 until September 2012, the Picarro calibration system was not working properly due to a leakage. For this reason, the data obtained during this period are associated with a reduced accuracy. We thus use the  $\delta D$  measurements only, for which this higher uncertainty is acceptable. After the replacement of the faulty elements on 18 September 2012, the instrument has revealed good stability and reliability. A detailed overview of the WS-CRDS measurement system setup, calibration, and maintenance can be found in Bastrikov et al. (2014). In summary, every 6 hours of ambient air measurements are followed by a two-standards calibration lasting 30 min for each reference water standard using Picarro Standards Delivery Module. The liquid standards are vaporized at 140 °C using Picarro Vaporizer Module A0211, then mixed with dried room-air desiccated with Drierite (W.A. Hammond Drierite Company, Ltd., USA) and measured by the analyzer. The water standards are calibrated on the VSMOW-SLAP (Vienna Standard Mean Ocean Water-Standard Light Antarctic Precipitation) scale by accurate laboratory mass spectrometer measurements at LSCE (Laboratoire des Sciences du Climat et de l'Environnement).

### 2.3.2 Other measurements at Kourovka

In addition to the water vapor measurements, precipitation samples have been collected at Kourovka at the daily time scale since the end of October 2012. Measurements are performed on the Picarro isotopic analyzer L2130-i installed at the Ural Federal University (Ekaterinburg), which is equipped with a liquid water analysis system. Instrumental precision is 1.0‰ for  $\delta D$  and 0.1‰ for  $\delta^{18}\text{O}$ . We use the data from the end of October 2012 up to the end of December 2012.

Basic meteorological measurements are performed on an automatic meteorological station. The model is MetPak-II from Gill Instruments. It is installed 1 m below the Picarro input. We use the temperature measurements to better interpret our  $q$  measurements.

### 2.3.3 Precipitation networks

To put the Kourovka measurements into a broader regional context and to evaluate the capacity of LMDZ to capture the spatial and seasonal patterns of precipitation isotopic composition, we combine two networks: GNIP (Global Network for Isotopes in Precipitation, Rozanski et al., 1993) and SNIP (Siberian Network for Isotopes in Precipitation, Kurita et al., 2004). Both networks sample monthly precipitation. Both  $\delta^{18}\text{O}$  and  $\delta D$  are measured in the rain samples, allowing us to calculate  $d$  excess. However, in the case of SNIP, the  $d$  excess needs to be considered with caution due to possible rain evaporation effects after sampling (Kurita et al., 2004).

### 2.3.4 Satellite data sets

To evaluate the spatial and seasonal patterns of vapor isotopic composition, we use two satellite data sets measuring tropospheric  $\delta D$ . At present, satellite measurements cannot provide  $\delta^{18}\text{O}$  with sufficient precision for  $d$  excess calculations to be useful for scientific applications. GOSAT (Greenhouse gases Observing SATellite) measurements enable the retrieval of the total-column water vapor content in both  $\text{H}_2\text{O}$  and HDO (Frankenberg et al., 2013). Since most of the total-column vapor is in the lower troposphere, column-integrated  $\delta D$  is mainly sensitive to the  $\delta D$  of the boundary layer (BL).

TES (Tropospheric Emission Spectrometer) measurements enable the retrieval of some information on the vertical distribution of  $q$  and  $\delta D$  in the troposphere (Worden et al., 2006, 2007). Recent processing of the data leads to enhanced sensitivity in northern latitudes and to a higher degree of freedom of the signal (Worden et al., 2012). For clear sky scenes these data can distinguish air-parcels at 900 hPa from those at 400 hPa. A correction is applied on observed  $\delta D$  following the calibration study of Worden et al. (2011). More details on the GOSAT and TES data used and the quality selection criteria can be found in Risi et al. (2013).

In order to rigorously compare LMDZ with GOSAT or TES, we take into account spatiotemporal sampling and we apply averaging kernels to the model outputs to account for the vertical resolution and use of a priori constraints of the satellite retrievals. More details on the model–data comparison methodology are in Risi et al. (2012a, 2013). We focus only on comparing spatial and temporal variations in order to minimize uncertainties related to biases in the satellite data (Worden et al., 2011; Frankenberg et al., 2013).

## 2.4 $\delta D$ - $q$ diagrams

### 2.4.1 Theoretical curves in $\delta D$ - $q$ diagrams

To a first order, in mid and high latitudes, the water vapor isotopic ratio of HDO to H<sub>2</sub>O follows Rayleigh distillation (Dansgaard, 1964):

$$\ln(R_v) = \ln(R_{v0}) + (\alpha - 1) \cdot \ln\left(\frac{q}{q_0}\right), \quad (1)$$


where  $R_v$  and  $q$  are the final isotopic ratio and specific humidity,  $R_{v0}$  and  $q_0$  are the initial isotopic ratio and specific humidity, and  $\alpha$  is the fractionation coefficient.

Since  $R_v$  remains close to unity,  $\delta D$  can be approximated by:

$$\delta D \simeq \ln(R_v) \cdot 1000 \quad (2)$$

Therefore, to first order,  $\delta D$  is tightly related to  $q$ . When investigating what we can learn from water isotopic measurements, we need to investigate the added value compared to  $q$ , for example by analyzing the relationship of  $\delta D$  as a function of  $q$  (Worden et al., 2007; Schneider et al., 2010; Galewsky and Hurley, 2010; Noone et al., 2011; Noone, 2012). For even better consistency with a Rayleigh distillation, here we analyze the relationship of  $\delta D$  as a function of  $\ln(q)$ , in which the Rayleigh distillation is approximately a straight line. Figure 1 shows how different processes may affect the relationship of  $\delta D$  as a function of  $\ln(q)$ . An air mass that cools and loses water vapor by condensation follows the Rayleigh distillation line (red). Mixing between air masses that have undergone different degrees of distillation follows a hyperbolic shape with more enriched values for a given  $q$  (green) (Galewsky and Hurley, 2010). Recycling of precipitation, either through local transpiration of soil water or through re-evaporation of falling raindrops follows mixing lines with more depleted values for a given  $q$  (blue and magenta).

Such plots can be instructive qualitatively. They may, however, be difficult to apply quantitatively to the data due to various factors affecting these curves. For example, the Rayleigh distillation line is sensitive to  $\delta D$  in the initial vapor, which may depend on the existence of convective activity (Jouzel and Koster, 1996; Lawrence et al., 2004). The mixing lines are very sensitive to the  $q$ - $\delta D$  properties of the components




**Figure 1.** Theoretical lines in the  $\delta D$ - $q$  plot. The initial vapor (red circle) is assumed to be formed over ocean, with a surface temperature of 25 °C and surface relative humidity of 70 % according to the Merlivat and Jouzel (1979) closure assumption. This vapor follows a Rayleigh distillation following equation 1 (red line). The green lines show mixing lines between the initial vapor and a vapors distilled down to different temperatures: 0 °C (thick line), −5 °C (dashed line) and 5 °C (dotted line). These lines are similar to those in Worden et al. (2007). The blue and magenta lines show mixing lines between vapor distilled down to 10 °C and the re-evaporation of rain. We assume that the rain is in equilibrium with the overlying vapor. The blue line represents the evaporation of rain without any fractionation, as is the case for transpiration of soil water. The magenta lines represents the evaporation of rain with fractionation, following Stewart (1975) and Bony et al. (2008): re-evaporation of rain in an equal amount of water vapor with air humidity of 70 % (solid), in an equal amount of water vapor with 90 % humidity (dotted) or in a twice larger amount of water vapor with 70 % humidity (dashed). Note that these re-evaporation lines are different from those in Worden et al. (2007), because they neglected the evolution of the raindrop composition during re-evaporation, whereas we do a more precise calculation, and because they plotted a combination of distillation and re-evaporation, whereas we plotted the effect of re-evaporation only.

that are being mixed (compare the different green lines in Fig. 1). Re-evaporation lines are sensitive to evaporation conditions (compare the different magenta lines in Fig. 1).

Note that in the following, we discuss the relationship between  $q$  and water vapor  $\delta D$  in the near-surface air, or in the total column, i.e., between the precipitable water ( $Q$ ) and the column-integrated water vapor  $\delta D$ .

### 2.4.2 Consequences for the interpretation of model–data differences in $\delta D$

Model–data differences in  $\delta D$  ( $\Delta\delta D$ ) can be interpreted in the light of  $\delta D$ - $q$  diagrams: if  $\delta D$  is misrepresented, it could be either because  $q$  is misrepresented, or because the  $\delta D$ - $q$  relationship is misrepresented. For example, if  $\delta D$  is controlled by Rayleigh distillation and LMDZ misrepresents the intensity of this distillation, then LMDZ will overestimate both  $q$  and  $\delta D$ . On days when LMDZ overestimates  $q$  the most, LMDZ will overestimate  $\delta D$  the most. In addition, the slope of  $\Delta\delta D$  vs.  $\Delta\ln(q)$  would be the same as that of  $\delta D$  vs.  $\ln(q)$ : indeed, based on Eq. (1) and applying the



**Figure 2.** Annual mean maps of observed (left) and simulated (right) precipitable water (a–d) and  $\delta D$  in the total column water vapor (e–g) as observed by GOSAT (a–b, e–f), and by TES (c–d, g–h). The black dot indicates the location of Kourovka. Here we plot  $\delta D$  values without any subtraction because LMDZ happens to show values similar to those of GOSAT and TES. The black dot indicates the location of Kourovka.

approximation of Eq. (2),  $\Delta\delta D$  relates to  $\Delta q$  following:

$$\Delta\delta D \simeq 1000 \cdot (\alpha - 1) \cdot \Delta \ln(q)$$

Similarly, if  $\delta D$  is controlled by mixing and if LMDZ misrepresents the proportion of this mixing, it can be shown that LMDZ will overestimate  $\delta D$  the most on days when it overestimates  $q$  the most and that the  $\Delta\delta D - \ln(q)$  slope would also be similar to the  $\delta D - \ln(q)$  slope.


In contrast, if LMDZ misrepresents the initial  $\delta D$  of water vapor, there will be a systematic offset between the data and the model  $\delta D$ , and no particular relationship is expected between  $\Delta\delta D$  and  $\Delta \ln(q)$ .

### 3 Model evaluation of spatial and seasonal variations


To evaluate the spatial and seasonal variations over Siberia simulated by LMDZ, we use satellite and precipitation network data.

#### 3.1 Spatial variations

Figure 2 shows the maps of  $Q$ , and of annual-mean vertically integrated water vapor  $\delta D$ . Both GOSAT and TES data exhibit the temperature effect, with  $\delta D$  decreasing with latitude, and the continental effect, with  $\delta D$  decreasing along trajectories from west to east (Fig. 2a, c). To first order, LMDZ captures these patterns qualitatively well (Fig. 2b, d, f).



**Figure 3.** Annual mean maps of observed (left) and simulated (right)  $\delta D$  in the surface precipitation (a–b) and  $d$  excess in the surface precipitation (c–d). The black dot indicates the location of Kourvka.




**Figure 4.** Annual mean north–south transects of observed (black) and simulated (green) precipitable water observed by GOSAT (a) and by TES (b),  $\delta D$  in the total column water vapor as observed by GOSAT (c) and by TES (d),  $\delta D$  in the surface precipitation (e) and  $d$  excess in the surface precipitation (f). Transects are taken around the longitude of Kourvka: 50–70° E. For satellite data sets, the annual-mean  $\delta D$  averaged over 50–70° E–30–80° N is subtracted to focus on the latitudinal variations. LMDZ outputs are collocated with each data set and averaging kernels are applied to compare with satellite data sets. The dashed line indicates the latitude of Kourvka.

The maps for precipitation  $\delta D$  are consistent with those for vapor  $\delta D$  (Fig. 3a–b). The scarcity of precipitation  $d$  excess data makes it difficult to extract any clear spatial signal, although some poleward decreasing  $d$  excess trend can be noticed (Fig. 3c). LMDZ captures this pattern qualitatively well (Fig. 3d). For a more quantitative evaluation, Figs. 4 and 5 show north–south and west–east transects around Kourvka and are described below.

### 3.1.1 Latitudinal gradients in $Q$ and in $\delta D$

Observed  $Q$  decreases with latitude, as expected from the decrease in temperature. This is very well simulated by LMDZ (Fig. 4a–b).

For satellite  $\delta D$  data, we subtract domain average values to focus on spatiotemporal variations independently of possible systematic biases in the data. The poleward depletion associated with the temperature effect can clearly be seen in



**Figure 5.** Annual mean east–west transects of observed (black) and simulated (green) precipitable water observed by GOSAT (a) and by TES (b),  $\delta D$  in the total column water vapor as observed by GOSAT (c) and by TES (d),  $\delta D$  in the surface precipitation (e) and  $d$  excess in the surface precipitation (f). Transects are taken around the latitude of Kourovka: 50–64° N. For satellite data sets, the annual-mean  $\delta D$  averaged over 20–120° E–50–64° N is subtracted to focus on the longitudinal variations. LMDZ outputs are collocated with each data set and averaging kernels are applied to compare with satellite data sets. The dashed line indicates the longitude of Kourovka.

GOSAT, TES, and precipitation network data sets (Fig. 4c–e). Compared to both satellite data sets, LMDZ underestimates the latitudinal gradient of  $\delta D$  by about 30 % (Fig. 4c–d). This bias was already noticed by Risi et al. (2012a).

We investigate the latitudinal gradients at different altitudes using the TES data, which has some vertical information (not shown). LMDZ underestimates the latitudinal gradient from the surface to 800 hPa, and slightly overestimates it from 800 to 550 hPa. 800 hPa corresponds approximately to the top of the BL. Above 550 hPa, the TES sensitivity to  $\delta D$  becomes too low to draw conclusions. Therefore, the underestimation of the latitudinal gradient originates from the BL. For example, it could be due to a wrong representation of the latitudinal variations in evapotranspiration, with too much evapotranspiration in the northern part of Siberia, or too little evapotranspiration in the southern part. A seasonal analysis of the latitudinal gradients shows that the latitudinal gradient is underestimated only in summer. This could be consistent with the hypothesis that evapotranspiration is misrepresented, since evapotranspiration occurs mainly in summer. However, sensitivity tests using LMDZ-ORCHIDEE suggest that purely atmospheric processes are responsible for this bias (Sect. 3.3.4).

For the precipitation, the data is noisier due to the scarcity of observations. We cannot detect any obvious bias in the simulation of the latitudinal gradient of  $\delta D$  compared to the data (Fig. 4e).

### 3.1.2 East–west gradients in $Q$ and $\delta D$


$Q$  decreases westward over Siberia, reflecting the progressive rainout along air masses trajectories towards the east. LMDZ overestimates slightly this decrease compared to both GOSAT and TES (Fig. 5a–b).

GOSAT, TES and the precipitation networks all feature an eastward decrease of  $\delta D$  (Fig. 5c–e). This decrease has been attributed to the so-called “continental effect” (Rozanski et al., 1993). This effect is due to the fact that as air masses move eastward, they lose heavy isotopes through precipitation. A fraction of these heavy isotopes are returned to the atmosphere through evapotranspiration (Gat, 2000), but the remaining is lost through river runoff. This is why the amount of continental recycling (i.e., the fraction of the precipitation water which is returned to the atmosphere through evapotranspiration) is known to modulate the continental effect (i.e., the inland depletion of water vapor and precipitation) (Salati et al., 1979; Kurita et al., 2004).

The eastward depletion associated with the continental effect is very well captured by LMDZ compared to GOSAT, TES, and precipitation network data sets (Fig. 5a–c). If the continental effect is modulated by continental recycling, then this suggests that LMDZ represents the east–west gradient in evapotranspiration satisfactorily.

### 3.1.3 Spatial variations in $d$ excess

For  $d$  excess, the data looks much noisier than LMDZ. This could be due to the large uncertainty in the  $d$  excess



**Figure 6.** Seasonal cycles of observed (black) and simulated (green) precipitable water observed by GOSAT (a) and by TES (b),  $\delta D$  in the total column water vapor as observed by GOSAT (c) and by TES (d),  $\delta D$  (e) and  $d$  excess (f) in the surface precipitation. We average over the region of Kourovka ( $50\text{--}64^\circ\text{N}$ – $50\text{--}70^\circ\text{E}$ ). For satellite data sets, the annual-mean  $\delta D$  is subtracted to focus on the seasonal variations. For GNIP/SNIP data sets, the spatial standard deviation is also plotted as an envelope. LMDZ outputs are collocated with each data set and averaging kernels are applied to compare with satellite data sets.

measurement. The extent of post-sampling evaporation effects are difficult to quantify, but they could reach several ‰ (Kurita et al., 2004), which is of the same order of magnitude as the north–south  $d$ -excess gradient simulated by LMDZ. The apparent data noise could also be due to the potentially large spatial heterogeneity of  $d$  excess at the scale of a few kilometers: for example, the local surface type could affect  $d$  excess (Welp et al., 2012). LMDZ cannot capture this heterogeneity. This could also explain why LMDZ looks smoother than the data.

In spite of the noisiness in the data, a decreasing trend with latitude can be observed. This could be associated with the Rayleigh distillation, which first decreases  $d$  excess until about  $-20^\circ\text{C}$  and increases it below (Masson-Delmotte et al., 2008). In Siberia, only the decreasing trend can be seen because temperature are infrequently below  $-20^\circ\text{C}$ . LMDZ captures the  $d$  excess decrease with latitude, with a decrease from  $14\text{‰}$  at  $35^\circ\text{N}$  to  $5\text{‰}$  at  $70^\circ\text{N}$  (Fig. 4d).

No clear eastward trend can be noticed in observed precipitation  $d$  excess. The large noise and lack of clear signal in the data makes it difficult to assess whether the model is consistent or not with the data.

### 3.2 Seasonal variations

The observed seasonal cycle of  $Q$  follows that of temperature, with moister air in summer (Fig. 6a–b). LMDZ captures this seasonal cycle qualitatively, but is too dry in summer (consistent with the common dry bias previously mentioned,

Kittel et al., 1997; Cattiaux et al., 2013) and is too moist in autumn and winter. The LMDZ seasonal cycle is delayed by a few weeks. The correct simulation of  $Q$  noticed in the previous section in annual mean hides seasonal discrepancies.

As is common in most of the Northern Hemisphere, observed  $\delta D$  is more enriched in summer and more depleted in winter (Fig. 6c–e), consistent with the temperature effect. LMDZ captures this seasonality qualitatively well, though  $\delta D$  variations are underestimated compared to both satellite data sets (Fig. 6c–d). The LMDZ seasonal cycle is delayed by a few weeks, consistent with the delay noticed for  $Q$ . These problems do not appear in the precipitation networks (Fig. 6e). Both TES and GOSAT have fewer usable data points in the winter. It is possible that there are too few samples to make a robust comparison.

The precipitation networks show large spatial variability for  $d$  excess (Fig. 6f). However the comparison suggests that LMDZ misrepresents the observed  $d$  excess minimum in summer.

### 3.3 Possible causes of model–data differences

In the previous section, we identified three main model–data differences: (1) LMDZ underestimates  $Q$  in summer, (2) LMDZ underestimates the seasonal variation in  $\delta D$  and (3) LMDZ underestimates the latitudinal gradient in  $\delta D$ . For  $\delta D$ , a common bias of GOSAT and TES towards overestimating  $\delta D$  variations is unlikely given that they used

**Table 3.** Relationships between precipitable water ( $Q$ ) and total column water vapor  $\delta D$  as observed by GOSAT or TES and as simulated by LMDZ. We show the relationships for the latitudinal transects as plotted in Fig. 4 and for seasonal cycles as plotted in Fig. 6. For each relationship, we give successively the  $Q$  range (minimum and maximum values, in  $\text{kg m}^{-2}$ ), the  $\delta D$  range (maximum minus minimum values, in ‰, we do not give absolute values since they might be subject to calibration issues) and the slope of the  $\delta D$ - $\ln(Q)$  relationship (in ‰). The correlation coefficients for the  $\delta D$ - $\ln(Q)$  relationship are all between 0.82 and 0.84. When we compare LMDZ to GOSAT or TES, we collocate model outputs with each data set and apply the adequate averaging kernels.

Type of relationship	Data set	$\delta D - Q$ properties in the data		$\delta D - Q$ properties in LMDZ	
Latitudinal gradient	GOSAT	6.4–13.7 $\text{kg m}^{-2}$	182 ‰ 14.3 ‰	6.0–12.8 $\text{kg m}^{-2}$	140 ‰ 12.7 ‰
	TES	7.0–17.4 $\text{kg m}^{-2}$	79 ‰ 9.2 ‰	7.0–16.6 $\text{kg m}^{-2}$	43 ‰ 6.6 ‰
Seasonal cycle	GOSAT	2.8–18.8 $\text{kg m}^{-2}$	237 ‰ 9.6 ‰	2.8–18.4 $\text{kg m}^{-2}$	158 ‰ 8.8 ‰
	TES	4.6–26.5 $\text{kg m}^{-2}$	60.5 ‰ 5.0 ‰	2.9–22.3 $\text{kg m}^{-2}$	50.2 ‰ 2.6 ‰

**Table 4.** Characteristics of the spatial distribution in  $q$ ,  $\delta D$  and in  $d$  excess of near-surface vapor, for the LMDZ simulation and for the different LMDZ-ORCHIDEE sensitivity tests listed in Table 1. At Kourouka, we calculate an average in the 52–62°, 55–65° E domain. The latitudinal gradient is quantified as the difference between the average in the 30–40° N, 55–65° E domain and in the 70–80° N, 55–65° E domain. The longitudinal gradient is quantified as the difference between the average in the 52–62° N, 20–30° E domain and in the 52–62° N, 110–120° E domain.

Model version	Annual-mean $q$ at Kourouka ( $\text{g kg}^{-1}$ )	Annual-mean $\delta D$ at Kourouka (‰)	Annual-mean $d$ excess at Kourouka (‰)	Latitudinal $q$ gradient ( $\text{g kg}^{-1}/10^\circ$ )	North-south $\delta D$ gradient (‰) / $10^\circ$	North-south $d$ -excess gradient (‰ / $10^\circ$ )	East-west $q$ gradient ( $\text{g kg}^{-1}/10^\circ$ )	East-west $\delta D$ gradient (‰ / $10^\circ$ )	East-west $d$ -excess gradient (‰ / $10^\circ$ )
OR	5.1	−134	12.2	−0.82	−14.8	−1.7	−0.22	−5.4	0.7
ORnofrac	5.1	−132	10.6	−0.82	−14.8	−1.9	−0.22	−5.1	0.4
ORrveg	4.9	−146	9.0	−0.86	−14.0	−1.3	−0.26	−7.4	0.4
ORhumcste	4.9	−141	12.1	−0.78	−14.0	−1.6	−0.19	−5.7	0.7
ORdpu	5.0	−137	11.7	−0.80	−13.9	−1.7	−0.19	−5.5	0.6
ORbaresoil	5.0	−140	14.7	−0.81	−14.8	−1.5	−0.25	−6.4	1.4
LMDZ	3.7	−139	11.7	−0.63	−12.7	−2.4	−0.29	−6.2	0.3

independent wavelengths and retrieval algorithms. This section explores possible causes for these model biases.

### 3.3.1 Spatial pattern of the summer bias

The latitudinal gradient in  $\delta D$  is underestimated the most in summer. Therefore, the underestimation of both the  $\delta D$  seasonal variations and the annual-mean  $\delta D$  latitudinal gradient could be due to the underestimation of the  $\delta D$  latitudinal gradient in summer. Figure 7 shows the model–data difference for  $Q$  and  $\delta D$  compared to GOSAT and TES. The underestimation of the  $\delta D$  latitudinal gradient is apparent (Fig. 7c–d). This is associated with an underestimation of the  $Q$  latitudinal gradient (Fig. 7a–b). The lack of calibration for  $\delta D$  data prevents us to decide whether it is the northern part that is too enriched or it is the southern part that is too depleted, but both GOSAT and TES data for  $Q$  shows that the northern part is too moist and the southern part is too dry in LMDZ. As air masses move towards the southeast, their humidity decrease too much in LMDZ compared to the data along air mass trajectories. This suggests that in LMDZ, there is an excess of dehydrating processes, or a deficit of moistening processes, in Western Siberia. The location of Kourouka is ideal to in-


vestigate these processes since it is where the air masses start to become too dry along their trajectories.

### 3.3.2 $\delta D$ - $Q$ diagrams

As explained in Sect. 2.4, the underestimation of  $\delta D$  variations may be associated either with an underestimation of  $q$  variations or with an underestimation of the slope of  $\delta D$ - $Q$  slope. Table 3 attempts to separate these two effects.

For the latitudinal gradient, the simulated  $Q$  range is comparable with observations, but the  $\delta D$ - $Q$  slope is weaker in LMDZ (Fig. 4a–b, Table 3). Therefore, the  $\delta D$  discrepancies are not due to temperature or  $Q$  variations, but rather to the type of hydrological processes (condensation, mixing or re-evaporation). For example, there could be too much diffusion in the advection scheme (Risi et al., 2012a; Risi et al., 2012b) or an over-estimated continental recycling (Risi et al., 2013). Sensitivity tests with ORCHIDEE will however suggest purely atmospheric processes are responsible for the latitudinal gradient mismatch (Sect. 3.3.4).

For the seasonal cycle, LMDZ underestimates  $Q$  variations, consistent with the dry bias in summer (Figs. 6a–d, 3). In addition, the  $\delta D$ - $Q$  slope is weaker in LMDZ. Therefore,



**Figure 7.** June–July–August (JJA) mean model–data difference for precipitable water (**a–b**) and total-column water vapor  $\delta D$  (**c–d**) compared to GOSAT (left) and TES (right). LMDZ outputs are collocated with each data set and averaging kernels are applied to compare with satellite data sets. The black dot indicates the location of Kourovka. Superimposed are the simulated surface winds. They are the same for all figures.

the underestimation of the  $\delta D$  seasonal cycle is due to both an underestimation of the  $Q$  seasonal cycle and of the  $\delta D$ - $Q$  slope.

### 3.3.3 Impact of the representation of fractionating evapotranspiration

The fact that we neglect the fractionation during the bare soil evaporation component of evapotranspiration may contribute to underestimate the latitudinal gradient of  $\delta D$  near the surface. To quantify this, we compare two LMDZ simulations coupled with ORCHIDEE in which the fractionation during bare soil evaporation is activated (OR) or disabled (ORnofrac).

When there is isotopic fractionation during bare soil evaporation, less heavy isotopes are recycled back into the atmosphere. Therefore, we expect a stronger continental effect (Salati et al., 1979), i.e., a stronger east–west gradient in  $\delta D$ . The OR simulation indeed shows a slightly larger east–west gradient in  $\delta D$  than the ORnofrac simulation:  $-5.4\text{‰}/10^\circ$  compared  $-5.1\text{‰}/10^\circ$  (Table 4). This difference is too small to consider fractionating evaporation as a key improvement. The north–south gradient in  $\delta D$  is not affected (Table 4). This suggests that the north–south gradient is con-


trolled by purely atmospheric processes, such as progressive condensation along air mass trajectories.

Regarding  $d$  excess, when there is fractionation during bare soil evaporation, the evaporation of HDO is favored relatively to the evaporation of  $\text{H}_2^{18}\text{O}$ . This increases  $d$  excess in the recycled water vapor (Gat and Matsui, 1991; Risi et al., 2013). The OR simulation indeed shows a significantly larger east–west gradient in  $\delta D$  than the ORnofrac simulation:  $0.7\text{‰}/10^\circ$  compared  $0.4\text{‰}/10^\circ$  (Table 4). However, the noisiness in the GNIP/SNIP data does not allow one to judge whether considering fractionating evaporation is an improvement.

To summarize, neglecting isotopic fractionation during bare soil evaporation does not appear to be a major caveat of our study.

### 3.3.4 Impact of the representation of the land surface

To check to what extent our results are sensitive to the representation of the land surface, we compare different sensitivity tests using LMDZ-ORCHIDEE sensitivity tests. We find that the longitudinal  $q$  gradient is relatively sensitive to the representation of the land surface (Table 4). In contrast, the latitudinal  $q$  gradient is much more robust among tests. This suggests that land surface processes are important for



**Figure 8.** (a) Annual mean north–south transects of water vapor  $\delta D$  at 600 hPa simulated by different SWING2 models. Transects are taken around the longitude of Kourovka: 50–70° E. The annual-mean  $\delta D$  averaged over 50–70° E–30–80° N is subtracted to focus on the latitudinal variations. The spatial averaging are the same as in Fig. 3. (b) Water vapor  $\delta D$  at 600 hPa as a function of humidity at 600 hPa. (c) Seasonal amplitudes (June–July–August minus December–January–February) of  $\delta D$  at 600 hPa in the region of Kourovka (50–64° N–50–70° E), as a function of the seasonal amplitude in humidity at 600 hPa.

the Siberian climate, although the latitudinal gradient is controlled mainly by purely atmospheric processes.

The latitudinal gradient in  $\delta D$  is a remarkably robust feature of LMDZ and LMDZ-ORCHIDEE simulations. This supports once again that the latitudinal gradient is controlled mainly by purely atmospheric processes, and cannot be used to evaluate the simulation of continental recycling. In contrast, the east–west gradient of water vapor  $\delta D$  is significantly sensitive to the representation of the land surface, with values varying from  $-5.4\text{‰}/10^\circ$  to  $-7.4\text{‰}/10^\circ$ .

The east–west gradient in  $d$  excess are very sensitive to the representation of the land surface, with values varying from 0.4 to  $1.4\text{‰}/10^\circ$  depending on the LMDZ-ORCHIDEE simulations. This suggests that  $d$  excess measurements along an east–west transect could be very useful to evaluate the representation of land surface processes. However, the noise in the GNIP/SNIP  $d$  excess data is too large compared to the east–west variations.

We note that LMDZ and LMDZ-ORCHIDEE simulations provide significantly different results. We thus reiterate our warning that some of the conclusions reached in this paper might be specific to GCMs with very simple land surface schemes. However, the good match between our LMDZ simulation and TES and GOSAT data suggests that the continental recycling in this simulation is reasonably well represented.

### 3.4 Comparison with other models

As for LMDZ, the European Centre Hamburg Model (ECHAM) model was already compared to the same satellite data sets and showed a good capacity for simulating the observed spatial variations (Butzin et al., 2014). To put the LMDZ results into a broader context, we compare them with those of other model simulations from the SWING2 archive (Fig. 8). Since daily outputs are not available, we cannot collocate the model outputs with the satellite data sets and we cannot convolve them with the appropriate averaging kernels. Therefore, in this section, we just compare the climatological averages of the different models with each other, without any comparison with TES or with GOSAT. SWING2 simulations exhibit a large spread in their representation of the latitudinal gradient in the mid troposphere (Fig. 8a), with gradients ranging from  $11\text{‰}/10^\circ$  to  $25\text{‰}/10^\circ$ . Compared to the other models, LMDZ does not simulate the weakest gradient, suggesting that other models might share the same tendency to underestimate this gradient compared to the data.

What might cause this spread? First, some of this spread is related to the simulated  $q$ , which reflects the basic climatology. For example, the steepest latitudinal gradient in  $\delta D$  is featured by the free (i.e., not nudged) simulation of LMDZ, which is associated with the largest range of  $q$  along the latitudinal gradient (Fig. 8b). The weakest latitudinal gradient in  $\delta D$  is featured by the CAM2 model, which is associated with the smallest range of  $q$  along the latitudinal gradient, while both models have a similar  $\delta D$ - $q$  slope (Fig. 8b). Second,

**Table 5.** Daily correlation coefficient ( $r$ ) and its significance ( $p$  value) between observations at Kourovka and LMDZ simulation results for humidity ( $q$ ), water vapor  $\delta D$ ,  $\delta^{18}\text{O}$ ,  $d$  excess and differences of these variables between precipitation and water vapor. During the December–January–February (DJF) season, data is available only for December. If the  $p$  value is lower than 5 %, we assume that the correlation coefficient is statistically significant. N/S means “not significant”.

Phase period $r$ or $p$ value	Vapor	Vapor	Vapor	Vapor	Precip-vapor	Precip-vapor	Precip-vapor	Precip-vapor
	JJA $r$	JJA $p$ value	DJF $r$	DJF $p$ value	entire period $r$	entire period $p$ value	entire period $r$	entire period $p$ value
$q$	0.63	<1%	0.94	<1%	0.90	<1%	N/A	N/A
$\delta D$	0.54	<1%	0.8	<1%	0.95	<1%	0.47	<5%
$\delta^{18}\text{O}$	0.55	<1%	0.8	<1%	0.94	<1%	0.32	N/S
$d$ excess	N/A	N/A	0.27	N/S	0.27	<1%	0.26	N/S

some of the spread is related to the  $\delta D$ - $q$  slope, which reflects more subtle physical processes. For example, one of the steepest latitudinal gradients in  $\delta D$  is featured by the Hadley Centre Atmospheric Model (HadAM), which is associated with the steepest  $\delta D$ - $q$  slope (Fig. 8b). The reverse is true for isoGSM (Isotopes-incorporated Global Spectral Model).

SWING2 simulations also exhibit a large spread in their representation of the seasonal cycle of  $\delta D$  at Kourovka, with seasonal magnitudes ranging from 40 to 160 ‰ (Fig. 8c). Again, LMDZ does not simulate the weakest seasonality among the models, suggesting that other models might share the same seasonal bias. There is no relationship between the amplitude in the seasonal cycle in  $\delta D$  and that in  $q$  among the different SWING2 models (Fig. 8c). This shows that the seasonality in  $\delta D$  reflects some physical processes that are not immediately detectable when looking at conventional variables, thus supporting the added value of water isotopic measurements to better evaluate these processes.

#### 4 Model evaluation of the daily variability at Kourovka

##### 4.1 Specific humidity and isotopic composition of the water vapor

Continuous measurements of water vapor isotopic composition from Kourovka with the Picarro instrument allow us to analyze daily time series from April to December 2012. A comparison of observations with the results of LMDZ simulation of water vapor for 2012 at Kourovka is shown in Fig. 9. For LMDZ, we use outputs from the closest grid point from Kourovka. Since LMDZ is nudged by reanalyses, it captures the daily variations in circulation, so that it is possible to make a day-to-day comparison. The LMDZ results correlate very well with the observations of both  $q$  and  $\delta D$  for the whole period (Table 5).

LMDZ underestimates  $q$  from June to November and the difference between observations and model reaches a maximum ( $8 \text{ g kg}^{-1}$ ) in August. This is consistent with the summer dry bias of LMDZ discussed earlier. A dry bias was also noticed in the free troposphere compared to the IASI (In-


frared Atmospheric Sounding Interferometer) data (Pommier et al., 2014). The daily model–data correlation for  $q$  is better in winter and rises to 0.94.

LMDZ almost overestimates observed  $\delta D$  and  $\delta^{18}\text{O}$ , with the exception of December, where there is very low  $q$ . The fact that the LMDZ results are too enriched compared to observations is consistent with the fact that the LMDZ results are too enriched compared to SNIP observations (Figs. 4 and 5). Compared to both data sets, the LMDZ results are on average about 20 ‰ too enriched.


As previously mentioned in Sect. 2.3.1, we decide not to use the data for  $d$  excess from April to the end of September due to a leakage in the Picarro calibration system. Confidence in  $d$  excess for observations is in doubt for this period, and we limit the analysis of these data to the last 3 months, October to December. For this period modeled  $d$  excess show fewer variations than observed values and remain in the range of 9 to 15 ‰. An underestimation of daily  $d$  excess variability by GCMs had already been noticed for other mid-latitude sites (Risi et al., 2012a). Despite the large differences in values, there is a good qualitative agreement of the results in November. For example, LMDZ captures the  $d$  excess increase in the end of October, the decrease in early November and the increase in late November.

The vapor is collected at 8 m above ground level. In the model, the first layer is 70 m thick and the model outputs represent vapor integrated over this depth. The difference in vertical footprint could explain some model–data discrepancy, though we expect this effect to be small. For an average  $\delta D$  gradient of  $-15 \text{ ‰ km}^{-1}$ , the expected difference between 8 m and 33 m (mean altitude of the LMDZ first level) is only 0.3 ‰.

To summarize, LMDZ captures well the temporal variations observed in ground-based measurements, especially in the winter. During the summer, the model underestimates  $q$ . All year long,  $\delta D$  is systematically too enriched.



**Figure 9.** Daily mean time series of humidity (a), water vapor  $\delta D$  (b) and  $d$  excess (c) for observations in Kourovka (red) and simulated by LMDZ (blue).



**Figure 10.** Daily mean difference between precipitation and water vapor  $\delta D$  (a) and  $d$  excess (b) for observations in Kourovka (red) and LMDZ (blue). The green line represents a theoretical estimation of this difference.

#### 4.2 Difference of isotopic composition between precipitation and water vapor

Fig. 10 shows the daily precipitation amount and difference in  $\delta D$  and  $d$  excess between precipitation and water vapor:  $\delta D_p - \delta D_v$  and  $d_p - d_v$ . The theoretical estimation of this dif-


ference, assuming isotopic equilibrium between precipitation and vapor, is shown in green. Equilibrium fractionation coefficients between vapor and liquid water or ice are calculated following Majoube (1971a, b); Merlivat and Nief (1967). We take into account kinetic effects during snow formation, following Jouzel and Merlivat (1984).

Precipitation is snow, except during the first 3 days. Its amount is well captured by the model (Fig. 10a).

We find significant correlation between the model and observations for  $\delta D_p - \delta D_v$  (Table 5). This good agreement is probably due to the fact that most of the precipitation is snow. The isotopic composition of snow is easier to simulate than that of rain because it is less affected by post-condensational processes. Observed precipitation is on average about 80‰ more enriched in  $\delta D$  than the water vapor at the surface (Fig. 9a, red dots). The LMDZ results are consistent with these observations, though there are some model–data differences for individual events (Fig. 10a, blue dots). If the snow was in equilibrium with the surface water vapor, it would be about 115‰ more enriched (Fig. 10a, green curve). The  $\delta D_p - \delta D_v$  of 80‰ can be explained by the fact that snow forms from vapor at a higher altitude. To check this quantitatively, we calculate the daily condensation altitude as the average altitude weighted by the condensation rate. In LMDZ, the condensation occurs at an altitude of 2 km on average.  $\delta D$  decreases with altitude and the vertical gradient between the surface and 2 km is about  $-15\text{‰ km}^{-1}$ . Therefore, most of the snow forms on average from water vapor which is about 30‰ more depleted than at the surface. The fact that the observed snow is about 35‰ less enriched than predicted based on equilibrium with the surface water vapor is thus consistent with the fact that the snow is formed from water vapor at 2 km. In addition, daily variations in  $\delta D_p - \delta D_v$  reflect variations in condensation altitude: in LMDZ, the correlation between  $\delta D_p - \delta D_v$  and the condensation altitude for the entire period is  $-0.51$ .

In Sect. 3.1, we showed that LMDZ simulates a precipitation that is systematically too enriched. The fact that LMDZ correctly simulates  $\delta D_p - \delta D_v$  confirms that the cause of the overestimation of the precipitation  $\delta D$  (both at Kourouka and on all GNIP and SNIP sites) is the overestimation of the  $\delta D$  of the vapor from which the precipitation is formed.

Observed  $d_p - d_v$  is 3‰ on average (Fig. 10b). LMDZ simulates  $d_p - d_v$  values of  $-2\text{‰}$  on average. If the snow was in equilibrium with the surface water vapor,  $d_p - d_v$  would be about  $-5\text{‰}$ . The  $d$  excess increases with altitude and the vertical gradient between the surface and 2 km is  $1\text{‰ km}^{-1}$ . Taking this effect into account,  $d_p - d_v$  should be about  $-3\text{‰}$ . This theoretical estimate is very consistent with what is simulated by LMDZ. Why observed  $d_p - d_v$  is 3‰ rather than  $-3\text{‰}$  could be due to microphysical processes or post-condensational processes. However, the large spread of  $d_p - d_v$  values prevent us from concluding for sure that observations are inconsistent with LMDZ and with the theoretical estimate.



**Figure 11.** Schematic representation of the hydrological cycle which includes physical process: advection, deep convection, large-scale condensation, re-evaporation, surface evaporation and boundary-layer processes.

## 5 Processes controlling water vapor and $\delta D$

### 5.1 Understanding the simulated evolution in humidity and $\delta D$

We showed that LMDZ reproduces well, at least qualitatively, the seasonal (Sect. 3.2, Fig. 6) and daily (Sect. 4.1, Fig. 9) variations in  $q$  and water vapor  $\delta D$  in the lower troposphere. Therefore, we can make use of LMDZ simulations to investigate in more detail the physical processes controlling these variations.

#### 5.1.1 Method based on the tendency analysis

The different processes affecting  $q$  and  $\delta D$  at the surface in the model in general are schematically illustrated in Fig. 11. Below we focus in more detail on each of them.

1. Vertical and horizontal advection by the large-scale winds (red). Since we focus on surface  $q$  and  $\delta D$ , only the horizontal component of the advection is nonzero. Horizontal advection may moisten or dehydrate the air depending on the horizontal  $q$  gradients and on the direction of the wind. Similarly, it may enrich or deplete the water vapor.
2. Deep convection (green). This represents the effect of vertical motions and phase changes in convective systems. At the surface, convection dehydrates the air through subsident motions such as unsaturated downdrafts (Zipser, 1977). This subsidence also has a depleting effect on water vapor (Risi et al., 2008, 2010b). Convection may also moisten the lower levels through rain re-evaporation (Folkens and Martin, 2005). In this case, its effect on  $\delta D$  can be either enriching or depleting (Worden et al., 2007; Risi et al., 2010a; Field et al., 2010).

**Table 6.** Daily correlation coefficient ( $r$ ) and its significance ( $p$  value) between temporal derivatives of  $q$  or  $\delta D$  and tendencies from different processes simulated by LMDZ: horizontal advection (adv), deep convection (conv), large-scale condensation and re-evaporation (cond), surface evaporation and boundary-layer dynamics (evap). N/S means “not significant”.

Temporal derivatives	Tendencies	Annual		DJF		JJA	
		$r$	$p$ value	$r$	$p$ value	$r$	$p$ value
$q$	adv	0.47	< 1 %	0.65	< 1 %	0.40	< 1 %
$q$	conv	0.06	N/S	N/A	N/A	0.03	N/S
$q$	cond	0.07	N/S	0.16	N/S	0.15	N/S
$q$	evap	0.26	< 1 %	0.67	< 1 %	0.16	N/S
$\delta D$	adv	0.40	< 1 %	0.44	< 1 %	0.30	< 1 %
$\delta D$	conv	0.06	N/S	N/A	N/A	0.20	< 5 %
$\delta D$	cond	0.11	< 5 %	0.08	N/S	0.31	< 1 %
$\delta D$	evap	0.31	< 1 %	0.59	< 1 %	0.17	N/S

### 3. Large-scale condensation and re-evaporation (blue).

This represents the effect of phase changes occurring outside of the convective systems, such as in frontal systems or stratiform clouds. Near the surface, it may moisten the BL through the evaporation of the precipitation formed by such systems or clouds. As for the evaporation of convective rain, this can either enrich or deplete the water vapor. Occasionally, it may dehydrate and deplete the vapor through in situ condensation in fogs.

- ### 4. Surface evaporation and BL processes (cyan).
- Our model diagnostics do not allow for the direct separation of these two effects despite their different effects on  $q$  and on  $\delta D$  of near-surface vapor. Surface evaporation moistens the BL. Since we assume no fractionation during land surface evaporation, this always has an enriching effect (Risi et al., 2013). In contrast, BL mixing is associated with vertical redistribution of moisture, which has a dehydrating and depleting effect on the lower levels. To qualitatively separate the effect of surface evaporation and BL processes, we use the fact that surface evaporation (which is a model output) and BL mixing (which is expected to be more active in summer, especially during the warmest days) have opposite effects. For example, if the “surface evaporation and BL processes” are more moistening when both surface evaporation and BL mixing are stronger, then we suggest that surface evaporation drives the moistening effect. In contrast, if the “surface evaporation and BL processes” are more moistening when both surface evaporation and BL mixing are weaker, then we suggest that the weaker BL mixing drives the moistening effect.


In LMDZ, the temporal derivatives of  $q$  and  $\delta D$  are computed as the sum of different processes. Their contribution is shown in Fig. 12 and in Table 6.

### 5.1.2 Contribution to humidity variations

At the seasonal scale, the increase of  $13 \text{ g kg}^{-1}$  in  $q$  from spring to summer (Fig. 8a) is associated with a positive and increasing contribution in the “surface evaporation and BL processes” component, with a maximum of  $6 \text{ (g kg}^{-1}) \text{ day}^{-1}$  in July (Fig. 12a). Since we expect BL mixing to be stronger in summer, surface evaporation likely drives the moistening in spring. This increased moistening is partly compensated by an increased dehydration caused by summertime deep convection and large-scale advection (about  $4 \text{ (g kg}^{-1}) \text{ day}^{-1}$  for both). In autumn, the decrease in  $q$  is associated with a negative contribution of the “surface evaporation and BL processes” component. Since the BL is expected to be most active in summer, the decrease in surface evaporation likely drives the dehydration in autumn. Advection processes also take part in this decrease with  $1 \text{ (g kg}^{-1}) \text{ day}^{-1}$ .

At the daily scale, in summer,  $q$  variations correlate the best with the “horizontal advection” component ( $r = 0.40$ , Table 6). In addition, increases in  $q$  are associated with large values in the “surface evaporation and BL processes” component. Therefore, surface evaporation also drives the daily variability of  $q$  in the summer. This is consistent with the important role of continental recycling on  $q$  variations diagnosed by Risi et al. (2013). This consistency could be explained by the fact that the model is the same.

In winter, variations in  $q$  are also mainly associated with variations in the large-scale advection component and “surface evaporation and BL processes”. This is confirmed by the good correlation between  $q$  and “advection” and “surface evaporation and BL” tendencies and ( $r = 0.65$  and  $0.67$  respectively, Table 6). The importance of advection is consistent with the predominance of synoptic disturbances which modify the direction of the winds. Since evaporation is low during winter, “surface evaporation and BL processes” are likely associated mostly with BL processes.



**Figure 12.** Temporal derivative (black line) of (a) humidity and (b)  $\delta D$  at the surface simulated by LMDZ. This temporal derivative can be decomposed into the tendencies from different processes (illustrated in Fig. 11): horizontal advection (red); deep convection (green); large-scale condensation and re-evaporation (blue); surface evaporation and boundary-layer dynamics (cyan). We used a 5-day filter to focus on seasonal and synoptic variations.

**Table 7.** Model–data difference in near-surface air specific humidity in  $\text{g kg}^{-1}$  and its different contributions associated with temperature ( $T$ ) or with relative humidity (RH). The  $\Delta$  sign refers to the model–data difference.

Season	DJF	JJA
Mean $\Delta q$	0.52	−2.0
Mean $\Delta q$ attributed to $\Delta T$	0.33	2.3
Mean $\Delta q$ attributed to $\Delta \text{RH}$	0.13	−3.3
Correlation between $\Delta q$ and $\Delta T$	0.91	−0.52
Correlation between $\Delta q$ and $\Delta \text{RH}$	0.68	0.80
Correlation between $\Delta q$ and $q$	−0.71	−0.77

### 5.1.3 Contribution to $\delta D$ variations

For  $\delta D$ , the contributions of the different processes to the time derivative mirror those for  $q$  (Fig. 11b): most moisten-

ing processes act to enrich the water vapor, and vice versa. However, the relative amplitudes of the different processes are different. This supports the idea that  $\delta D$  provides some independent information compared to  $q$ . At the seasonal scale, surface evaporation contributes to the increase in  $\delta D$  in spring and to its decrease in summer, consistent with what we explained for  $q$ .

In the winter, “surface evaporation and BL processes” make the biggest contribution to  $\delta D$  variations: they are well correlated, with  $r = 0.59$  (Table 6). However, in early spring, large-scale advection also plays a significant role in the enrichment of the water vapor ( $20\text{--}30\text{‰ day}^{-1}$ ). At the daily level, surface evaporation drives the spikes of  $\delta D$  in summer with maximum in July with  $30\text{‰ day}^{-1}$ , and large-scale advection is mainly responsible for the  $\delta D$  fluctuations in winter ( $r = 0.44$ ), consistent with our explanation for  $q$ . In summer, the large-scale condensation also plays a slightly enriching role, due to the re-evaporation of rain in the BL.

**Table 8.** Relationships between  $\delta D$  and  $q$  and between  $\Delta\delta D$  and  $\Delta\ln(q)$ . The  $\Delta$  sign refers to the model–data difference. N/S means “not significant”.

Season	annual	DJF	JJA
Correlation $\delta D$ vs. $\ln(q)$ observations	0.95	0.93	0.87
Correlation $\delta D$ vs. $1/q$ observations	−0.84	−0.90	−0.85
Correlation $\delta D$ vs. $\ln(q)$ LMDZ	0.96	0.97	0.88
Correlation $\delta D$ vs. $1/q$ LMDZ	−0.90	−0.95	−0.87
Correlation $\Delta\delta D$ vs. $\Delta\ln(q)$	0.39	0.11	0.87
Slope $\delta D$ vs. $\ln(q)$ observations (‰)	49.9	37.3	47.5
Slope $\delta D$ vs. $\ln(q)$ LMDZ (‰)	64.4	61.2	49.3
Slope $\Delta\delta D$ vs. $\Delta\ln(q)$ (‰)	21.4	N/S	50.7
Intercept $\delta D$ vs. $\ln(q)$ observations (‰)	−260	−259	−248
Intercept $\delta D$ vs. $\ln(q)$ LMDZ (‰)	−244	−245	−211
Intercept $\Delta\delta D$ vs. $\Delta\ln(q)$ (‰)	26	N/S	41

In spring and autumn, large-scale condensation strongly depletes the water vapor on some days. This is consistent with the formation of fog (Noone et al., 2013). These fog events occur on days with strong surface evaporation but relatively stable and shallow BL. On these days, the depletion by large-scale condensation compensates for the enrichment by surface evaporation.

Thus we suggest that the BL dynamics and the large-scale advection control the daily variability of  $q$  and isotopic composition especially in winter. In summer, surface evaporation also plays an important role.

## 5.2 Interpreting model–data differences

The goal of this section is to interpret model–data differences in water isotopic composition, and to investigate what we can learn from water isotopic measurements about the representation of processes in models. We investigate first the model–data differences in  $q$ , and then the model–data differences in the  $\delta D$ – $\ln(q)$  relationship and how they contribute to model–data differences in  $\delta D$ .

### 5.2.1 Model–data differences in specific humidity

LMDZ tends to estimate  $q$  correctly during winter, and underestimate it during summer (Fig. 9a). The specific humidity ( $q$ ) can be expressed as a function of temperature ( $T$ ) and relative humidity (RH):  $q = \text{RH} \cdot q_s(T)$ , with  $q_s$  being the specific humidity at saturation. At the large scale,  $T$  reflects mainly dynamical and radiative processes, whereas RH reflects mainly dynamical, surface and cloud processes.  $T$  and RH may also reflect small scale processes that are not represented on the coarse grid of LMDZ.

Table 7 shows that on average in winter, LMDZ overestimates  $q$  because it overestimates both the temperature (accounting for 72 % of the overestimation of  $q$ ) and the relative humidity, compared to meteorological data. LMDZ overestimates  $q$  the most on days when it overestimates  $T$  the most. This occurs mainly during the driest days in the observations.

One hypothesis is that LMDZ overestimates the advection of warm and moist air from the southwest during these days.

In summer, Table 7 shows that on average, LMDZ underestimates  $q$  because it strongly underestimates the relative humidity, although it overestimates the temperature. LMDZ underestimates  $q$  the most on days when it is too warm. Also, LMDZ underestimates  $q$  the most during the moistest days in observations. One hypothesis is that LMDZ overestimates the advection of warm and dry air from the south. Another hypothesis is that LMDZ underestimates the surface evapotranspiration. More evapotranspiration would both moisten the atmosphere and cool the surface.

In the next subsection, we investigate whether water isotopic measurements can help us test these hypotheses.


### 5.2.2 Model–data differences in the $\delta D$ – $\ln(q)$ relationship

Figure 13a shows daily vapor  $\delta D$  as a function of  $\ln(q)$ . The surface observations cluster along a line, consistent with  $\delta D$  varying along a Rayleigh distillation line (Sect. 2.4). The correlations are high (Table 8). We compare the observed  $\delta D$ – $\ln(q)$  slope with that predicted by Rayleigh distillation (Eq. 1). We assume that the initial temperature is 25 °C, the initial RH is 70 % and that the initial  $\delta D$  is predicted by the Merlivat and Jouzel (1979) closure using these temperature and RH conditions. The following results are not strongly sensitive to these assumptions. We calculate the fractionation coefficient using the same temperature as the one used to calculate the saturation specific humidity. We calculate that the theoretical  $\delta D$ – $\ln(q)$  slope should be 80 to 120 ‰. The observed slopes are twice lower than expected from the theory: 40 to 60 ‰. This suggests that  $\delta D$  does not follow a pure distillation line. It might also be affected by mixing processes (Hurley et al., 2012).

If  $\delta D$  is affected by mixing processes, then  $\delta D$  is expected to vary linearly with  $1/q$ . To test this hypothesis, we calculate the correlations of  $\delta D$  as a function of  $1/q$  (Table 8). Correlations are slightly lower but still very high. Therefore, the influence of mixing processes on  $\delta D$  cannot be completely excluded.

Figure 13 and Table 8 show that LMDZ captures the  $\delta D$ – $\ln(q)$  slopes reasonably well in summer and in winter. This suggests that the Rayleigh distillation processes, or mixing processes (if they exist), are well represented. However,  $\delta D$  values are systematically offset: LMDZ is systematically more enriched by about 15 ‰ than observations, for a given  $q$ . This suggests that the origin of water vapor that undergoes the distillation is not properly represented.

We analyze the relationship between model–data differences in  $\delta D$  and in  $\ln(q)$  (Fig. 13b). In winter, there is no systematic relationship between model–data differences in  $\delta D$  and those in  $\ln(q)$ . This suggests that the too-large LMDZ enrichment is not related to a Rayleigh distillation that is too weak. Rather, some processes in LMDZ, independent of the



**Figure 13.** (a)  $\delta D$  as a function of  $\ln(q)$ , in the observed data (red) and in the model (green). (b)  $\Delta\delta D$  as a function of  $\Delta\ln(q)$ .  $\Delta$  refers to the model–data difference. Symbols refer to the season: December–January–February (filled squares), June–July–August (empty squares) and March–April–May–September–October–November (crosses). (c) Comparison of the simulated  $\delta D$ – $\ln(q)$  relationships in JJA in the near-surface vapor for the different days at Kourovka (green squares), for different latitudes at the longitude of Kourovka (magenta crosses) and for different longitudes at the latitude of Kourovka (blue stars).

**Table 9.** Characteristic of the daily  $\delta D$ – $\ln(q)$  distribution in JJA for the LMDZ simulation, for the different LMDZ–ORCHIDEE sensitivity tests listed in Table 1 and for in situ observations. The “ $\delta D$  values for  $\ln(q) = 2.5$ ” are calculated as  $2.5 \cdot a + b$  where  $a$  is the slope (given in the first column) and  $b$  is the intercept of the linear regression. This gives an idea of the systematic offsets between the different simulations when plotted in the  $\delta D$ – $\ln(q)$  diagram. The uncertainty on the slopes is about 6%.

Model version	Slope of $\delta D$ vs. $\ln(q)$ (‰)	JJA-mean $q$ ( $\text{g kg}^{-1}$ )	Minimum $q$ value	$\delta D$ value for $\ln(q) = 2.5$ (‰)
OR	43	7.6	5.9	−114
ORnofrac	44	7.6	5.9	−115
ORrveg	50	6.7	4.2	−110
ORhumcste	44	7.1	4.9	−108
ORDpu	45	7.5	5.2	−108
ORbaresoil	35	7.7	6.0	−117
LMDZ	48	8.6	6.5	−98
data	49	10.7	7.4	−131

Rayleigh distillation, are misrepresented, and they lead to biases in  $\delta D$  that are not directly related to biases in  $q$ . We could speculate on different hypotheses, such as the origin of water vapor issues or cloud processes. However, these are difficult to test.

In contrast, in summer, there is a systematic relationship between model–data differences in  $\delta D$  and those in  $\ln(q)$ . When LMDZ has the largest enrichment bias in  $\delta D$ , LMDZ simulates the largest  $q$  (the closest to observations). When LMDZ has the most depleted  $\delta D$  (the closest to observations), LMDZ has the largest dry bias in  $q$ . Furthermore, the

slope of the relationship between  $\Delta\delta D$  and  $\Delta\ln(q)$  is similar to that between  $\delta D$  and  $q$  (Table 8). On days when LMDZ is the driest, the slope is the same as other days. Therefore, the model–data differences in  $q$  and in  $\delta D$  are probably due to the same processes as those controlling the daily variability of  $q$  and  $\delta D$  in nature, i.e., surface evaporation, BL processes and large-scale advection (Sect. 5.1).

We notice that the simulated  $\delta D$ – $\ln(q)$  slope for the daily data in summer is the same as for the north–south gradient in  $\delta D$  (Fig. 13c). This suggests two possibilities: (1) the  $\delta D$ – $\ln(q)$  slopes are not a good way to discriminate between

different processes, or (2) the processes controlling the daily variability in  $\delta D$  are the same as those controlling the north–south gradient in  $\delta D$ . The slope for the east–west gradient is significantly different from the slope for the north–south gradient (Fig. 13c, blue), which may discard the first possibility. Section 3.3.4 suggested that the north–south gradient in  $\delta D$  was controlled by purely atmospheric processes. This would discard issues in the surface evaporation as the cause of the dry bias. This would leave BL processes and large-scale advection.

To summarize, analyzing observations and model–data differences in  $\delta D$ - $\ln(q)$  plots reveals some information about the sources of model biases, though it does not allow us to pinpoint them with certainty. The model is systematically too enriched all year long probably due to issues in the composition of the moisture at its source. In winter, the  $\delta D$  bias is modulated on a daily basis by processes that are independent from the Rayleigh distillation. In summer, the  $\delta D$  bias is modulated by the same processes as those explaining the daily variability and the north–south gradient in observations, i.e., BL processes and large-scale advection.

### 5.2.3 Impact of the representation of the land surface

To check whether the enriched bias in LMDZ could be due to the fact that we neglect fractionation during bare soil evaporation, we compare LMDZ simulations with fractionation during bare soil evaporation activated or disabled. When fractionation during bare soil evaporation is activated,  $\delta D$  increases mainly during the driest days of winter. This is because the driest days are associated with less transpiration and more bare soil evaporation into air masses on their way to Kourovka. Since the bare soil evaporation has a lower  $\delta D$  (Risi et al., 2013), more bare soil evaporation leads to a lower  $\delta D$ . Compared to the data, this is not an improvement since the simulated  $\delta D$ - $\ln(q)$  slope in winter is already too large in winter.

To qualitatively assess the impact of the representation of the land surface, we compare the sensitivity tests with LMDZ-ORCHIDEE. We find that the representation of the land surface has an important impact on the simulation of  $q$  at Kourovka in summer (Table 9). The minimum daily  $q$  value varying from 4.2 to 6.0 g kg<sup>-1</sup> depending on land surface parameters. This suggests that the land surface representation is important to properly simulate the Siberian climate.

In contrast, the  $\delta D$ - $\ln(q)$  slopes are very robust across all sensitivity tests, within the uncertainty. Again, there are two possible interpretations to this robustness in slopes: (1) the  $\delta D$ - $\ln(q)$  diagram is not sufficient to distinguish between different processes; (2) the intensity of the moistening and dehydrating processes vary across the different simulations, but keep the same proportions, so that the slopes are the same. Identifying the correct interpretation would require a detailed analysis of the model tendencies for the LMDZ-ORCHIDEE sensitivity tests for which all daily outputs are not available.

The different representations of the land surface result in  $\delta D$  shifts of less 10‰. This is much smaller than the model–data difference of about 30‰. Therefore, we suggest that purely atmospheric processes are to cause for the enriched bias of LMDZ.

## 6 Conclusions

In this paper, we evaluate the humidity and isotopic composition of water vapor and precipitation simulated by the LMDZ GCM over Siberia using several data sets: TES and GOSAT satellite observations of tropospheric water vapor, GNIP and SNIP networks of precipitation, and daily, in situ measurements of water vapor and precipitation at the Kourovka site in Western Siberia.

LMDZ captures the spatial, seasonal and daily variations reasonably well, except for a few features. LMDZ overestimates the  $\delta D$  in precipitation compared to the precipitation networks, by about 20‰. Consistently with this result, LMDZ overestimates the  $\delta D$  observed in both the vapor and precipitation at Kourovka. Based on the analysis of  $\delta D$ - $Q$  diagrams, this bias is most likely associated with a problem with the composition of the vapor at the moisture source. LMDZ slightly underestimates the latitudinal gradient in  $\delta D$  compared to satellite data sets. LMDZ also underestimates the seasonality at Kourovka compared to satellite data sets, but not at the surface compared to the in situ data. Finally, LMDZ captures some aspects of the spatial and daily variations in  $d$  excess.

The performance of LMDZ in capturing the spatial and seasonal variations in  $\delta D$  is consistent with other state-of-the-art models participating in the SWING2 intercomparison project. There is a large spread in the simulation of the latitudinal and seasonal variations in  $\delta D$ , which is not explained by the spread in the simulation of  $q$ . This confirms the added value of deuterium measurements compared to  $q$  measurements only, though we still need to make progress to better understand why there are systematic biases in  $\delta D$  in models and why different models simulate different  $\delta D$  variations.

Using LMDZ to investigate the processes controlling the daily variability, we find that two processes dominate. First, the large-scale advection determines the origin of the moisture, enriched in the south and west and depleted in the north and east. Second, surface evaporation and BL processes determine the proportion of the vapor coming from enriched surface evaporation or from the more depleted free troposphere.

Most GCMs suffer from a warm and dry bias over mid-latitude continents in summer. LMDZ shares this same bias. In addition to a systematic bias towards too enriched  $\delta D$  values, LMDZ exhibits the strongest dry bias on days when it simulates the most depleted  $\delta D$ . Moreover, the slope of  $\delta D$  biases vs.  $\ln(q)$  biases is consistent with the observed and simulated  $\delta D$ - $\ln(q)$  slopes at the daily scale. The slope is also

consistent with the observed and simulated  $\delta D$ - $\ln(q)$  slopes for latitudinal variations and inconsistent with those for longitudinal variations. This suggests that the same processes that explain the joint  $\delta D$ - $q$  variability at the daily scale and for latitudinal variations explain the biases in  $q$ . We suggest that the cause of the dry bias could be either a problem in the large-scale advection bringing too much dry and warm air from the south, or excessive BL mixing.

This paper shows the potential of combining  $\delta D$  and  $q$  measurements in  $\delta D$ - $q$  or  $\delta D$ - $\ln(q)$  diagrams, to interpret model–data and model–model differences in terms of the representation of physical processes. However, even using such diagrams, it is difficult to discriminate for sure between Rayleigh lines and mixing lines. In addition, different kinds of  $\delta D$ - $\ln(q)$  regressions may have the same slope: daily data in summer, daily data in summer for the driest days, and latitudinal gradient in summer. Observations, LMDZ simulations and different sensitivity tests on the land surface may feature large differences in  $q$  but still share the same  $\delta D$ - $\ln(q)$  slope. The similarity between different observational, simulated and theoretical slopes leaves us with some ambiguity that we cannot resolve here. Are the  $\delta D$ - $\ln(q)$  diagrams a sufficient framework to interpret isotopic data, or do we need to develop a more sophisticated theoretical framework? Or does the similarity between the different slopes shows that the same processes are at play in the observations, in all simulations and for both daily and latitudinal variations?

To resolve this issue, more work would be needed to develop new theoretical frameworks, or to better constrain the existing  $\delta D$ - $\ln(q)$  framework. A better spatial coverage of water vapor isotopic measurements would be useful for documenting the composition of the water vapor from the different air masses that are being mixed. Measuring vertical gradient in isotopic composition would be useful for documenting the composition of the evapotranspiration. Furthermore, since the summer dry bias develops as air masses move over the Kourouka region towards the southeast, daily data over stations along a southeast–northwest transect would be useful to document how the dry bias is being formed during synoptic events. Finally, more precise measurement and a better understanding of  $d$  excess could add an additional constraint to the system of isotopic equations that has so far suffered from too many unknowns compared to the number of equations.

*Acknowledgements.* This research was supported by the grants of Russian government under the contract 11.G34.31.0064 and the project #2189 within the State tasks (base part) of the High Education Ministry of Russian Federation. The authors would like to thank Francesca Guglielmo and Laura Kerber for their helpful comments and discussions. Part of this research was carried out at the Jet Propulsion Laboratory, California Institute of Technology, under a contract with the National Aeronautics and Space Administration. The LMDZ simulations were run on the

IDRIS supercomputers. We thank two anonymous reviewers for their constructive comments which help to improve the paper.

Edited by: I. Aben

## References

- Barnes, C. and Allison, G.: Tracing of water movement in the unsaturated zone using stable isotopes of hydrogen and oxygen, *J. Hydrol.*, 100143–176, 1988.
- Bastrikov, V., Steen-Larsen, H. C., Masson-Delmotte, V., Gribanov, K., Cattani, O., Jouzel, J., and Zakharov, V.: Continuous measurements of atmospheric water vapour isotopes in western Siberia (Kourouka), *Atmos. Meas. Tech.*, 7, 1763–1776, doi:10.5194/amt-7-1763-2014, 2014.
- Bellprat, O., Kotlarski, S., Lüthi, D., and Schär, C.: Physical constraints for temperature biases in climate models, *Geophys. Res. Lett.*, 42, 4042–4047, doi:10.1002/grl.50737, 2013.
- Boberg, F. and Christensen, J. H.: Overestimation of mediterranean summer temperature projections due to model deficiencies, *Nat. Clim. Change*, 2433–436, doi:10.1038/nclimate1454, 2012.
- Bony, S., Risi, C., and Vimeux, F.: Influence of convective processes on the isotopic composition ( $\delta^{18}O$  and  $\delta D$ ) of precipitation and water vapor in the Tropics. Part 1 Radiative-convective equilibrium and TOGA-COARE simulations, *J. Geophys. Res.*, 113, D19305, doi:10.1029/2008JD009942, 2008.
- Boé, J.: Modulation of soil moisture-precipitation interactions over France by large-scale circulation, *Clim. Dynam.*, 40875–40892, doi:10.1007/s00382-012-1380-6, 2013.
- Boé, J. and Terray, L.: Uncertainties in summer evapotranspiration changes over Europe and implications for regional climate change, *Geophys. Res. Lett.*, 35, L05702, doi:10.1029/2007GL032417, 2008.
- Butzin, M., Werner, M., Masson-Delmotte, V., Risi, C., Frankenberg, C., Gribanov, K., Jouzel, J., and Zakharov, V. I.: Variations of oxygen-18 in West Siberian precipitation during the last 50 years, *Atmos. Chem. Phys.*, 14, 5853–5869, doi:10.5194/acp-14-5853-2014, 2014.
- Cattiaux, J., Douville, H., and Peings, Y.: European temperatures in cmip5 origins of present-day biases and future uncertainties, *Clim. Dynam.*, 41, 2889–2907, doi:10.1007/s00382-013-1731-y, 2013.
- Cheruy, F., Campoy, A., Dupont, J. C., Ducharne, A., Hourdin, F., Haefelin, M., Chiriaco, M., and Idelkadi, A.: Combined influence of atmospheric physics and soil hydrology on the simulated meteorology at the sirta atmospheric observatory, *Clim. Dynam.*, 40, 2251–2269, doi:10.1007/s00382-012-1469-y, 2013.
- Christensen, J. H. and Boberg, F.: Temperature dependent climate projection deficiencies in cmip5 models, *Geophys. Res. Lett.*, 39, L24705, doi:10.1029/2012GL05365, 2012.
- Dansgaard, W.: Stable isotopes in precipitation, *Tellus*, 16, 436–468, 1964.
- d’Orgeval, T.: Impact du changement climatique sur le cycle de l’eau en Afrique de l’Ouest Modélisation et incertitudes, PhD thesis, Université Paris 6, 2006.
- Ducoudré, N., Laval, K., and Perrier, A.: SECHIBA, a new set of parametrizations of the hydrological exchanges at the land-atmosphere interface within the LMD atmospheric general circulation model, *J. Clim.*, 6248–273, 1993.

- Field, R. D., Jones, D. B. A., and Brown, D. P.: The effects of post-condensation exchange on the isotopic composition of water in the atmosphere. *J. Geophys. Res.*, 115, D24305, doi:10.1029/2010JD014334, 2010.
- Folkins, I. and Martin, R.: The vertical structure of tropical convection and its impact on the budgets of water vapor and ozone, *J. Atmos. Sci.*, 62, 560–1573, 2005.
- Frankenberg, C., Yoshimura, K., Warneke, T., Aben, I., Butz, A., Deutscher, N., Griffith, D., Hase, F., Notholt, J., Schneider, M., Schrijver, H., and Röckmann, T.: Dynamic processes governing lower-tropospheric HDO/H<sub>2</sub>O ratios as observed from space and ground, *Science*, 325, 1374–1377, 2009.
- Frankenberg, C., Wunch, D., Toon, G., Risi, C., Scheepmaker, R., Lee, J.-E., Wennberg, P., and Worden, J.: Water vapor isotopologue retrievals from high-resolution GOSAT shortwave infrared spectra, *Atmos. Meas. Tech.*, 6, 263–274, doi:10.5194/amt-6-263-2013, 2013.
- Galewsky, J. and Hurley, J. V.: An advection-condensation model for subtropical water vapor isotopic ratios, *J. Geophys. Res.*, 115, D16115, doi:10.1029/2009JD013651, 2010.
- Gat, J.: Atmospheric water balance—the isotopic perspective, *Hydrolog. Proc.*, 14, 1357–1369, 2000.
- Gat, J. R. and Matsui, E.: Atmospheric water balance in the Amazon basin An isotopic evapotranspiration model, *J. Geophys. Res.*, 96, 13179–13188, 1991.
- Hoffmann, G., Werner, M., and Heimann, M.: Water isotope module of the ECHAM atmospheric general circulation model A study on timescales from days to several years, *J. Geophys. Res.*, 103, 16871–16896, 1998.
- Hourdin, F., Musat, I., Bony, S., Braconnot, P., Codron, F., Dufresne, J.-L., Fairhead, L., Filiberti, M.-A., Friedlingstein, P., Grandpeix, J.-Y., Krinner, G., Levan, P., Li, Z.-X., and Lott, F.: The LMDZ4 general circulation model climate performance and sensitivity to parametrized physics with emphasis on tropical convection, *Clim. Dynam.*, 27, 787–813, 2006.
- Hurley, J. V., Galewsky, J., Worden, J., and Noone, D.: A test of the advection-condensation model for subtropical water vapor using stable isotopologue observations from Mauna Loa observatory, Hawaii, *J. Geophys. Res.*, 117, D19118, doi:10.1029/2012JD018029, 2012.
- Iijima, Y., Ohta, T., Kotani, A., Fedrov, A., Kodama, Y., and Maximov, T.: Sap flow changes in relation to permafrost degradation under increasing precipitation in an eastern Siberian larch forest. *Ecohydrology*, 7, 177–187, doi:10.1002/eco.1366, 2014.
- Jasechko, S., Sharp, W., Zachary, D., Sharp, J. J., Birks, S. J., Yi, Y., and Fawcett, P. J.: Terrestrial water fluxes dominated by transpiration, *Nature*, 496, 347–350, doi:10.1038/nature11983, 2013.
- Jouzel, J. and Koster, R. D.: A reconsideration of the initial conditions used for stable water isotope models, *J. Geophys. Res.*, 101, 22933–22938, 1996.
- Jouzel, J. and Merlivat, L.: Deuterium and oxygen 18 in precipitation modeling of the isotopic effects during snow formation, *J. Geophys. Res.*, 89, 11749–11757, 1984.
- Kittel, T. G. F., Giorgi, F., and Meehl, G. A.: Intercomparison of regional biases and doubled CO<sub>2</sub> sensitivity of coupled atmosphere-ocean general circulation model experiments, *Clim. Dynam.*, 141–15, doi:10.1007/s00382005020, 1997.
- Klein, S. A., Jiang, X., Boyle, J., Malyshev, S., and Xie, S.: Diagnosis of the summertime warm and dry bias over the U.S. southern great plains in the GFDL climate model using a weather forecasting approach, *Geophys. Res. Lett.*, 33, L18805, doi:10.1029/2006GL027567, 2006.
- Krinner, G., Viovy, N., de Noblet-Ducoudre, N., Ogee, J., Polcher, J., Friedlingstein, P., Ciais, P., Sitch, S., and Prentice, I. C.: A dynamic global vegetation model for studies of the coupled atmosphere-biosphere system, *Global Biogeochem. Cy.*, 19, GB1015, doi:10.1029/2003GB002199, 2005.
- Kurita, N., Noone, D., Risi, C., Schmidt, G. A., Yamada, H., and Yoneyama, K.: Intraseasonal isotopic variation associated with the Madden-Julian Oscillation, *J. Geophys. Res.*, 116, D24101, doi:10.1029/2010JD015209, 2011.
- Kurita, N., Yoshida, N., Inoue, G., and Chayanova, E. A.: Modern isotope climatology of Russia A first assessment, *J. Geophys. Res.*, 109, D03102, doi:10.1029/2003JD004046, 2004.
- Lawrence, J. R., Gedzelman, S. D., Dexheimer, D., Cho, H.-K., Carrie, G. D., Gasparini, R., Anderson, C. R., Bowman, K. P., and Biggerstaff, M. I.: Stable isotopic composition of water vapor in the tropics, *J. Geophys. Res.*, 109, D06115, doi:10.1029/2003JD004046, 2004.
- Lee, J.-E., Fung, I., DePaolo, D., and Fennig, C. C.: Analysis of the global distribution of water isotopes using the NCAR atmospheric general circulation model, *J. Geophys. Res.*, 112, D16306, doi:10.1029/2006JD007657, 2007.
- Lee, J.-E., Pierrehumbert, R., Swann, A., and Lintner, B. R.: Sensitivity of stable water isotopic values to convective parameterization schemes, *Geophys. Res. Lett.*, 36, L23801, doi:10.1029/2009GL040880, 2009.
- Majoube, M.: Fractionnement en oxygene 18 entre la glace et la vapeur d'eau, *J. Chimie Phys.*, 68, 625–636, 1971a.
- Majoube, M.: Fractionnement en oxygene-18 et en deuterium entre l'eau et sa vapeur. *J. Chim. Phys.*, 10, 1423–1436, 1971b.
- Masson-Delmotte, V., Hou, S., Ekaykin, A., Jouzel, J., Aristarain, A., Bernardo, R. T., Bromwich, D., Cattani, O., Delmotte, M., Falourd, S., Frezzotti, M., Gallée, H., Genoni, L., Isaksson, E., Landais, A., Helsen, M., Hoffmann, G., Lopez, J., Morgan, V., Motoyama, H., Noone, D., Oerter, H., Petit, J., Royer, A., Uemura, R., Schmidt, G., Schlosser, E., Simões, J., Steig, E., Stenni, B., Stievenard, M., van den Broeke, M., van de Wal, R., van den Berg, W.-J., Vimeux, F., and White, J.: A review of Antarctic surface snow isotopic composition observations, atmospheric circulation and isotopic modelling, *J. Climate*, 21, 3359–3387, 2008.
- Meehl, G. A., Covey, K., Delworth, T., Latif, M., McAvaney, B., Mitchell, J. F. B., Stouffer, R. J., and Taylor, K.: The WCRP CMIP3 multimodel dataset A new era in climate change research, *B. Am. Meteor. Soc.*, 7, 1383–1394, 2007.
- Merlivat, L. and Jouzel, J.: Global climatic interpretation of the Deuterium-Oxygen 18 relationship for precipitation, *J. Geophys. Res.*, 84, 5029–5332, 1979.
- Merlivat, L. and Nief, G.: Fractionnement isotopique lors des changements d'état solide-vapeur et liquide-vapeur de l'eau à des températures inférieures à 0 °C. *Tellus*, 19, 122–127, 1967.
- Moberg, A. and Jones, P.: Regional climate model simulations of daily maximum and minimum near-surface temperatures across Europe compared with observed station data 1961–1990, *Clim. Dynam.*, 23, 695–715, 2004.
- Noone, D.: Pairing measurements of the water vapor isotope ratio with humidity to deduce atmospheric moistening and dehydra-

- tion in the tropical mid-troposphere, *J. Climate*, 25, 4476–4494, 2012.
- Noone, D., Galewsky, J., Sharp, Z., Worden, J., Barnes, J., Baer, D., Bailey, A., Brown, D., Christensen, L., Crosson, E., Dong, F., Hurley, J. L., Johnson, M. S., D. Toohey, A. V. P., and Wright, J.: Properties of air mass mixing and humidity in the subtropics from measurements of the D/H isotope ratio of water vapor at the Mauna Loa Observatory, *J. Geophys. Res.*, 116, D22113, doi:10.1029/2011JD015773, 2011.
- Noone, D., Risi, C., Bailey, A., Berkelhammer, M., Brown, D. P., Buening, N., Gregory, S., Nusbaumer, J., Schneider, D., Sykes, J., Vanderwende, B., Wong, J., Meillier, Y., and Wolfe, D.: Determining water sources in the boundary layer from tall tower profiles of water vapor and surface water isotope ratios after a snowstorm in Colorado, *Atmos. Chem. Phys.*, 13, 1607–1623, doi:10.5194/acp-13-1607-2013, 2013.
- Polcher, J., Laval, K., Dfimenil, L., Lean, J., and Rowntree, P.: Comparing three land surface schemes used in general circulation models, *J. Hydrol.*, 180, 373–394, 1996.
- Pommier, M., Lacour, J.-L., Risi, C., Bréon, F. M., Clerbaux, C., Coheur, P.-F., Griбанov, K., Hurtmans, D., Jouzel, J., and Zakharov, V.: Observation of tropospheric  $\delta D$  by IASI over western Siberia: comparison with a general circulation model, *Atmos. Meas. Tech.*, 7, 1581–1595, doi:10.5194/amt-7-1581-2014, 2014.
- Risi, C.: Les isotopes stables à l'eau applications à l'étude du cycle de l'eau et des variations du climat, PhD thesis, Université Pierre et Marie Curie, 2009.
- Risi, C., Bony, S., and Vimeux, F.: Influence of convective processes on the isotopic composition (O18 and D) of precipitation and water vapor in the Tropics Part 2 Physical interpretation of the amount effect, *J. Geophys. Res.*, 113, D19306, doi:10.1029/2008JD009943, 2008.
- Risi, C., Bony, S., Vimeux, F., Chong, M., and Descroix, L.: Evolution of the water stable isotopic composition of the rain sampled along Sahelian squall lines, *Q. J. Roy. Meteor. Soc.*, 136, 227–242, 2010a.
- Risi, C., Bony, S., Vimeux, F., Frankenberg, C., and Noone, D.: Understanding the Sahelian water budget through the isotopic composition of water vapor and precipitation, *J. Geophys. Res.*, 115, D24110, doi:10.1029/2010JD014690, 2010b.
- Risi, C., Bony, S., Vimeux, F., and Jouzel, J.: Water stable isotopes in the LMDZ4 General Circulation Model model evaluation for present day and past climates and applications to climatic interpretation of tropical isotopic records, *J. Geophys. Res.*, 115, D12118, doi:10.1029/2009JD013255, 2010c.
- Risi, C., Noone, D., Worden, J., Frankenberg, C., Stiller, G., Kiefer, M., Funke, B., Walker, K., Bernath, P., Schneider, M., Wunch, D., Sherlock, V., Deutscher, N., Griffith, D., Wernberg, P., Bony, S., Jeonghoon Lee, D. B., Uemura, R., and Sturm, C.: Process-evaluation of tropical and subtropical tropospheric humidity simulated by general circulation models using water vapor isotopic observations. Part 1 model-data intercomparison, *J. Geophys. Res.*, 117, D05303, doi:10.1029/2011JD016621, 2012a.
- Risi, C., Noone, D., Worden, J., Frankenberg, C., Stiller, G., Kiefer, M., Funke, B., Walker, K., Bernath, P., Schneider, M., Wunch, D., Sherlock, V., Deutscher, N., Griffith, D., Wernberg, P., Bony, S., Lee, J., Brown, D., Uemura, R., and Sturm, C.: Process-evaluation of tropical and subtropical tropospheric humidity simulated by general circulation models using water vapor isotopic observations. Part 2 an isotopic diagnostic of the mid and upper tropospheric moist bias, *J. Geophys. Res.*, 117, D05304, doi:10.1029/2011JD016623, 2012b.
- Risi, C., Noone, D., Frankenberg, C., and Worden, J.: Role of continental recycling in intraseasonal variations of continental moisture as deduced from model simulations and water vapor isotopic measurements, *Water Resour. Res.*, 49, 4136–4156, doi:10.1002/wrcr.20312, 2013.
- Rozanski, K., Araguas-Araguas, L., and Gonfiantini, R.: Isotopic patterns in modern global precipitation, *Geophys. Monogr. Ser.*, AGU, Climate Change in Continental Isotopic records, 1993.
- Salati, E., Dall'Olio, A., Matsui, E., and Gat, J.: Recycling of water in the Amazon basin An isotopic study, *Water Resour. Res.*, 15, 1250–1258, 1979.
- Schmidt, G., LeGrande, A., and Hoffmann, G.: Water isotope expressions of intrinsic and forced variability in a coupled ocean-atmosphere model, *J. Geophys. Res.*, 112, D10103, doi:10.1029/2006JD007781, 2007.
- Schneider, M., Yoshimura, K., Hase, F., and Blumenstock, T.: The ground-based FTIR network's potential for investigating the atmospheric water cycle, *Atmos. Chem. Phys.*, 10, 3427–3442, doi:10.5194/acp-10-3427-2010, 2010.
- Simonin, K. A., Link, P., Rempe, D., Miller, S., Oshun, J., Bode, C., Dietrich, W. E., Fung, I., and Dawson, T. E.: Vegetation induced changes in the stable isotope composition of near surface humidity, *Ecohydrol.*, 7, 936–949, doi:10.1002/eco.1420, 2013.
- Steen-Larsen, H.-C., Johnsen, S., Masson-Delmotte, V., Stenni, B., Risi, C., Sodemann, H., Balslev-Clausen, D., Blunier, T., Dahl-Jensen, D., Ellehoej, M., Falourd, S., Gkinis, V., Grinsted, A., Jouzel, J., Popp, T., Sheldon, S., Simonsen, S., Sjolte, J., Steffensen, J., Sperlich, P., Sveinbjornsdottir, A., Vinther, B., and White, J.: Continuous monitoring of summer surface water vapour isotopic composition above the greenland ice sheet, *Atmos. Chem. Phys.*, 13, 4815–4828, doi:10.5194/acp-13-4815-2013, 2013.
- Stewart, M. K.: Stable isotope fractionation due to evaporation and isotopic exchange of falling waterdrops: applications to atmospheric processes and evaporation of lakes, *J. Geophys. Res.*, 80, 1133–1146, 1975.
- Taylor, K. E., Stouffer, R. J., and Meehl, G. A.: An overview of CMIP5 and the experiment design. *B. Am. Meteorol. Soc.*, 93, 485–498, 2012.
- Tindall, J. C., Valdes, P., and Sime, L. C.: Stable water isotopes in HadCM3 Isotopic signature of El Nino-Southern Oscillation and the tropical amount effect, *J. Geophys. Res.*, 114, D04111, doi:10.1029/2008JD010825, 2009.
- Uppala, S., Kallberg, P., Simmons, A., Andrae, U., da Costa Bechtold, V., Fiorino, M., Gibson, J., Haseler, J., Hernandez, A., Kelly, G., Li, X., Onogi, K., Saarinen, S., Sokka, N., Allan, R., Andersson, E., Arpe, K., Balmasada, M., Beljaars, A., van de Berg, L., Bidlot, J., Bormann, N., Caires, S., Chevallier, F., Dethof, A., Dragosavac, M., Fisher, M., Fuentes, M., Hagemann, S., Holm, E., Hoskins, B., Isaksen, I., Janssen, P., Jenne, R., McNally, A., Mahfouf, J.-F., Morcrette, J.-J., Rayner, N., Saunders, R., Simon, P., Sterl, A., Trenberth, K., Untch, A., Vasiljevic, D., Viterbo, P., and Woollen, J.: The ERA-40 re-analysis, *Q. J. Roy. Meteor. Soc.*, 131, 2961–3012, 2005.

- Washburn, E. and Smith, E.: The isotopic fractionation of water by physiological processes, *Science*, 79, 188–189, 1934.
- Welp, L., Lee, W., Griffis, T. J., Wen, X.-F., Xiao, W., Li, S., Sun, X., Hu, Z., Val Martin, M., and Huang, J.: A meta-analysis of water vapor deuterium-excess in the midlatitude atmospheric surface layer, *Global Biogeochem. Cy.*, 26, GB3021, doi:10.1029/2011GB004246, 2012.
- Williams, D. G., Cable, W., Hultine, K., Hoedjes, J. C. B., Yezpe, E. A., Simonneaux, V., Er-Raki, S., Boulet, G., de Bruin, H. A. R., Chehbouni, A., Hartogensis, O. K., and Timouk, F.: Evapotranspiration components determined by stable isotope, sap flow and eddy covariance techniques, *Agr. Forest. Meteorol.*, 125, 241–258, 2004.
- Worden, J., Bowman, K., Noone, D., Beer, R., Clough, S., Eldering, A., Fisher, B., Goldman, A., Gunson, M., Herman, R., Kulawik, S. S., Lampel, M., Luo, M., Osterman, G., Rinsland, C., Rodgers, C., Sander, S., Shephard, M., and Worden, H.: Tropospheric Emission Spectrometer observations of the tropospheric HDO/H<sub>2</sub>O ratio Estimation approach and characterization, *J. Geophys. Res.*, 111, D16309, doi:10.1029/2005JD006606, 2006.
- Worden, J., Kulawik, S., Frankenberg, C., Payne, V., Bowman, K., Cady-Peirara, K., Wecht, K., Lee, J.-E., and Noone, D.: Profiles of CH<sub>4</sub>, HDO, H<sub>2</sub>O, and N<sub>2</sub>O with improved lower tropospheric vertical resolution from Aura TES radiances, *Atmos. Meas. Tech.*, 5, 397–411, doi:10.5194/amt-5-397-2012, 2012.
- Worden, J., Noone, D., and Bowman, K.: Importance of rain evaporation and continental convection in the tropical water cycle, *Nature*, 445, 528–532, 2007.
- Worden, J., Noone, D., Galewsky, J., Bailey, A., Bowman, K., Brown, D., Hurley, J., Kulawik, S., Lee, J., and Strong, M.: Estimate of bias in Aura TES HDO/H<sub>2</sub>O profiles from comparison of TES and in situ HDO/H<sub>2</sub>O measurements at the Mauna Loa observatory, *Atmos. Chem. Phys.*, 11, 4491–4503, doi:10.5194/acp-11-4491-2011, 2011.
- Yoshimura, K., Kanamitsu, M., and Dettinger, M.: Regional downscaling for stable water isotopes A case study of an atmospheric river event, *J. Geophys. Res.*, 115, D18114, doi:10.1029/2010JD014032, 2010.
- Yoshimura, K., Kanamitsu, M., Noone, D., and Oki, T.: Historical isotope simulation using reanalysis atmospheric data, *J. Geophys. Res.*, 113, D19108, doi:10.1029/2008JD010074, 2008.
- Zipser, E.: Mesoscale and convective scale downdrafts as distinct components of squall-line structure, *Mon. Weather Rev.*, 105, 1568–1589, 1977.