

The colour of forcing statistics in resolvent analyses of turbulent channel flows

Pierluigi Morra^{1,†}, Petrônio A. S. Nogueira², André V. G. Cavalieri²
and Dan S. Henningson¹

¹Department of Engineering Mechanics, FLOW, KTH Royal Institute of Technology,
SE-10044 Stockholm, Sweden

²Aerodynamics Department, Instituto Tecnológico de Aeronáutica, São José dos Campos,
12228900, Brazil

(Received 3 April 2020; revised 7 August 2020; accepted 16 September 2020)

In resolvent analyses of turbulent channel flows it has been common practice to neglect or model the nonlinear forcing term that forms the input of the resolvent. However, the spatiotemporal structure of this term is mostly unknown. Here, this nonlinear forcing term is quantified. The Fourier transform of its two-point space–time correlation, its cross-spectral density (CSD), is computed. The CSD is evaluated for two channel flows at friction Reynolds numbers $Re_\tau = 179$ and $Re_\tau = 543$ via direct numerical simulations (DNS). The CSDs are computed for energetic structures typical of buffer-layer and large-scale motions, for different temporal frequencies. It is found that the forcing is structured and that its solenoidal part, which is the only one affecting the velocity field, is the combination of an oblique streamwise vortical forcing and a streamwise component that counteract each other, as in a destructive interference. It is shown that a rank-2 approximation of the forcing, with only the most energetic spectral proper orthogonal decomposition (SPOD) modes, leads to the bulk of the response. Moreover, it is found that the nonlinear forcing term has a non-negligible projection onto the linear sub-optimal forcings of resolvent analysis, which demonstrates that the linear optimal forcing is not representative of the nonlinear forcing. Finally, it is clarified that the Cess eddy-viscosity-modelled forcing improves the accuracy of resolvent analysis prediction because the modelled forcing projects onto the linear sub-optimal forcings similarly to DNS data.

Key words: turbulent boundary layers

1. Introduction

Despite general agreement on the existence of self-sustained processes in wall-bounded turbulence, there are different understandings of the mechanisms involved. A common

† Email address for correspondence: pmorra@mech.kth.se

technique to tackle this problem consists in writing the Navier–Stokes (N–S) equations as a linear evolution equation with nonlinear feedback; the nonlinear feedback being a forcing that includes the instantaneous nonlinear advection terms associated with the velocity fluctuations. The flow is decomposed into a time-invariant reference state and a fluctuation component, the reference state is usually assumed to be known, and the fluctuations become the unknown variable. Thus, the system dynamics is clearly described as the combination of the energy amplification and the energy redistribution mechanisms, which are represented by the linear operator and the nonlinear forcing.

The choice of the reference state and the treatment of the nonlinear forcing in the mentioned framework is key. A set of studies bypassed the explicit computation of the nonlinear term and dealt solely with the linear evolution operator. The approach consists of taking the time-averaged field as the reference state and introducing assumptions to avoid the computation of the nonlinear forcing (Malkus 1956; Butler & Farrell 1993; Farrell & Ioannou 1993; McKeon & Sharma 2010). Another approach, first proposed by Reynolds & Tiederman (1967), Reynolds & Hussain (1972) and later revived by Bottaro, Souied & Galletti (2006), del Álamo & Jimenez (2006), Cossu, Pujals & Depardon (2009), Pujals *et al.* (2009) and Hwang & Cossu (2010*a,c*), consists of modelling part of the nonlinear forcing with an eddy viscosity and introducing assumptions to avoid the computation of the remainder of the nonlinear forcing. This leads to a modified linear operator. A review of these two approaches with the benefits and limitations of using an eddy-viscosity model can be found in McKeon (2017) or Cossu & Hwang (2017). It is noteworthy that these approaches do not need *a priori* knowledge of the flow fluctuations.

A set of studies takes the time-averaged field as a reference state and treats the nonlinear forcing as an unknown (exogenous) stochastic input. This approach consists of assuming this stochastic input as uncorrelated in space and time, and in predicting the dynamics with a ‘to-be-designed’ estimator as the Kalman filter (Chevalier *et al.* 2006; Illingworth, Monty & Marusic 2018). The estimator consists of the original system without the nonlinear forcing (i.e. the stochastic input) but with the addition of a correction term, which is designed to minimize the variance of the prediction error. It is noteworthy that this approach requires the instantaneous knowledge of a linear combination (i.e. a measurement) of the fluctuation quantities.

Another approach, introduced by Zare, Jovanović & Georgiou (2017), consists of computing simultaneously the covariances of both the flow fluctuations and the stochastic input. The stochastic input is not restricted to be uncorrelated in space or time, nor it is assumed to be a function of the fluctuations. The relationship between the fluctuations and the input is enforced by the Lyapunov equation associated with the original system with the nonlinear forcing treated as an unknown (exogenous) stochastic input. The method is a constrained optimization problem. The constraints are the Lyapunov equation and the fact that the covariance of the fluctuation quantities must be consistent with available data. The objective function to minimize is the result of a ‘regularized maximum entropy formalism’, where the ‘maximum entropy formalism’ utilized is known to be equivalent to the ‘maximum likelihood formalism’ (see Goodwin & Payne (1977) or Della Pietra, Della Pietra & Lafferty (1997) for details).

Another approach, presented by Towne, Lozano-Durán & Yang (2020), uses the resolvent to compute an approximation of the cross-spectral density (CSD) of the nonlinear forcing. The method exploits the input–output relationship described by the resolvent in the frequency domain. The approach assumes the knowledge of the output, which is taken with a number of sensors, and makes use of the singular values and singular vectors of the resolvent to reconstruct the corresponding input, which is the nonlinear forcing.

The technique consists of a projection approach, equivalent to the application of the pseudo-inverse of the resolvent operator to the known statistics. Therefore, the computed forcing is the best attainable in a least-squares sense.

The aforementioned works deal with an approximation of the nonlinear forcing based on available statistics. Quantifying this forcing directly from the nonlinear advection term of the sole fluctuation velocity, which is the definition, is not sought there. Rosenberg & McKeon (2019) analysed this term for two ‘exact coherent states’ (i.e. invariant solutions of the N–S) of an incompressible channel flow at friction Reynolds number $Re_\tau = 85$ (Nagata 1990; Park & Graham 2015). They utilized the Orr–Sommerfeld–Squire (OSS) equations (Schmid & Henningson 2001) to build the resolvent operator and focused on the solenoidal part of the nonlinear forcing, which is the only one affecting the velocity field of an incompressible flow (Chorin & Marsden 1993). However, the authors focused on the variance of the solenoidal forcing, so the analysis did not distinguish between the contribution of different frequencies. Symon, Sipp & McKeon (2019) isolated the contribution of each frequency by employing the spectral proper orthogonal decomposition (SPOD) (Lumley 1970; Picard & Delville 2000). However, they used data from particle image velocimetry (PIV) of the flow around a NACA0018 airfoil at a chord-based Reynolds number $Re = 10\,250$, and the forcing is not decomposed in its solenoidal and irrotational parts.

The nonlinear forcing term is non-solenoidal by construction. To evaluate its solenoidal part, one of the variants of the Helmholtz–Hodge decomposition (HHD) can be performed (see Chorin & Marsden (1993) or Bhatia *et al.* (2013) for details; see Wu, Zhou & Wu (1996) or Rosenberg & McKeon (2019) for examples of applications). The HHD requires specific boundary conditions to assure the orthogonality and the uniqueness of the resulting solenoidal and irrotational fields (Chorin & Marsden 1993; Bhatia *et al.* 2013), which amounts to imposing *a priori* the unknown solenoidal field be parallel to the wall. This assumption and the use of the HHD can be avoided when using the OSS because the solenoidal part of the forcing can be retrieved directly with the operators of the OSS, as presented here in [appendix B](#).

Access to a quantitative characterization of the nonlinear forcing term can be helpful for addressing the domain of validity of modelling techniques that aim at mimicking its effects on the dynamics. Beneddine *et al.* (2016) mentioned that such quantification is convenient also to assess the validity of mean flow stability analysis, which has generally been based on the sole singular values of the resolvent. Moreover, even though there is general agreement on the existence of self-sustained coherent motions and visualizations of such motions are presented, there is no documentation of the spatiotemporal structure of the nonlinear forcing terms resulting from the fluctuation velocities for turbulent channel flows. As these nonlinear forcing terms cause the feedback mechanism in the linearized system dynamics, its quantification is of interest to further understand the ‘recycling’ of the amplified outputs in the input from the nonlinear terms.

Moreover, it is understood that the shape of the linear optimal forcing that results from resolvent analyses similar to Farrell & Ioannou (1993) or McKeon & Sharma (2010) does not necessarily coincide with that of the nonlinear forcing term of a turbulent channel flow. Beneddine *et al.* (2016), among others, remarked on this. This linear optimal forcing is the right singular vector of the resolvent associated with the highest singular value. Morra *et al.* (2019) showed a case where using the right-singular vectors as forcing to the resolvent does not result in the same velocity field of direct numerical simulations (DNS). As the right singular vectors of the resolvent form a basis that spans the forcing space, it

can be inferred that the nonlinear forcing term has significant projection onto the linear sub-optimals. However, there is no such verification.

When dealing with coherent motions in the framework of stochastic forcing and response, the resolvent operator and the SPOD prove to be useful tools. SPOD assures the resulting modes to be coherent in space and time (Towne, Schmidt & Colonius 2018), whereas the resolvent operator can describe the input–output relationship between the CSDs of the input and the output, on which the SPOD is based. The usage of the CSD allows us to isolate the dominant energetic structures, so it avoids blurring the interpretation of the results. It is known that a relation exists between the SPOD modes and the singular modes of the resolvent operator (Towne *et al.* 2018; Cavalieri, Jordan & Lesshafft 2019; Lesshafft *et al.* 2019), but investigations of turbulent channel flows have been based on assumptions, without quantifying the effects of the nonlinear forcing term as input.

In this work a quantification of the nonlinear forcing term, usually treated as an input in resolvent analyses, is accomplished for turbulent channel flows. The investigated flows have friction Reynolds numbers $Re_\tau = 179$ and $Re_\tau = 543$. The resolvent framework is employed. The reference state upon which the resolvent is built is the time-averaged field, so the nonlinear forcing term consists of the advection term with the fluctuation velocities. The nonlinear forcing is quantified through its CSD for the most energetic near-wall and large-scale structures, such that the input–output relation of the most energetic motions is highlighted. The CSD of the nonlinear forcing term is computed directly from snapshots of DNS data by means of the Welch method, with the same technique as discussed by Nogueira *et al.* (2021). The complete non-solenoidal forcing and its solenoidal part are presented, and its effects on the output discussed. The expected coherence of the forcing is quantified here. Moreover, inspired by the discussion in Beneddine *et al.* (2016), a quantification of the key parameters to assess the accuracy of resolvent analyses is possible and performed here. Thus, an evaluation of the errors introduced by neglecting or modelling the nonlinear forcing is possible and presented. The aim of this work is to compensate the lack in the literature of an explicit characterization of the spatiotemporal structure of the nonlinear forcing term for turbulent channel flows, and provide a foundation for all the studies which choose to include assumptions about this nonlinear forcing term to facilitate the mathematical treatment.

This paper is structured as follows. In § 2 the governing equations of the problem addressed are summarized. In § 3 the results of the DNS are presented, the CSD of the forcing is shown and discussed. In § 4 the effects of the nonlinear forcing term are analysed and the low-rank property of the associated CSD demonstrated. In § 5 an assessment of the errors introduced when resorting to modelling the nonlinear forcing term are discussed by comparison with the nonlinear forcing term computed from DNS data. The results are summarized and discussed in § 6. Further details about the operators involved in the analysis and the Welch method are provided in [appendices A, B, and C](#).

2. Governing equations

2.1. Evolution equations for the fluctuation quantities

This work focuses on the dynamics of perturbations about the time-averaged fields in a channel flow. The flow is incompressible and the density constant. The quantities treated here are non-dimensionalized, and the Reynolds number $Re = (3/2)U_{bulk}h/\nu$ is based on the channel half-height h , the constant mass-averaged streamwise velocity U_{bulk} and

the fluid molecular viscosity ν . The domain is described with Cartesian coordinates $\mathbf{x} = (x, y, z)^T$, which correspond to the streamwise, wall-normal and spanwise directions. The total velocity and pressure fields can be described as the superposition of the time-averaged fields and the fluctuations, $\mathbf{u}_{tot} = \mathbf{U} + \mathbf{u}$ and $p_{tot} = P + p$, as in the Reynolds decomposition. Here, $\mathbf{U} = (U(y), 0, 0)^T$ is the mean flow in the channel, $P = P(x)$ the time-averaged pressure field, $\mathbf{u} = (u(\mathbf{x}, t), v(\mathbf{x}, t), w(\mathbf{x}, t))^T$ the perturbation velocity and $p = p(\mathbf{x}, t)$ the perturbation pressure; t being the non-dimensional time. Both the mean flow and the perturbation velocity are subject to the incompressibility condition $\nabla \cdot \mathbf{U} = 0$ and $\nabla \cdot \mathbf{u} = 0$, with $\nabla = (\partial_x, \partial_y, \partial_z)^T$ such that $\nabla^2 = \nabla \cdot \nabla$. Assuming \mathbf{U} and P to be known, the momentum equations

$$\frac{\partial \mathbf{u}}{\partial t} + (\mathbf{U} \cdot \nabla)\mathbf{u} + (\mathbf{u} \cdot \nabla)\mathbf{U} = -\nabla p + \frac{1}{Re}\nabla^2\mathbf{u} + \mathbf{b} + \mathbf{f}, \tag{2.1}$$

are the evolution equations for the fluctuations, where the density is included in the pressure term, $\mathbf{b} = -\nabla P + Re^{-1}\nabla^2\mathbf{U} - (\mathbf{U} \cdot \nabla)\mathbf{U}$ includes the contribution of time-averaged quantities only, and $\mathbf{f} = -(\mathbf{u} \cdot \nabla)\mathbf{u}$ the instantaneous Reynolds stresses from the fluctuations; it is assumed that there is no external body force. It is notable that (2.1) has the same structure of the perturbation equation of a flow linearized about an equilibrium solution of the N-S equations, in which case $\mathbf{b} = 0$ by construction.

2.2. Harmonic and stochastic forcing analysis

As the mean flow is homogeneous in the wall-parallel directions, the Fourier transform can be applied along those directions and the same manipulations to obtain the OSS equations can be performed. Thus, by introducing $\hat{\mathbf{q}}^* = (\hat{v}(\alpha, y, \beta, t), \hat{\omega}_y(\alpha, y, \beta, t))$ as the vector containing the wall-normal velocity and vorticity Fourier modes, (2.1) can be written in terms of $\hat{\mathbf{q}}^*(\alpha, y, \beta, t) \exp(i(\alpha x + \beta z))$ and $\hat{\mathbf{f}}^*(\alpha, y, \beta, t) \exp(i(\alpha x + \beta z))$ Fourier modes. Moreover, by discretizing the wall-normal direction with N_y points, and by introducing the vectors $\hat{\mathbf{q}}, 2N_y \times 1$, and $\hat{\mathbf{f}}, 3N_y \times 1$, as the discrete counterparts of $\hat{\mathbf{q}}^*$ and $\hat{\mathbf{f}}^*$, (2.1) reduces to the system

$$\frac{\partial \hat{\mathbf{q}}}{\partial t} = \mathbf{A}\hat{\mathbf{q}} + \mathbf{B}\hat{\mathbf{f}}, \tag{2.2}$$

where \mathbf{b} is not included because the focus of this study is on $\alpha \neq 0$ and $\beta \neq 0$, and \mathbf{b} is constant along the wall-parallel directions. In the discretized domain the Fourier modes of the fluctuation velocity $\hat{\mathbf{u}}^*(\alpha, y, \beta, t) \exp(i(\alpha x + \beta z))$ correspond to the vector $\hat{\mathbf{u}}, 3N_y \times 1$, and can be computed as $\hat{\mathbf{u}} = \mathbf{C}\hat{\mathbf{q}}$, whereas $\hat{\mathbf{q}} = \mathbf{D}\hat{\mathbf{u}}$. The expressions for the matrices \mathbf{A} , \mathbf{B} , \mathbf{C} and \mathbf{D} are given in appendix A. For the sake of readability dependencies on the wavenumbers α and β are no longer written explicitly.

As \mathbf{U} and P are the time-averaged fields of a turbulent channel flow, the system described by (2.2) is linearly stable (Reynolds & Tiederman 1967), so a finite amplitude forcing can be studied by performing the Fourier transform in time on (2.2). Then, the harmonic forcing $\hat{\mathbf{f}} = \tilde{\mathbf{f}}(\omega) e^{-i\omega t}$ and the harmonic response $\hat{\mathbf{u}} = \tilde{\mathbf{u}}(\omega) e^{-i\omega t}$ are related by $\tilde{\mathbf{u}}(\omega) = \mathbf{R}(\omega)\tilde{\mathbf{f}}(\omega)$, with

$$\mathbf{R}(\omega) = -\mathbf{C}(i\omega\mathbf{I} + \mathbf{A})^{-1}\mathbf{B}, \tag{2.3}$$

the $3N_y \times 3N_y$ matrix form of the resolvent operator (with boundary conditions $\tilde{v} = \partial\tilde{v}/\partial y = \tilde{\omega}_y = 0$ or, equivalently, $\tilde{u} = \tilde{v} = \tilde{w} = 0$, at $y = \pm 1$). A singular value decomposition (SVD) allows the resolvent matrix $\mathbf{R}(\omega)$ to be expressed in terms of its

left-singular vectors $\psi_i(\omega)$, its singular values $\sigma_i(\omega)$ and its right-singular vectors $\phi_i(\omega)$, such that

$$\phi_i^H \mathbf{W} \phi_j = \delta_{ij}, \tag{2.4a}$$

$$\psi_i^H \mathbf{W} \psi_j = \delta_{ij}, \tag{2.4b}$$

with H the complex conjugate transpose, δ_{ij} the Kronecker delta and \mathbf{W} the positive-definite Hermitian matrix, $3N_y \times 3N_y$, of quadrature weights necessary to compute the energy norm on the discrete grid of the wall-normal direction.

If instead of harmonic excitation a stochastic and statistically stationary forcing is considered, the response will also be stochastic and statistically stationary. In this case the Fourier transform in time cannot be applied because $\int_{-\infty}^{\infty} |\hat{u}|^2 dt < \infty$ (or $\int_{-\infty}^{\infty} |\hat{q}|^2 dt < \infty$) and $\int_{-\infty}^{\infty} |\hat{f}|^2 dt < \infty$ do not hold (Chibbaro & Minier 2014). A quantity that exists and can be computed for a statistically stationary process is the CSD (Stark & Woods 1986), which is defined for the vectors \hat{u} and \hat{f} as

$$\mathbf{S}(\omega) = \lim_{T \rightarrow \infty} \frac{\mathbb{E} \left[\left(\frac{1}{2\pi} \int_{-T}^T \hat{u}(t) e^{-i\omega t} dt \right) \left(\frac{1}{2\pi} \int_{-T}^T \hat{u}(t)^H e^{i\omega t} dt \right) \right]}{2T}, \tag{2.5a}$$

$$\mathbf{P}(\omega) = \lim_{T \rightarrow \infty} \frac{\mathbb{E} \left[\left(\frac{1}{2\pi} \int_{-T}^T \hat{f}(t) e^{-i\omega t} dt \right) \left(\frac{1}{2\pi} \int_{-T}^T \hat{f}(t)^H e^{i\omega t} dt \right) \right]}{2T}, \tag{2.5b}$$

where T is the total time, the expectation $\mathbb{E}[\cdot]$ is the ensemble average over different stochastic realizations and the CSDs are the $3N_y \times 3N_y$ matrices $\mathbf{S}(\omega)$ and $\mathbf{P}(\omega)$. The diagonals of $\mathbf{S}(\omega)$ and $\mathbf{P}(\omega)$ contain the power-spectral density (PSD) of the three velocity and forcing components at the discrete points of the wall-normal direction for a given angular frequency ω (and the omitted α and β). For the sake of readability the streamwise, wall-normal and spanwise components on the diagonal of $\mathbf{S}(\omega)$ and $\mathbf{P}(\omega)$ are from now on referred to with the $N_y \times 1$ vectors s_{uu}, s_{vv}, s_{ww} , and p_{uu}, p_{vv}, p_{ww} . Then, the premultiplied streamwise kinetic energy spectra can be computed as

$$\alpha\beta e_{uu}^{kin} = \alpha\beta \int_{-\infty}^{\infty} s_{uu}(\omega) d\omega. \tag{2.6}$$

As the system in (2.2) is stable, it also holds (Stark & Woods 1986)

$$\mathbf{S}(\omega) = \mathbf{R}(\omega)\mathbf{P}(\omega)\mathbf{R}(\omega)^H, \tag{2.7}$$

which is the input–output relation of the CSDs. For the sake of readability dependencies on the angular frequency ω are no longer written explicitly.

As \mathbf{S} and \mathbf{P} are CSDs, the Karhunen–Loève decomposition can be performed, which for quantities in the frequency domain is referred to as SPOD (Lumley 1970; Picard & Delville 2000; Towne *et al.* 2018). The SPOD modes of the matrices \mathbf{S} and \mathbf{P} correspond to the $3N_y \times 1$ eigenvectors ξ_i and ζ_i of the matrix eigenvalue problems $\mathbf{S}\mathbf{W}\xi_i = \mu_i\xi_i$ and $\mathbf{P}\mathbf{W}\zeta_i = \eta_i\zeta_i$. The eigenvectors are orthogonal in $\xi_i^H \mathbf{W} \xi_j = \delta_{ij}$ and $\zeta_i^H \mathbf{W} \zeta_j = \delta_{ij}$. Thus, the CSDs can be expanded as $\mathbf{S} = \sum_i \mu_i \xi_i \xi_i^H$ and $\mathbf{P} = \sum_i \eta_i \zeta_i \zeta_i^H$, such that the diagonal of \mathbf{S}

and \mathbf{P} can be written as

$$\text{diag}(\mathbf{S}) = \sum_i \mu_i |\xi_i|^2, \tag{2.8a}$$

$$\text{diag}(\mathbf{P}) = \sum_i \eta_i |\xi_i|^2, \tag{2.8b}$$

with $|\cdot|$ the absolute value of each entry of the vector. It can be noted that because the SPOD modes are orthogonal in the inner product associated with the energy norm, the ratios $\mu_i / \sum_i \mu_i$ and $\eta_i / \sum_i \eta_i$ represent the fraction of power associated with the i th SPOD mode.

The computation of the left- and right-singular vectors of \mathbf{R} allows the input–output relation $\mathbf{S} = \mathbf{R}\mathbf{P}\mathbf{R}^H$ to be split into three steps: (i) the projection of \mathbf{P} onto the right-singular vectors ϕ_i , which results in a scalar

$$b_i^2 = \phi_i^H \mathbf{W}\mathbf{P}\mathbf{W}\phi_i \tag{2.9}$$

for each ϕ_i ; (ii) the amplification or damping of the associated singular values σ_i by b_i , which results in a scalar $a_i = \sigma_i b_i$; and (iii) the linear combination of the left-singular vectors ψ_i weighted with a_i such that

$$\text{diag}(\mathbf{S}) = \sum_i |\psi_i|^2 a_i^2. \tag{2.10}$$

As σ_i do not depend on \mathbf{P} and $a_i^2 = \sigma_i^2 b_i^2$, it is the coefficients b_i that quantify the contribution of the forcing \mathbf{P} to the output \mathbf{S} . Note that if $b_i = 1$, then $\mathbf{P} \equiv \mathbf{I}$.

It can be remarked that \mathbf{S} is built upon a solenoidal vector field because the velocity field is divergence free in incompressible flows, whereas \mathbf{P} is built upon a non-solenoidal vector field because the divergence of the nonlinear forcing \mathbf{f} is non-zero. Moreover, if the flow is incompressible only the solenoidal part of the forcing affects the velocity field (Chorin & Marsden 1993). Therefore, if the forcing is written as the sum of a solenoidal and an irrotational vector field, the irrotational part gives a null response in (2.7). This implies that \mathbf{R} is singular, and that its null space spans the set of all possible non-solenoidal fields.

It follows that there must be an injective linear transformation between the velocity field and the solenoidal part of the nonlinear forcing field, which may be exploited to extract the solenoidal part of \mathbf{P} when \mathbf{S} is known. In [appendix B](#) it is shown that

$$\mathbf{L} = -\mathbf{C}(i\omega\mathbf{I} + \mathbf{A})\mathbf{D} \tag{2.11}$$

constitutes such a linear relationship. The solenoidal part of \mathbf{P} can be retrieved as $\mathbf{L}\mathbf{S}\mathbf{L}^H$. It should be noted that \mathbf{L} is not exactly the inverse of \mathbf{R} in (2.7) because \mathbf{R} is singular. In [appendix B](#) it is also shown that if the forcing $\hat{\mathbf{f}}$ is known, its solenoidal part can be computed also as $\mathbf{C}\mathbf{B}\hat{\mathbf{f}}$, which can be employed to evaluate the solenoidal part of \mathbf{P} as $(\mathbf{C}\mathbf{B})\mathbf{P}(\mathbf{C}\mathbf{B})^H$. Resorting to \mathbf{L} or $\mathbf{C}\mathbf{B}$ to compute the solenoidal part of the forcing is equivalent. A more detailed discussion about \mathbf{L} and $\mathbf{C}\mathbf{B}$ is presented in [appendix B](#).

2.3. Modelling the nonlinear forcing terms

The input–output relationship described by (2.7) includes the contribution of the nonlinear terms, those responsible for the Reynolds stresses, in the input \mathbf{P} . The nonlinear terms are

usually unknown, and the input \mathbf{P} is modelled. The lack of knowledge about the nonlinear terms implies that the accuracy of these modelling techniques cannot be based on a direct comparison with them. Instead, the error in the prediction of the velocity field or its statistics is evaluated. As this work aims at presenting the actual \mathbf{P} that appears in the N–S, its direct comparison with a modelled \mathbf{P} can be evaluated. Moreover, \mathbf{P} has never been quantified from instantaneous realizations $\hat{\mathbf{f}}$ of a turbulent channel flow. Thus, a comparison with the results from often used modelling methods is clearly of interest.

The two modelling approaches discussed in this work are: (i) the assumption that the nonlinear terms are uncorrelated in space $\mathbf{P} = \gamma_v \mathbf{I}$ (with γ_v a normalization scalar, and \mathbf{I} the identity); and (ii) the introduction of an eddy-viscosity ν_t to model a part of the nonlinear terms via the Boussinesq expression. In (ii) the unmodelled part of the nonlinear terms is treated as uncorrelated in space. The two approaches lead to the predictions

$$\mathbf{S}_{R_v} = \gamma_v \mathbf{R} \mathbf{R}^H, \tag{2.12a}$$

$$\mathbf{S}_{R_{\nu_t}} = \gamma_{\nu_t} \mathbf{R}_{\nu_t} \mathbf{R}_{\nu_t}^H, \tag{2.12b}$$

where \mathbf{R}_{ν_t} is a modified resolvent that includes the eddy-viscosity modelling (details about the operator are given in [appendix A](#)), and γ_{ν_t} a normalization scalar.

The forcing necessary to obtain the prediction $\mathbf{S}_{R_{\nu_t}}$ by means of \mathbf{R} , such that $\mathbf{S}_{R_{\nu_t}} = \mathbf{R} \mathbf{P}_{\nu_t} \mathbf{R}^H$, can be computed as

$$\mathbf{P}_{\nu_t} = \mathbf{L} \mathbf{S}_{R_{\nu_t}} \mathbf{L}^H, \tag{2.13}$$

which quantifies how the eddy-viscosity approach models \mathbf{P} . The effects of the modelling with $\mathbf{P} = \gamma_v \mathbf{I}$, of the eddy-viscosity approach with $\mathbf{P} = \mathbf{P}_{\nu_t}$, are compared with the \mathbf{P} computed from instantaneous realizations of $\hat{\mathbf{f}}$ via the coefficients b_i in [\(2.9\)](#).

The normalization scalars γ_v and γ_{ν_t} are function of the wavenumbers α , β and the angular frequency ω . They are computed here from the PSDs as

$$\gamma_v(\alpha, \beta, \omega) = \frac{\|\text{diag}(\mathbf{S})\|_\infty}{\|\text{diag}(\mathbf{R}_v \mathbf{R}_v^H)\|_\infty}, \tag{2.14a}$$

$$\gamma_{\nu_t}(\alpha, \beta, \omega) = \frac{\|\text{diag}(\mathbf{S})\|_\infty}{\|\text{diag}(\mathbf{R}_{\nu_t} \mathbf{R}_{\nu_t}^H)\|_\infty}, \tag{2.14b}$$

and represent a rescaling factor to compensate for the lack of knowledge on the amplitude of the modelled forcing term such that the responses match the DNS $\text{diag}(\mathbf{S})$ in the ∞ -norm. The scalars also give an indication of the offset of the prediction of the amplitude; in fact, if the modelled forcing were to coincide with that computed from the DNS data, $\gamma_v = 1$ or $\gamma_{\nu_t} = 1$. For the sake of readability, from now on the explicit dependency of the scalars γ_v , γ_{ν_t} on α , β , ω is dropped. The ∞ -norm of a vector \mathbf{g} is intended as $\|\mathbf{g}\|_\infty = \max_i |g_i|$ with i the i th term of the vector.

3. Direct numerical simulations

The flow cases analysed are at $Re_\tau = 179$ and $Re_\tau = 543$ with the box details presented in [table 1](#). The mean velocity profile and the root-mean-square (rms) of the three velocity components are presented in [figure 1](#), where it is shown that the profiles are in agreement with the results of del Álamo & Jiménez (2003). The CSD are computed with Welch’s method (Welch 1967), as in Towne *et al.* (2018) or Pintelon & Schoukens (2012).

Re_τ	Re_{bulk}	L_x	L_z	Δx^+	Δz^+	Δy_{min}^+	Δy_{max}^+
179	2800	4π	2π	11.78	5.89	5.42×10^{-2}	4.42
543	10000	2π	π	8.89	4.44	4.09×10^{-2}	6.67

TABLE 1. Reynolds number, box dimensions and details about the resolution used in the DNS.




FIGURE 1. Comparison of mean velocity U^+ and rms values from DNS data (symbols) and the results presented in del Álamo & Jiménez (2003) (lines). (a) Mean velocity U^+ in inner units; black is $Re_\tau = 179$, red is $Re_\tau = 543$; (b) u_{rms}^+ , v_{rms}^+ , w_{rms}^+ in inner units for $Re_\tau = 179$; black is u_{rms}^+ , red is v_{rms}^+ , blue is w_{rms}^+ ; (c) u_{rms}^+ , v_{rms}^+ , w_{rms}^+ in inner units for $Re_\tau = 543$; black is u_{rms}^+ , red is v_{rms}^+ , blue is w_{rms}^+ .

Note that the input–output relationship is based on the windowed data. The presence of the window, which is a function of time, needs to be accounted for in the time derivative. Consequently, the input–output relationship in (2.2) is not valid (Martini *et al.* 2019). A compensation term of the form $-\hat{q} dW(t)/dt$, with $W(t)$ the Hann window, is added to the forcing in order to preserve the identity in (2.2). The same procedure investigated in Nogueira *et al.* (2021) is followed here. More details can be found in appendix C.

3.1. Computation of CSDs: $Re_\tau = 179$

The focus is on dominant structures of streamwise velocity in the buffer layer and at $y = 0.5$. Therefore, the corresponding wavenumbers are chosen by inspecting the premultiplied streamwise kinetic energy spectra $\alpha\beta e_{uu}^{kin}$ at $y^+ = 15$ and $y = 0.5$, shown in figure 2. The maxima of the premultiplied spectral densities are at $(\lambda_x^+, \lambda_z^+) = (1130, 113)$ for the near-wall structures and $(\lambda_x, \lambda_z) = (4.19, 1.26)$ for the large-scale structures; where λ_x and λ_z are streamwise and spanwise wavelengths normalized by the outer scale h , and the $+$ superscript is used when quantities are normalized by the viscous scale. These wavenumbers represent energetically significant self-sustaining dynamics of the near-wall and large-scale motions. Figures 3(a) and 3(b) show the PSD of the streamwise velocity fluctuation s_{uu} for the near-wall structures $(\lambda_x^+, \lambda_z^+) = (1130, 113)$ (figure 3a) and the large-scale structures $(\lambda_x, \lambda_z) = (4.19, 1.26)$ (figure 3b). The near-wall structures have a peak at $y^+ \approx 15$ with $\omega_{max}^+ = 0.065$ that corresponds to a time in viscous scale $\lambda_t^+ \approx 100$, whereas the large scales have a peak around $y = 0.35$ with $\omega_{max} = 1.05$. These peaks




FIGURE 2. Premultiplied streamwise energy spectra $\alpha\beta e_{uu}^{kin}$, with $Re_\tau = 179$: (a) $y^+ = 15$ plane, spectra in inner units; (b) $y = 0.5$ plane, spectra in outer units.




FIGURE 3. Streamwise velocity PSDs s_{uu} and p_{uu} versus phase speed $c^+ = \omega^+/\alpha^+$, with $Re_\tau = 179$. Dashed black line, mean velocity U^+ in wall units; (a) s_{uu} , near-wall structures, $(\lambda_x^+, \lambda_z^+) = (1130, 113)$; (b) s_{uu} , large-scale structures, $(\lambda_x, \lambda_z) = (4.19, 1.26)$; (c) p_{uu} , near-wall structures, $(\lambda_x^+, \lambda_z^+) = (1130, 113)$; (d) p_{uu} , large-scale structures, $(\lambda_x, \lambda_z) = (4.19, 1.26)$.

correspond to a wave speed $c_{max}^+ \approx 12$ for the near-wall structures and $c_{max}^+ \approx 16$ for the large-scale structures; the peaks are located in the region where the mean velocity equals the wave speed $U^+ = c^+$.

Figures 3(c) and 3(d) show the PSD of the streamwise forcing p_{uu} for the same near-wall and large-scale structures. Both the forcing terms have the peak at the ω_{max} (or c_{max}^+) of




FIGURE 4. PSD, with $Re_\tau = 179$: (a,b) symbols, $\mathbf{S} = \mathbf{RPR}^H$, output \mathbf{S} with \mathbf{P} from DNS; lines, output \mathbf{S} from DNS; triangles (black), streamwise component; squares (red), wall-normal component; circles (blue), spanwise component; (c,d) solid lines, \mathbf{P} from DNS; dashed lines, solenoidal part of \mathbf{P} ; colour legend as in (a,b); (a) s_{uu}, s_{vv}, s_{ww} near-wall, $\omega_{max}^+ = 0.065$ ($c_{max}^+ \approx 12$); (b) s_{uu}, s_{vv}, s_{ww} large scale, $\omega_{max} = 1.05$ ($c_{max}^+ \approx 16$); (c) p_{uu}, p_{vv}, p_{ww} near-wall, $\omega_{max}^+ = 0.065$ ($c_{max}^+ \approx 12$); (d) p_{uu}, p_{vv}, p_{ww} large scale, $\omega_{max} = 1.05$ ($c_{max}^+ \approx 16$).

the corresponding \mathbf{S}_{11} . Moreover, it is notable that both the near-wall and the large-scale structures are forced by a near-wall forcing. This phenomenon can be appreciated also in figure 4, where the forcing \mathbf{P} computed from the DNS data is used to predict $\mathbf{S} = \mathbf{RPR}^H$. The fact that the curves and the symbols in figures 4(a) and 4(b) are on top of each other is evidence of the accuracy of the computed \mathbf{P} . Figures 4(c) and 4(d) show both the forcing \mathbf{P} based on the nonlinear terms and its solenoidal part. The streamwise component is nearly unchanged, whereas the wall-parallel components are different. In particular, the amplitude of the wall-parallel components of the solenoidal part of the forcing is lower than it is for the total forcing and the solenoidal forcing is non-zero on the wall, but it is parallel to it.

3.2. Computation of CSDs: $Re_\tau = 543$

Figure 5 shows the premultiplied streamwise kinetic energy spectra $\alpha\beta e_{uu}^{kin}$ at $y^+ = 15$ and $y = 0.5$ for $Re_\tau = 543$. In this case the highest energetic activity is for $(\lambda_x^+, \lambda_z^+) = (1137, 100)$ for the near-wall structures and $(\lambda_x, \lambda_z) = (6.28, 1.57)$ for the large-scale structures, so these wavenumbers are chosen for the following analysis. Figures 6(a) and 6(b) present the PSD of the streamwise velocity fluctuation s_{uu} for both the near-wall and large-scale structures. The near-wall structures have a peak at $\omega_{max} = 0.065$ ($\lambda_t^+ \approx 100$) and at $y^+ = 15$, whereas large-scale structures have a peak at $\omega_{max} = 0.65$ and $y = 0.45$. These peaks correspond to a wave speed $c_{max}^+ \approx 12$ for the near-wall structures and $c_{max}^+ \approx 18$ for the large-scale structures; the peaks are located in the region where the mean




FIGURE 5. Premultiplied streamwise energy spectra $\alpha\beta e_{uu}^{kin}$, with $Re_\tau = 543$: (a) $y^+ = 15$ plane, spectra in inner units; (b) $y = 0.5$ plane, spectra in outer units.

velocity equals the wave speed $U^+ = c^+$. An appreciable amount of scale separation is present for this Reynolds number. Moreover, the large-scale structure has a local maximum at $y^+ = 12$, which disappears when frequencies or wavenumbers are aggregated because of its low amplitude. A similar peak emerges also for the turbulent channel flow at $Re_\tau = 1007$ in Morra *et al.* (2019), where the frequency and wavenumber separation is taken as in this paper. It is shown in § 4.1 that this peak is generated by the streamwise component of the nonlinear forcing.

Figures 6(c) and 6(d) present the PSD of the streamwise forcing p_{uu} for both near-wall and large-scale structures. The peaks of the forcing of both types of structures are localized in the inner layer. The near-wall structures show a peak at $\omega_{max}^+ = 0.065$ ($\lambda_t^+ \approx 100$) and $y^+ = 15$, whereas the large-scale structures show a peak at $\omega_{max} = 0.65$ and $y^+ = 6$. The input \mathbf{P} and the output \mathbf{S} show a peak at the same ω . The shape of all the three components of \mathbf{P} and \mathbf{S} at the respective ω_{max} is shown in figure 7, where also the relationship $\mathbf{S} = \mathbf{RPR}^H$ (the symbols in figures 7a and 7b) is presented to demonstrate the accuracy of the computed input \mathbf{P} . Figures 7(c) and 7(d) show the input \mathbf{P} . The near-wall structures present a peak of the streamwise component at $y^+ = 17$ and at $y^+ = 20$ for the wall-normal and the spanwise components. The large-scale structures have a peak in \mathbf{P} at $y^+ = 6$ for the streamwise component, at $y^+ = 12$ for the wall-normal component, and at $y^+ = 9$ for the spanwise component. However, in addition to this near-wall peak, the forcing of large-scale structures is spatially extended throughout the channel. It is demonstrated in § 4.3 that it is the spatial extension of the streamwise component of this forcing which is responsible for the bulk of the response, whereas the near-wall peak solely accounts for the near-wall local maximum in the response. The solenoidal part of the input is also presented in figures 7(c) and 7(d) (red lines without symbols). The streamwise component is nearly unchanged, whereas the transverse components are different, as occurs for $Re_\tau = 179$. Moreover, the amplitude of the wall-parallel components of the solenoidal part of the forcing is lower than it is for the total forcing and the solenoidal forcing is non-zero on the wall, i.e. there is a component parallel to the wall. The occurrence of a very localized peak for the streamwise component of the Reynolds shear stresses is also documented in Kawata & Alfredsson (2018) and Cho, Hwang & Choi (2018).

4. Input–output analysis

4.1. Effect of the sub-blocks of the input on the output

Here, the effects of the sub-blocks of the input \mathbf{P} on the output \mathbf{S} are analysed. As \mathbf{P} is the CSD matrix of the forcing vector $\hat{\mathbf{f}}$, it can be split into nine sub-blocks of equal dimensions. Each sub-block is a CSD. The three sub-blocks on the diagonal




FIGURE 6. Streamwise velocity PSDs s_{uu} and p_{uu} versus phase speed $c^+ = \omega^+/\alpha^+$, with $Re_\tau = 543$. Dashed black line: mean velocity U^+ in wall units; (a) s_{uu} , near-wall structures, $(\lambda_x^+, \lambda_z^+) = (1137, 100)$; (b) s_{uu} , large-scale structures, $(\lambda_x, \lambda_z) = (6.28, 1.57)$; (c) p_{uu} , near-wall structures, $(\lambda_x^+, \lambda_z^+) = (1137, 100)$; (d) p_{uu} , large-scale structures, $(\lambda_x, \lambda_z) = (6.28, 1.57)$.

are the CSD of the streamwise, wall-normal and spanwise components alone, whereas the six off-diagonal sub-blocks are the CSD of pairs of different components. As the input–output relationship is described in terms of CSD, quantifying the effect of each sub-block on the output \mathbf{S} amounts to a component-wise analysis, which here provides insights into the nonlinear feedback mechanism of the self-sustained processes of wall-bounded turbulence. Moreover, the influence of the off-diagonal terms on the output is of interest for modelling the nonlinear forcing because some sub-blocks may be negligible.

The effects of the sub-blocks of the input \mathbf{P} on the output \mathbf{S} can be analysed by expanding \mathbf{P} into a sum of nine matrices as

$$\mathbf{P} = \mathbf{P}_{11} + \mathbf{P}_{12} + \mathbf{P}_{13} + \mathbf{P}_{21} + \mathbf{P}_{22} + \mathbf{P}_{23} + \mathbf{P}_{31} + \mathbf{P}_{32} + \mathbf{P}_{33}, \quad (4.1)$$

with the \mathbf{P}_{ij} matrices having only the ij th sub-block different from zero. The \mathbf{P}_{ij} matrices that contain the CSD of the streamwise, wall-normal and spanwise components alone are \mathbf{P}_{11} , \mathbf{P}_{22} and \mathbf{P}_{33} . The matrices \mathbf{P}_{ij} with $i \neq j$ have the only non-zero sub-block that




FIGURE 7. PSD, with $Re_\tau = 543$: (a,b) symbols, $\mathbf{S} = \mathbf{RPR}^H$, output \mathbf{S} with \mathbf{P} from DNS; lines, output \mathbf{S} from DNS; triangles (black), streamwise component; squares (red), wall-normal component; circles (blue), spanwise component; (c,d) solid lines, \mathbf{P} from DNS; dashed lines, solenoidal part of \mathbf{P} ; colour legend as in (a,b); (a) s_{uu} , s_{vv} , s_{ww} near-wall, $\omega_{max}^+ = 0.065$ ($\lambda_t^+ \approx 100$, $c_{max}^+ \approx 12$); (b) s_{uu} , s_{vv} , s_{ww} large scale, $\omega_{max} = 0.65$ ($c_{max}^+ \approx 18$); (c) p_{uu} , p_{vv} , p_{ww} near-wall, $\omega_{max}^+ = 0.065$ ($\lambda_t^+ \approx 100$, $c_{max}^+ \approx 12$); (d) p_{uu} , p_{vv} , p_{ww} large scale, $\omega_{max} = 0.65$ ($c_{max}^+ \approx 18$) (inset: enlarged view of the near-wall region, spanwise component only).

correspond to the CSD between pairs of different components. In other words, \mathbf{P}_{ij} is

$$P_{ij} = \lim_{T \rightarrow \infty} \frac{\mathbb{E} \left[\left(\frac{1}{2\pi} \int_{-T}^T \hat{f}_i(t) e^{-i\omega t} dt \right) \left(\frac{1}{2\pi} \int_{-T}^T \hat{f}_j(t)^H e^{i\omega t} dt \right) \right]}{2T}, \tag{4.2}$$

with \hat{f}_i a $3N_y \times 1$ vector made solely of the i th $N_y \times 1$ component of the $3N_y \times 1$ vector \hat{f} and the other components set to zero; with $i = 1, 2, 3$ corresponding to the streamwise, wall-normal and parallel directions. Here, the focus is on the portion of the output that corresponds to each sub-block, $\mathbf{RP}_i\mathbf{R}^H$. Note that the output $\mathbf{RP}_i\mathbf{R}^H$ where $i \neq j$ implies the output given by $\mathbf{R}(\mathbf{P}_{ij} + \mathbf{P}_{ji})\mathbf{R}^H$ because \mathbf{P} is Hermitian.

For the case with $Re_\tau = 179$ the results are presented in figure 8 for s_{uu} . For both near-wall and large-scale structures the terms with $i \neq j$ give a negative contribution. In particular, for the large-scale structures in figure 8(b) only the terms related to the spanwise direction ($j = 3$) provide a negative contribution, whereas for the near-wall structures all the terms with $i \neq j$ give a negative contribution. Moreover, even though the magnitude of the streamwise component of the solenoidal part of the forcing is around one order of magnitude higher than the wall-normal and spanwise components, the forcing cannot be approximated by the streamwise component only. In fact, the amplitudes of the outputs associated with the wall-normal and spanwise components have the same




FIGURE 8. Response $\mathbf{S} = \mathbf{R}\mathbf{P}_{ij}\mathbf{R}^H$ from sub-blocks of \mathbf{P}_{ij} , with $Re_\tau = 179$: solid lines, response from \mathbf{P}_{1j} (sub-blocks related to the streamwise component); dashed lines, response from \mathbf{P}_{ij} with $i \neq 1$; (a) s_{uu} near-wall, $\omega_{max}^+ = 0.065$; (b) s_{uu} large scale, $\omega_{max} = 1.05$.

order of magnitude of the output associated with the streamwise component. This can be attributed to the lift-up effect, which greatly enhances the efficiency of forcing in the wall-normal or spanwise directions, leading to streamwise vortices that, in turn, form amplified streaks (Moffatt 1967; Ellingsen & Palm 1975; Landahl 1980; Hwang & Cossu 2010c, 2011; Brandt 2014). It is seen here that the wall-normal and spanwise components of the forcing, associated with lift-up, lead to high-amplitude outputs when considered in isolation (see the curves associated with \mathbf{P}_{22} and \mathbf{P}_{33} in figures 8a and 8b), but a complex phase relationship between the three forcing components leads to cancellations in such a way that the DNS output is of lower magnitude than what is predicted by considering a single forcing component. This is a first indication of relevance of forcing colour to the channel dynamics, as incoherent forcing components would lead to output PSDs that could simply be summed to form the full PSD. The high magnitude of cross terms shows that this is not the case: forcing components are coherent between them, and neglecting such coherence would lead to appreciable errors in the prediction of the output. Similar effects were observed for a minimal Couette flow unit by Nogueira *et al.* (2021).

For the case with $Re_\tau = 543$ the contribution of the terms \mathbf{P}_{ij} on the output \mathbf{S} are presented in figure 9. As occurs for $Re_\tau = 179$, the off-diagonal terms ($i \neq j$) provide a negative contribution to the output, indicating that coherence between the forcing components, or forcing colour, is an important feature of the dynamics, as discussed previously. Similar to $Re_\tau = 179$, the forcing cannot be approximated by the streamwise component only, even though its peak amplitude is one order of magnitude higher than it is for the wall-normal and the spanwise components. In fact, as shown in figures 9(a) and 9(b), the amplitudes of the outputs associated with the wall-normal and spanwise components of the forcing are larger than the output associated with the streamwise component, owing to the higher efficiency associated with the lift-up effect. Moreover, at $Re_\tau = 543$ the large-scale structures show a low-amplitude near-wall peak in the PSD of the streamwise velocity component s_{uu} at $y^+ = 12$. This low-amplitude near-wall peak is demonstrated to be generated by the streamwise component of the forcing \mathbf{P} . In fact, in figure 9(c) it is clear that it is only the components of \mathbf{P} associated with the streamwise forcing ($i = 1$) that are responsible for the peak around $y^+ = 12$ (compare the solid and




FIGURE 9. Response $\mathbf{S} = \mathbf{R}\mathbf{P}_{ij}\mathbf{R}^H$ from sub-blocks \mathbf{P}_{ij} , with $Re_\tau = 543$: solid lines, response from \mathbf{P}_{1j} (sub-blocks related to the streamwise component); dashed lines, response from \mathbf{P}_{ij} with $i \neq 1$; (a) s_{uu} near-wall, $\omega_{max}^+ = 0.065$ ($\lambda_t^+ \approx 100$); (b) s_{uu} large-scale, $\omega_{max} = 1.05$; (c) zoom of (b) in the near-wall region (note that \mathbf{P}_{1j} are the only components contributing to the near-wall peak).

the dashed lines in figure 9c). Thus, the low-amplitude near-wall peak at $y^+ = 12$ in s_{uu} must be related to the near-wall peak at $y^+ = 6$ in p_{uu} .

4.2. Low-rank approximation

Effort has been made to reconstruct the input \mathbf{P} from sensor measurements with system identification techniques (Jovanovic & Bamieh 2001; Zare *et al.* 2017; Illingworth *et al.* 2018; Towne *et al.* 2020). Here, a low-rank approximation of \mathbf{P} , referred to as \mathbf{P}_{lr} , is computed *a posteriori* by retaining the first two SPOD modes of \mathbf{P} , so that

$$\mathbf{P}_{lr} = \eta_1 \boldsymbol{\zeta}_1 \boldsymbol{\zeta}_1^H + \eta_2 \boldsymbol{\zeta}_2 \boldsymbol{\zeta}_2^H. \quad (4.3)$$

The second SPOD mode is also included because in a channel flow the modes are paired because of the symmetry of the flow case. The approximated output $\mathbf{S}_{P_{lr}}$ is computed with \mathbf{R} and compared with the output \mathbf{S} from DNS data in figure 10. It is remarkable that considering only the first two SPOD modes of \mathbf{P} leads to a recovery of most of the output in all the cases presented. It can be remarked that for the large-scale structure of the flow at $Re_\tau = 543$ even the local maximum at $y^+ = 12$ is mostly retrieved. This shows that the forcing is highly structured and coherent, as already suggested by the results in § 3, and its dominant structure, which is represented by the first two symmetrical and anti-symmetrical SPOD modes, is responsible for the bulk of the flow response for both near-wall and large-scale motions in both $Re_\tau = 179$ and $Re_\tau = 543$. This result suggests a direction for the modelling of the structures considered here: the identification of the nonlinear processes that lead to the observed coherent forcing may form a foundation for reduced-order models of self-sustaining mechanisms in turbulent channel flows, similarly to the developments of Hamilton, Kim & Waleffe (1995) and Farrell & Ioannou (2012) for low Reynolds turbulent Couette flow in minimal boxes.

Assessing the low-rank behaviour of the forcing is helpful for those techniques that account for the forcing through system identification methods, in a similar fashion to Jovanovic & Bamieh (2001), Zare *et al.* (2017) or Illingworth *et al.* (2018). The low-rank




FIGURE 10. PSD of the velocity fluctuations from the low-rank approximation: solid lines, \mathbf{S} from DNS data; dashed lines, \mathbf{S}_{lr} from low-rank approximation of \mathbf{P}_{lr} ; black, streamwise component; red, wall-normal component; blue, spanwise component; (a) $Re_\tau = 179$, small scale; (b) $Re_\tau = 179$, large scale; (c) $Re_\tau = 543$, small scale; (d) $Re_\tau = 543$; large scale.

behaviour of the forcing can be a benefit because identification techniques may lose accuracy when the number of unknown parameters increases (Hjalmarsson & Mårtensson 2007). In this case identifying the first eigenvector of the cross-power spectral density \mathbf{P} instead of the whole \mathbf{P} reduces the number of unknowns from $3N_y(3N_y + 1)/2$ to $3N_y$ (N_y is the number of discrete point in the wall-normal direction). Thus, in this case the number of unknowns would be reduced by two orders of magnitude. The second SPOD mode can be retrieved later by exploiting the symmetry of the flow case.

As most of the output can be obtained from the presented low-rank approximation of the input \mathbf{P} , the field given by the first SPOD mode ζ_1 is of interest, so it is presented in figure 11 together with its solenoidal part. The second SPOD mode ζ_2 is not presented because the modes are symmetric and anti-symmetric with respect to the center line of the channel and their behaviour on one wall is sufficient. Even though the mode ζ_1 does not clearly appear to force the lift-up mechanism, its solenoidal part, which is the only one responsible for the velocity field, is actually accelerating the flow in the directions and areas typical for the occurrence of the lift-up mechanism. In fact, the solenoidal field takes the shape of oblique vortices that appear to push near-wall fluid particles away from the wall and further fluid particles towards the wall. This occurs for both $Re_\tau = 179$ and $Re_\tau = 543$, and for both large- and small-scale structures. Thus, it appears that the feedback of the nonlinear terms arising from the fluctuations of the velocity field presents a significant vortical structure forcing the lift-up mechanism. It is also notable that the magnitude of the streamwise component of the solenoidal part of the forcing is higher than it is for the wall-normal and the spanwise components. This behaviour is opposite to that predicted by the linear optimal forcing, which coincides with the first right-singular vector of the resolvent (Hwang & Cossu 2010b).




FIGURE 11. First SPOD mode of \mathbf{P} , ξ_1 : (a–d) $Re_\tau = 179$; (e–h) $Re_\tau = 543$; (a,b,e,f) small scales; (c,d,g,h) large scale; (a,c,e,g) full ξ_1 ; (b,d,f,h) solenoidal part of ξ_1 . Contours: streamwise component of ξ_1 . Vectors: spanwise and wall-normal components of ξ_1 .

Figure 11 suggests that the streamwise component counteracts the effect of the wall-normal and spanwise components, as appears in figures 8 and 9 and is discussed in § 4.1. In figure 11 it can be observed that in regions where the wall-normal and spanwise components of the forcing would generate a negative velocity fluctuation, the streamwise component pushes the flow in the positive direction, and vice versa, in a destructive interference. This is in accordance with the fact that the energy amplification predicted with an approach that focuses only on the linear operator is much higher than that observed in DNS of the nonlinear N–S. In fact, focusing solely on the linear operator implies assuming that the forcing is mainly the linear optimal forcing, or the first right-singular vector of \mathbf{R} , whose streamwise component has a negligible magnitude with respect to the other two (Hwang & Cossu 2010*b*). In other words, focusing the analysis of a turbulent channel flow solely on the non-normal linear operator can be definitely misleading, as pointed out already by Waleffe (1995). Nevertheless, because expanding the N–S system in a reference state and its relative fluctuations is entirely general, as already clarified by Henningson (1996), rewriting the system in terms of a (non-normal) linear operator without dropping the nonlinear forcing terms in the analysis can be helpful to shed light on the ‘recycling’ of the amplified outputs in the input from the nonlinear terms.

4.3. Influence of the near-wall forcing on the large-scale output: $Re_\tau = 543$

Flores & Jiménez (2006) and Flores, Jiménez & del Álamo (2007) showed with one-point statistics that changes in the wall boundary conditions in the DNS of a turbulent channel flow, which completely alter the near-wall statistics, did not influence the statistics in the outer layer. Hwang & Cossu (2010*c*) demonstrated, with the aid of large-eddy simulations, that large-scale motions are still present in a turbulent channel flow even when the smaller scales typical of near-wall motions are filtered out; the filtering was possible by adjusting the constant of the Smagorinsky eddy-viscosity model employed. Flores & Jimenez (2010) and Hwang & Cossu (2011) further confirmed that the dynamics of large-scale structures, although affected by smaller near-wall eddies, is mostly related to processes with similar length scales. These results suggest that the response \mathbf{S} is weakly influenced by the structure of the input \mathbf{P} near the wall. However, for the large-scale structure $(\lambda_x, \lambda_z) = (6.28, 1.57)$ at $Re_\tau = 543$ the streamwise component of the nonlinear forcing \mathbf{p}_{uu} presents a high-amplitude absolute maximum at $y^+ = 6$, and in § 4.1 it is shown that \mathbf{P}_{11} is non-negligible to retrieve the correct response. The analysis in § 4.1 only shows that the low-amplitude peak at $y^+ = 12$ in the streamwise component of the response s_{uu} is caused solely by \mathbf{P}_{11} , but no conclusion can be drawn on how the near-wall peak in \mathbf{P}_{11} influences the bulk of the response. However, according to the conclusions of the aforementioned studies and the results in § 4.1 it is reasonable to speculate that the structure of \mathbf{P} near the wall does not strongly influence the bulk of the response \mathbf{S} .

In order to verify this statement all the points of the input \mathbf{P} from DNS data that are close to the wall, with $y^+ < 30$, are set to zero, a new input \mathbf{P}_h is computed, and the output $\mathbf{S}_h = \mathbf{R}\mathbf{P}_h\mathbf{R}^H$ is evaluated. The PSD of the resulting output \mathbf{S}_h is presented in figure 12(*a*), where the symbols represent the original output from the DNS data, the shaded area is the area where the forcing is non-zero and the red lines are the PSDs of the output \mathbf{S}_h . The curves of the PSDs of \mathbf{S}_h are almost unaltered when compared with those of \mathbf{S} for $y^+ \geq 30$, where the forcing is not set to zero. In the near-wall region $y^+ < 30$, where the forcing is set to zero, the PSDs of \mathbf{S}_h do not match the DNS data, and clearly the peak in the streamwise component is absent. In order to verify the effects of the near-wall portion of the forcing, another forcing \mathbf{P}_{y^+} is computed by setting to zero the points in $y^+ \geq 30$, and the output $\mathbf{S}_{y^+} = \mathbf{R}\mathbf{P}_{y^+}\mathbf{R}^H$ is evaluated. The PSD of the output \mathbf{S}_{y^+} is presented in




FIGURE 12. Effect of the inner layer on the large-scale motion of $Re_\tau = 543$. PSD: symbols, $\mathbf{S} = \mathbf{RPR}^H$; triangle, streamwise component; circle, spanwise component; square, wall-normal component; black lines. DNS: red lines, $\mathbf{S}_h = \mathbf{RP}_h\mathbf{R}^H$ (a, outer layer), $\mathbf{S}_{y^+} = \mathbf{RP}_{y^+}\mathbf{R}^H$ (b, inner layer); solidline, streamwise component; dotted line, spanwise component; dashed line, wall-normal component; grey area, interval of y where the \mathbf{P} is not zero.

figure 12(b), where it appears that the near-wall peak in the velocity is present, but the PSDs are not matching the DNS data for $y^+ \geq 30$. It follows that the low-amplitude peak at $y^+ = 12$ in s_{uu} of the DNS data must be caused by the near-wall portion of the streamwise forcing \mathbf{P}_{11} , and that the response \mathbf{S} is not strongly influenced by the structure of the input \mathbf{P} near the wall.

5. Role of forcing statistics in linear resolvent analyses

Having access to \mathbf{P} allows to quantify its projection onto the right-singular vectors of the resolvent \mathbf{R} , which are the key quantity to assess the accuracy of linear resolvent analyses (Beneddine *et al.* 2016). These projections are quantified here for the first time for the turbulent channel flows presented. The resolvent \mathbf{R} is decomposed into its left- and right-singular vectors, and the projections of the forcing term onto the right-singular vectors of \mathbf{R} are computed. These projections are evaluated for the forcing \mathbf{P}_v , modelled with eddy viscosity, and for the forcing \mathbf{P} from DNS data. The effects of the modelling choice on the predictions are also discussed.

5.1. Forcing uncorrelated in space

The assumption $\mathbf{P} = \gamma_v \mathbf{I}$ leads to the prediction $\mathbf{S}_{R_v} = \gamma_v \mathbf{R}\mathbf{R}^H$. In this case, the PSD of the output can be written as $\text{diag}(\mathbf{S}_{R_v}) = \gamma_v \sum_i \sigma_i^2 |\boldsymbol{\psi}_i|^2$, which is the sum of the left singular vectors of \mathbf{R} times the square of the corresponding singular values. As $b_i^2 = \text{diag}(\boldsymbol{\phi}_i^H \mathbf{W}\mathbf{P}\mathbf{W}\boldsymbol{\phi}_i)$, $\text{diag}(\mathbf{S}_{R_v}) = \sum_i |\boldsymbol{\psi}_i|^2 a_i^2$ and $a_i = \sigma_i b_i$ from (2.9) and (2.10), this modelling corresponds to setting $b_i = \gamma_v$ or $a_i = \sigma_i \gamma_v$. If there are sufficiently large gains σ_i to neglect the others, the shape of $\text{diag}(\mathbf{S}_{R_v})$ is mainly given by the $\boldsymbol{\psi}_i$ corresponding to such σ_i . It is shown in Morra *et al.* (2019) and Pickering *et al.* (2020) that for turbulent channel flows and for turbulent jets predictions with a diagonal input matrix can lead to significant errors in the output. In Morra *et al.* (2019) \mathbf{P} is not presented, and the conclusions are drawn by comparing \mathbf{S}_{R_v} with \mathbf{S} from the DNS results. The reason for the mismatch between the prediction $\mathbf{S}_{R_v} = \gamma_v \mathbf{R}\mathbf{R}^H$ and the DNS results is clear once the nonlinear forcing \mathbf{P} from the DNS is projected onto the basis of the right-singular vectors $\boldsymbol{\phi}_i$, as shown in figure 13.

In figure 13 the trends are normalized by their value at the first mode $i = 1$; the reference value for the normalization and the γ_v used are summarized in table 2. The resolvent




FIGURE 13. Singular values σ_i of \mathbf{R} , projection coefficients b_i , weights $a_i = \sigma_i b_i$. The values are rescaled by their value at $i = 1$ (see table 2): triangle, projection of \mathbf{P} onto the right-singular vectors ϕ_i of \mathbf{R} (b_i coefficients); filled symbols, DNS data; empty symbols, eddy-viscosity model; square, singular values σ_i of \mathbf{R} ; circle, $a_i = \sigma_i b_i$; filled symbols, DNS data; empty symbols, eddy-viscosity model; (a,c) $Re_\tau = 179$; (b,d) $Re_\tau = 543$; (a,b) small scales; (c,d) large scales.

gains σ_i are plotted as red squares for both near-wall and large-scale structures and for both $Re_\tau = 179$ and $Re_\tau = 543$. In turbulent channel flows the resolvent modes appear in pairs with nearly identical gains because of the symmetrical or anti-symmetrical behaviour of the flow at the walls. It appears that for all considered cases there is a notable gain separation between the leading pair of gains σ_1 and σ_2 and the subsequent ones. However, there are other two worthwhile observations. First, for both $Re_\tau = 179$ and $Re_\tau = 543$ and for both near-wall and large-scale structures the coefficients b_i are such that the forcing has a non-negligible projection onto the right-singular vectors of \mathbf{R} , ψ_i , which correspond to the σ_i with lower magnitude. In figure 13 note that the magnitude of b_1 and b_2 is lower than it is for all other b_i with $i > 2$, and compare b_i with σ_i for $i > 2$ (black-filled triangle symbols in figure 13). Second, for both $Re_\tau = 179$ and $Re_\tau = 543$ the average magnitude of this projection onto higher-order right eigenfunctions is more significant for large-scale structures than for small-scale structures. The first observation explains why the assumption $\mathbf{P} = \gamma_v \mathbf{I}$ can lead to an erroneous prediction $\text{diag}(\mathbf{S}_{R_v}) = \gamma_v \text{diag}(\mathbf{R}\mathbf{R}^H) = \gamma_v \sum_i \sigma_i^2 |\psi_i|^2$. The magnitude of the projections of the forcing \mathbf{P} onto the right-singular vector ϕ_i , which is b_i , can compensate a small singular value σ_i and increase the relative weight $a_i = \sigma_i b_i$ of a left-singular vector ψ_i in the linear combination that leads to the output. The coefficients a_i are shown with blue-filled circle symbols in figure 13. The second observation explains why the assumption $\mathbf{P} = \gamma_v \mathbf{I}$ gives less erroneous predictions $\mathbf{S}_{R_v} = \gamma_v \sum_i \sigma_i^2 |\psi_i|^2$ for near-wall structures: the magnitude of the projection \mathbf{P} onto ϕ_i is such that the trend of the weights a_i , which multiply the left-singular vector ψ_i in the linear combination, is less modified than it is for large-scale structures. This can be seen by comparing figures 13(a) and 13(b) with figures 13(c) and 13(d): for the near-wall structures the trend of the blue-filled circle symbols, which are a_i , is

more similar to the square red symbols, which represent σ_i , than it is for the large-scale structures.

The discussion about the coefficients a_i , b_i , and the singular values σ_i and their effect on the output is consistent with the results shown in [figure 14](#), where the streamwise component of \mathbf{S}_{R_i} is presented. In particular, the assumption $\mathbf{P} = \gamma_v \mathbf{I}$ leads to very localized large-scale structures, which do not resemble the DNS data, whereas the near-wall structures approximate better the shape of the DNS data, as presented by Morra *et al.* (2019) for a turbulent channel at $Re_\tau = 1007$. This occurs owing to the discrepancy, which is more pronounced for the large-scale structures than the near-wall structures, between σ_i and $a_i = \sigma_i b_i$. It is noticeable that for both the Re_τ presented and for both small-scale and large-scale structures the prediction based on the assumption that the forcing arising from the nonlinear terms is uncorrelated in space is erroneous because the assumption is not verified in a turbulent flow, as the shapes of \mathbf{P} in [figures 3](#) and [6](#) show.

5.2. Forcing from the eddy-viscosity model

In eddy-viscosity modelling the nonlinear forcing term is modelled by means of the Boussinesq expression, which states that the unknown Reynolds stresses are proportional to the rate of strain tensor given by the known field through a scalar ν_t . Here ν_t is the eddy (or turbulent) viscosity, whose structure is prescribed by the chosen modelling approach. In the most general case ν_t is not constant in space, so its effect on the dynamics are (i) modifying the local dissipation rate by a factor $1 + \nu_t/\nu$ and (ii) introducing some additional terms proportional to the (partial) derivatives of ν_t and linear in the velocity fluctuations.

The focus of this work is neither a discussion on the choice of the eddy-viscosity modelling strategy nor a detailed study on the specific effects of a specific eddy-viscosity model. Here, the eddy-viscosity model employed in the resolvent analyses of Hwang & Cossu (2010a,c) and Morra *et al.* (2019) is used as an example, and its effects are compared with those produced by the forcing \mathbf{P} computed from the DNS data. It is noteworthy that the model for the eddy viscosity ν_t adopted here, taken from Cess (1958), is tuned at $Re_\tau = 2000$, so its performance at lower Re_τ is not assured. This eddy-viscosity modelling approach was first proposed by Reynolds & Hussain (1972) and is based on the assumption that the fluctuations around the mean flow can be decomposed into a coherent and an incoherent part. The incoherent part is assumed to be unknown, so its contribution to the Reynolds stresses is modelled, whereas the coherent part is assumed to be known and it is used for the modelling (see Reynolds & Hussain (1972) for more details). The results from the eddy-viscosity modelling are discussed by comparing \mathbf{P} from DNS data with \mathbf{P}_{ν_t} , where \mathbf{P}_{ν_t} is the equivalent forcing introduced by the eddy-viscosity model such that $\mathbf{S}_{R_{\nu_t}} = \mathbf{R} \mathbf{P}_{\nu_t} \mathbf{R}^H = \gamma_{\nu_t} \mathbf{R} \mathbf{R}^H$ and is computed as in (2.13). The normalization scalars are presented in [table 2](#).

The square root of the coefficients $b_i^2 = \text{diag}(\phi_i^H \mathbf{W} \mathbf{P}_{\nu_t} \mathbf{W} \phi_i)$, which quantify the projection of \mathbf{P}_{ν_t} onto the right-singular vectors ϕ_i of \mathbf{R} , are presented in [figure 13](#) with black empty triangles. The coefficients $a_i = \sigma_i b_i$ which define the shape of the prediction $\text{diag}(\mathbf{S}_{R_{\nu_t}}) = \sum_i |\psi_i|^2 a_i^2$ are also presented in [figure 13](#) as blue empty circles. These quantities are presented for both $Re_\tau = 179$ and $Re_\tau = 543$, and for both near-wall and large-scale structures. The trends presented in [figure 13](#) are normalized by their value for the first mode; the reference for the normalization is presented in [table 2](#). It appears that the equivalent forcing \mathbf{P}_{ν_t} , provided by the eddy-viscosity modelling, is able to modify the relative weights $a_i = \sigma_i b_i$ in the linear combination

Re_τ (length scale)	γ_v	γ_{v_t}	σ_1	b_1
179 (large scale)	2.54×10^{-9}	8.70×10^{-7}	2.14×10^2	7.46×10^{-6}
179 (near wall)	1.83×10^{-8}	5.26×10^{-7}	1.10×10^2	6.50×10^{-5}
543 (large scale)	9.61×10^{-10}	2.29×10^{-6}	1.11×10^3	2.91×10^{-6}
543 (near wall)	1.03×10^{-8}	4.65×10^{-7}	3.74×10^1	5.27×10^{-6}

TABLE 2. Normalization factors γ_v and γ_{v_t} ; first singular value σ_1 ; first projection coefficient b_1 ; $Re_\tau = 179$ and $Re_\tau = 543$. Large-scale and near-wall structures.




FIGURE 14. PSD. Streamwise component s_{uu} : (a,b) $Re_\tau = 179$; (c,d) $Re_\tau = 543$; (a,c) small scale; (b,d) large scales. Black line with triangles: DNS data. Red line with squares: $\mathbf{S}_v = \gamma_v \mathbf{R} \mathbf{R}^H$. Blue line with circles: $\mathbf{S}_{v_t} = \gamma_{v_t} \mathbf{R}_{v_t} \mathbf{R}_{v_t}^H$.

$\text{diag}(\mathbf{S}_{R_{v_t}}) = \sum_i |\psi_i|^2 a_i^2$ of the right-singular vectors ψ_i of \mathbf{R} similarly to \mathbf{P} from DNS data, as shown in figure 13. In this figure DNS data are represented by the black filled triangles and blue filled circles. This occurs because \mathbf{P}_{v_t} provides coefficients b_i whose magnitude is comparable with that of the coefficients b_i given by \mathbf{P} from DNS data.

The discussion about the coefficients a_i , b_i and the singular values σ_i and their effect on the output is consistent with the results shown in figure 14, where the streamwise component of $\mathbf{S}_{R_{v_t}}$ is presented. Here $\mathbf{S}_{R_{v_t}}$ is in better accordance with \mathbf{S} than \mathbf{S}_{R_v} , as shown in Morra *et al.* (2019) for a turbulent channel at $Re_\tau = 1007$. In particular, the eddy-viscosity modelling gives an improved approximation of the output also for near-wall structures. This is expected from the trend of the coefficients a_i (and b_i) in figure 13: the empty circles (and triangles) which represent a_i (and b_i) from \mathbf{P}_{v_t} are closer to the filled circles (and triangles) which represent a_i (and b_i) for \mathbf{P} from DNS data than they are for $\mathbf{P} = \gamma_v \mathbf{I}$. Note that for $\mathbf{P} = \gamma_v \mathbf{I}$ it is $a_i = \sigma_i \gamma_v$ and $a_i/a_1 = \sigma_i/\sigma_1$ in figure 13 coincide with the red-filled squares.

It is noteworthy that the prediction improves when the relative weight a_i for $i > 2$ is $a_i > \sigma_i$ in all the cases presented, which is expected by inspecting the trend of a_i and b_i based on \mathbf{P} from DNS data. The right-singular vectors of \mathbf{R} with $i > 2$ correspond to sub-optimal in linear analyses based on the resolvent \mathbf{R} . Thus, if a significant part of the forcing is spanned by linear sub-optimal, such linear analyses can be inaccurate. It is remarked in Beneddine *et al.* (2016) that the assessment of the accuracy of linear analyses based solely on the resolvent \mathbf{R} should not hinge solely on the trend of the singular values σ_i but on the coefficients $a_i = \sigma_i b_i$, which include the projection of the forcing onto the

right-singular vectors of \mathbf{R} . Here, this statement is quantified for the presented channel flows.

Thus, the results with the eddy-viscosity model indicate that accounting for the nonlinear forcing term \mathbf{P} improves accuracy for all the cases presented here, not only for large-scale structures, which is in accordance with the discussion in Pickering *et al.* (2020) and Morra *et al.* (2019). However, it is notable that also in this case the prediction is erroneous because the provided forcing is not exactly the \mathbf{P} computed from the DNS data. In fact, in figure 13 the filled symbols and the empty symbols for a_i and b_i , which represent the projections b_i and the coefficients a_i of the linear combination of ϕ_i for \mathbf{P} and for \mathbf{P}_{v_i} , are not superposed. Nevertheless, it is clear that the accuracy of the prediction is improved if the modelled forcing term mimics the coefficients b_i from the projection of \mathbf{P} computed from the DNS data. Thus, an eddy-viscosity modelling approach may be tempting for these sort of predictions, as it leads to an effective forcing \mathbf{P}_{v_i} , whose structure, or colour, leads to outputs close to the observations from DNS data.

6. Conclusions

In this work the CSD of the nonlinear forcing term associated with the velocity fluctuation, which is the input to the resolvent operator based on the mean flow, is quantified for the first time for turbulent channel flows. The computation is based on snapshots of DNS of turbulent channel flows at $Re_\tau = 179$ and $Re_\tau = 543$. The nonlinear forcing is computed at fixed time instants and the realizations are used with the Welch method. The CSD of the velocity fluctuations is computed with the same technique. The CSDs are computed for highly energetic structures typical of buffer-layer motions, $(\lambda_x^+, \lambda_z^+) = (1130, 113)$ at $Re_\tau = 179$ and $(\lambda_x^+, \lambda_z^+) = (1137, 100)$ at $Re_\tau = 543$, and large-scale motions, $(\lambda_x, \lambda_z) = (4.19, 1.26)$ at $Re_\tau = 179$ and $(\lambda_x, \lambda_z) = (6.28, 1.57)$ at $Re_\tau = 543$. The accuracy of the computed nonlinear forcing term is assessed by computing its response with the resolvent. This response is then compared with the velocity fluctuations from DNS data. The two PSDs appear to be indistinguishable, which shows the evaluation to be accurate. The computed CSD of the forcing owing to the nonlinear terms is shown not to be uncorrelated (or white) in space, which implies the forcing is structured.

As the nonlinear forcing is non-solenoidal by construction and the velocity field of the incompressible N-S is affected only by the solenoidal part of the forcing (Chorin & Marsden 1993), the PSD associated with the solenoidal part of the nonlinear forcing is evaluated and presented. It is seen that the wall-normal and the spanwise components of the nonlinear forcing are very different from their solenoidal counterpart for all the cases presented. In particular, in the solenoidal part of the forcing these two components have the shape of quasi-streamwise vortices, which are typical of the lift-up mechanism. On the other hand, the streamwise component of the forcing is almost unchanged in its solenoidal counterpart. For all the cases presented, it is shown that the transverse components of the forcing generate a response which is counteracted by the response of the streamwise component of the forcing, as in a destructive interference. It is also demonstrated that the high-amplitude peak at $y^+ = 6$ in the streamwise component of the forcing for the large-scale structure $(\lambda_x, \lambda_z) = (6.28, 1.57)$ at $Re_\tau = 543$ is necessary to recover the local maximum at $y^+ = 12$ of the streamwise component of the velocity, thus, the streamwise shear, but it is not relevant for the bulk of the response. This explicitly verifies the conclusions of Flores & Jimenez (2010); Hwang & Cossu (2011) that the dynamics of large-scale motions, although affected by smaller near-wall structures, is mostly related to similar length scales. This last statement is also verified by the fact that a low-rank

approximation of the forcing, which includes only the pair of most energetic symmetric and antisymmetric SPOD modes that have the same length scale of the response, leads to the bulk of the response for both near-wall and large-scale structures and for both Reynolds numbers.

The projection of the nonlinear forcing term onto the right-singular vectors of the resolvent is evaluated. It appears that the multiplication of the singular values σ_i of the resolvent with the projection coefficients b_i modifies the relative importance of the left-singular vectors of the resolvent in the linear combination that defines the shape of the response. It is seen that the left-singular vectors of the resolvent associated with very low-magnitude singular values are non-negligible because the nonlinear forcing term has a non-negligible projection onto the linear sub-optimals of the resolvent analysis introduced by McKeon & Sharma (2010). This occurs for both near-wall and large-scale structures at both Reynolds numbers, but the effect is stronger for large-scale structures. As the response is given by the linear combination of the left-singular vectors of the resolvent weighted with the terms $a_i = \sigma_i b_i$, the evaluation of b_i is an explicit quantification of the accuracy of resolvent analysis, as discussed in Beneddine *et al.* (2016). The same coefficients b_i are computed when the stochastic forcing is modelled with an eddy-viscosity approach. It is here clarified that this modelling leads to an improvement in the accuracy of the prediction of the response (Morra *et al.* 2019) because the resulting coefficients b_i are closer to those associated with the nonlinear forcing term evaluated from DNS data.

These findings corroborate the conjecture that the nonlinear forcing term of turbulent channel flows have spatiotemporal coherence, and indicate that the level of coherence is high. Spatiotemporal coherence was already hypothesized by Reynolds & Hussain (1972) but has never been quantified explicitly for a turbulent channel flow, even though it has been used as ‘ansatz’ in many studies. Instead, the question of ‘how much’ coherent may be the forcing has been addressed by some recent studies on turbulent jets (Schmidt *et al.* 2018; Lesshafft *et al.* 2019). These studies show reasonable predictions of the flow quantities with the assumption of a forcing uncorrelated in space. However, because here a rank-2 approximation of the forcing leads to the bulk of the response, it can be concluded that the forcing has high coherence for the present turbulent channel flows.

The found coherence affects positively the techniques that account for the forcing through system identification methods, in a similar fashion to Jovanovic & Bamieh (2001), Zare *et al.* (2017) or Illingworth *et al.* (2018). In fact, the low-rank characteristic of the forcing reduces the number of unknown parameters to identify, which reduces the complexity of the identification problem and increases the accuracy of the estimation (Hjalmarsson & Mårtensson 2007). Moreover, the found low-rank approximation of the forcing can be helpful to the control community for the design or placement of a counteracting forcing as actuator, following ideas similar to Sasaki *et al.* (2020).

Finally, these findings are valid for the presented Reynolds numbers and cannot be used to infer the level of spatiotemporal coherence of the nonlinear forcing for flows with higher Reynolds number. Investigations along these directions are under way.

Acknowledgements

The authors would like to thank C. Cossu for fruitful discussions. The authors would like to acknowledge the Swedish–Brazilian Research and Innovation Centre CISB and the European Research Council (ERC) under grant agreement

694452-TRANSEP-ERC-2015-AdG for funding. The simulations were performed on resources provided by the Swedish National Infrastructure for Computing (SNIC) at NSC, HPC2N and PDC.

Declaration of interests

The authors report no conflict of interest.

Appendix A. Resolvent operators

The linear system in (2.2) is derived from the (2.1), as in Schmid & Henningson (2001). The matrices **A** and **B** are defined as

$$\mathbf{A} = \begin{bmatrix} \Delta^{-1} \mathcal{L}_{OS} & 0 \\ -i\beta U' & \mathcal{L}_{SQ} \end{bmatrix}, \quad \mathbf{B} = \begin{bmatrix} -i\alpha \Delta^{-1} \mathcal{D} & -k^2 \Delta^{-1} & -i\beta \Delta^{-1} \mathcal{D} \\ i\beta & 0 & -i\alpha \end{bmatrix}, \quad (\text{A } 1a,b)$$

where the discretized version of the generalized OSS operators (Cossu *et al.* 2009; Pujals *et al.* 2009) are

$$\mathcal{L}_{OS} = -i\alpha(U\Delta - U'') + \nu_T \Delta^2 + 2\nu_T' \Delta \mathcal{D} + \nu_T'' (\mathcal{D}^2 + k^2), \quad (\text{A } 2a)$$

$$\mathcal{L}_{SQ} = -i\alpha U + \nu_T \Delta + \nu_T' \mathcal{D}, \quad (\text{A } 2b)$$

with \mathcal{D} and $'$ representing d/dy , $k^2 = \alpha^2 + \beta^2$, $\Delta = \mathcal{D}^2 - k^2$, and $U(y)$ the reference flow. $\nu_T = \nu + \nu_t$ with ν the molecular viscosity and ν_t the eddy-viscosity model. Note that setting $\nu_t = 0$ reduces (A 2) and (2.2) to the standard OSS equations. The eddy-viscosity used is that proposed by Cess (1958), as reported by Reynolds & Tiederman (1967),

$$\frac{\nu_t}{\nu} = \frac{1}{2} \left[1 + \frac{\kappa^2 Re_\tau^2}{9} (1 - y^2)^2 (1 + 2y^2)^2 (1 - \exp(-Re_\tau(1 - |y|)/A))^2 \right]^{1/2} - \frac{1}{2}, \quad (\text{A } 3)$$

with $Re_\tau = u_\tau h/\nu$ the Reynolds number based on the friction velocity. The von Kármán constant is $\kappa = 0.426$ and the constant $A = 25.4$ as in Pujals *et al.* (2009) and Hwang & Cossu (2010b). This model is tuned for $Re_\tau = 2000$. Here $\nu_t = 0$ results in (2.12a), whereas ν_t as in (A 3) results in (2.12b). Homogeneous boundary conditions are enforced on both walls: $\hat{v}(\pm 1) = \partial_y \hat{v}(\pm 1) = \hat{\omega}_y(\pm 1) = 0$. The matrices relating $\hat{\mathbf{u}}$ and $\hat{\mathbf{q}}$ are

$$\mathbf{C} = \frac{1}{k^2} \begin{bmatrix} i\alpha \mathcal{D} & -i\beta \\ k^2 & 0 \\ i\beta \mathcal{D} & i\alpha \end{bmatrix}, \quad \mathbf{D} = \begin{bmatrix} 0 & 1 & 0 \\ i\beta & 0 & -i\alpha \end{bmatrix}. \quad (\text{A } 4a,b)$$

Appendix B. Solenoidal part of the forcing with *L* or *CB*

Take a general forcing field \mathbf{f} as the sum of a solenoidal field \mathbf{f}^s and an irrotational field \mathbf{f}^r , such that $\nabla \cdot \mathbf{f}^s = 0$ and $\nabla \times \mathbf{f}^r = 0$. Take $\mathbf{f}^r = \nabla \chi$, with χ a scalar field. For given wavenumbers (α, β) the Fourier modes of \mathbf{f} , \mathbf{f}^s and \mathbf{f}^r , discretized with N_y points in the wall-normal direction are the $3N_y \times 1$ vectors $\hat{\mathbf{f}}, \hat{\mathbf{f}}^s, \hat{\mathbf{f}}^r$ and the Fourier mode of χ

discretized with N_y points in the wall-normal direction is the $N_y \times 1$ vector $\hat{\chi}$. Applying \mathbf{B} to $\hat{\mathbf{f}}$ corresponds to $\mathbf{B}\hat{\mathbf{f}} = \mathbf{B}\hat{\mathbf{f}}^s + \mathbf{B}\hat{\mathbf{f}}^r$. It holds that

$$\mathbf{B}\hat{\mathbf{f}}^r = \begin{bmatrix} k^2\mathcal{D}\hat{\chi} - k^2\mathcal{D}\hat{\chi} \\ -\alpha\beta\hat{\chi} + \beta\alpha\hat{\chi} \end{bmatrix} = 0, \tag{B 1}$$

and

$$\mathbf{B}\hat{\mathbf{f}}^s = \begin{bmatrix} \hat{\mathbf{f}}_y^s \\ i\beta\hat{\mathbf{f}}_x^s - i\alpha\hat{\mathbf{f}}_z^s \end{bmatrix} \equiv \mathbf{D}\hat{\mathbf{f}}^s, \tag{B 2}$$

with $\hat{\mathbf{f}}_x^s$, $\hat{\mathbf{f}}_y^s$ and $\hat{\mathbf{f}}_z^s$ the $N_y \times 1$ vectors of the streamwise, wall-normal and spanwise components of $\hat{\mathbf{f}}^s$.

As $\hat{\mathbf{u}} = \mathbf{C}\hat{\mathbf{q}}$ and $\hat{\mathbf{q}} = \mathbf{D}\hat{\mathbf{u}}$, it follows that $\hat{\mathbf{u}} = \mathbf{CD}\hat{\mathbf{u}}$. Thus, $\hat{\mathbf{f}}^s = \mathbf{CD}\hat{\mathbf{f}}^s = \mathbf{CB}\hat{\mathbf{f}}$, which provides a first way to isolate the solenoidal part of the forcing.

The Fourier transform in time of (2.2) leads to $-(i\omega\mathbf{I} + \mathbf{A})\tilde{\mathbf{q}} = \mathbf{B}\tilde{\mathbf{f}}$, which is equivalent to $-(i\omega\mathbf{I} + \mathbf{A})\mathbf{D}\tilde{\mathbf{u}} = \mathbf{D}\tilde{\mathbf{f}}^s$. Thus, $\mathbf{L}\tilde{\mathbf{u}} = \mathbf{CD}\tilde{\mathbf{f}}^s = \tilde{\mathbf{f}}^s$, with $\mathbf{L} = -\mathbf{C}(i\omega\mathbf{I} + \mathbf{A})\mathbf{D}$.

It follows that $\mathbf{L}\tilde{\mathbf{u}} = \tilde{\mathbf{f}}^s = \mathbf{CB}\tilde{\mathbf{f}}$, which leads to the solenoidal part of the forcing from the velocity field. Thus, using \mathbf{L} or \mathbf{CB} to compute the solenoidal part of the forcing is equivalent.

Appendix C. DNS and data analysis details

The simulations were performed by means of the SIMSON code (see Chevalier *et al.* (2007) for details) for the simulation of the turbulent channel at $Re_\tau = 179$ and by means of Channelflow code (see www.channelflow.ch (2018) for details) for the simulation of the turbulent channel at $Re_\tau = 543$.

The initial transient of the simulation is discarded. Welch’s method with Hann windowing and 75 % overlap is used to compute the CSDs \mathbf{S} and \mathbf{P} using a total of $N_s = 10001$ snapshots of the DNS solutions with sampling interval $\Delta t_s = 0.5$ for a total acquisition time $T_{max} = 5000$ for $Re_\tau = 179$, and using $N_s = 2000$ snapshots sampled every $\Delta t_s = 0.15$ for a total acquisition time $T_{max} = 299.85$ for $Re_\tau = 543$. Data have also been averaged between the two walls.

REFERENCES

DEL ÁLAMO, J. C. & JIMÉNEZ, J. 2003 Spectra of the very large anisotropic scales in turbulent channels. *Phys. Fluids* **15** (6), L41–L44.

DEL ÁLAMO, J. C. & JIMENEZ, J. 2006 Linear energy amplification in turbulent channels. *J. Fluid Mech.* **559**, 205–213.

BENEDDINE, S., SIPP, D., ARNAULT, D., DANDOIS, J. & LESSHAFFT, L. 2016 Conditions for validity of mean flow stability analysis. *J. Fluid Mech.* **798**, 485–504.

BHATIA, H., NORGARD, G., PASCUCCI, V. & BREMER, P.-T. 2013 The Helmholtz–Hodge decomposition – a survey. *IEEE Trans. Vis. Comput. Graphics* **19** (8), 1386–1404.

BOTTARO, A., SOUIED, H. & GALLETTI, B. 2006 Formation of secondary vortices in a turbulent square-duct flow. *AIAA J.* **44**, 803–811.

BRANDT, L. 2014 The lift-up effect: the linear mechanism behind transition and turbulence in shear flows. *Eur. J. Mech. B/Fluids* **47**, 80–96.

BUTLER, K. M. & FARRELL, B. F. 1993 Optimal perturbations and streak spacing in wall-bounded turbulent shear flow. *Phys. Fluids A* **5**, 774–777.

- CAVALIERI, A. G. V., JORDAN, P. & LESSHAFFT, L. 2019 Wave-packet models for jet dynamics and sound radiation. *Appl. Mech. Rev.* **71** (2), 020802.
- CESS, R. D. 1958 A survey of the literature on heat transfer in turbulent tube flow. *Research Report* 8–0529–R24. Westinghouse.
- CHEVALIER, M., HËPPFNER, J., BEWLEY, T. R. & HENNINGSON, D. S. 2006 State estimation in wall-bounded flow systems. Part 2: turbulent flows. *J. Fluid Mech.* **552**, 167–187.
- CHEVALIER, M., SCHLATTER, P., LUNDBLADH, A. & HENNINGSON, D. S. 2007 A pseudo-spectral solver for incompressible boundary layer flows. *Tech. Rep.* TRITA-MEK 2007:07. KTH Mechanics, Stockholm, Sweden.
- CHIBBARO, S. & MINIER, J. P. 2014 *Stochastic Methods in Fluid Mechanics*. Springer.
- CHO, M., HWANG, Y. & CHOI, H. 2018 Scale interactions and spectral energy transfer in turbulent channel flow. *J. Fluid Mech.* **854**, 474–504.
- CHORIN, A. J. & MARSDEN, J. E. 1993 *A Mathematical Introduction to Fluid Mechanics*, 3rd edn. Texts in Applied Mathematics, vol. 4. Springer.
- COSSU, C. & HWANG, Y. 2017 Self-sustaining processes at all scales in wall-bounded turbulent shear flows. *Phil. Trans. R. Soc. Lond. A* **375** (2089), 20160088.
- COSSU, C., PUJALS, G. & DEPARDON, S. 2009 Optimal transient growth and very large scale structures in turbulent boundary layers. *J. Fluid Mech.* **619**, 79–94.
- DELLA PIETRA, S., DELLA PIETRA, V. & LAFFERTY, J. 1997 Inducing features of random fields. *IEEE Trans. Pattern Anal. Mach. Intell.* **19** (4), 380–393.
- ELLINGSEN, T. & PALM, E. 1975 Stability of linear flow. *Phys. Fluids* **18**, 487–488.
- FARRELL, B. F. & IOANNOU, P. J. 1993 Optimal excitation of three-dimensional perturbations in viscous constant shear flow. *Phys. Fluids* **5**, 1390–1400.
- FARRELL, B. F. & IOANNOU, P. J. 2012 Dynamics of streamwise rolls and streaks in turbulent wall-bounded shear flow. *J. Fluid Mech.* **708**, 149–196.
- FLORES, O. & JIMÉNEZ, J. 2006 Effect of wall-boundary disturbances on turbulent channel flows. *J. Fluid Mech.* **566**, 357–376.
- FLORES, O. & JIMENEZ, J. 2010 Hierarchy of minimal flow units in the logarithmic layer. *Phys. Fluids* **22**, 071704.
- FLORES, O., JIMÉNEZ, J. & DEL ÁLAMO, J. C. 2007 Vorticity organization in the outer layer of turbulent channels with disturbed walls. *J. Fluid Mech.* **591**, 145–154.
- GOODWIN, G. C. & PAYNE, R. L. 1977 *Dynamic System Identification: Experiment Design and Data Analysis, Mathematics in Science and Engineering*, vol. 136. Academic Press.
- HAMILTON, J. M., KIM, J. & WALEFFE, F. 1995 Regeneration mechanisms of near-wall turbulence structures. *J. Fluid Mech.* **287**, 317–348.
- HENNINGSON, D. S. 1996 Comment “Transition in shear flows. Nonlinear normality versus non-normal linearity”. *Phys. Fluids* **8**, 2257.
- HJALMARSSON, H. & MÅRTENSSON, K. 2007 A geometric approach to variance analysis in system identification: theory and nonlinear systems. In *2007 46th IEEE Conference on Decision and Control*, pp. 5092–5097. IEEE.
- HWANG, Y. & COSSU, C. 2010a Amplification of coherent streaks in the turbulent couette flow: an input–output analysis at low Reynolds number. *J. Fluid Mech.* **643**, 333–348.
- HWANG, Y. & COSSU, C. 2010b Linear non-normal energy amplification of harmonic and stochastic forcing in turbulent channel flow. *J. Fluid Mech.* **664**, 51–73.
- HWANG, Y. & COSSU, C. 2010c Self-sustained process at large scales in turbulent channel flow. *Phys. Rev. Lett.* **105** (4), 044505.
- HWANG, Y. & COSSU, C. 2011 Self-sustained processes in the logarithmic layer of turbulent channel flows. *Phys. Fluids* **23**, 061702.
- ILLINGWORTH, S. J., MONTY, J. P. & MARUSIC, I. 2018 Estimating large-scale structures in wall turbulence using linear models. *J. Fluid Mech.* **842**, 146–162.
- JOVANOVIĆ, M. R. & BAMIEH, B. 2001 Modeling flow statistics using the linearized Navier–Stokes equations. In *Proceedings of the 40th IEEE Conference on Decision and Control (Cat. No. 01CH37228)*, vol. 5, pp. 4944–4949. IEEE.

- KAWATA, T. & ALFREDSSON, P. H. 2018 Inverse interscale transport of the Reynolds shear stress in plane Couette turbulence. *Phys. Rev. Lett.* **120**, 244501.
- LANDAHL, M. T. 1980 A note on an algebraic instability of inviscid parallel shear flows. *J. Fluid Mech.* **98**, 243–251.
- LESSHAFFT, L., SEMERARO, O., JAUNET, V., CAVALIERI, A. V. G. & JORDAN, P. 2019 Resolvent-based modeling of coherent wave packets in a turbulent jet. *Phys. Rev. Fluids* **4** (6), 063901.
- LUMLEY, J. L. 1970 *Stochastic Tools in Turbulence*. Academic Press.
- MALKUS, W. V. R. 1956 Outline of a theory of turbulent shear flow. *J. Fluid Mech.* **1**, 521–539.
- MARTINI, E., CAVALIERI, A. G. V., JORDAN, P. & LESSHAFFT, L. 2019 Accurate frequency domain identification of odes with arbitrary signals. [arXiv:1907.04787](https://arxiv.org/abs/1907.04787).
- MCKEON, B. J. 2017 The engine behind (wall) turbulence: perspectives on scale interactions. *J. Fluid Mech.* **817**, P1.
- MCKEON, B. J. & SHARMA, A. S. 2010 A critical-layer framework for turbulent pipe flow. *J. Fluid Mech.* **658**, 336–382.
- MOFFATT, H. K. 1967 The interaction of turbulence with strong wind shear. In *Proceedings of the URSI-IUGG Colloquium on Atmospheric Turbulence and Radio Wave Propagation* (ed. A. M. Yaglom & V. I. Tatarsky), pp. 139–154. Nauka.
- MORRA, P., SEMERARO, O., HENNINGSON, D. S. & COSSU, C. 2019 On the relevance of reynolds stresses in resolvent analyses of turbulent wall-bounded flows. *J. Fluid Mech.* **867**, 969–984.
- NAGATA, M. 1990 Three-dimensional finite-amplitude solutions in plane couette flow: bifurcation from infinity. *J. Fluid Mech.* **217**, 519–527.
- NOGUEIRA, P. A. S., MORRA, P., MARTINI, E., CAVALIERI, A. V. G. & HENNINGSON, D. S. 2021 Forcing statistics in resolvent analysis: application in minimal turbulent Couette flow. *J. Fluid Mech.* (in Press).
- PARK, J. S. & GRAHAM, M. D. 2015 Exact coherent states and connections to turbulent dynamics in minimal channel flow. *J. Fluid Mech.* **782**, 430–454.
- PICARD, C. & DELVILLE, J. 2000 Pressure velocity coupling in a subsonic round jet. *Intl J. Heat Fluid Flow* **21** (3), 359–364.
- PICKERING, E. M., TOWNE, A., JORDAN, P. & COLONIUS, T. 2020 Resolvent-based jet noise models: a projection approach. In *AIAA Scitech 2020 Forum*. AIAA.
- PINTELO, R. & SCHOUKENS, J. 2012 *System Identification: A Frequency Domain Approach*. Wiley-IEEE Press.
- PUJALS, G., GARCÍA-VILLALBA, M., COSSU, C. & DEPARDON, S. 2009 A note on optimal transient growth in turbulent channel flows. *Phys. Fluids* **21**, 015109.
- REYNOLDS, W. C. & HUSSAIN, A. K. M. F. 1972 The mechanics of an organized wave in turbulent shear flow. Part 3. Theoretical models and comparisons with experiments. *J. Fluid Mech.* **54** (2), 263–288.
- REYNOLDS, W. C. & TIEDERMAN, W. G. 1967 Stability of turbulent channel flow, with application to Malkus's theory. *J. Fluid Mech.* **27** (2), 253–272.
- ROSENBERG, K. & MCKEON, B. J. 2019 Efficient representation of exact coherent states of the Navier–Stokes equations using resolvent analysis. *Fluid Dyn. Res.* **51** (1), 011401.
- SASAKI, K., MORRA, P., CAVALIERI, A. V. G., HANIFI, A. & HENNINGSON, D. S. 2020 On the role of actuation for the control of streaky structures in boundary layers. *J. Fluid Mech.* **883**, A34.
- SCHMID, P. J. & HENNINGSON, D. S. 2001 *Stability and Transition in Shear Flows*. Applied Mathematical Sciences, vol. 142. Springer.
- SCHMIDT, O. T., TOWNE, A., RIGAS, G. & COLONIUS, T. 2018 Spectral analysis of jet turbulence. *J. Fluid Mech.* **855**, 953–982.
- STARK, H. & WOODS, J. W. 1986 *Probability, Random Processes, and Estimation Theory for Engineers*. Prentice-Hall Inc.
- SYMON, S., SIPP, D. & MCKEON, B. J. 2019 A tale of two airfoils: resolvent-based modelling of an oscillator versus an amplifier from an experimental mean. *J. Fluid Mech.* **881**, 51–83.
- TOWNE, A., LOZANO-DURÁN, A. & YANG, X. 2020 Resolvent-based estimation of space-time flow statistics. *J. Fluid Mech.* **883**, A17.
- TOWNE, A., SCHMIDT, O. T. & COLONIUS, T. 2018 Spectral proper orthogonal decomposition and its relationship to dynamic mode decomposition and resolvent analysis. *J. Fluid Mech.* **847**, 821–867.

- WALEFFE, F. 1995 Transition in shear flows. Nonlinear normality versus non-normal linearity. *Phys. Fluids* **7**, 3060.
- WELCH, P. 1967 The use of fast fourier transform for the estimation of power spectra: a method based on time averaging over short, modified periodograms. *IEEE Trans. Audio Electroacoust.* **15** (2), 70–73.
- WU, J. Z., ZHOU, Y. & WU, J. M. 1996 Reduced stress tensor and dissipation and the transport of lamb vector. *ICASE Report No. 96-21*. NASA Langley Research Center.
- WWW.CHANNELFLOW.CH 2018 Channelflow 2.0.
- ZARE, A., JOVANOVIĆ, M. R. & GEORGIU, T. T. 2017 Colour of turbulence. *J. Fluid Mech.* **812**, 636–680.