# THE HII REGION-MOLECULAR CLOUD COMPLEX W3: OBSERVATIONS OF CO, CS, AND HCN

HÉLÈNE R. DICKEL AND JOHN R. DICKEL

Department of Astronomy, University of Illinois; and Sterrewacht, Leiden

WILLIAM J. WILSON

Electronics Research Laboratory, Aerospace Corporation

MICHAEL W. WERNER

Division of Physics, Mathematics, and Astronomy, California Institute of Technology Received 1979 August 9; accepted 1979 October 22

#### ABSTRACT

The distributions of the emission from <sup>12</sup>CO, <sup>13</sup>CO, CS, and HCN have been mapped in the W3 molecular cloud. The emission is divided into three components according to the spatial distribution of the intensity and the associated velocity. Although the overall cloud is investigated, the emphasis is on the brightest condensation referred to as the W3 core. This dense and dynamically active region contains several embedded compact H II regions, IR sources, and masers. Strong <sup>12</sup>CO self-absorption occurs toward the compact infrared source IRS 5 where emission from dust at 1 mm and in the far-infrared and the emission from <sup>13</sup>CO and HCN are strongest, but the emission from CS, by contrast, is rather weak. Collapse of the W3 core is inferred from the line profiles. A velocity gradient is observed across the W3 core. The observations and derived physical parameters which are presented in this paper will be used in a subsequent paper to develop a model of the W3 region.

Subject headings: interstellar: molecules — nebulae: general — nebulae: individual

### I. INTRODUCTION

IC 1795-W3 is a giant H II region/molecular cloud complex located in the Perseus spiral arm at  $l \sim 133^\circ$ 5. This section of the Perseus arm between  $l \sim 133^\circ$ 5. This section of the Perseus arm between  $l \sim 133^\circ$ 5 and 137° is especially rich in star clusters—Cas OB6, Ocl 352, Ocl 364 (e.g., Ishida 1970; Hagen 1970; Alter, Ruprecht, and Vanysek 1970), ionized hydrogen—W3, W4, and W5 (Westerhout 1958; Wendker and Altenhoff 1977; Rohlfs, Braunsfurth, and Hills 1977), and molecules—clouds associated with W3 and W5 (Dickel 1973; Wilson et al. 1974; Lada et al. 1978). The core or densest part of the W3 molecular cloud contains several embedded compact H II regions which have been studied with high spatial resolution at both the core of the way and the contains several embedded compact H II regions which have been studied with high spatial resolution at both near-infrared and radio wavelengths (Wynn-Williams, Becklin, and Neugebauer 1972; Wynn-Williams 1971). OH and H<sub>2</sub>O masers have also been observed (Rogers et al. 1967; Goss, Lockhart, and Fomalont 1975; Genzel and Downes 1977; Forster, Welch, and Wright 1977). Figure 1 is a sketch of the W3-4 region to orient the reader and to show the general location of many of the features mentioned in this discussion.

The present study of the W3 complex began as part of the wavelength of

II]). In this paper we present detailed observations of the CO emission in W3 which complement the CO maps of Lada et al, (1978) of a much larger region, of our CO mapping program for which we have previously published the results for NGC 6334 (Dickel, Dickel, and Wilson 1977 [Paper I]) and (Dickel, Dickel, and Wilson 1971 | raper 1) and W75-DR 21 (Dickel, Dickel, and Wilson 1978 [Paper W75-DR 21 (Dickel, Dickel, and Wilson 1978 [Paper W75-DR 21 (Dickel, Dickel, and Wilson 1971 | Paper 1

> including W3, W4, and W5, with lower angular resolution. In addition we have made maps of the emission from CS (J=2-1) and HCN (J=1-0) which arise in the denser core of the W3 molecular cloud. They allow further constraints to be placed on IC 1795-W3 complex and its relationship to the rest of the galactic environment; the model is presented line profiles given in this paper has allowed the development of a model of the structure and dynamics of the the derived physical parameters than is possible from the <sup>13</sup>CO and <sup>12</sup>CO data alone. The analysis of the

in a subsequent paper (Dickel 1980).

In § II the observations are described. In § III the profiles and maps are presented, the significant observational features are discussed, and a number of physical parameters of the W3 cloud are determined. A brief summary is given in § IV.

### II. OBSERVATIONS

Since the equipment and observing procedure used

for these observations were described in full in Paper I, only the important parameters are repeated in Table I. The data consist of spectra obtained at fixed points on a grid which is centered on the group of near-infrared sources IRS 5-6-7 at  $\alpha(1950) = 0.021153^{\circ}$  and  $\delta(1950) = +61^{\circ}52'15''$ . This "CENTER" posiand  $\delta(1950) = +61^{\circ}52'15''$ . tion is marked by the intersection of the two inner axes drawn on most of the figures. The CO spectra of the outer parts of the W3 cloud, which were obtained with both the Aerospace and NRAO telescopes, cover

TABLE 1
OBSERVATIONAL PARAMETERS

			Frequency	Half- Power Beamwidth	Typical Integration Time		Reso	LUTION	rms Noise ON Spectrum	Orion A
EQUIPMENT	Molecule	Transition	(kHz)	(arcsec)	(min)	Bandwidth (MHz)	(kHz)	(km s <sup>-1</sup> )	(K)	$T_A^*$ (K)
Aerospace 4.6 m, 1976	<sup>12</sup> CO	J=1-0	115.271204	150	15	32.0	250	0.65	0.8	60.0
NRAO 11 m, 1973	12CO	J = 1 - 0	115.271204	70	15	12.5	250	0.65	1.0	60.0
	13CO	J = 1 - 0	110.201370	70	30	12.5	250	0.67	0.4	9.3
NRAO 11 m, 1974, 1975, 1976	<sup>12</sup> CO	J = 1 - 0	115.271204	70	6	25.6	100	0.26	1.4	60.0
	<sup>13</sup> CO	J = 1 - 0	110.201370	70	10	25.6	100	0.27	0.4	9.3
NRAO 11 m, 1975	CS	J = 2-1	97.981007	80	15	64.0	250	0.77	0.15	4.5
	HCN	J=1-0, F=2-1	88.631847	90	15	64.0	250	0.84	0.20	(5.9 at 2'S) 17.2




Fig. 1.—Schematic diagram of part of the Perseus spiral arm showing the location of the H II regions W3-4 (dashed outlines) and the associated molecular cloud (solid line). The stars in the OB association Cas OB6 cover the entire area. The center of the open cluster Ocl 352 which excites W4 is marked by an asterisk. The line of constant galactic latitude  $b = 0^{\circ}$  is drawn with tick marks every 1° in galactic longitude, and the central  $\alpha$ ,  $\delta$  axes of the CO observing grid are drawn.

 $\sim \frac{1}{2}^{\circ}$  in α and δ with a spacing of 2'-4' between positions. For the inner part of the W3 cloud, the spacing between points was 1' for  $^{13}$ CO,  $^{12}$ CO, and CS, and somewhat larger for HCN. A finer grid, every ½', was used for the  $^{12}$ CO observations in the very central region. During each observing session, the observations at the center were repeated about once each hour to correct for atmospheric extinction. The absolute calibration was provided by measuring the emission from Orion A and normalizing to the CO and HCN values taken from Ulich and Haas (1976). These are given in the last column of Table 1. Corrected antenna temperatures outside the atmosphere,  $T_A^*$ , are used throughout and are related to the brightness temperature by the forward beam efficiency which is  $\geq 0.9$  (Ulich and Haas 1976).

> width across the profile,  $\Delta V_w$ , in column (8); both quantities are measured in the line wings at the 1 K level for <sup>12</sup>CO and <sup>13</sup>CO and 0.5 K for CS and HCN. In Table 2B, columns (4)–(8) refer to <sup>12</sup>CO, and the same parameters appear in columns (9)–(13) for <sup>13</sup>CO. The spatial and frequency resolution of these observarather than multiple components (Dickel et al. 1975). The integrated brightness in column (6) is for the entire profile (except in a few instances in Table 2A where maximum value of the ratio, max r; the velocity at which this maximum occurs,  $V_r$ ; and the extent in velocity,  $\Delta V_r$ , for which the ratio is  $\gtrsim 0.2$ . (For r less than 0.2, the velocity extent over which the ratio is the quantities were measured from profiles with 250 kHz resolution. The last three columns of Table 2B contain the following information relating to the intensity ratio of <sup>13</sup>CO to <sup>12</sup>CO across the profile: the midpoint of the line,  $V_w$ , in ≥0.15 is given in parentheses.) In addition to the CO, CS, and HCN data, we have also utilized in § IIIc(ii) a footnote (d) appears in column (1) to indicate that tions are 1' and 100 kHz, respectively, except where metric profiles we have also given the velocity at the individual components are separated enough to give Dickel (1973). the 6 cm formaldehyde data for W3 published for each component). column (7) and the Because of the asymfull

# III. DISCUSSION OF THE MOLECULAR DATA

### i) Nomenclature

To arrive at conclusions about various physical parameters in the complex, it is necessary to compare the present data with data in other wavelength ranges. A summary of the information available on all the important features in this complex is collected in Table 4. Although most of the entries are not new in this paper, this table is the only place where all the facts requiring explanation by a complete model of the W3 complex have been brought together. The tabular presentation is also important for sorting out the confusion in names which exist in the literature and for separating overlapping components. We shall henceforth refer to features by their designations

TABLE 2A
Observational Parameters for CO in W3

E00	E00	W08° E00	W09 <sup>d</sup>	W16° W09°	W16	W16	W24° W24° W24°	W32 W32	W32 W32 W32	W40°	W40°	W40 <sup>d</sup>	W40° W40° W40°	W48	W48	W64	W64	W64	W64	W64	W64 W64	W80 W64	₩80°	W80c	70/11	₩₩ 86 86 86 86 87 87 87 87 87 87 87 87 87 87 87 87 87	Δ <sub>α</sub>	FRO
S05 S04	S08	N0.5 S16 S12	<b>NO1</b>	N07	N04	S04	S03 N00 N03	S04	\$16 \$12 \$08	N05	N02	N00	S10 S05 N00	N04	S04	N04	N02	N00	S02	S04	S12 S08	N02	S02 N00	S05	SOA	S08 S08 S08	Δδ (arcmin)	POSITION FROM CENTER <sup>6</sup>
ø	n v		n 0,0	, ,	, <i>u</i>	n on	יס י	<b>5</b> 5	; t	י ד	; v		·	, פי נסי	<del>o</del>	Q	טי נ	ם ו		י י	1			ŋ	þ	<b>-</b> -		
2.4 5.1 3.6	7.4 7.4	30.0 10.2 11.3	7.4	31.0	10.6	6.2 3.3	10.3 18.0 9.6	13.2 11.5 5	1.73	4.5 6.5		4.1	4.2 9.1 9.1	1.8? 4.8?	4.4.1 8.8.4 8.8.4	6.7 6.7	4.8	6.9	1.1	2.5.2 2.4.0	0.0 0.0	3.4 4.3	6.1 5.6	5.6 5.6	8.1	9.5 8.6 4.8 [0.7	(K) (I	
-40.0 $-37.8$ $-41.0$	- 43.1 - 40.8	- 42.0 - 43.6 - 43.6	- 39.5 - 43.1	-40.2 $-41.4$ $-43.3$ $-46.7$	- 40.7 - 40.7	-42.9 $-41.0$ $-30.13$	- 44.9 - 41.9 - 40.8 - 39.5	-40.5 $-41.0$ $-37.8$ $-41.0$	- 43.5 - 43.6	144.3 144.3	- 39.0 - 39.0		- 40.0 - 43.0	-37.6 -38.5 -44.5	-45.1 -40.4	-43.6	- 44.1 - 44.1	- 44. / - 40.4	- 40.0	- 44.2 - 44.8	- 44.4 - 40.4	-44.2 -43.5	-41.3 $-40.7$	- 43.6 - 40.0 - 42.2	-44.4 43.0	-41.5 -40.0 -42.5 -40.3	$V_p$ (km s <sup>-1</sup> ) (	<sup>b</sup> (250 k Line
18 21	25	244 24 24	30	19 233	57	21	41 99 54	45 77	12 7 15	36	50	10	13 24 38	35	27	18	21	24	51	23	14 27	110	30 21	35 ±	ò	58 58 58 58 58	$(\mathbf{K} \cdot \mathbf{km}  \mathbf{s}^{-1})$	(250 kHz resolution) LINE PARAMETERS
-39.8 -39.3	-42.1	-41.8 -43.1 -42.4	-42.3	-41.2 $-43.9$	-41.5	-40.6	-41.6 -41.4 -40.4	-41.0 $-41.7$	-43.4 -42.6 -41.6	-42.7	-42.9	-38.6	-40.2 -43.4 -42.3	-41.5	-42.0	-42.9	-43.6	-43.0	-43.0	-43.2	$-44.4 \\ -42.3$	-43.8 -43.5	-41.9 $-40.7$	-42.6 $-43.1$	Š	-44.0 $-43.7$ $-42.5$ $-43.3$	(km s <sup>-1</sup> )	on)
4.4 7.9	6.2	17.0 4.6 5.7	9.3	7.0 15.3	11.6	6.0	6.5 11.0 9.8	5.7 13.9	3.1 3.9 7.3	13.1	12.8	6.0	4.2 8.0 11.4	11.4	10.4	6.2	8.3	8.3	8.4	7.4	8.3 8.3	တ <u>ထ</u> ယ ယ		8. o. o	0	11.7 11.1 6.2 9.4	$\frac{\Delta V_{w}}{(\mathrm{km  s^{-1}})}$	

	_
	ABLE
l	(-)
	2A—Continued

E80°	E74 <sup>d</sup> E76	E64	E64	E56° E56° E64	E56°	E48	E47° E47° E48	E48	E48 E48	шшна 400° с	E32	E32	E24° E24° E24° E24°	E24	E16 E16 E24	E00 E04 <sup>d</sup> E16	E00°	E00°.4	E00°,	$\Delta_{\alpha}$ (s)	Posi FROM
S15	N09 S17	N04	N02	X03 X07 X00	S01	N04	S02 N00	S04	S14 S12	S05 N00 N00 N00 N00 S16	N10	S04	NO3	S12 S08	N04 N10 S16	NO2 NO2 NO3	N05	NNN N02 200	S02 N00	Δδ (arcmin)	POSITION FROM CENTER <sup>8</sup>
_		· .			ā	n. 12	, <del>,</del> ,	•			უ <b>%</b> უ	o s		'a	-a •		n so	<b>'</b> c	3		
p 11.3 11.2	15.8 15.8		143	_	л 8.1	10.5	1.4? 10.9 1.6 20.6	15.4	7.0 7.0 7.0	5.1 13.6 4.2 12.4 12.3 2.1			13.7 2.5 19.3 10.5		17.5 ≤1.3 4.4 1.6		7.9 4.6	6.2 16.0 17.8	7.9 25.7	$T_A^*$ (K)	
-44.9 $-47.2$	-42.7 -39.2 -47.4	- 42.6 - 38.8	- 38.6 - 38.6 - 38.6	- 39.1 - 42.2 - 38.6	1 40.0 34 9	- 40.2 - 37.3	- 30.3 - 40.6 - 39.1	-39.4	-43.4 -43.4 -43.4	- 39.5 - 39.6 - 39.6 - 41.2 - 41.8	$ \begin{array}{r} -31.6 \\ -42.9 \\ -39.1 \\ -34.0 \end{array} $	-38.6 $-41.0$ $-45.2$	- 39.6 - 39.6 - 40.6 - 41.7	-41.8 $-36.4$	-40.4 -42.6 -44.4 -47.0	-41.7 $-39.0$ $-38.1$	- 46.2 - 40.6 - 43.2	- 39.0 - 40.8 - 40.2	-38.0 -41.6	$(\text{km s}^{V_p})$	b (250 Lin
75	78 78	47	53	50 39 62	38	55	4 39 4 72	20	35 37	14 57 11 62 41 8	3 17 4	30 3	479 8 67 479 8 7		87 4 17	19 19 31	46	27 76 86	48 203	$(\mathbf{K} \cdot \mathbf{km}  \mathbf{s}^{-1})$	(250 kHz resolution) LINE PARAMETERS
-46.3	-39.6 -46.5	-39.9	-39.7	- 39.4 - 41.8 - 45.8 - 39.9	-37.8	-39.4	-30.2 $-40.5$ $-38.9$ $-38.1$	-40.4	-43.4 $-45.0$	- 39.5 - 40.1 - 39.0 - 39.6 - 41.5 - 44.5	-31.6 $-41.1$ $-34.0$	-39.1 $-45.2$	- 40.2 - 40.4 - 40.4 - 41.5	- 42.5 - 49.1 - 36.4	-39.9 -42.7 -45.0	-41.6 -39.6 -38.2	-42.2	-39.2 -41.3 -41.1	-39.0 -40.0	$(\text{km s}^{V_w})$	on)
11.9	8.4 7.8	 	10.0	6.9 6.9 5.4 14.9	10.2	10.0	6.8 3.7 8.6	4.7	10.4 8.8	822773845 822333	2.1 6.2 2.6	6.0 1.6	7.3 7.3	0.1.2.3 2.2.3.3	8.1 5.8	6.4 10.3 6.9	8.9	9.2 9.5 11.8	10.4 17.6	$(\text{km s}^{-1})$	

# DICKEL, DICKEL, WILSON, AND WERNER

TABLE 2A—Continued

P	POSITION FROM CENTER®		<sup>b</sup> (250 Lin	250 kHz resolution) LINE PARAMETERS	″કાં
$\Delta \alpha$ (s)	Δδ (arcmin)	$T_A^*$ (K)	$(\mathrm{km}\mathrm{s}^{-1})$	(K:k	$(\mathbf{K} \cdot \mathbf{kms^{-1}})  (\mathbf{km  s^{-1}})$
E80d	S15	5.0	-47.4		25
₩ 6 6 6 6 6 7 8 8 8 8 8 8 8 8 8 8 8 8 8 8	S10	11.7 4.3	- 46.8 - 44.6		70 7
E80	S08	12.7	-46.0		<u>s</u>
E80°	S05	s 5.8	- 49.5 - 46.8		30
E80	S02	s 3.9	-41.2 -46.2		19
;		s 4.3	-43.4		;
100	400	p 4.4	-43.8		ŧ
E80°	Z05	P 2.2 4.1	- 38.8 - 40.5		25
E80°	N10	5.4	-43.1		17
E84°	S13.5	17.6	-48.6		120
E84d	S13.5	5.5	-47.5		27
E94	S17		-47.5		45
E96 E112	S08	12.7 3.0	-47.5		15 83
		1			
)		0000			

- <sup>a</sup> Center at  $a(1950) = 02^h21^m53^s$ ,  $\delta(1950) = +61^\circ52'15''$ .

  <sup>b</sup> <sup>12</sup>CO Aerospace data with 2' beam (but see exceptions in footnotes c, d below).

  <sup>c</sup> <sup>12</sup>CO NRAO data with 1' beam.

  <sup>d</sup> <sup>13</sup>CO NRAO data with 1' beam.
- Average of 10 scans.
- f Average of 11 scans.

position of the component in galactic and equatorial coordinates is tabulated in columns (4) and (5). Pertinent references for the entries in column (3) are in column (2), other names of the object and/or associated emission are listed in column (3), and the given in the last column. in column (1) of this table. A brief description follows

A reproduction of the red Sky Survey print of the W3 area is in Figure 2, and the "northern group" of sources is portrayed in Figure 3. The overall W3-W4 region is sketched in Figure 1.

### b) Large-Scale Features

# i) The Association of the W3 Molecular Cloud with the W4 H II Region

red print in Figure 2a. For comparison, a map of the radio continuum emission from the W3 region at 49 cm made with the Westerbork Synthesis Radio Telescope (WSRT) by Harten (1980) is shown in Figure 2b. Only the brightest parts of the CO cloud are shown down to  $T_A^* \ge 2$  K. Low-level emission  $(T_A^* < 10 \text{ K})$  extends over 3 square degrees (Lada et al. 1978) and stops abruptly where it encounters the et al. 1978) and stops abruptly where it encounters the western ionization front of the W4 H II region (part of which is seen in the lower left of Fig. 2 to the east of  $\alpha \sim 2^{\text{h}}25^{\text{m}}$ ). Because of the similar distance of area is shown overlaid on the Palomar Sky Survey of  $\alpha \sim 2^{\rm n}25^{\rm m}$ ). Because of the similar distance of  $\sim 2$  kpc for the exciting stars of the W3 and W4 H II regions (Ishida 1969, 1970; Ogura and Ishida 1976) and the apparent interaction of the W3 molecular cloud The distribution of the <sup>12</sup>CO emission in the W3

with the W4 H  $\scriptstyle\rm II$  region, it is concluded that the W3 molecular cloud and the W4 H  $\scriptstyle\rm II$  region are in physical

# ii) Regions of Enhanced CO Intensity

(Another source along this border, AFGL 333 at  $\alpha \sim 2^{\text{h}}24^{\text{m}}6$  and  $\delta \sim 61^{\circ}14.7$ , has been observed in CO by Lada *et al.* 1978). The remaining weak CO emission may be considered as a third component of the strongest radio continuum emission (compare Figs. 2a and 2b). A second such region of enhanced CO emission is along the border with W4 and includes the W3-OH maser at  $\alpha \sim 2^{\text{n}}23^{\text{m}}3$ ,  $\delta \sim 61^{\circ}39'$ . There is a small enhancement of the radio continuum emission along this ridge (Wendker and Altenhoff 1977). cloud is strongest toward regions of enhanced density and/or temperature as indicated by the presence of embedded compact H II regions, near-infrared sources, and masers. The strongest CO emission occurs in the main "W3 core," whose central part coincides with Our CO data show that the emission from the W3 W3 molecular cloud. radio

### iii) Velocity Structure

distinct regions discussed above according to its velocity as shown in Figure 2a: the brightest part of the W3 molecular cloud, "W3 core," has a velocity referred to the local standard of rest of  $\sim$  -40.5  $\pm$  2.5 km s<sup>-1</sup>; the region along the W4 ionization front has a radial velocity of  $\sim$  -47  $\pm$  2 km s<sup>-1</sup>; and the The CO emission can also be divided into the three

TABLE 2B

OBSERVATIONAL PARAMETERS FOR <sup>12</sup>CO and <sup>13</sup>CO for Inner Part of W3

	SITION CENTER <sup>8</sup>			<sup>12</sup> CO ( Li	(100 kHz resol ine Parametei	ution) RS				100 kHz resol NE PARAMETE			max r =		For $r \ge 0.2$
$\frac{\Delta \alpha}{(s)}$	Δδ (′)		<i>T<sub>A</sub></i> * (K)	$V_p$ (km s <sup>-1</sup> )	∫ <i>TdV</i> (K km s <sup>-1</sup> )	V <sub>w</sub> (km s <sup>-1</sup> )	$\Delta V_w$ (km s <sup>-1</sup> )	T <sub>A</sub> * (K)	$V_p$ (km s <sup>-1</sup> )	∫ <i>TdV</i> (K km s <sup>-1</sup> )	$V_w$ (km s <sup>-1</sup> )	$\Delta V_w$ (km s <sup>-1</sup> )	$\frac{T_A*(^{13}CO)}{T_A*(^{12}CO)}$	(km s <sup>-1</sup> )	$\Delta V_r$ (km s <sup>-1</sup> )
W42	S02		8.3	-41.2	21	-40.3 -40.4	4.2 7.5	3.6	-40.0	8	-39.9	2.6	0.31	-40.0	2.0
W34 W34	S01 N00		11.7 12.8	-40.4 $-40.0$	47 58	-40.4 -40.0	7.3 7.9	3.6 4.4 1.5	-40.0 $-40.0$ $-37.7$	13	-39.4	4.9	0.32	-40.0	4.0
W34	N01	S	8.5 14.1	-38.0 $-40.0$	56	-39.7	9.3	3.2	-40.0	10	-39.5	3.6	0.25	-39.5	1.0
W34	N02		10.8	- 39.4	44	-39.6	6.4	2.3	-39.0	6	-39.0	3.1	0.25	-38.5	0.5
w25	S02		14.3	-41.6	62	-41.1	9.3	1.6	-41.0	6	-41.0	3.2	0.17	-39.8	(0.5)
W25	S01		17.6	-41.0	.97	-41.6	10.0	3.1	-40.0	13	-40.4	5.0	0.22	-38.5	2.0
W25	N00		18.4	-40.5	110	-41.6	11.1	4.0	-40.5	20	-40.2	6.8	0.23	$-38.8 \\ -39.7$	4.0
W25	N01		15.1	-39.7	51	-40.8	7.5	2.1	-39.6	6	-39.5	3.0 6.0	0.14 0.28	- 39.7 - 38.8	1.5
W25	N02		12.7	-39.7	76	-41.0	9.6	3.2 1.1	-38.9 -42.4	10	-40.0	6.0	0.26	- 30.0	1.5
W25	N03	s s	7.5	-42.5				3.9 1.9	-42.4 $-38.8$ $-41.0$	11	-40.0	5.5			
W17	S02	3	8.9	-41.5	36	-41.6	8.7	1.1	-39.7	5	-39.3	2.2	0.20	-39.7	1.5
w17	S01		19.8	-41.0	78	-41.1	7.7	3.2	-40.5	17	-41.2	5.2	0.22	-39.7	1.5
W18	S0.5		27.5	-42.0	222	-42.9	16.2								
	20.0	s	17.1	-39.2										40.0	5.0
W17	N00		25.6	-42.5	144	-41.5	11.0	5.1	-41.0	28	-40.8	8.8	0.35	-40.0	5.0
W18	N0.5		20.7	-41.8	126	-42.5	12.1								
		S	15.3	-39.2	0.5	44.4	12.0	2.2	-42.2	22	-41.0	7.0	0.24	-38.8	5.5
W17	N01		18.8	-42.5	95	-41.4	13.2	3.2 1.5	- 42.2 - 39.1	22 16	-41.0 -39.3	7.0 7.0	0.24	-36.6 $-39.0$	(2.0)
W17	N02		13.0	-40.5	83 59	-41.8 -40.4	12.0 9.3	2.0	-39.1 $-38.5$	7	- 39.3 - 39.4	4.0	0.17	-38.2	1.5
W17	N03	_	14.7 9.8	-40.0 $-38.0$	39	-40.4	9.3	2.0 1.6	-36.5 -40.5	,	- 39.4	4.0	0.20	- 30.2	1.5
W08	S02	S	9.8 6.8	-38.0 -41.2	32	-40.8	6.3	1.3	-39.2	5	-39.8	5.0	0.25	-38.5	3.0
W08	S02 S01		16.8	-39.8	99	-40.8	15.0	4.4	-40.2	21	-39.8	5.2	0.30	-39.7	3.5
W08	N00		30.5	-42.2	226	-41.2	19.5	5.7	-41.8	46	-41.8	9.8	0.33	-39.7	7.0
W09	N0.5		29.7	-43.5	265	-42.9	16.2	· · · ·							
*****	110.5	s	15.9	- 39.2											
W08	N01	_	31.0	-43.7	241	-43.0	14.0	4.6	-43.0	26	-41.5	9.0	0.15	-43.0	(1.0)
		S	13.0	-38.8				2.3	-39.3				0.20	-39.2	1.0
W08	N01		31.0	-43.0	276	-42.5	19.6	4.8	-43.8	34	-42.4	10.2	0.16	-43.5	(1.5)
		S	18.0	-39.0				2.7	-39.6				0.16	-38.5	(1.0)
W09	N1.5		15.9	-41.4	123	-42.2	13.2		40.5	10	40.5		0.15	-41.0	(2.0)
W08	N02		13.9	-43.5	97	-42.5	13.2	1.7	-40.5	10	-40.5	6.0	0.13	-41.0	(2.0)
11/00	NIOS	S	12.0 10.9	40.3 40.7	41	-41.2	8.0	2.3	-40.5	7	40.5	1.5	0.28	-40.0	1.5
W08 W02	N03 N00		30.2	-40.7 -41.8	254	-41.2 $-41.1$	20.8	2.3	40.3	,		1,5	0.20	10.0	1.5
W U.Z	מטאז	·s	20.0	-41.6 -45.2	434	- 71.1	20.0								
E00	S03	8	3.7	-40.0	26	-40.3	9.7								
E00	S02		5.1	-39.1	33	-39.3	13.2	1.5	-38.8	6	-38.2	1.5	0.25	-38.8	0.5
E00	S01		14.4	-39.4	96	-39.8	12.5	6.1	-38.0	21	-38.2	8.8	0.55	-38.0	7.0
E00a	N00		25.6	-41.3	212	-39.7	17.8	6.8	-39.2	28	- 39.5	10.0	0.44	-38.7	4.0
		S	21.4	-36.0											

TABLE 2B—Continued


	ITION Center <sup>a</sup>				(100 kHz reso ine Paramete					(100 kHz reso INE PARAMETE			max r =		For $r \ge 0.2$
Δα (s)	Δδ (′)	7	T <sub>A</sub> * (K)	$V_p$ (km s <sup>-1</sup> )	∫ <i>TdV</i> (K km s <sup>-1</sup> )	V <sub>w</sub> (km s <sup>-1</sup> )	$\frac{\Delta V_w}{(\text{km s}^{-1})}$	$T_A^*$ (K)	$V_p$ (km s <sup>-1</sup> )	∫ <i>TdV</i> (K km s <sup>-1</sup> )	$V_w$ (km s <sup>-1</sup> )	$\frac{\Delta V_w}{(\text{km s}^{-1})}$	$\frac{T_A*(^{13}CO)}{T_A*(^{12}CO)}$	$V_{\tau}$ (km s <sup>-1</sup> )	$\Delta V_r $ (km s <sup>-1</sup> )
E00a,b	N00		25.8 21.6	-41.2 -36.3	212	-38.6	24.0	6.2	- 38.9	22	-38.9	7.6	0.38	-38.5	3.0
E00	N0.5	2	24.7 8.1	-36.3 -40.6 -45.2	168	-40.3	17.4								
E00	N01	2	23.2	-40.7	161	-41.5	14.5	3.4	-39.3	20	-40.8	7.2	0.16	-39.5	(6.0)
E00	N02	1	2.2 5.4	-45.0 $-40.3$	74	-42.3	11.2	1.3 1.7	-44.5 -41.5	10	-41.5	3.0	0.20	-42.5	1.0
E00 E08	N03 S02	1	3.4 8.5 5.4 1.0	-45.0 -40.3 -39.0 -23.3	37 75 3	-40.2 $-39.7$ $-23.5$	6.2 10.2 2.8	1.9 4.2	-39.3 -38.3	7 12	-39.3 -39.8	4.2 4.5	0.22 0.30	-39.7 -38.0	1.0 1.5
E08 E08	S01 N00	1 2	8.3 4.4 0.7	-39.5 $-40.3$ $-37.2$	91 149	-38.0 $-38.6$	9.5 14.8	5.3 4.9	-39.7 $-38.3$	18 18	$-38.1 \\ -39.2$	5.3 6.2	0.36 0.33	$-38.0 \\ -38.0$	4.0 2.0
E08 E08 E08	N01 N02 N03	2 1 2	3.2 5.4 1.8 2.6	-40.8 -39.5 -39.8 -44.5?	100 62 88	-39.5 -40.5 -40.0	9.0 8.0 10.0	2.5 2.1 2.8 0.7?	-39.0 $-40.0$ $-39.2$ $-43.0$	11 11 11	-39.2 -40.7 -38.9	4.5 6.2 4.2	0.20 0.18 0.19	-38.0 -40.0 -39.0	0.5 (4.0) (1.0)
E17 E17	S05 S02	≤ 1	1.8 3.7 4.6	-40.0 -22.6 -38.8 -22.8	4 58	-22.6 $-38.8$	2.7 7.2	< 0.4 ≤ 0.8 5.3	-39.0 -22.4 -39.2	≤1 17	-39.2	5.0	≤0.1 0.35	-38.8	5.0
E16 E17 E17 E17 E17 E17 E24	S01 N00 N01 N02 N03 N05 S02	1° 2 20 20 1° 10	1.0 7.3 1.4 0.7 0.7 7.5 0.7 8.7	- 22.8 - 39.5 - 39.7 - 39.4 - 40.0 - 39.6 - 40.8 - 38.5 - 23.0	91 99 94 80 75 54	-39.8 -39.8 -40.3 -40.8 -39.5 -41.2 -39.2	11.2 8.5 8.0 7.5 7.5 7.8 8.0	5.7 4.5 3.2 4.9 4.4 4.7 3.8	-39.8 -38.6 -38.8 -39.0 -39.6 -41.2 -38.5	16 13 8 15 13 12 8	-39.8 -38.8 -38.6 -39.0 -39.5 -40.8 -38.7	3.8 4.5 2.2 4.0 4.5 3.8 3.0	0.37 0.30 0.19 0.30 0.23 0.35 0.21	-38.5 -38.0 -38.5 -38.5 -39.8 -41.0 -38.5	2.0 2.5 1.0 2.5 1.5 4.0 1.0
E24 E25 E25 E25 E34 E42	S01 N01 N02 N03 N04 S02	1; 1 1; 1; 1;	8.3 9.9 3.6 9.5 5.0 7.1 1.0	-39.2 -38.5 -39.5 -40.2 -41.3 -39.5 -23.0	60 41 60 83 58 52	-39.2 -39.5 -39.6 -39.7 -40.2 -39.0	6.8 6.4 8.4 8.2 7.0 6.0	4.8 1.8 2.9 2.4 1.3	- 39.5 - 39.5 - 40.0 - 39.2 - 40.5	11 5 11 11 3	- 39.2 - 39.6 - 39.7 - 39.4 - 40.6	3.5 3.0 4.5 4.9 1.0	0.25 0.18 0.20 0.15 0.11	-39.7 -40.0 -39.8 -38.8 -40.0	2.0 (2.0) 1.5 (0.5)
E42 E59° E59 E59 E68°	N07 S05 N9.5 N11.5 S03	1 1 1	1.0 5.1 3.7 1.5 0.5 2.2 1.2 0.6	-34.0 -41.7 -33.7 -42.8 -42.8 -45.2 -39.0 -34.0	52 3 38 28 7	-41.2 -33.2 -43.1 -43.2 -45.2 -35.7	7.0 4.8 5.0 4.2 1.8 2.0	2.7	<b>-41.0</b>	9	-41.2	3.5	0.25	-40.5	1.0

TABLE 2B—Continued


	SITION CENTER <sup>2</sup>				(100 kHz reso ine Paramete					(100 kHz reso INE PARAMETE			max r =		For $r \ge 0.2$
$\frac{\Delta \alpha}{(s)}$	Δδ (′)		<i>T<sub>A</sub></i> * (K)	V <sub>p</sub> (km s <sup>-1</sup> )	∫ <i>TdV</i> (K km s <sup>-1</sup> )	V <sub>w</sub> (km s <sup>-1</sup> )	$\frac{\Delta V_w}{(\text{km s}^{-1})}$	<i>T<sub>A</sub></i> * (K)	$V_p$ (km s <sup>-1</sup> )	∫ <i>TdV</i> (K km s <sup>-1</sup> )	$V_w$ (km s <sup>-1</sup> )	$\Delta V_w$ (km s <sup>-1</sup> )	$\frac{T_A*(^{13}CO)}{T_A*(^{12}CO)}$	(km s <sup>-1</sup> )	$\Delta V_r$ (km s <sup>-1</sup> )
E74 E74	S15 S13		12.9 15.9	-45.7 -45.2	52 115	-46.2 -45.0 -44.6	11.0 11.0 8.8	3.6	-46.0	12	-45.7	4.7	0.25	<b>-46</b> .	1.0
E74 E76 E76 E76 E92 E92 E92	S11 N07 N9.5 N11.5 S15 S13 S11		11.5 8.1 7.8 6.8 14.9 19.5	-44.8 -41.8 -42.2 -42.7 -47.3 -48.3 -48.5	48 24 32 17 74 117 76	-44.6 -40.5 -42.0 -42.7 -46.0 -48.4 -47.2	8.8 6.0 8.0 3.5 9.5 13.2 8.5	≤0.8 ≤1.0 ≤1.0 3.4 5.3 2.7	-43.0 -42.7 -47.0 -47.8 -48.2 -45.5	2 2 11 16 11	-42.8 -42.7 -47.2 -48.0 -46.6	3.0 1.0 3.2 5.0 5.2	≤0.06 0.14 ≤0.20 0.23 0.30 ≤0.20 0.20	-43.0 -42.7 -46.8 -47.7 -48.2 -45.2	(2.0) 1.5 2.0 (0.5) 2.5
E94° E94 E94 E111 E111	N07 N9.5 N11.5 S15 S13	S	6.1 2.4 3.2 5.5 4.6 3.2	-45.0 -41.0 -41.2 -42.7 -47.5 -48.7	10 16 9 14 22	-41.7 -41.6 -42.1 -48.5 -47.2	6.5 6.2 3.2 7.5 9.0	1.3 ≤0.8	-43.3 -47.7	≤4			≤0.25	-47.5	≤1,0
E111	S11	p	1.8 6.8	-43.0 -48.3	16	-47.2	4.5						-		

<sup>&</sup>lt;sup>a</sup> Center at  $\alpha(1950) = 02^{\text{b}}21^{\text{m}}53^{\text{s}}$ ,  $\delta(1950) = +61^{\circ}52'15''$ . <sup>b</sup> <sup>12</sup>CO average of 11 scans, <sup>13</sup>CO average of 13 scans.

<sup>° 250</sup> kHz resolution.



Frg. 2.—Composite pictures of the W3 region. The background is a reproduction of the red Sky Survey print courtesy of the Hale Observatories, with the following overlays: (a) Map of the <sup>12</sup>CO emission: Units are corrected antenna temperature with solid lines for mean radial velocities (referred to the local standard of rest) between – 38 and – 42 km s<sup>-1</sup>, dashed lines for radial velocities between – 42 and – 44 km s<sup>-1</sup> and dot-dashed lines for radial velocities between – 45 and – 49 km s<sup>-1</sup>. Above 5 K, the contour interval is 5 K.



Frg. 2b.—Map of the continuum emission of 49 cm observed with the Westerbork Synthesis Radio Telescope (Harten 1979). The contour values are 0.050 to 0.425 Jy/beam in steps of 0.125 Jy/beam and 1.0 to 2.5 Jy/beam in steps of 0.5 Jy/beam.

TABLE 3
OBSERVATIONAL PARAMETERS FOR CS AND HCN IN W3

Po FROM	POSITION FROM CENTER <sup>a</sup>		CS (250 Line	CS (250 kHz resolution) Line Parameters	rtion) Rs			HCN (2:	HCN (250 kHz resolution) Line Parameters	olution) RS	
$\Delta_{\alpha}$	Δδ (arcmin)	$T_{\Lambda^*}$ (K)	$V_p \int TdV V_w (\text{km s}^{-1}) (\text{K m s}^{-1}) (\text{km s}^{-1})$	∫ <i>TdV</i> K km s <sup>-1</sup> )	$V_w$ (km s <sup>-1</sup> )	$\Delta V_w$ (km s <sup>-1</sup> )	(K)	$V_{\mathfrak{p}}$ (km s <sup>-1</sup> )	$\int TdV K km s^{-1}$	$V_p$ $\int T dV$ $V_w$ $\Delta V_w$ (km s <sup>-1</sup> ) (K km s <sup>-1</sup> ) (km s <sup>-1</sup> )	$\Delta V_w$ (km s <sup>-1</sup>
W34 W25	SOI NOO	×0.3	-39.5 -41.0	922	-41.0	1.5	≤0.4	-36.5	2		
W25 W17	801 N.X	1.8	-41.0 $-42.0$	92	-42.0	7.0	1.6	-42.0	10	-42.0	6.0
W17	N01	1.2	-43.5	4	-43.0	3.5	0.4	-49.0			
W17 W08	S01	0.4 0.3 0.8	- 43.0 - 40.0	61	-41.5	7.0	≤0.3 0.8	$-43.0 \\ -42.0$	<u>≤1</u>	-43.5	7.0
W08	N00	2.4	- 43.5	16	-42.5	9.0	0.4	-37.0			
W08	N01	1.8 0.8	- 44.0 - 40.0	12	-43.0	8.0	2.0 0.6	-43.5 -49.5	12	$-43.0 \\ -49.5$	8.0 3.0
₩08 80% 80%	NO2 NO2 NO2 NO2 NO2 NO2 NO2 NO2 NO2 NO2	N N N N 0.0.0.4 4 4 6 6 6	- 44.0 - 41.0 - 38.0	<sup> ∧</sup> 21	- 41 <b>3</b>	~70	<0.3 ≤0.4	- 45.0 - 44.0		i 40 0	<b>35</b> 0
							0.6 0.5	-37.5 $-32.0?$ $-49.0?$			
E00	NO1	0.3	- 40.0 - 45.0	<b>4</b> 4 (	-40.0	4.0	, ,		,	3	1
E17	Z	∧ 0.3 5.5	-43.0 -39.5	2	- 39.5	1.0	0.7	- 38.5	o ,	- 38.0	6.0
							∧ 0.4 0.3	-34.0 $-46.5$			

Center at  $\alpha(1950) = 02^{h}21^{m}53^{s}$ ,  $\delta(1950) = +61^{\circ}52'15''$ .




Fig. 3.—The northern group of embedded sources in the W3 core: dashed lines show the 10% level of the 1 mm emission from dust (from Westbrook et al. 1976), crosses indicate location of near IR sources (found by Wynn-Williams et al. 1972; Dyck and Simon 1977), the × marks the position of the 1720 OH maser (Wynn-Williams, Werner, and Wilson 1974), the filled triangles indicate locations of the H<sub>2</sub>O masers (Genzel and Downes 1977), heavy solid lines outline the main radio continuum sources seen at 6 cm (from WSRT map of Harten 1980) with their letter designation (from Wynn-Williams 1971; Harris and Wynn-Williams 1976; and Harten 1980). The light solid circles show the location and size of the 1' beam used to obtain the profiles in Fig. 5a. The intersection of the inner axes marks the CENTER position referred to in later figures.

1 ABLE 4
COMPONENTS OF W3 COMPLEX AND VICINITY

				Positio	ON OF CENTER		
Designation	Description	OTHER NAMES— ASSOCIATED EMISSION	ı	ь	α(1950)	δ(1950)	References
Large scale features: Cas OB6	(see Fig. 1) OB star association: $l=134^{\circ}$ to $138^{\circ}$ , $b=-0.3$ to $+0.3^{\circ}$	OB assoc. #43	135°9	+1°3	02h39m3	61°06′	2
W4 (radio) IC 1805 (optical)	H II region ~1°.5 diameter	Sh 190	134.7	+0.9	02 29.5	61 13	2, 9, 15, 20, 29, 34,
Ocl 352 (stars) W3 (radio) IC 1795 (optical) W3 molecular cloud	exciting stars for W4 H II region (see Fig. 2b) $\sim \frac{1}{2}$ ° diameter molecular cloud, $\sim 1.5$ diameter		133.8 133.4	+1.2 +1.6	02 22.7 02 23.2 02 18.0	61 51 61 51 61 30	8, 9, 20, 21, 26 27, 34, 36, 38 1, 6, 21, 38
Components of W3: W3-W4 border	includes western ionization front of W4 and eastern high intensity	far-IR emission					43
W3-OH	region of CO cloud CO condensation, includes OH and	IRS 8 and 9	133°9	+1:1	$02^{h}23^{m}16^{s}$	61°39′.0	1, 13, 17, 21, 40, 41
AFGL 333	H <sub>2</sub> O masers CO condensation with far-IR and radio emission	FIRS 5, radio #12	134.2	+0.8	02 24 37	61 14.7	11, 21, 24, 31, 34
G133.8+1.4	partly obscured H II region with some CO emission	O8 exciting star #102, radio #9	133.8	+1.4	02 23 05	62 02.0	1, 18, 23, 30
W3 main	region of brightest optical line, radio continuum and molecular emission					<1050/15#	1 7 21 22 22 25
W3 core	strongest CO emission, covers part of diffuse H II region and all the northern group	1 mm emission, molecular emission, far-IR emission	133°70	+1.21	02h21m46s	61°52′17″	1, 7, 21, 22, 33, 35, 11, 42
Diffuse H II region	main part of IC 1795 (Fig. $2b$ ),	Tat-IK Chinssion	133.8	+1.2	02 22 38	61 49.6	8,9
N-S dust lane	extension on WSRT 50 cm map at eastern edge of diffuse H II region, $15'$ in $\delta$ by $1'$ in $\alpha$		133.9	+1.2	02 23 10	61 40–55	1
Northern group: A IRS 2 \	(see Fig. 3) shell type H II region exciting stars of A	IRS 1, radio #8	133.72 133.72	+1.23 +1.22	02 21 57 02 21 57	61 52 49 61 52 41	4, 14, 16, 18, 30, 39 3, 14, 40
IRS 2a \( \) optical jet	Hα and [O III] emission from A		133.71 133.71	$+1.22 \\ +1.23$	02 21 56 02 21 57	61 52 44 61 52 52	1, 8
B C	compact H II region small intense compact H II region	IRS 3 IRS 4, part of radio #3	133.71 133.69	+1.21 + 1.21	02 21 51 02 21 44	61 52 21 61 52 46 61 52 55	14, 18, 30, 39, 40 18, 28, 30, 39, 40 10, 18, 28, 30, 39, 4
D E H	compact H II region small, weak radio source	IRS 10, part of radio #3	133.69 133.70	+1.22 +1.21	02 21 42 02 21 48	61 52 04	14, 16
Ĥ	H II region	radio #4	133.69	+1.23	02 21 45	61 53 30	4, 18, 38, 40

TABLE 4—Continued

				Positio	n of Center		
Designation	DESCRIPTION	OTHER NAMES— Associated Emission	$\overline{}_{l}$	b	α(1950)	δ(1950)	References
H <sub>2</sub> O maser #1			133°68	+1°22	02 <sup>h</sup> 21 <sup>m</sup> 41 <sup>s</sup>	61°53′26″	12
between C, D, H IRS 5 and H <sub>2</sub> O maser #2	massive protostar(s)	self-absorbed <sup>12</sup> CO emission, peak of 1 mm emission, strong	133.71	+1.21	02 21 53	61 52 21	1, 7, 12, 14, 19, 35 37, 40
IRS 6 IRS 7 1720 OH maser 5 cm OH absorption	20 μm IR source compact H π region	10 μm absorption	133.71 133.71 133.70 133.68	+1.21 +1.21 +1.21 +1.20	02 21 54 02 21 53 02 21 46 -2 21 35	61 52 16 61 52 10 61 52 17 61 52 23	40 49 14, 32, 41 25
Southern group: radio #7 H <sub>2</sub> O maser #3	(see Fig. 2b) compact H II region		133.73 133.74	+1.18 +1.20	02 21 57 02 22 06	61 50 06 61 50 40	4, 18, 28, 30 5, 12
NE of radio #7 radio #2 radio #6 NGC 896	compact H II region partly obscured H II region	IR cluster radio #1	133.70 133.73 133.72	+1.17 +1.15 +1.11	02 21 41 02 21 51 02 21 38	61 50 12 61 48 10 61 46 36	4, 18, 28, 30 4, 18, 28, 30 4, 9, 18, 28, 30

#### REFERENCES

- 1. This paper.
- Alter, Ruprecht, and Vanysek 1970.
   Beetz, Elsässer, and Weinberger 1974.
- Beetz, Eisasser, and Wein
   Beetz et al. 1976.
   Cesarsky et al. 1978.
   Dickel 1973.
   Dickel et al. 1975.
   Dickel and Harten 1980.
   Dreyer 1910.

- 10. Dyck and Simon 1977.
  11. Fazio *et al.* 1975.
  12. Genzel and Downes 1977.
- 13. Goss, Lockart, and Fomalont 1975.14. Hackwell et al. 1978.
- 15. Hagen 1970.

- 16. Harris and Wynn-Williams 1976.
  17. Harten 1976.
  18. Harten 1980.
  19. Hills et al. 1972.
  20. Ishida and Kawajiri 1968.
  21. Lada et al. 1978.
  22. Morris et al. 1974.
  23. Ogura and Ishida 1976.
  24. Price and Walker 1976.
  25. Rickard, Zuckerman, and Palmer 1975.
  26. Schmitter 1971.
  27. Schraml and Mezger 1969.
- Schraml and Mezger 1969.
- 28. Schultz, Proetel, and Schmidt 1978. 29. Sharpless 1959.

- 30. Sullivan and Downes 1973.
- 31. Thronson, Harvey, and Gatley 1979.
- 32. Turner 1970.
- 33. Turner and Gammon 1975.34. Wendker and Altenhoff 1977.
- 35. Westbrook et al. 1976.

- 35. Westbrook et al. 1976.
  36. Westerhout 1958.
  37. Willner 1977.
  38. Wilson et al. 1979.
  39. Wynn-Williams 1971.
  40. Wynn-Williams, Becklin, and Neugebauer 1972.
  41. Wynn-Williams, Werner, and Wilson 1974.
  42. Werner et al. 1980.
  43. Thronson, Campbell, and Hoffmann 1979.

remainder of the surrounding cloud is at ~43 ± I km s<sup>-1</sup>. The ± values refer to a typical range in velocities, not to their errors. The LSR velocities of the optically visible ionized hydrogen are similar to the molecular velocities: Georgelin and Georgelin (1976) find an average velocity of -40.7 km s<sup>-1</sup> toward W3 and -46 km s<sup>-1</sup> toward W4. The eastern edge of the radio continuum emission associated with W3 coincides with the prominent, narrow north-south dust lane which separates the faint Hα emission of W4 to the east from the bright Hα emission of W3 to the west (refer to Fig. 2). Along this same boundary, <sup>12</sup>CO emission is detected at both velocities, -40 km s<sup>-1</sup> and -46 km s<sup>-1</sup>. The average velocity of the stars in the open cluster Ocl 352 which excite W4 is -34 km s<sup>-1</sup> (Hagen 1970). This significant difference in the velocity of the stars compared to that of the molecular and ionized gas may be the result of passage through a galactic shock and later expansion of the W4 H II region as will be described in the subsequent paper.

### c) The W3 Complex

## i) Distribution of the <sup>12</sup>CO Emission

As mentioned in § IIIb(ii), the strongest  $^{12}$ CO emission comes from the W3 core (see Fig. 2a). Figure 2a shows all the details of the distribution of  $T_A*^{(12)}$ CO) which are apparent with our sampling grid and the I' and 2' beams. The central part with  $T_A*^{(12)}$ CO)  $\gtrsim$  17 K coincides with the region of 1 mm emission (Westbrook et al. 1976) outlined in Figure 3, and with the region of high-far-infrared surface brightness (Fazio et al. 1975; Werner et al. 1980). The 30 K contour is centered close to compact H II region C, and includes most of the "northern group" of sources which are drawn as heavy lines in Figure 3 (from the 6 cm radio continuum data of Harten 1980). The maximum observed  $^{12}$ CO temperature is 31 K; because of the universal 2.7 K background radiation, the minimum kinetic temperature needed to produce this is 35 K. Thus the kinetic temperature be greater than or equal to 35 K in at least part of the cloud. By contrast the dust temperature over the central few arc minutes of the W3 core lies in the range 60-90 K (Werner et al. 1980).

greater than or equal to 35 K in at least part of the cloud. By contrast the dust temperature over the central few arc minutes of the W3 core lies in the range 60–90 K (Werner et al. 1980).

The CO emission extends to the partly obscured H II region G133.8+1.4 which lies 16' to the northeast of C, but falls off sharply in the direction of the "southern group" of H II regions listed in Table 4 (compare Figs. 2a and 2b). This apparent cutoff suggests that there is a physical boundary between the CO cloud (W3 core) and this southern group of sources. The 21 cm continuum map (Harten 1980) also shows a distinct break between the northern and southern group. To the east, the CO emission covers much of the optical, diffuse H II region IC 1795, but some of this CO emission probably comes from behind the H II region. Otherwise, one would not expect the H II region to be so bright optically in the presence of the accompanying extinction associated with the molecular cloud.

### ii) Line Shapes and Widths

The molecular lines are asymmetrical and broad where the CO emission is strongest, i.e., within the region of the 1 mm dust emission and toward the embedded sources of excitation shown in Figure 3. The 12CO and 13CO profiles for this area are shown in Figures 4a and 4b. The position labeled CENTER is at the intersection of the inner axes in Figure 3 toward the group of near-infrared sources IRS 5, 6, and 7 where the 1 mm emission and the 13CO emission have their maximum intensities. It is toward CENTER and 8° east of it that we find the self-absorbed 12CO profiles (Dickel et al. 1975). The fact that the peak of the 13CO emission falls in the region of the dip in the 12CO profile indicates that this is indeed self-absorption, not a second velocity component in the 12CO profile. Figure 5a displays the profiles of 12CO, 13CO, HCN, and CS observed toward the inner eight positions indicated by the circular beams in Figure 3. The self-absorption dip in the 12CO profile toward IRS 5-7 is displaced about 1½ km s-1 toward the positive velocities relative to the velocity of the peak of the 13CO emission. The profiles at neighboring positions are asymmetric, with the more gradual slope of the line; we have interpreted this to mean that there is incipient self-absorption throughout the region. The midpoint of the base of these lines is centered close to the peak of the 13CO emission. These facts mean that foreground material which is just becoming optically thick (with 713co ~ 3) is moving away from the observer by a few km s-1 relative to the bulk of the material which forms the core of the line. Since the 13CO line does not show self-absorption effects, 713co < 1.

The CS (J=2-1) lines have asymmetric shapes similar to the <sup>12</sup>CO lines: the CS emission extends just as far as the <sup>13</sup>CO emission in the direction of positive velocities but well beyond the edge of the <sup>13</sup>CO emission profile for more negative velocities. Most of the CS lines shown in Figure 5a have  $T_A^*$  of the peak emission between 1 and 2.5 K (note that both the CS and HCN profiles in Fig. 5a have been multiplied by a factor of 10). However, toward IRS 5-7 the CS emission has fallen to ~0.5 K, where it is nearly lost in the noise. We feel that this effect is real since the positions IRS 5-7, and E17 (see Table 3) were observed in CS at the same air mass and within 25 minutes of the CS observations at the positions N1W8 and W17.

The HCN (J = 1-0) line has three hyperfine components: the F = 2-1 line is the strongest; the F = 1-1 line has a frequency shift equivalent to  $\sim +5$  km s<sup>-1</sup> from the F = 2-1 line and should be about 60% as intense for an optically thin, LTE situation; and the F = 0-1 line at  $\sim -7$  km s<sup>-1</sup> should be about 20% as intense. The intensities of the hyperfine lines may well be in the proper LTE ratios for weak lines away from the center (e.g., E17 and W08S01 in Table 3), but the low signal-to-noise precludes an accurate assessment here. However, where the lines are stronger such as toward positions N1W8 and W17 the intensity

726






Fig. 4.—(a), (b) Profiles of the CO emission from the region shown in Fig. 3. The individual profiles are spaced according to the right ascension and declination relative to CENTER as indicated by the top and right-hand axes. The CENTER position is toward IRS 5-7 at  $\alpha(1950) = 02^{\text{h}}21^{\text{m}}53^{\text{s}}$  and  $\delta(1950) = +61^{\circ}52'15''$ . The frequency resolution is 100 kHz, and the spatial resolution is 70''. (a) 12CO: the interval of corrected antenna temperature between tick marks on the left-hand axis is 10 K. (b) 13CO: the interval of corrected antenna temperature between the tick marks on the left-hand axis is 5 K.









Fig. 5a.—Line profiles toward the positions marked by the light circles in Fig. 3. Each profile is labeled with its position in arcminutes north and/or seconds of time east or west of the CENTER. The main excitation sources within the beam are given in the parentheses. The <sup>12</sup>CO profiles are drawn by (tall) dark solid lines, the <sup>13</sup>CO profiles by (low) light solid lines, the CS profiles by dashed lines, and the HCN profiles by light dot-dashed lines. The temperature scale for <sup>12</sup>CO and <sup>13</sup>CO is marked in 5 K intervals along the vertical axis; for CS and HCN the numbers must be divided by 10 to obtain the temperature (0.5 K intervals). The vertical axis within each profile is at a radial velocity of –40 km s<sup>-1</sup>, and 5 km s<sup>-1</sup> intervals are marked along the horizontal axis.

are marked along the horizontal axis.

FIG. 5b.—The  $^{13}$ CO emission profile observed with a velocity resolution of  $\sim \frac{1}{4}$  km s $^{-1}$  and spatial resolution of  $\sim 1$  toward the CENTER position (dashed line), the Gaussian-weighted average of the  $^{13}$ CO emission profiles within a circle of diameter 5% centered on this position (solid line), and the corresponding  $H_2$ CO absorption profile at 6 cm, (line antenna temperature) observed with a velocity resolution of  $\sim \frac{1}{4}$  km s $^{-1}$  and spatial resolution  $\sim 6\%$ .




Frg. 6.—Line widths in km s<sup>-1</sup>,  $\Delta V_w$ , toward W3: <sup>13</sup>CO widths at the  $T_A* \sim 1$  K level (solid lines), H<sub>2</sub>CO widths at the  $|T_A| \sim 0.25$  K level (dashed lines), and CS widths at the  $T_A* \sim 0.5$  K level (dot-dashed lines). For this and the following figures, the intersection of the inner axes marks the position of the CENTER at  $\alpha(1950) = 0.2^{12}1^{23}$  and  $\delta(1950) = +61^{\circ}52'15''$ , lines of constant galactic latitude are labeled, and the crosses indicate the positions of reference stars.

of the F = 0-1 hyperfine line is equal to or slightly greater than the optically thin LTE value whereas the F = 1-1 line is down by a factor of 4 or more (refer to Fig. 5a and Table 3). This behavior, which is typical of other molecular clouds, is not yet fully understood (e.g., Kwan and Scoville 1975; Gottlieb et al. 1975). The HCN (F = 2-1) line is centered nearer to the peak rather than the midpoint velocity of the overall <sup>12</sup>CO profile (refer to profiles at positions N1W8 and W17 in Figure 5a). Toward IRS 5-7 where the CS emission is weak, the HCN emission remains high and the line shape is almost identical to that of the <sup>12</sup>CO.

The  $H_2CO$  profile (obtained with a 6.6 beam and 0.24 km s<sup>-1</sup> velocity resolution by Dickel 1973) is shown in Figure 5b along with two <sup>13</sup>CO emission profiles (with 0.27 km s<sup>-1</sup> resolution): the dashed

curve is for a 1' beam centered on IRS 5-7, and the solid curve is the Gaussian-weighted average of the H2CO profiles within a circle of diameter 5.8 centered on this position. This is nearly the same as the 6.6 HPBW observing beam used for the H2CO observations. The H2CO absorption profile at 6 cm toward IRS 5-7 looks remarkably like the 13CO emission profile in both velocity and line width, so both lines are sampling nearly the same material along the line of sight. Since the H2CO line is seen in absorption, its profile is governed mainly by the material in front of the continuum sources. Both the 6 cm H2CO profile in Figure 5b and the 2 cm one of Evans et al. (1975, with resolutions of 1' and 1 km s<sup>-1</sup>) are asymmetric, with the line being steeper on the negative-velocity side. The excess gas at the most negative velocities seen in emission in the average 13CO profile but missing from






Fig. 7.—The distribution of midpoint velocities in km s<sup>-1</sup>,  $V_w$ , toward W3. Dashed lines indicate uncertain location of the contour. (a) <sup>12</sup>CO. (b) CS.

the H<sub>2</sub>CO profiles is most likely located behind the continuum sources in the rear of the cloud, which mean that the back of the cloud is moving toward the observer relative to the bulk of the material. Since the foreground material and background material are moving toward each other, the cloud is collapsing.

In addition to the missing H<sub>2</sub>CO gas at the most negative velocities, there may be an emission component near the middle of the absorption line which could be responsible for some of the asymmetry such as seen toward NGC 7538 by Downes and Wilson

(1974). Current observations of H<sub>2</sub>CO at 6 cm with the Westerbork Synthesis Radio Telescope (by H. Dickel and collaborators) should allow us to see the structure of the profile at various positions within the cloud.

All the molecular lines are wider toward the embedded excitation sources as seen in Figure 6 in which the inner axes intersect at the CENTER position. To avoid the problems introduced by asymmetries, the width,  $\Delta V_w$ , was measured in the wings of the lines at the base of the profile just above the noise levels as described in the figure legend. The HCN line widths are not included because of the complicating hyperfine structure. Although the CS and HCN lines are generally narrower than the CO lines, the F = 2-1 hyperfine line of HCN is just as broad as the <sup>12</sup>CO line at IRS 5-7 (compare the profiles at NIW8 and CENTER in Fig. 5a).

Fig. 5a). Since the nature of both the <sup>12</sup>CO self-reversal and the  $H_2$ CO absorption compared to the <sup>13</sup>CO emission are consistent with an overall collapse of the molecular core, part of the increased line width toward the center of the cloud is probably due to this collapse motion. However, in the outskirts of the cloud (in the plane of the sky), the observed line widths should be dominated by turbulent motion. If  $v_t$  is the turbulent velocity (as defined by Leung 1978) and  $\Delta V$  is the observed full width at half-intensity, then for an optically thin gas such as <sup>13</sup>CO with  $0 < \tau < 1$ ,  $1.7v_t < \Delta V < 2.5v_t$  (Leung and Lizzt 1976; Leung 1978). In the outer parts of the cloud,  $\Delta V(^{13}\text{CO}) \approx 3-4$  km s<sup>-1</sup>, so the turbulent velocity is on the order of 2 km s<sup>-1</sup>.

#### iii) Velocities

In trying to unravel the dynamics in the W3 region, we must consider that the observed radial velocities across the cloud are a composite of the motion of the cloud as a whole in the spiral arm, hereafter referred to as the "rest velocity," and systematic motions within the cloud due to such processes as collapse or rotation. If a cloud has uniform temperature and dehsity, the velocity of the peak of the emission line,  $V_p$ , would be the average velocity of the gas along the line of sight, and the rest velocity would be the  $V_p$  observed in the direction of the cloud center. In the midst of nonuniformities which can seriously shift the  $V_p$  of an optically thick or thin line away from the (unweighted) average velocity of the gas along a particular line of sight, we feel that a better measure of this average velocity is  $V_{wp}$ , which is the radial velocity of the midpoint of the line measured near the base of the profile.

The midpoint velocity,  $V_w$ , for the <sup>12</sup>CO (from col. [7] of Table 2) is plotted in Figure 7a. The rest velocity of the W3 core is around  $-40.5 \,\mathrm{km \, s^{-1}}$ , but there is a gradient in the average radial velocity in the core of the <sup>12</sup>CO emission from  $-38 \,\mathrm{km \, s^{-1}}$  in the southeast to  $-43 \,\mathrm{km \, s^{-1}}$  in the northwest (with the maximum effect roughly along a line connecting the three  $\mathrm{H_2O}$  masers tabulated by Genzel and Downes 1977; see Table 4). Although the exact velocities differ, the same trend is observed for CS (Fig. 7b), <sup>13</sup>CO, and


HCN as well, irrespective of whether the peak or midpoint velocity is plotted. The contours of Figure 7a might suggest solid-body rotation with a period of about 106 years for an embedded region perhaps 2 pc across (at a distance of 2 kpc). In the subsequent paper, evidence for and against such a rotation is presented and an alternative set of circumstances is suggested to explain the gradient.

# iv) <sup>13</sup>CO Optical Depths and the Velocity of the Absorbing <sup>12</sup>CO Gas

The optical depth at the center of the J=1-0 line of <sup>13</sup>CO,  $\tau$ (<sup>13</sup>CO), would be equal to r, the ratio of the <sup>13</sup>CO intensity to the <sup>12</sup>CO intensity, under conditions of LTE and small r. Therefore, the distribution of r is an indication of the variation of  $\tau$ . The values of maximum r in column (14) of Table 2B have been multiplied by 100 and plotted in Figure 8a with an uncertainty of ~5 units due to uncertainties in the location of the inner axes in Figure 8a marks the CENTER position. The "northern group" of compact H II regions is located mainly to the north of the inner horizontal axis, and the "southern group" begins at and extends to the south of the line representing galactic latitude b=1?2. One sees that max r, and

thus the optical depth of the <sup>13</sup>CO line, is highest just in the region between the northern and southern group. Another maximum occurs in the southeast in the region of the W3-OH maser which is marked by the filled square.

The velocity where the ratio within the profile is a maximum,  $V_r$ , is a density-weighted mean of the velocity of the CO gas along the line of sight so that  $V_r$  is close to  $V_p(^{13}\text{CO})$ . However, where self-absorption effects occur in the  $^{12}\text{CO}$  line,  $V_r$  will be closer to the velocity of the gas which is just becoming optically thick (since the  $^{12}\text{CO}$  dip or shoulder is usually displaced 1 or  $^{12}\text{CM}$  so  $^{-1}$  from the  $^{13}\text{CO}$  peak as mentioned in §IIIc[ii]). The velocity  $V_r$  (in col. [15] of Table 2B) has been plotted in Figure 8b. It is not well defined to the northwest of CENTER (hatched area) because the optical depth is fairly uniform with  $r \lesssim 0.2$  across the profile between -39 km s<sup>-1</sup> to -43 km s<sup>-1</sup>. The variation in  $V_r$  seen in Figure 8b is similar to that seen for the midpoint velocities in Figures 7a and 7b. In the southeast where the optical depths are higher, we find (1) the (density-weighted) velocity  $V_r$  is 1 to 2 km s<sup>-1</sup> more positive than the mean velocity of  $^{12}\text{CO}$ ,  $V_w$ ; (2) the lines of constant velocity run parallel to the edge of the diffuse H II region; and (3) the most positive velocities ( $\sim$ -38 km s<sup>-1</sup>) are along the border with the diffuse






Fig. 8.—(a) The distribution of 100 (max r) toward W3 where (max r) is the maximum value across the profile of the ratio of the <sup>13</sup>CO intensity to the <sup>12</sup>CO intensity. Dashed lines indicate uncertain location of the contour. As discussed in the text, this shows the approximate distribution of the optical depth in the <sup>13</sup>CO line. (b) The distribution of  $V_r$ , (the velocity where the intensity ratio of <sup>13</sup>CO to <sup>12</sup>CO across the profile has a maximum). Dashed lines indicate uncertain location of the contour. Contours of  $V_r$  are not plotted within the hatched area because they are ill determined there.

Fig.

HII region. These findings are important for the overall interpretation of the dynamics in the W3 core presented in the subsequent paper.

# Distributions of CS and HCN Emission

brightness (and also the temperature at the peak of the line) are similar for CS and HCN. However, in the eastern part, the integrated brightness of CS is much weaker while that of HCN remains strong. Since, for the same molecular densities, the intensities of the CS (J = 2-1) and HCN (J = 1-0, F = 2-1) lines should be quite similar, one expects very similar intensity distributions with the maximum emission for both HCN. One sees that the maximum integrated brightness for HCN is toward IRS 5-7, where the peak in the 1 mm emission implies that density is highest. values in the vicinity of the maser sources. In Figure 9 the integrated brightness is plotted so that it includes the emission from all the hyperfine components of more, there must be *changes in density* from perhaps  $10^3 \text{ cm}^{-3}$  where the HCN and 1 mm emission fall the W3 core indicate that the average hydrogen density is at least 10<sup>4</sup> cm<sup>-3</sup> there. these high-excitation molecules and the high column densities of dust and gas determined from 1 mm emismetric (see Fig. 9). central region of W3 where the <sup>12</sup>CO lines are asymsuggest a variation in the abundance of CS within W3 cloud. This is discussed in more detail in CS and HCN occurring where the density is highest toward IRS 5, but the CS maximum is 8<sup>8</sup> to the west. In the western half of the core, the values of integrated cules are excited and, of course, to locally much higher below detection to possibly 105 where the HCN molesubsequent paper. Thus, the observed variation in the relative intensities was a variation in the abundance of CS within the Both the CS and HCN emission are confined to the CO emission coupled with the small size of The presence of the emission from in the abundance of molecular Further-

#### IV. SUMMARY

active region. Pronounced self-absorption is seen in the <sup>12</sup>CO profile toward IRS 5 and to a lesser degree transition of CS, and the J = 1-0 transition of HCN have been presented which show the "core" of the W3 with different sizes, ages, and types of emission from young, dust-embedded possible protostellar objects to older, diffuse H II regions which are seen optically. Maps of the distribution of the emission from the J = 1-0 transition of  $^{12}\text{CO}$  and  $^{13}\text{CO}$ , the J = 2-1molecular cloud (Fig. 3) to be a dense and dynamically The W3 complex includes a wide variety of objects




Fig. 9.—Integrated brightnesses  $\int TdV$  in  $\mathbf{K} \cdot \mathbf{km} \, s^{-1}$  for CS (solid lines) and HCN (dashed lines).

collapsing. Additional systematic motions occur close to the border with IC 1795. The physical parameters which have been determined from the data here will be used in the next paper (Dickel, 1980) to develop a model of the W3 molecular cloud to explain some towards the compact H II region C. The <sup>13</sup>CO and HCN emission peak at the position of IRS 5, whereas the CS emission peaks 8<sup>s</sup> to the west in the direction of the 1720 OH maser. Emission from both HCN and are asymmetric. emission from dust is strongest and the 12CO profiles of these puzzling observational features. CS is confined to the inner region where the 1 mm throughout the core. The W3 core as a whole appears to be The maximum <sup>12</sup>CO emission is <sup>13</sup>CO and

the Netherlands-America Commission for Educational Exchange. H. R. D. and J. R. D. enthusiastically acknowledge the hospitality and support of the Sterrewacht te Leiden. contract with the National Science Foundation. The research of H. R. D. was partially supported by NSF grants AST 75-22208 and AST 77-21021. J. R. D. jointly by the National Science Foundation grant MPS-73-04554 and the Aerospace Corporate Programs for Research and Investigation. The NRAO is acknowledges a Fulbright-Hays travel award from operated spectral line radio astronomy program was supported White for help with the observations. The Aerospace We thank N. Z. Scoville, R. B. Pomphrey, and J. D. Associated Universities, Inc., under

### REFERENCES

Alter, G., Ruprecht, J., and Vanysek, V. 1970, in Catalogue of Star Clusters and Associations, ed. G. Alter, B. Balázo, and J. Ruprecht (Budapest: Akadémiai Kiadó).

Beetz, M., Elsässer, H., Poulakos, C., and Weinberger, R. 1976, Astr. Ap., 50, 41.

Beetz, M., Elsässer, H., and Weinberger, R. 1974, Astr. Ap., 34, 335.

Cesarsky, C. J., Cesarsky, D. A., Churchwell, E., and Lequeux, J. 1978, Astr. Ap., 68, 33.
Dickel, H. R. 1973, in IAU Symposium 52, Interstellar Dust and Related Topics, ed. J. M. Greenberg and H. C. van de Hulst (Dordrecht: Reidel), p. 277.

Dickel, H. R. 1980, Ap. J., in press (sequel to this paper).
Dickel, H. R., Dickel, J. R., and Wilson, W. J. 1977, Ap. J.,
217, 56 (Paper I).
Dickel, H. R., Dickel, J. R., Wilson, W. J., and Pomphrey,
R. B. 1975, Bull. AAS, 7, 556.
Dickel, H. R., and Harten, R. 1980, in preparation.
Dickel, J. R., Dickel, H. R., and Wilson, W. J. 1978, Ap. J.,
223, 840 (Paper II).
Downes, D., and Wilson, T. L. 1974, Ap. J. (Letters), 191,

Downes, D., L77.

Dreyer, J. L. E. 1910, *Mem. R.A.S.*, **59**, 114. Dyck, H. M., and Simon, T. 1977, *Ap. J.*, **211**, 421.

0

Z o.

Evans, N. J., Zuckerman, B., Morris, G., and Sato, T. 1975, Ap. J., 196, 433.

Fazio, G. G., Kleinmann, D. E., Noyes, R. W., Wright, E. L., Zeilik, M., II, and Low, F. J. 1975, Ap. J. (Letters), 199, L177.

Forster, J. R., Welch, W. J., and Wright, M. C. H. 1977, Ap. J. (Letters), 216, L121.

Genzel, R., and Downes, D. 1977, Astr. Ap. Suppl., 30, 145.

Georgelin, Y. M., and Georgelin, Y. P. 1976, Astr. Ap., 49, 57.

Goss, W. M., Lockhart, I. A., and Fomalont, E. B. 1975, Astr. Ap., 40, 439.
Gottlieb, C. A., Lada, C. J., Gottlieb, E. W., Lilley, A. E., Litvak, M. M. 1975, Ap. J., 202, 655.
Hackwell, J. A., Gehrz, R. D., Smith, J. R., and Briotta, D. A. 1978, Ap. J., 221, 797.
Hagen, G. 1970, Pub. DDO, Vol. 4.
Harris, S., and Wynn-Williams, C. G. 1976, M.N.R.A.S., 174, 649.

Harten, R. 1976, Astr. Ap., 146, 109.

Hills, R., Janssen, M. A., Thornton, D. D., and Welch, W. J. 1972, Ap. J. (Letters), 175, L59.
Ishida, K. 1969, M.N.R.A.S, 144, 55.
Ishida, K., and Kawajiri, N. 1968, Pub. Astr. Soc. Japan, 20, 95.

Kwan, J., and Scoville, N. Z. 1975, Ap. J. (Letters), 195, L85. Lada, C. J., Elmegreen, B. G., Cong, H.-Ih., and Thaddeus, P. 1978, Ap. J. (Letters), 226, L39.
Leung, C. M. 1978, Ap. J., 225, 427.
Leung, C. M., and Liszt, H. S. 1976, Ap. J., 208, 732.
Morris, M., Palmer, P., Turner, B. E., and Zuckerman, B. 1974, Ap. J., 191, 349.
Ogura, K., and Ishida, K. 1976, Publ. Astr. Soc. Japan, 28, 651. Price, S. D., and Walker, R. G. 1976, The AFGL Four Color Infrared Sky Survey (Washington: GPO AFGL-TR-0208).

Rickard, 200, 6. Rohlfs, K., Braunsfurth, E., and Hills, D. L. 1977, Astr. Suppl., 30, 369.
Schmitter, E. F. 1971, A.J., 76, 571.
Schraml, J., and Mezger, P. G. 1969, Ap. J., 156, 269.
Schultz, A., Proetel, K., and Schmidt, Th. 1978, Astr. 64, L13. Rogers, A. E. E., Moran, J. M., Crowther, P. P., Burke, B. F., Meeks, M. L., Ball, J. A., and Hyde, G. M. 1967, Ap. J., 147, 369.

Rohlfs, K., Braunsfurth, E., and Hills, D. L. 1977, Astr. Ap. Suppl., 30, 369. L. J, Zuckerman, B., and Palmer, P. 1975, Ap. J.,

Ap.,

Sharpless, S. 1959, Ap. J. Suppl., 4, 257.
Sharpless, S. 1959, Ap. J. Suppl., 4, 257.
Sullivan, W. T., III, and Downes, D. 1973, Astr. Ap., 29, 369.
Thronson, H. A., Campbell, M. F., and Hoffmann, W. F.
1979, preprint.
Thronson, H. A., Harvey, P. M., and Gatley, I. 1979, Ap. J.
(Letters), 229, L133.
Turner, B. E. 1970, Ap. Letters, 6, 99.
Turner, B. E., and Gammon, R. H. 1975, Ap. J., 198, 71.
Ulich, B. L., and Haas, R. W. 1976, Ap. J. Suppl., 30, 247.
Wendker, H. J., and Altenhoff, W. J. 1977, Astr. Ap., 54, 301.
Werner, M. W., Becklin, E. E., Gatley, I., Harper, D. A.,
Lowenstein, R., Mosley, H., Neugebauer, G., Sellgren, K.,
and Thronson, H. A. 1980, in preparation.
Westbrook, W. E., Werner, M. W., Elias, J. H., Gezari, D. Y.,
Hauser, M. G., Lo, K. Y., and Neugebauer, G. 1976, Ap. J.,
209, 94.

Westerhout, G. 1958, BAN, 14, 215.
Willner, S. P. 1977, Ap. J., 214, 706.
Wilson, W. J., Schwartz, P. R., Epstein, E. E., Johnson, W. A., Etcheverry, R. D., Mori, T. T., Berry, G. G., and Dyson, H. B. 1974, Ap. J., 191, 357.
Wynn-Williams, C. G., 1971, M.N.R.A.S., 151, 397.
Wynn-Williams, C. G., Becklin, E. E., and Neugebauer, G. 1972, M.N.R.A.S., 160, 1.
Wynn-Williams, C. G., Werner, M. W., and Wilson, W. J. 1974, Ap. J., 187, 41.

HÉLÈNE R. DICKEL and JOHN R. DICKEL: Astronomy Department, University of Illinois, 341 Astronomy Building 1011 W. Springfield Avenue, Urbana, IL 61801

MICHAEL W. WERNER: Division of Physics, Downes Laboratory 320-47, Pasadena, CA 91125 Mathematics and Astronomy, California Institute of Technology

WILLIAM J. WILSON: Electronics Research Laboratory, Aerospace Corporation A6/2457, Box 92957, Los Angeles