

# Pure and Applied Geophysics

## The seismotectonics of the Po Plain (northern Italy): tectonic diversity in a blind faulting domain

--Manuscript Draft--

<b>Manuscript Number:</b>	PAAG-D-14-00070R1
<b>Full Title:</b>	The seismotectonics of the Po Plain (northern Italy): tectonic diversity in a blind faulting domain
<b>Article Type:</b>	Report-Top.Vol. Crustal Fault Zones
<b>Keywords:</b>	Blind faulting; seismogenic source; active tectonics; seismic hazard; inherited faults; Po Plain.
<b>Corresponding Author:</b>	Paola Vannoli, Ph.D. Istituto Nazionale di Geofisica e Vulcanologia Roma, ITALY
<b>Corresponding Author Secondary Information:</b>	
<b>Corresponding Author's Institution:</b>	Istituto Nazionale di Geofisica e Vulcanologia
<b>Corresponding Author's Secondary Institution:</b>	
<b>First Author:</b>	Paola Vannoli, Ph.D.
<b>First Author Secondary Information:</b>	
<b>Order of Authors:</b>	Paola Vannoli, Ph.D. Pierfrancesco Burrato, M.D. Gianluca Valensise, Ph.D.
<b>Order of Authors Secondary Information:</b>	
<b>Abstract:</b>	<p>We present a systematic and updated overview of a seismotectonic model for the Po Plain (northern Italy). This flat and apparently quiet tectonic domain is in fact rather active as it comprises the shortened foreland and foredeep of both the Southern Alps and the Northern Apennines. Assessing its seismic hazard is crucial due to the concentration of population, industrial activities and critical infrastructures, but it is also complicated because a) the region is geologically very diverse, and b) nearly all potential seismogenic faults are buried beneath a thick blanket of Pliocene-Pleistocene sediments, and hence can be investigated only indirectly.</p> <p>Identifying and parameterizing the potential seismogenic faults of the Po Plain requires proper consideration of their depth, geometry, kinematics, earthquake potential and location with respect to the two confronting orogens. To this end we subdivided them into four main homogeneous groups. Over the past 15 years we developed new strategies for coping with this diversity, resorting to different data and modeling approaches as required by each individual fault group.</p> <p>The most significant faults occur beneath the thrust fronts of the Ferrara-Romagna and Emilia arcs, which correspond to the most advanced and buried portions of the Northern Apennines and were the locus of the destructive May 2012 earthquake sequence. The largest known Po Plain earthquake, however, occurred on an elusive reactivated fault cutting the Alpine foreland south of Verona. Significant earthquakes are expected to be generated also by a set of transverse structures segmenting the thrust system, and by the deeper ramps of the Apennines thrusts.</p> <p>The new dataset is intended to be included in the next version of the Database of Seismogenic Sources (DISS; <a href="http://diss.rm.ingv.it/diss/">http://diss.rm.ingv.it/diss/</a>, version 3.2.0, developed and maintained by INGV) to improve completeness of potential sources for seismic hazard assessment.</p>

1           **The seismotectonics of the Po Plain (northern Italy):**  
2  
3           **tectonic diversity in a blind faulting domain**  
4  
5

6  
7  
8  
9           *Abbreviated title: “The seismotectonics of the Po Plain”*  
10  
11

12  
13  
14  
15           Paola Vannoli, Pierfrancesco Burrato and Gianluca Valensise  
16

17  
18           *Istituto Nazionale di Geofisica e Vulcanologia, Seismology and Tectonophysics Unit*  
19

20           *Via di Vigna Murata 605, 00143 Rome, Italy.*  
21  
22  
23  
24

25           Corresponding Author:  
26

27           Paola Vannoli  
28

29           paola.vannoli@ingv.it  
30

31           fax number: +39-06-51860507  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1 **Keywords:** Blind faulting, seismogenic source, active tectonics, seismic hazard, inherited  
2  
3 faults, Po Plain.  
4  
5  
6  
7

## 8 **Abstract**

9

10  
11  
12 We present a systematic and updated overview of a seismotectonic model for the Po Plain  
13  
14 (northern Italy). This flat and apparently quiet tectonic domain is in fact rather active as it  
15  
16 comprises the shortened foreland and foredeep of both the Southern Alps and the Northern  
17  
18 Apennines. Assessing its seismic hazard is crucial due to the concentration of population,  
19  
20 industrial activities and critical infrastructures, but it is also complicated because a) the region  
21  
22 is geologically very diverse, and b) nearly all potential seismogenic faults are buried beneath a  
23  
24 thick blanket of Pliocene-Pleistocene sediments, and hence can be investigated only  
25  
26 indirectly.  
27  
28  
29  
30  
31  
32  
33

34  
35 Identifying and parameterizing the potential seismogenic faults of the Po Plain  
36  
37 requires proper consideration of their depth, geometry, kinematics, earthquake potential and  
38  
39 location with respect to the two confronting orogens. To this end we subdivided them into  
40  
41 four main homogeneous groups. Over the past 15 years we developed new strategies for  
42  
43 coping with this diversity, resorting to different data and modeling approaches as required by  
44  
45 each individual fault group.  
46  
47  
48  
49

50  
51 The most significant faults occur beneath the thrust fronts of the Ferrara-Romagna and  
52  
53 Emilia arcs, which correspond to the most advanced and buried portions of the Northern  
54  
55 Apennines and were the locus of the destructive May 2012 earthquake sequence. The largest  
56  
57 known Po Plain earthquake, however, occurred on an elusive reactivated fault cutting the  
58  
59 Alpine foreland south of Verona. Significant earthquakes are expected to be generated also by  
60  
61  
62  
63  
64  
65

1 a set of *transverse structures* segmenting the thrust system, and by the deeper ramps of the  
2 Apennines thrusts.  
3

4  
5 The new dataset is intended to be included in the next version of the Database of  
6 Seismogenic Sources (DISS; <http://diss.rm.ingv.it/diss/>, version 3.2.0, developed and  
7 maintained by INGV) to improve completeness of potential sources for seismic hazard  
8 assessment.  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

## 1. Introduction

The Po Plain is one of Italy's major geographical features, extending for over 400 km in a roughly east-west direction from the Alps to the Adriatic Sea and corresponding to the drainage basin of the Po River, the country's longest and most important watercourse. Geologically the Po Plain and part of the current Adriatic Sea comprise the foreland of two opposing verging fold-and-thrust belts: the Southern Alps to the north, and the Northern Apennines to the south. Although it is underlain by actively growing orogens in the context of ongoing convergence, the Po Plain is an almost perfectly flat area that may appear tectonically quiet, bounded by two mountain ranges. The morphological borders of the Po Plain correspond with the contact between the Quaternary alluvium cropping out in the plain and the pre-Quaternary rocks exposed along the two mountain fronts.

Despite the appearances, however, the Po Plain is in itself quite active. Several earthquakes hit the plain and both mountain fronts through history (ISIDE WORKING GROUP, 2010; ROVIDA *et al.*, 2011), testifying that the geodynamic processes which led to the convergence between the two orogens are still active. Due to the occurrence of many historical centers combined with an extraordinary concentration of critical facilities and the associated lifelines, the Po Plain certainly represents a major concern for local administrations and civil defence authorities. Despite these circumstances, and probably due to the scattered nature of local seismicity, much of the Po Plain has entered the Italian seismic code only recently, in 2004, and the new provisions have become mandatory even more recently, in 2010. For these reasons even earthquakes in the magnitude range 5 to 6 can be catastrophic, as tragically demonstrated by the 2012 Emilia sequence ( $M_L$  5.9; ISIDE WORKING GROUP, 2010), which caused 26 casualties and severe damage to monumental and industrial buildings.

1 The Italian earthquake record is normally considered complete for M 6+ earthquakes  
2 only for the past ca. 700 years (STUCCHI *et al.*, 2004), but major known earthquakes probably  
3 recur every 1,000-2,000 years (VALENSISE and PANTOSTI, 2001a; GALLI *et al.*, 2008).  
4 Consequently, faults that released their most recent large earthquake before 700 years ago  
5 may not appear in the historical record. Identifying all potential seismogenic faults and  
6 estimating their potential is fundamental for characterizing input for probabilistic seismic  
7 hazard assessment (PSHA); but given the short length of the historical record and the poor  
8 surface expression of potential seismogenic sources, we may be surprised by future damaging  
9 earthquakes (MULARGIA, 2013), a fact that was tragically illustrated by the 2012 Emilia  
10 sequence. The 20 and 29 May earthquakes occurred in an area for which no historical  
11 seismicity was reported but where seismogenic sources had been identified through tectonic  
12 geomorphology and seismic profiles (DISS 2.0, VALENSISE and PANTOSTI, 2001b; CIUCCI *et*  
13 *al.*, 2002). Resorting to the geological record is hence mandatory for outlining all seismogenic  
14 sources of a problematic area such as the Po Plain and assessing its potential effectively (e.g.  
15 FACCIOLI, 2013).

16 Fault plane solutions of major instrumental earthquakes show that compressional  
17 mechanisms are dominant in the Po Plain (PONDRELLI *et al.*, 2006; SCOGNAMIGLIO *et al.*,  
18 2012, among others), which agrees with geologic and modern strain (GPS) evidence (e.g.  
19 DEVOTI *et al.*, 2011) and with predictions from geodynamic models. Relatively recent active  
20 tectonic studies have acknowledged that faulting is dominantly blind and that strain rates are  
21 rather low (see VALENSISE and PANTOSTI, 2001b; BURRATO *et al.*, 2003; BASILI *et al.*, 2008;  
22 TOSCANI *et al.*, 2009; DISS WORKING GROUP, 2010; MAESANO *et al.*, 2013; MAESANO *et al.*,  
23 submitted). However, correlating individual seismogenic sources and associating them with  
24 specific historical earthquakes is not straightforward. A number of additional circumstances  
25 add to the complications, including 1) the scattered distribution of seismicity; 2) the large

1 sedimentary rates in the Po Plain proper, often larger than tectonic rates; 3) the presence of  
2 inherited landscape and lithological discontinuities in the foothills; 4) locally large man-  
3 induced vertical ground motions; and 5) widespread anthropogenic modifications of the  
4 natural fluvial network (e.g. the construction of levees and of artificial channels).  
5  
6

7  
8  
9 Due to all these circumstances, for many years few investigation of active faults in the  
10 subsurface of the Po Plain were begun as most field geologists concentrated on the more  
11 visible – and hence more scientifically appealing – faults exposed across the Alps and the  
12 Apennines. Identifying and characterizing seismogenic sources in the Po Plain requires an  
13 integrated approach that combines morphotectonic analyses, seismicity data and subsurface  
14 geological data such as commercial seismic lines, wells, in situ stress measurements, etc.  
15  
16 Anomalous stream morphology has proven to be the landscape feature that is most sensitive  
17 to subtle topographic changes caused by underlying active faults in the flattest portions of the  
18 Po Plain, and has been a keystone of our approach (BURRATO *et al.*, 2003; BURRATO *et al.*,  
19 2012). In the foothill areas where regional uplift dominates, active thrusting is normally  
20 identified by differentially uplifted and tilted Quaternary markers, such as river and even  
21 coastal terraces (e.g. AMOROSI *et al.*, 1996, 2004; VANNOLI *et al.*, 2004; PICOTTI and  
22 PAZZAGLIA, 2008; PONZA *et al.*, 2010; GUNDERSON *et al.*, 2013, 2014).  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40

41 The case of the Po Plain is especially complex, however, also in view of its extreme  
42 tectonic diversity, testified by the wide range of hypocentral depths and focal mechanisms  
43 displayed by current seismicity. The characteristic flat-and-ramp structure and arcuate shape  
44 of most compressional systems worldwide, including those encircling the Po Plain, imply that  
45 active thrust and reverse faults occur at different depths and with different strike, thus  
46 requiring multiple and flexible geological approaches and a wealth of subsurface data. The  
47 presence of inherited faults in the basement rocks of the Po Plain further complicates the  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1 matter, as their reactivation under the current compressional regime may result in earthquakes  
2 that are difficult to anticipate based on the evolution of the overlying mountain chains.  
3

4 We present an updated overview of the seismogenic sources of the Po Plain and of the  
5 two adjacent mountain fronts, most of which are listed in the latest version of the DISS  
6 Database (Figure 1), focusing specifically on their existence, geometry, kinematics,  
7 earthquake potential and complexity. Their characterization in terms of slip rate and  
8 seismogenic potential is required for probabilistic seismic hazard analysis but it is beyond our  
9 current scopes. For a summary of strain rates across the Po Plain and beyond the reader may  
10 refer to PETRICCA *et al.* (2013) and MAESANO *et al.* (submitted).  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20

21 All potential seismogenic sources correspond to blind faults, which are based on  
22 scientific inferences and subject to considerable uncertainties, partially compensated by the  
23 exceptional density of underground information. We will discuss the reasoning adopted in  
24 each single case, the uncertainties and the research directions that may help setting firmer  
25 constrains during future investigation efforts (e.g. FACCIOLI, 2013).  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38

## 39 **2. Geological and seismological framework: data and interpretations**

### 40 **2.1 Regional tectonic framework**

41 The Po Plain is the foreland of two fold-and-thrust belts verging toward one another: the S-  
42 verging central Southern Alps to the north, and the N-NE-verging Northern Apennines to the  
43 south. The two belts developed due to convergence between the African and European plates  
44 beginning in the Cretaceous, and were associated with two oppositely-dipping subduction  
45 zones involving both European and African lithosphere (CARMINATI and DOGLIONI, 2012, and  
46 references therein). Hence the Po Plain coincides with the foreland of both chains; it also  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65



1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

hosts their foredeeps, and for this reason it has undergone steady subsidence and sedimentation over the past 5 Ma (FANTONI and FRANCIOSI, 2010).

Buried compressional structures comprising the most advanced fronts of the two orogens were extensively explored by seismic reflection lines and deep well logs obtained for oil exploration after the end of World War II. The local Pliocene-Quaternary sedimentary sequence is characterized by uneven thickness, ranging between several thousand meters in the depocenters to a hundred meters over the top of the buried anticlines (BIGI *et al.*, 1992; GHIELMI *et al.*, 2013). Tectonically-induced, short-wavelength variations in the geometry of the sedimentary sequence are superimposed onto a longer-wavelength signal due to the larger subsidence of the Northern Apennines foredeep with respect to that of the Southern Alps. As a result, the thickness of the sedimentary wedge - and similarly the depth and dip of the basal detachment of the thrust wedge - generally increases towards the Northern Apennines mountain front (i.e., southward; MARIOTTI and DOGLIONI, 2000; BIGI *et al.*, 2003). Rapid asymmetric subsidence caused by the tectonic load of the Northern Apennines chain across the whole Po Plain created a large accommodation space, resulting in large sedimentation rates in the complex system of elongate foredeeps (e.g. BARTOLINI *et al.*, 1996; GHIELMI *et al.*, 2013). Subsidence takes place at up to 2-3 mm/a (ARCA and BERETTA, 1985; CARMINATI and MARTINELLI, 2002; CUFFARO *et al.*, 2010) and has always been consistently larger than the tectonic uplift rates along the active thrust-related folds, which caused them to drown in the subsurface of the Po Plain.

The outer arcs of the Northern Apennines are currently buried below the Pliocene-Quaternary marine and continental deposits infilling the Po Plain basin and are organized in three complex fold systems: the Monferrato Arc, Emilia Arc, and Ferrara-Romagna Arc, respectively from west to east (Figure 2). To the rear of the Emilia and Ferrara-Romagna arcs the sub-emergent Pedepenninic Thrust Front (BOCCALETTI *et al.*, 1985) lies at the foot of the

1 Northern Apennines. This important morphological and structural feature has been interpreted  
2 in recent studies also as the anticline forelimb of a deeper thrust ramp, and hence not as  
3 evidence of a shallow thrust (PICOTTI and PAZZAGLIA, 2008). Such interpretation has  
4 significant implications as population concentrates in cities and towns that lie near or on the  
5 Pedepenninic Thrust Front; hence establishing whether this is the surface evidence of a string  
6 of shallow thrust faults or rather of substantially deeper ramps implies significantly different  
7 ground shaking expected in future earthquakes. Continuous Quaternary activity is poorly  
8 expressed along the mountain front, yet it is witnessed by progressive deformation and tilting  
9 of river terraces and of outcropping syntectonic sediments (e.g. BOCCALETTI *et al.*, 1985,  
10 2011; PICOTTI and PAZZAGLIA, 2008; WEGMANN and PAZZAGLIA, 2009; PONZA *et al.*, 2010;  
11 GUNDERSON *et al.*, 2013, 2014).

12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26 In contrast, the buried outer thrust fronts of the Southern Alps exhibit simpler  
27 geometries that define a single wide arc running from Milano to the Garda Lake (Figure 2).  
28 This outer arc is connected to the east to the NNE-trending Giudicarie thrust system  
29 (CASTELLARIN and CANTELLI, 2000; MASSIRONI *et al.*, 2006), and is associated with high  
30 angle back-thrusts and small topographic highs emerging in the northern Po Plain that were  
31 first investigated by Desio (1965) (see also LIVIO *et al.*, 2009). Unlike the Northern  
32 Apennines mountain front, the foothills of the western Southern Alps do not comprise a  
33 tectonics-controlled mountain front, the only reported exception being a small area north of  
34 Milan (MICHETTI *et al.*, 2012).

35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48 The active Northern Apennines thrust fronts exhibit a rather complex architecture,  
49 comprising potential seismogenic sources corresponding to thrust ramps lying at different  
50 structural levels. The occurrence of complex thrust geometries is due to the presence of  
51 several potential detachment levels in the sedimentary multilayer deformed by the thrust belt.  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65  
66  
67  
68  
69  
70  
71  
72  
73  
74  
75  
76  
77  
78  
79  
80  
81  
82  
83  
84  
85  
86  
87  
88  
89  
90  
91  
92  
93  
94  
95  
96  
97  
98  
99  
100  
101  
102  
103  
104  
105  
106  
107  
108  
109  
110  
111  
112  
113  
114  
115  
116  
117  
118  
119  
120  
121  
122  
123  
124  
125  
126  
127  
128  
129  
130  
131  
132  
133  
134  
135  
136  
137  
138  
139  
140  
141  
142  
143  
144  
145  
146  
147  
148  
149  
150  
151  
152  
153  
154  
155  
156  
157  
158  
159  
160  
161  
162  
163  
164  
165  
166  
167  
168  
169  
170  
171  
172  
173  
174  
175  
176  
177  
178  
179  
180  
181  
182  
183  
184  
185  
186  
187  
188  
189  
190  
191  
192  
193  
194  
195  
196  
197  
198  
199  
200  
201  
202  
203  
204  
205  
206  
207  
208  
209  
210  
211  
212  
213  
214  
215  
216  
217  
218  
219  
220  
221  
222  
223  
224  
225  
226  
227  
228  
229  
230  
231  
232  
233  
234  
235  
236  
237  
238  
239  
240  
241  
242  
243  
244  
245  
246  
247  
248  
249  
250  
251  
252  
253  
254  
255  
256  
257  
258  
259  
260  
261  
262  
263  
264  
265  
266  
267  
268  
269  
270  
271  
272  
273  
274  
275  
276  
277  
278  
279  
280  
281  
282  
283  
284  
285  
286  
287  
288  
289  
290  
291  
292  
293  
294  
295  
296  
297  
298  
299  
300  
301  
302  
303  
304  
305  
306  
307  
308  
309  
310  
311  
312  
313  
314  
315  
316  
317  
318  
319  
320  
321  
322  
323  
324  
325  
326  
327  
328  
329  
330  
331  
332  
333  
334  
335  
336  
337  
338  
339  
340  
341  
342  
343  
344  
345  
346  
347  
348  
349  
350  
351  
352  
353  
354  
355  
356  
357  
358  
359  
360  
361  
362  
363  
364  
365  
366  
367  
368  
369  
370  
371  
372  
373  
374  
375  
376  
377  
378  
379  
380  
381  
382  
383  
384  
385  
386  
387  
388  
389  
390  
391  
392  
393  
394  
395  
396  
397  
398  
399  
400  
401  
402  
403  
404  
405  
406  
407  
408  
409  
410  
411  
412  
413  
414  
415  
416  
417  
418  
419  
420  
421  
422  
423  
424  
425  
426  
427  
428  
429  
430  
431  
432  
433  
434  
435  
436  
437  
438  
439  
440  
441  
442  
443  
444  
445  
446  
447  
448  
449  
450  
451  
452  
453  
454  
455  
456  
457  
458  
459  
460  
461  
462  
463  
464  
465  
466  
467  
468  
469  
470  
471  
472  
473  
474  
475  
476  
477  
478  
479  
480  
481  
482  
483  
484  
485  
486  
487  
488  
489  
490  
491  
492  
493  
494  
495  
496  
497  
498  
499  
500  
501  
502  
503  
504  
505  
506  
507  
508  
509  
510  
511  
512  
513  
514  
515  
516  
517  
518  
519  
520  
521  
522  
523  
524  
525  
526  
527  
528  
529  
530  
531  
532  
533  
534  
535  
536  
537  
538  
539  
540  
541  
542  
543  
544  
545  
546  
547  
548  
549  
550  
551  
552  
553  
554  
555  
556  
557  
558  
559  
560  
561  
562  
563  
564  
565  
566  
567  
568  
569  
570  
571  
572  
573  
574  
575  
576  
577  
578  
579  
580  
581  
582  
583  
584  
585  
586  
587  
588  
589  
590  
591  
592  
593  
594  
595  
596  
597  
598  
599  
600  
601  
602  
603  
604  
605  
606  
607  
608  
609  
610  
611  
612  
613  
614  
615  
616  
617  
618  
619  
620  
621  
622  
623  
624  
625  
626  
627  
628  
629  
630  
631  
632  
633  
634  
635  
636  
637  
638  
639  
640  
641  
642  
643  
644  
645  
646  
647  
648  
649  
650  
651  
652  
653  
654  
655  
656  
657  
658  
659  
660  
661  
662  
663  
664  
665  
666  
667  
668  
669  
670  
671  
672  
673  
674  
675  
676  
677  
678  
679  
680  
681  
682  
683  
684  
685  
686  
687  
688  
689  
690  
691  
692  
693  
694  
695  
696  
697  
698  
699  
700  
701  
702  
703  
704  
705  
706  
707  
708  
709  
710  
711  
712  
713  
714  
715  
716  
717  
718  
719  
720  
721  
722  
723  
724  
725  
726  
727  
728  
729  
730  
731  
732  
733  
734  
735  
736  
737  
738  
739  
740  
741  
742  
743  
744  
745  
746  
747  
748  
749  
750  
751  
752  
753  
754  
755  
756  
757  
758  
759  
760  
761  
762  
763  
764  
765  
766  
767  
768  
769  
770  
771  
772  
773  
774  
775  
776  
777  
778  
779  
780  
781  
782  
783  
784  
785  
786  
787  
788  
789  
790  
791  
792  
793  
794  
795  
796  
797  
798  
799  
800  
801  
802  
803  
804  
805  
806  
807  
808  
809  
810  
811  
812  
813  
814  
815  
816  
817  
818  
819  
820  
821  
822  
823  
824  
825  
826  
827  
828  
829  
830  
831  
832  
833  
834  
835  
836  
837  
838  
839  
840  
841  
842  
843  
844  
845  
846  
847  
848  
849  
850  
851  
852  
853  
854  
855  
856  
857  
858  
859  
860  
861  
862  
863  
864  
865  
866  
867  
868  
869  
870  
871  
872  
873  
874  
875  
876  
877  
878  
879  
880  
881  
882  
883  
884  
885  
886  
887  
888  
889  
890  
891  
892  
893  
894  
895  
896  
897  
898  
899  
900  
901  
902  
903  
904  
905  
906  
907  
908  
909  
910  
911  
912  
913  
914  
915  
916  
917  
918  
919  
920  
921  
922  
923  
924  
925  
926  
927  
928  
929  
930  
931  
932  
933  
934  
935  
936  
937  
938  
939  
940  
941  
942  
943  
944  
945  
946  
947  
948  
949  
950  
951  
952  
953  
954  
955  
956  
957  
958  
959  
960  
961  
962  
963  
964  
965  
966  
967  
968  
969  
970  
971  
972  
973  
974  
975  
976  
977  
978  
979  
980  
981  
982  
983  
984  
985  
986  
987  
988  
989  
990  
991  
992  
993  
994  
995  
996  
997  
998  
999  
1000

1 depth, well imaged in the CROP03 seismic reflection profile as a relatively high angle portion  
2 of a regional thrust (BARCHI *et al.*, 1998; FINETTI *et al.*, 2001). This thrust has been  
3 interpreted: 1) as a major lithospheric structure, cutting the whole crust from the metamorphic  
4 basement up to the higher levels (BARCHI *et al.*, 1998; LAVECCHIA *et al.*, 2003, 2004); or 2) as  
5 one of the leading elements of the accretionary prism of the Apennine belt (BALLY *et al.*,  
6 1986; DOGLIONI *et al.*, 1994). In the absence of geological evidence for shortening across this  
7 deep ramp, seismicity becomes the only available indicator of its activity. In fact, a number of  
8 earthquakes that occurred in the region northeast of the Northern Apennines crest at an  
9 estimated depth larger than ordinary (i.e. below 15 km) can be tentatively associated with this  
10 structure.  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22

23  
24 GPS studies show that convergence of Africa and Eurasia at the latitude of northern  
25 Italy is progressing at 3 to 8 mm/a (e.g. SERPELLONI *et al.*, 2007) and that shortening across  
26 the Po basin proceeds at 1-3 mm/a, increasing from west to east (e.g. DEVOTI *et al.*, 2011).  
27 Shortening is accomplished by counter-clockwise rotation of the Adriatic promontory, of  
28 which the Po basin is the northern termination, with respect to the European plate, with a pole  
29 of rotation located in the western Alps (ANDERSON and JACKSON, 1987; WEBER *et al.*, 2010  
30 and references therein). Borehole breakout data show Sh-max axes perpendicular to the trend  
31 of the buried thrust fronts, in agreement with evidence from focal mechanisms (HEIDBACH *et*  
32 *al.*, 2008; MONTONE *et al.*, 2012; CARAFA and BARBA, 2013).  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50

## 51 **2.2. Paleogeographic control on active tectonics**

52 The Cenozoic compressional architecture of both the Alps and the Apennines was strongly  
53 influenced by the inherited Mesozoic palaeogeographic setting of its foreland, i.e. the Adriatic  
54 plate. This was characterized by carbonate platforms and deep marine basins, separated by  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1 roughly NNE-trending extensional faults developed during the Tethyan rifting of the ancient  
2 African passive margin ( BOSELLINI and HSU, 1973; BERTOTTI *et al.*, 1993; CHANNELL, 1996;  
3  
4 RAVAGLIA *et al.*, 2006; FANTONI and FRANCIOSI, 2010). As a consequence of this inheritance,  
5  
6 the lithosphere progressively deformed by the two thrust belts developed through stratigraphic  
7  
8 sequences having uneven thickness and variable sedimentary facies (Table 1). Similarly, the  
9  
10 basement rocks and the overlying sedimentary successions involved in the construction of the  
11  
12 orogenic belts were characterized by strong lateral variations resulting in strong rheological  
13  
14 contrasts (CUFFARO *et al.*, 2010).  
15  
16  
17  
18

19 The variations in the properties of the subducting lithosphere controlled the evolution  
20  
21 and the shape of the thrust fronts, that is to say, the development of salients and recesses  
22  
23 respectively in front of basins and carbonate highs (MARIOTTI and DOGLIONI, 2000; CUFFARO  
24  
25 *et al.*, 2010). In its turn, the linearity of the thrusts is related to the spacing between  
26  
27 subsequent fronts, which is controlled by two important geometrical parameters of the orogen  
28  
29 development: 1) the dip of the foreland monocline (MARIOTTI and DOGLIONI, 2000; CUFFARO  
30  
31 *et al.*, 2010), and 2) the depth of the basal detachment, i.e. of the deepest thrust of the  
32  
33 accretionary prism, usually lying at or near the transition between the crystalline basement  
34  
35 and the sedimentary cover (BIGI *et al.*, 2003). Along with the occurrence of shallower  
36  
37 detachment horizons resulting from the vertical heterogeneities of the sedimentary sequence,  
38  
39 these two properties of the subducting lithosphere have had a profound impact on the  
40  
41 subsequent development of the thrust fronts on either side of the Po Plain. Table 1  
42  
43 summarizes how the development of the Alps and Apennines thrusts was controlled by the  
44  
45 different characteristics of the sedimentary cover scraped off the foreland lithosphere, and  
46  
47 hence of the accretionary prisms, and lists the resulting geometrical characteristics of the two  
48  
49 thrust belts. In the following we will discuss some implications of this palaeogeographic  
50  
51 control on active faulting.  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

The palaeogeographic inheritance may also have controlled 1) the reactivation in the present-day regime of *inherited* faults that bounded the Mesozoic rift system, and 2) the creation of foreland monocline panels characterized by different dip values; we speculate that such panels are separated by transfer zones characterized by strike-slip or transpressional motion and that are usually perpendicular to the thrust fronts, or *transverse* (see Fig. 4 in CUFFARO *et al.*, 2010; Figure 2). Both types of faults, *inherited* and *transverse*, lie below the basal detachment of the accretionary prisms, being rooted in the lithosphere of the subducting foreland plate. In particular, we expect to find the *transverse* faults only below the Apennines prism, because the initial momentum for their development and kinematics is induced by changes in the dip of the foreland monocline that are seen only beneath the Apennines (MARIOTTI and DOGLIONI, 2000). Although the true geodynamic motivations definitely require further investigation, it is worth noting that many of the transverse structures that cut across the Apennines (see section on “Transverse structures”) are geographically coincident with the zones where changes in the dip of the monocline are more pronounced. On this basis we propose a genetic relationship between them and the changes in dip of the foreland monocline.

Another class of structures rooted in the subducting Adriatic lithosphere includes a set of high-angle normal faults that have been recently discussed in works dealing with the reconstruction of the deep structural setting of the Po Plain (ROGLEDI, 2010). These faults trend at a high angle with respect to the boundaries of the palaeogeographic domains (i.e. E-W to NW-SE); they have been mapped only in the "undeformed" portion of the Po Plain, i.e. beyond the outer fronts of the Alps and Apennines, but have been seen to extend below the Ferrara-Romagna Arc, possibly controlling its geometrical development (TOSCANI *et al.*, 2013; BONINI *et al.*, 2014). More specifically, TOSCANI *et al.* (2013) used analogue modeling to show that the location of the thrust ramps associated with the main anticlines has been

1 controlled by the presence of steps produced by such high-angle faults in the basement  
2 morphology. These faults are seen to trend sub-parallel to the inferred direction of the hinge  
3  
4 of the foreland monocline, and may hence be optimally oriented for being reactivated due to  
5  
6 the bending moment induced by the progressive increase of the monocline dip.  
7  
8  
9

### 10 11 12 13 14 **2.3. Seismicity and earthquake budgets** 15

16 Any investigation of the seismicity of the Po Plain must carefully take into account that in the  
17 past both its natural and human landscapes were very different from today. Currently the Po  
18 Plain is one of the most densely inhabited and cultivated areas of Italy: however it once was  
19 covered by large wooded patches and marshlands, particularly south of the Po river. The  
20 reconstruction of the historical seismicity of the Po Plain is a complex task as it implies  
21 knowledge of the distribution of settlements and roads of the time. Few large earthquakes are  
22 known, the 1117 *Veronese* event being the only one with an inferred  $M > 6.5$ . Table 2 lists the  
23 main parameters of the largest historical earthquakes known to have occurred in the study  
24 region (MELONI *et al.*, 1988; BOSCHI and GUIDOBONI, 2003; GUIDOBONI *et al.*, 2007; ROVIDA  
25 *et al.*, 2011). In the following sections we will describe these events individually: each one is  
26 keyed to a code (IDx) and is tentatively assigned to a seismogenic source (Table 2).  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42

43 Historical and instrumental catalogues (Tables 2 and 3; CASTELLO *et al.*, 2006; ISIDE  
44 WORKING GROUP, 2010) show that the seismicity of the Po Plain concentrates along the  
45 foothills and the buried thrust fronts of the Northern Apennines and Southern Alps (Figure 3),  
46 with a few notable exceptions including the 3 January 1117 earthquake ( $M_w$  6.7, *Veronese*; ID  
47 6). In general the Northern Apennines fronts exhibit more historical earthquakes than the  
48 Southern Alps fronts. Seismicity is not evenly distributed, however, but increases from west  
49 to east, i.e. from the Monferrato to the Ferrara-Romagna Arc.  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

As recalled earlier, the present-day activity of the two mountain fronts is characterized by compressional focal mechanisms (<http://www.bo.ingv.it/RCMT/searchRCMT.html>; PONDRELLI *et al.*, 2006), in full agreement with tectonic evidence. The 20 and 29 May 2012 Emilia earthquakes ( $M_L$  5.9 and 5.8, respectively; Table 3), the largest earthquakes ever recorded instrumentally in the region, were caused by purely reverse slip with  $S_h$ -max axes perpendicular to the buried thrust faults of the western Ferrara-Romagna Arc (e.g. SCOGNAMIGLIO *et al.*, 2012, among others). The 2012 sequence was highly complex as a total of seven  $M5+$  earthquakes occurred during the long aftershock sequence (about 2,500 events), activating a ~50 km-long stretch of this buried outer front. Most of the earthquakes occurred between 1 and 12 km depth, above the basal detachment of the outer thrust fronts.

Earthquake sequences characterized by multiple, similarly large mainshocks are rather common over the whole Italian territory (see Table 4 and Figure 4). In addition to stress transfer among adjacent faults, their occurrence is likely related to the country's structural complexity, which causes the active fault systems to be broken up by numerous transverse structures; on the one hand these effectively limit the fault length that may rupture in a single large earthquake, but on the other hand they make the triggering of adjacent faults more likely. The complex sequences of the Po Plain and surrounding areas are shown in Tables 2 and 3 and are highlighted in Figure 3b.

The Po Plain is also the locus of relatively deep earthquakes, conventionally assumed to coincide with all events located below 15 km depth. They occur below the basal detachment of the Northern Apennines and Southern Alps and therefore are not directly related to thrust tectonics. Two deep earthquakes that were felt over a large portion of northern and central Italy occurred in 2012 near Reggio nell'Emilia (25 January,  $M_L$  5.0, depth 29.0 km; ID 41) and near Parma (27 January,  $M_L$  5.2, depth 72.4 km; ID 63). Some historical earthquakes have affected large portions of the Po Plain and of the surrounding

1 ranges, causing widespread damage and suggesting that deeper events are a common  
2 occurrence in the region. For example, the effects of the 13 January 1909,  $M_w$  5.5, *Bassa*  
3 *Padana* earthquake (ID 16) are documented by 800 intensity points spread over an area of  
4 about 180.000 km<sup>2</sup>, and by 297 points with intensity V ( $N_v$ ) or larger (see panel b in Figure  
5 5). As first suggested by MELONI and MOLIN (1987), the 1909 event may have occurred at a  
6 relatively large depth, up to 40 km according to FACCIOLI (2013). These deep earthquakes  
7 may attain a significant magnitude, as shown by the 1909 event; in fact their true magnitude is  
8 likely to be substantially larger than the 5.5 estimate obtained from intensity data with  
9 automatic routine procedures, normally calibrated using upper crustal events. Therefore, the  
10 occurrence of such deep earthquakes cannot be ignored in developing a seismotectonic model  
11 of the Po Plain. Reasonably reliable depth data, however, are available only for earthquakes of  
12 the past thirty years. For older events we did not attempt a formal determination of the  
13 hypocentral depth, but we used the ratio of epicentral intensity and felt area and some expert  
14 judgment simply to separate deeper from shallower events. All earthquakes having  $M$  5.3+  
15 were thus carefully inspected and their intensity patterns compared (Figure 5). Tables 2 and 3  
16 list all earthquakes having an estimated depth below 15 km (highlighted in Figure 3b).

17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39 Based on the data presented in Tables 2 and 3 we analyzed the seismic release of the  
40 Po Plain and of the Apennines foothills in terms of shallow vs. deep earthquakes, with  
41 reference to the historical and to the most recent seismicity (Table 5). Even considering the  
42 limited completeness of the historical record, the total observed moment release ( $3.31 \times 10^{26}$   
43 dyne cm, equivalent to a single  $M_w$  7.0 earthquake) is rather small, especially if compared  
44 with the size of the investigated area (nearly 40,000 km<sup>2</sup>). This result must be considered also  
45 in light of the known limited *earthquake efficiency* of the Po Plain as a whole (BARBA *et al.*,  
46 2010). Shallow earthquakes dominate the global seismic release, but deep events release more  
47 moment over the instrumental time window, in spite of the large contribution to shallow  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65



1 moment release supplied by the 2012 Emilia sequence. This suggests (a) that deep historical  
2 events are under-represented, or (b) that their magnitude is systematically underestimated, or  
3  
4 a combination of these two end-members.  
5  
6  
7  
8  
9

### 10 11 **3. Seismogenic sources of the Po Plain**

#### 12 13 14 15 16 17 **3.1. Generalities**

18  
19 In this section we identify and characterize the main seismogenic sources that affect the Po  
20 Plain, i.e. those believed to be capable of producing  $M \geq 5.5$  earthquakes (VALENSISE and  
21 PANTOSTI, 2001b; BASILI *et al.*, 2008).  
22  
23  
24  
25

26  
27 The approach employed for compiling the DISS database is based on substantial  
28 geological and geophysical evidence. The strategy is based on two categories of sources: the  
29 *Individual Seismogenic Sources (ISS)*; stored in the database with a unique code beginning  
30 with ITIS followed by a three digit number), and the *Composite Seismogenic Sources (CSS)*;  
31 stored in the database with a unique code beginning with ITCS followed by a three digit  
32 number). The first category includes individual fault segments that may be responsible for  
33 specific historical or instrumental earthquakes, whereas the second category represents fault  
34 systems that may include one or more *ISSs*. Detailed descriptions of the DISS sources and the  
35 multi-step procedure to identify their parameters can be found in BASILI *et al.* (2008), BASILI  
36 *et al.* (2009), BURRATO *et al.* (2008), VANNOLI *et al.* (2012), KASTELIC *et al.* (2013) and on  
37 the database website (<http://diss.rm.ingv.it/diss/UserManual.html>).  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53

54 Following the rationale of the DISS database, our work aims to represent an *updated*  
55 and hopefully *complete* portrait of the seismogenic sources recognized in the Po Plain. The  
56 *completeness* of the data is normally assessed with reference to the observed seismicity,  
57  
58  
59  
60  
61  
62  
63  
64  
65

1 making sure that no significant historical earthquake is left unassigned to a mapped source.  
2 The sparseness of the historical record, however, makes this assessment rather difficult and  
3 potentially misleading. In fact, the geological moment release that can be calculated for the Po  
4 Plain sources outpaces the observed historical moment release, suggesting that either the  
5 historical earthquake record is incomplete, or that their *seismic coupling*, or *earthquake*  
6 *efficiency*, is rather low (e.g. BARBA *et al.*, 2010). This crucial aspect of the characterization of  
7 Po Plain sources is out of the scopes of this paper but will be the object of a future research  
8 effort.  
9

10  
11  
12  
13  
14  
15  
16  
17  
18  
19 As stated earlier, the seismogenic sources of the Po Plain originate from diverse  
20 geodynamic processes, occur at various depth, exhibit different kinematics, and as such they  
21 may induce very different ground shaking. For all of these reasons we subdivided them into  
22 four main groups (Figure 6):  
23

24  
25  
26  
27  
28  
29 Group #1) shallow thrusts of the Alps and Apennines fold-and-thrust belts, which include  
30 fault systems occurring along the Alps and Apennines piedmont and more external fronts  
31 extending further into and beneath the Po Plain;  
32

33  
34  
35  
36  
37  
38  
39 Group #2) deep ramps of the Apennines fold-and-thrust belts occurring beneath the Northern  
40 Apennines, northeast of the main drainage divide;

41  
42  
43  
44  
45  
46  
47 Group #3) inherited faults of the foreland, which includes older structures such as Mesozoic  
48 normal faults reactivated under the current compressional tectonic regime;

49  
50  
51  
52  
53  
54  
55 Group #4) transverse structures, faults that are roughly perpendicular to the main structural  
56 grain of the Northern Apennines thrust belt.  
57

58  
59  
60  
61  
62  
63  
64  
65  
Sources of Group #1 pose a significant hazard as they occur at shallow depth and near  
the more densely populated areas (e.g. Figures 5 and 6 in ZONNO *et al.*, 2012). As such they  
are also somehow easier to identify despite their blind nature. Conversely, sources of Group

1 #2 and #4 are usually responsible for moderate ground shaking over large areas, which  
2 partially compensates the difficulties involved in locating them precisely. Finally, sources of  
3  
4 Group #3 are perhaps the most dangerous as they are the most elusive, and hence their  
5  
6 earthquake potential is most uncertain. As discussed in the following, the largest known  
7  
8 earthquake of the Po Plain (3 January 1117,  $M_w$  6.7) is believed to belong to this group.  
9  
10 Although Groups #1 and #2 exhibit similar kinematics, we decided to keep them separate as  
11  
12 their impact on ground shaking is very different due to their location and depth.  
13  
14

15  
16 In this section we describe each *CSS* and *ISS* of the Po Plain included in the current  
17  
18 version of the DISS database (version 3.2.0), from north to south and from west to east. For  
19  
20 the study area DISS lists 21 *CSSs* and 13 *ISSs* (Figure 7). The sources in the DISS database  
21  
22 belong to Groups #1, #2, and #3. Sources of Group #4 are still being evaluated for possible  
23  
24 inclusion at a later time.  
25  
26

27  
28 Following is an example of the data used and the reasoning adopted for characterizing  
29  
30 an Individual Source, namely the source of the 4 April 1781, Romagna earthquake ( $M_w$  5.9;  
31  
32 ID 23, ITIS093). This upper crustal blind source (Group #1) is associated with gentle  
33  
34 warping of the Apennines foothills and drainage anomalies. Its three-dimensional geometry  
35  
36 was defined according to the following observations:  
37  
38

- 39 • the location was chosen by matching the larger faults that exists in the subsurface with the  
40  
41 earthquake macroseismic pattern;  
42  
43
- 44 • the strike was based on the local trend of the Pedeapenninic Thrust Front;  
45  
46
- 47 • the dips was set at  $35^\circ$  to the south, as suggested by subsurface data;  
48  
49
- 50 • the rake was assumed to be pure thrusting, based on geodynamic considerations  
51  
52 constrained by mesostructures affecting recent deposits of the area;  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63

- the length was evaluated based on subsurface data and on the extent of landscape modifications induced by fault activity, and was constrained by scaling relationships with the magnitude of the 4 April 1781 earthquake;
- the down-dip width was assessed based on subsurface data and constrained using the magnitude of the 1781 earthquake;
- finally, the minimum and maximum depth were constrained by analysis of subsurface data.

Although the Po Plain has been the object of intense investigations since the inception of the DISS database, some potential sources of damaging earthquakes still need to be fully characterized. The existence of most of these new sources has been highlighted by the occurrence of earthquakes that, due to their location and hypocentral depth, cannot be associated with the Alps and Apennines thrust systems, and hence belong to Groups #3 and #4 (see above). Some of these sources have been included in v. 3.2.0 of the DISS database, to be published in 2014, whereas others will be included in future releases.

### **3.2. Shallow sources of the Alps and Apennines fold-and-thrust belts (Group #1)**

The Seismogenic Sources belonging to this group correspond to the shallow outer thrusts of the S-verging Central Southern Alps and of the N-verging Northern Apennines fronts that exist in the subsurface of the northern and southern Po Plain, respectively. Active compression in the Po Plain generates moderate seismicity along complex thrust systems and intervening strike-slip faults, an interpretation supported by available seismological, GPS and stress field data. The occurrence of salients and recesses along strike of the main thrust fronts creates boundaries to the dynamic earthquake propagation, causing segmentation of the compressional fault systems and, therefore, of the relevant CSSs.

1 The following description is based on a comprehensive instrumental catalogue (ISIDE:  
2 ISIDE WORKING GROUP, 2010) and on historical catalogues (BOSCHI *et al.*, 2000; GUIDOBONI  
3 *et al.*, 2007; ROVIDA *et al.*, 2011). For an in-depth description of each source and a complete  
4 list of references the reader may refer to the DISS website (<http://diss.rm.ingv.it/diss/>.) All  
5 historical and instrumental earthquakes mentioned in the text are listed in Tables 2 and 3 and  
6 are highlighted in Figure 3 through their identifier (ID).

7  
8  
9  
10  
11  
12  
13  
14 Geodetic (D'AGOSTINO *et al.*, 2008), seismological (ISIDE WORKING GROUP, 2010;  
15 ROVIDA *et al.*, 2011) and tectonic (MAESANO *et al.*, submitted) evidence suggests that  
16 convergence rates decrease from east to west across the whole Po Plain. Slow tectonic activity  
17 characterizes the Monferrato Arc (Figure 2; e.g. MICHETTI *et al.*, 2012 and references therein),  
18 in the westernmost portion of the Po Plain, and seismicity nearly disappears west of the  
19 longitude of Milan. For these reasons the thrusts of the western end of the Southern Alps and  
20 of the Northern Apennines that fall in an area roughly corresponding with the administrative  
21 region of Piedmont have not yet been included in the DISS database. The only notable  
22 exceptions are the sources of the 2 and 16 April 1808, Val Pellice earthquakes ( $M_w$  5.7, 5.6),  
23 located off the western end of the Monferrato Arc at the Alps foothills. Nevertheless, we  
24 believe that an in-depth analysis of the structures of the Monferrato Arc is mandatory as they  
25 show distinct evidence of mild recent activity and may hence generate very infrequent  
26 earthquakes.

### 50 51 **3.2.1. Shallow thrusts of the central Southern Alps margin**

52 The southernmost compressional fault system of the Alps is a buried S-verging external arc  
53 that is clearly imaged by subsurface data between Milano and the Garda Lake (Figure 7; PIERI  
54 and GROPPI, 1981; CASSANO *et al.*, 1986; FANTONI and FRANCIOSI, 2010). The ITCS002  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1 follows faithfully this poorly expressed blind thrust fault system. This portion of the Po Plain  
2 exhibits a lower seismic release compared to areas to the east and north-east (STUCCHI *et al.*,  
3 2008), yet we believe that structures belonging to the ITCS002 are responsible for the 12 May  
4 1802 *Valle dell'Oglio* earthquake and possibly for the 26 November 1396 *Monza* earthquake  
5 (ID 2 and 1, respectively). The ITCS002 includes the *ISS* responsible for the 1802 earthquake  
6 (ITIS104: see Figure 7 and Tables 6 and 7) whose location and geometry are based on  
7 geomorphological evidence supplied by BURRATO *et al.* (2003), on oil industry data (e.g.  
8 PIERI and GROPPi, 1981; CASSANO *et al.*, 1986; FANTONI and FRANCIOSI, 2010) and on  
9 macroseismic data, that uniquely constrain the location of the thrust responsible for the 1802  
10 event (ALBINI and ROVIDA, 2010). Due to lack of suitable geological and macroseismic  
11 constraints, no *ISS* was derived for the 1396 event.

12 The S-verging front is accompanied by an active N-verging high-angle back-thrust  
13 located southwest of the Garda Lake (Figure 7; ITCS072). This source is associated with  
14 some of the small topographic highs first investigated and interpreted as culminations of  
15 anticlines related to buried compressional faults by DESIO (1965), later investigated by LIVIO  
16 *et al.* (2009) using shallow seismic reflection profiles. Both the frontal thrust (ITCS002) and  
17 its associated backthrust (ITCS072) are blind and their propagation toward the surface is  
18 expressed by secondary folds and fault planes (MICHETTI *et al.*, 2012). The frontal thrust and  
19 the backthrust exhibit a cumulative displacement of 1,200 and 5,700 m, respectively. The  
20 cumulative slip rate dropped from 3.45 mm/a in the interval 1.6-1.2 Ma to 2.75 mm/a between  
21 1.2 and 0.9 Ma and 0.47 mm/a from 0.9 Ma to Present, with consistently larger deformation  
22 being accommodated on the backthrust with respect to the frontal thrust during the most  
23 recent period (LIVIO *et al.*, 2009). Based on its macroseismic signature the 25 December 1222  
24 *Basso Bresciano* earthquake ( $M_w$  5.8; ID 4) may have been generated by either of these

1 structures, both large enough to generate an event of that size, but the data not allow to  
2 discriminate between these two scenarios.  
3

4 The buried outer arc of the Southern Alps is connected to the east with the NNE-  
5 trending Giudicarie System (Figures 2 and 7), commonly interpreted as a regional transfer  
6 zone between the Central and Eastern Southern Alps (e.g. CASTELLARIN and CANTELLI,  
7 2000). The Giudicarie System developed along the border between Lombardian basin, to the  
8 west, and the Trento platform, to the east. The ITCS073 straddles the region east of the Garda  
9 Lake and corresponds to a SE-verging more external arc assumed to be an active ramp of the  
10 Giudicarie System. The role and geometry of this source is based on regional geological data  
11 (e.g. CASTALDINI and PANIZZA, 1991). Historical and instrumental catalogues show scattered  
12 intermediate-size earthquakes across this region.  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24

25 The ITCS048 is a S- to SE-verging internal thrust ramp of the Giudicarie System. The  
26 30 October 1901 Salò earthquake occurred in this area ( $M_w$  5.7; ID 3; PESSINA *et al.*, 2013),  
27 followed about a century later and virtually in the same area by a further damaging thrust  
28 faulting earthquake on 24 November 2004 ( $M_L$  5.2, *Lago di Garda*; ID 39). The 1901 *Salò*  
29 earthquake has been associated with a segment of the ITCS048. The *Salò* Individual Source  
30 (ITIS069) is a 7 km-long, 231°-striking, NW-dipping blind thrust fault comprising a deeper  
31 ramp of the Giudicarie System. The depth of the ITIS069 was assigned based on felt reports  
32 of the 1901 earthquake. The 2004 earthquake occurred few kilometers north of the *Salò*  
33 source and was caused by slip on a portion of the ITCS048 source (PESSINA *et al.*, 2006). The  
34 focal solution of the 2004 event further constrained and confirmed the parameters of the  
35 existing 1901 earthquake seismogenic source (ITIS069).  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52

53 Farther to the west, the ITCS010 source is a S-verging internal thrust front of the  
54 Southern Alps. Historical and instrumental catalogues show scattered moderate-size  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1 seismicity along strike of this thrust front. The role and geometry of this source are based on  
2 regional subsurface geological and geophysical data (e.g. CASTALDINI and PANIZZA, 1991).  
3  
4  
5  
6  
7  
8

### 9 **3.2.2. Shallow thrusts of the Northern Apennines margin**

10  
11 The northernmost compressional fault system of the Northern Apennines is arranged in a  
12 series of N-verging thrust fronts: from west to east, they are the outermost Emilia Arc, the  
13 Ferrara-Romagna Arc and, to the south, the Pedepenninic Thrust Front (Figure 7).  
14  
15  
16  
17  
18  
19  
20

#### 21 *Emilia Arc*

22  
23 The ITCS018 is the westernmost source of the Emilia Arc and lies south of Pavia, beneath  
24 the region extending from the Po River to the Northern Apennines foothills. Historical and  
25 instrumental catalogues show little seismicity in this area, with the notable exception of the 9  
26 October 1828 earthquake ( $M_w$  5.8; ID 7), that hit the *Valle dello Staffora* area close to the  
27 southwestern boundary of the source.  
28  
29  
30  
31  
32  
33  
34  
35

36 The ITCS044 source straddles the region between Pavia and Cremona. This area is  
37 characterized by minor seismicity with the exception of the 28 July 1276 ( $M_w$  5.1)  
38 earthquake. The San Colombano active fold, one of the few anticlines emerging in the Po  
39 Plain (TOSCANI *et al.*, 2006), is the only surface expression of this source. Based on modeling  
40 of the geometry of the fold and of the associated growth strata, and adjusting the measured  
41 tectonic deformation with back-stripping of the differential compaction of the sediment,  
42 MAESANO *et al.* (submitted) calculated for this source an average slip rate of 0.48-0.54 mm/a  
43 over the past 1.81 Ma.  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54

55 The ITCS009 source runs in a NW-SE direction from Cremona to Reggio nell'Emilia.  
56 A number of damaging earthquakes hit this area over historical times, the most important of  
57  
58  
59  
60  
61  
62  
63  
64  
65



1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

which occurred on 11 June 1438 ( $M_w$  5.6, *Parmense*; ID 9), 11 September 1831 ( $M_w$  5.5, *Reggiano*; ID 12), and 15 July 1971 ( $M_w$  5.7, *Parmense*; ID 10). Based on their peculiar intensity patterns, the 13 March 1832 ( $M_w$  5.5, *Reggiano*; ID 11) and 9 November 1983 ( $M_L$  4.8, *Parmense*; ID 62; Figure 5c) earthquakes appear to be deeper than other events, and for this reason they may be tentatively interpreted as belonging to Group #4 (see below). The 1831 and 1832 earthquakes are close both in space and time, a phenomenon that is rather common for the Italian seismicity as shown also by the 2012 Emilia sequence (see Figure 4 and Tables 2, 3 and 4). The average Pleistocene slip rate calculated for this source falls in the range 0.16-0.53 mm/a (MAESANO *et al.*, submitted).

#### *Ferrara-Romagna Arc*

The ITCS049 is the westernmost source straddling the Ferrara-Romagna Arc. It extends to the NE of the city of Reggio nell'Emilia and follows the lateral ramp of the arc. This source accounts for a number of intermediate-size yet damaging earthquakes: 10 February 1547 ( $M_w$  5.1, *Reggio Emilia*), 20 June 1671 ( $M_w$  5.2, *Rubiera*), 12 February 1806 ( $M_w$  5.2, *Novellara*), 25 Dec 1810 ( $M_w$  5.3, *Novellara*), 24 April 1987 ( $M_L$  4.6; ID 44), 15 October 1996 ( $M_w$  5.4; ID 42), and 18 June 2000 ( $M_w$  4.5, *Parmense*; ID 43). Based on the intensity pattern the 2 May 1987 earthquake ( $M_w$  4.5; *Reggiano*; ID 45) may have been generated by a deep source, and for this reason it may be assigned to Group #4 (see below). The average post-middle Pleistocene slip rate calculated for this source falls in the range 0.04-0.16 mm/a (MAESANO *et al.*, submitted).

The ITCS050 follows the most external thrust front of the Northern Apennines. Infrequent activity characterizes this portion of the plain with the only exception of the 22 February 1346 ( $M_w$  4.9, *Ferrara*) and 17 November 1570 ( $M_w$  5.5, *Ferrara*; ID 13; Figure 5a) earthquakes. The 1346 event is crucial for the understanding of the earthquake potential of

1 this region as it may have been located close to the events of the 2012 Emilia sequence;  
2 unfortunately its macroseismic signature is insufficient to derive any firm conclusions  
3 concerning its focal parameters, starting with the magnitude, and further investigations are  
4 needed.  
5  
6  
7  
8

9 The most significant earthquake recorded in instrumental times occurred on 17 July  
10 2011 ( $M_L$  4.8; ID 59; Figure 3; MASSA *et al.*, 2012); it was located along the outermost front  
11 and had a reverse focal mechanism. In contrast with its low seismic activity, this area may  
12 hold a significant seismogenic potential, as suggested by subsurface geological and  
13 geophysical data (PIERI and GROPPi, 1981; BOCCALETTI and MARTELLI, 2004; MAESANO *et*  
14 *al.*, submitted) and by evidence of active surface deformation (BURRATO *et al.*, 2003). The  
15 1570 *Ferrara* earthquake was associated with an individual thrust of this arc and identified as  
16 ITIS090 (DISS Working Group, 2010). Its location and geometry are based on subsurface  
17 geological and geophysical information constrained by geomorphological observation of the  
18 occurrence of drainage anomalies on top of the buried structure.  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32

33 The ITCS103 extends across the lower Secchia River and Panaro River valleys.  
34 Seismicity is sparse, but recent studies of historical sources suggest that a moderate-size  
35 earthquake, probably overlooked by previous workers, occurred on 6 April 1639 (CASTELLI *et*  
36 *al.*, 2012). The 2012 Emilia sequence, which began with the 20 May 2012 earthquake  
37 (ITIS134 source), activated a 10 km-long portion of the ITCS103 (Figure 7; Table 8).  
38 Subsurface data (App\_Orien-1 seismic line, available from  
39 <http://unmig.sviluppoeconomico.gov.it/videpi/>) show well developed buried anticlines (Figure  
40 8), and the coseismic deformation of the ground-surface caused by the 20 May 2012  
41 earthquake (BIGNAMI *et al.*, 2012; PEZZO *et al.*, 2013, TIZZANI *et al.*, 2013) is consistent with  
42 the characteristics of this seismogenic source.  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1 The ITCS051 source encompasses the region across the lower Secchia River and Reno  
2 River valleys. CASTELLI *et al.* (2012) found historical evidence of moderate-size earthquakes  
3 that occurred in the area on 15 December 1761 and 11 May 1778. Subsurface data (e.g.,  
4 CASSANO *et al.*, 1986) show a number of well developed buried folds, the largest being the  
5 Mirandola anticline. BURRATO *et al.* (2003) proposed that a segment of the blind thrust  
6 imaged by subsurface data could be the source of infrequent  $M_w$  5.5 or larger earthquakes in  
7 this area. The ITIS107 *Mirandola* source was identified on the basis of tectonic  
8 geomorphology observations and considerations, stressing the relationships between peculiar  
9 drainage anomalies and a major buried active fault. Between Sorbara and San Prospero the  
10 Secchia and Panaro rivers are drawn toward the earthquake epicentral area, whereas between  
11 San Felice sul Panaro and Mirandola they are pushed away from it. The existence of the  
12 ITIS107 source explains well the drainage i) being attracted towards a locally subsiding area,  
13 and ii) being diverted away from an uplifted area. As the ITIS107 *Mirandola* was not  
14 associated with any historical earthquake, its assigned  $M_w$  6.2 was derived only from the  
15 geologically constraints on the source size. This potential seismogenic source was included in  
16 the version of DISS database presented in 2000 (v. 1.0) and published in 2001 (v. 2.0,  
17 VALENSISE and PANTOSTI, 2001b). The 29 May 2012 earthquake and its associated sequence  
18 were caused by the activation of a portion of ITCS051. Notably, the 29 May mainshock may  
19 have been caused by the ITIS107 itself, and the ITCS051 source has been identified in DISS  
20 as the source responsible for the uplift of the Mirandola anticline. The coseismic deformation  
21 of the ground-surface caused by the 29 May 2012 earthquake and measured by SAR  
22 interferometry (see BIGNAMI *et al.*, 2012, among others; Table 8) is consistent with  
23 predictions based on modeling of the characteristics of this seismogenic source. The source  
24 responsible for the 29 May 2012 event is described in detail in BURRATO *et al.* (2012). The  
25 average middle Pleistocene slip rate calculated for this source falls in the range 0.50-1.04  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1 mm/a (MAESANO *et al.*, submitted); this figure is specifically based on observations carried  
2 out along sections across the buried Mirandola anticline.  
3

4 The ITCS012 source extends across the lower Reno River valley and strikes E-W to  
5 NW-SE. A number of moderate-size to damaging events have affected the area, including the  
6  
7 19 March 1624 ( $M_w$  5.5, *Argenta*; ID 14) and 30 December 1967 ( $M_w$  5.2, *Bassa Padana*)  
8 earthquakes. The 1624 earthquake is assumed to have been caused by the ITIS141 source.  
9  
10 The ITCS012 corresponds to the most advanced of the Romagna thrust fronts and marks their  
11 termination to the east. The average middle Pleistocene slip rate calculated for this source  
12 falls in the range 0.49-0.55 mm/a (MAESANO *et al.*, submitted).  
13  
14  
15  
16  
17  
18  
19  
20

21 The ITCS109 and ITCS011 extend over the portion of the Po Plain located east of  
22 Bologna. These fault systems correspond to NE-verging inner arcs located north of the  
23 Romagna foothills. Local seismicity is sparse and moderate in size, with the exceptions of the  
24 10 July 1591 ( $M_w$  5.2, *Forlì*) and 11 April 1688 earthquakes ( $M_w$  5.8, *Romagna*; ID 22).  
25  
26 Subsurface data (PIERI AND GROPPÌ, 1981; CASSANO *et al.*, 1986; FANTONI and FRANCIOSI,  
27 2010) and evidence from a number of investigators point to fast active surface deformation  
28 resulting from the tectonic activity of the buried anticlines at the rear of the Ferrara-Romagna  
29 Arc. The average middle Pleistocene slip rate calculated for the ITCS011 falls in the range  
30 0.15-0.33 mm/a (MAESANO *et al.*, submitted). A segment of the ITCS109 (ITIS100) has been  
31 hypothesized as the source of the 11 April 1688, *Romagna* earthquake. The location and  
32 geometry of this source were based on a comparison between the 1688 damage pattern and  
33 the location of major thrusts of the Ferrara-Romagna Arc in the subsurface, whereas its size  
34 was scaled to the  $M_w$  5.8 obtained from intensity data.  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55

#### 56 *Pedeapenninic Thrust Front*

57  
58  
59  
60  
61  
62  
63  
64  
65

1 The ITCS045, ITCS046, ITCS047, and ITCS001 sources run along the Pedepenninic Thrust  
2 Front. They are NE-verging thrusts and folds generating the geomorphology of the Emilia-  
3 Romagna foothills (e.g. PONZA *et al.*, 2010). Their present-day activity and seismogenic  
4 potential are suggested by subsurface geophysical data (PIERI and GROPPi, 1981; CASSANO *et*  
5 *al.*, 1986; BRUNO *et al.*, 2011), evidence of drainage anomalies (AMOROSI *et al.*, 1996),  
6 structural data (CASTELLARIN *et al.*, 1985), morphotectonic analyses (PICOTTI and PAZZAGLIA,  
7 2008; PONZA *et al.*, 2010; GUNDERSON *et al.*, 2013), and evidence from past seismicity.

8  
9  
10  
11  
12  
13  
14  
15  
16  
17 In our interpretation, the ITCS045 source marks the western end of the active Northern  
18 Apennines mountain front and has been the locus of few moderate-size earthquakes. The  
19 ITCS046 source extends across the region south of the city of Reggio nell'Emilia. Moderate-  
20 size and damaging earthquakes are numerous but sparse all across the area. Key earthquakes  
21 have occurred on 5 June 1501 ( $M_w$  6.0, *Appennino Modenese*; ID 18), 9 December 1818 ( $M_w$   
22 5.2, *Langhirano*), and 4 March 1898 ( $M_w$  5.4, *Valle del Parma*; ID 17). A moderate-size  
23 earthquake took place in 91 B.C. ( $M_w$  5.7, *Modena-Reggio Emilia*) just north of this area, but  
24 its location is inevitably very uncertain (GUIDOBONI *et al.*, 2007).

25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36 The ITCS047 extends across the upper Reno River valley, near the city of Bologna.  
37 The region is the locus of both moderate-size and damaging earthquake, mostly concentrated  
38 in its central and western portions. Key earthquakes occurred on 25 July 1365 ( $M_w$  5.4,  
39 *Bologna*; ID 21), 20 July 1399 ( $M_w$  5.1, *Modenese*), 3 January 1505 ( $M_w$  5.6, *Bolognese*; ID  
40 20), and 20 April 1929 ( $M_w$  5.3, *Bolognese*; ID 19). BOSCHI and GIUDOBONI (2003) listed a  
41 number of moderate-size earthquakes that occurred near Bologna and its surroundings,  
42 including the 4 May 1433 (I=VI MCS), 6 February 1455 (I=VIII MCS), and 20 December  
43 1455 (I=VI-VII MCS) events. The 1929 and 1505 earthquakes have been associated with two  
44 portions of ITCS047 (ITIS103 and ITIS091, respectively). The ITIS103 and the ITIS091  
45 sources are consistent with evidence of recent activity of the Pedepenninic Thrust Front

1 southwest of Bologna, which includes triangular facets, the presence of a growing anticline  
2 and a fault scarp across Holocene alluvial fans. The rivers flowing southeast of Bologna are  
3 characterized by erosional behavior and uplifted terraces (e.g. PICOTTI and PAZZAGLIA, 2008).  
4  
5 The location of the ITIS103 source is consistent with the largest damage reported following  
6  
7 the 1929 earthquake. In the same area GUIDOBONI *et al.* (2007) reported landslides, surface  
8  
9 fractures and enhanced gas discharge in nearby gas and mud volcanoes. The location of the  
10  
11 source is constrained to the east by the proximity with the ITIS091 source, assumed to be the  
12  
13 causative fault of the 3 January 1505 earthquake located between Zola Predosa and Bologna.  
14  
15 Also this source was set in agreement with the largest reported damage, and also for this area  
16  
17 GUIDOBONI *et al.* (2007) reported diffuse landslides and surface fractures, while PRESTININZI  
18  
19 and ROMEO (2000) reported liquefaction at Zola Predosa. The location of the ITIS091 source  
20  
21 is constrained to the east by the location of another  $M_w$  5.1 earthquake on 20 January 1505  
22  
23 (BOSCHI and GUIDOBONI, 2003), and to the west by the location of the 20 April 1929  
24  
25 earthquake.  
26  
27  
28  
29  
30  
31  
32

33  
34 The ITCS001 source encompasses the region to the west of the upper Savio River  
35  
36 valley. The region exhibits a concentration of both moderate-size and damaging earthquakes,  
37  
38 including the 4 August 1383 ( $M_w$  5.4, *Forlì*; ID 25), 3 July 1428 ( $M_w$  5.5, *Predappio*; ID 27),  
39  
40 11 August 1483 ( $M_w$  5.7, *Romagna meridionale*; ID 26), 4 April 1781 ( $M_w$  5.9, *Romagna*; ID  
41  
42 23), 17 July 1781 ( $M_w$  5.6, *Romagna*; ID 24), 21 September 1813 ( $M_w$  5.3, *Romagna*  
43  
44 *centrale*), 30 October 1870 ( $M_w$  5.6, *Romagna*; ID 28), and 19 February 1911 ( $M_w$  5.2,  
45  
46 *Romagna meridionale*) events. The two 1781 earthquakes comprise an additional case of  
47  
48 “twin events” discussed earlier on (see Figure 4 and Table 4). An earthquake swarm caused  
49  
50 by slip on WNW-ESE striking blind thrusts between 7 and 14 km depth occurred in the area  
51  
52 in 2000 (mainshock on 10 May 2000,  $M_L$  4.5; ID 67). Based on observations of this sequence  
53  
54 CALDERONI *et al.* (2009) provided new insight on the role of fluids involved in the  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1 seismogenic process. A segment of the ITCS001 is believed to be responsible for the 4 April  
2 1781 earthquake (ITIS093). Our source model is consistent with the location of the largest  
3 damage, and the macroseismic pattern is suggestive of a shallow fault (see the “Generalities”  
4 section for further details on this source). In contrast, PICOTTI *et al.* (2009) hypothesized that  
5 the 1781 earthquake was produced by the *Riolo Terme* normal fault. This fault belongs to a  
6 set of normal faults occurring along the foothills of the Northern Apennines, showing  
7 evidence of recent activity and interpreted to develop along the outer shell of a large growing  
8 anticline as a consequence of a local inversion of the stress field (PICOTTI *et al.*, 2009). This  
9 interpretation, however, does not agree with the damage distribution of the 4 April 1781  
10 earthquake as it leaves most of the largest intensity data points in the footwall of the fault, in  
11 contrast with the common observation that the strongest shaking due to a dip-slip fault is  
12 experienced in the hangingwall. The seismogenic potential of the normal faults investigated  
13 by PICOTTI *et al.* (2009) is also at odds with their secondary nature, as they most likely formed  
14 as a consequence of surface warping driven by a blind thrust. This further stresses the  
15 hypothesis that the main seismogenic source is the blind thrust itself.  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40

### 41 **3.3. Deep ramps of the Northern Apennines (Group #2)**

42 The ITCS027 source is the most internal compressional Composite Source of the Northern  
43 Apennines. As anticipated in the “Regional tectonic framework” section, this source  
44 corresponds with a deep thrust that has been interpreted either as a major lithospheric  
45 structure cutting the whole crust from the metamorphic basement up to the higher levels, or as  
46 one of the leading elements of the accretionary prism of the Apennines belt. In the latter case  
47 the earthquakes would generate at the interface where the sedimentary cover is delaminated  
48 from the metamorphic basement. The main differences between the two end-members in the  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1 interpretation of the structural style of this region concern the position of the basal  
2 *decollement* level of the thrusting and the presence or absence of secondary decollement  
3 levels. Some investigators (e.g. BALLY *et al.*, 1986; DOGLIONI *et al.*, 1994) indicate the  
4 bottom of the Triassic evaporites as the basal *decollement* level, and propose that the  
5 Palaeogene-Neogene evolution of the belt has been characterized by thin-skinned tectonics.  
6 Others (e.g. BARCHI *et al.*, 1998; FINETTI *et al.*, 2001; LAVECCHIA *et al.*, 2003) contend that  
7 also the upper portion of the magnetic basement was involved in thrusting, and support a  
8 thick-skinned structural style. In general most workers (e.g. BARCHI *et al.*, 1998; COWARD *et*  
9 *al.*, 1999) agree on the presence of two main *decollement* levels inside the accretionary prism;  
10 the lower coincides with the bottom of the Triassic evaporites, on which the major thrust  
11 ramps originate, whereas the shallower coincides with the Marne a Fucoidi or Scaglia Cinerea  
12 formation, the level marking the detachment of minor thrusts sheets. As a result, also the  
13 deformation style is characterized by two main structural levels: 1) a lower level, consisting of  
14 deep and broad anticlines produced by deep thrust faults detaching on the Triassic evaporites  
15 and causing deformation of the overlying Mesozoic-Palaeogene carbonate  
16 successionevaporates; and 2) an upper level, made up of small and tight anticlines lying in the  
17 axial zones of the major anticlines and developed in the Neogene foredeep sediments. These  
18 latter structures exhibit a more complex structural pattern with respect to the deeper ones.

19 We believe that the northwesternmost portion of the ITCS027 source is responsible for  
20 the 25 June 1869 ( $M_w$  5.4, *Media Valle del Reno*; ID 30), 14 September 2003 ( $M_w$  5.3,  
21 *Appennino bolognese*; ID 66) and 23 December 2008 ( $M_L$  4.8 and 5.4, *Parmense*; ID 64 and  
22 65) earthquakes; the two most recent events exhibit a depth around 20 km and reverse focal  
23 mechanisms. The ITCS027 contains two *ISSs*, the ITIS135 and ITIS058 (Figure 7). The  
24 ITIS135 is a 4.9 km-long, N98°-striking, S-dipping blind thrust fault that is held responsible  
25 for the 23 December 2008,  $M_w$  5.4 earthquake. Its strike, dip and rake were chosen based on



1 the earthquake focal solution (<http://www.bo.ingv.it/RCMT/searchRCMT.html>; PONDRELLI *et*  
2 *al.*, 2011). The mainshock occurred at 24 km depth and most of the aftershocks occurred  
3 below 20 km depth (ISIDE WORKING GROUP, 2010). As a result, the earthquake was felt over  
4 a large area (INGV, <http://www.haisentitoilterremoto.it/repository/2205007630/index.html>;  
5 ERCOLANI *et al.*, 2009).

6  
7  
8  
9  
10  
11 The ITIS058 source is a 4 km-long, N94°-striking, S-dipping blind thrust fault thought  
12 to be the source of the 14 September 2003,  $M_w$  5.3, earthquake. Similarly to the previous  
13 event, this deeper earthquake was felt over a large area but caused no damage, and its focal  
14 parameters were chosen based on its RCMT focal solution. The mainshock was located at 20  
15 km depth; the aftershocks occurred between 15 and 22 km depth and showed a sharp NE-SW  
16 alignment. Almost all of the aftershocks were located E of the mainshock. Based on the depth  
17 distribution of the aftershocks PICCININI *et al.* (2006) suggested that the mainshock occurred  
18 on a NW-dipping back-thrust of the Northern Apennines. Conversely, we propose that the  
19 mainshock occurred on a SE-dipping plane, but then triggered an aftershock sequence along a  
20 deep, subvertical fault probably corresponding with the Prato-Sillaro Line (PSL in Figure 9;  
21 see the following section on “Transverse structures” for further details).

### 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 **3.4. Inherited faults of the foreland (Group #3)**

44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65  
66  
67  
68  
69  
70  
71  
72  
73  
74  
75  
76  
77  
78  
79  
80  
81  
82  
83  
84  
85  
86  
87  
88  
89  
90  
91  
92  
93  
94  
95  
96  
97  
98  
99  
100  
101  
102  
103  
104  
105  
106  
107  
108  
109  
110  
111  
112  
113  
114  
115  
116  
117  
118  
119  
120  
121  
122  
123  
124  
125  
126  
127  
128  
129  
130  
131  
132  
133  
134  
135  
136  
137  
138  
139  
140  
141  
142  
143  
144  
145  
146  
147  
148  
149  
150  
151  
152  
153  
154  
155  
156  
157  
158  
159  
160  
161  
162  
163  
164  
165  
166  
167  
168  
169  
170  
171  
172  
173  
174  
175  
176  
177  
178  
179  
180  
181  
182  
183  
184  
185  
186  
187  
188  
189  
190  
191  
192  
193  
194  
195  
196  
197  
198  
199  
200  
201  
202  
203  
204  
205  
206  
207  
208  
209  
210  
211  
212  
213  
214  
215  
216  
217  
218  
219  
220  
221  
222  
223  
224  
225  
226  
227  
228  
229  
230  
231  
232  
233  
234  
235  
236  
237  
238  
239  
240  
241  
242  
243  
244  
245  
246  
247  
248  
249  
250  
251  
252  
253  
254  
255  
256  
257  
258  
259  
260  
261  
262  
263  
264  
265  
266  
267  
268  
269  
270  
271  
272  
273  
274  
275  
276  
277  
278  
279  
280  
281  
282  
283  
284  
285  
286  
287  
288  
289  
290  
291  
292  
293  
294  
295  
296  
297  
298  
299  
300  
301  
302  
303  
304  
305  
306  
307  
308  
309  
310  
311  
312  
313  
314  
315  
316  
317  
318  
319  
320  
321  
322  
323  
324  
325  
326  
327  
328  
329  
330  
331  
332  
333  
334  
335  
336  
337  
338  
339  
340  
341  
342  
343  
344  
345  
346  
347  
348  
349  
350  
351  
352  
353  
354  
355  
356  
357  
358  
359  
360  
361  
362  
363  
364  
365  
366  
367  
368  
369  
370  
371  
372  
373  
374  
375  
376  
377  
378  
379  
380  
381  
382  
383  
384  
385  
386  
387  
388  
389  
390  
391  
392  
393  
394  
395  
396  
397  
398  
399  
400  
401  
402  
403  
404  
405  
406  
407  
408  
409  
410  
411  
412  
413  
414  
415  
416  
417  
418  
419  
420  
421  
422  
423  
424  
425  
426  
427  
428  
429  
430  
431  
432  
433  
434  
435  
436  
437  
438  
439  
440  
441  
442  
443  
444  
445  
446  
447  
448  
449  
450  
451  
452  
453  
454  
455  
456  
457  
458  
459  
460  
461  
462  
463  
464  
465  
466  
467  
468  
469  
470  
471  
472  
473  
474  
475  
476  
477  
478  
479  
480  
481  
482  
483  
484  
485  
486  
487  
488  
489  
490  
491  
492  
493  
494  
495  
496  
497  
498  
499  
500  
501  
502  
503  
504  
505  
506  
507  
508  
509  
510  
511  
512  
513  
514  
515  
516  
517  
518  
519  
520  
521  
522  
523  
524  
525  
526  
527  
528  
529  
530  
531  
532  
533  
534  
535  
536  
537  
538  
539  
540  
541  
542  
543  
544  
545  
546  
547  
548  
549  
550  
551  
552  
553  
554  
555  
556  
557  
558  
559  
560  
561  
562  
563  
564  
565  
566  
567  
568  
569  
570  
571  
572  
573  
574  
575  
576  
577  
578  
579  
580  
581  
582  
583  
584  
585  
586  
587  
588  
589  
590  
591  
592  
593  
594  
595  
596  
597  
598  
599  
600  
601  
602  
603  
604  
605  
606  
607  
608  
609  
610  
611  
612  
613  
614  
615  
616  
617  
618  
619  
620  
621  
622  
623  
624  
625  
626  
627  
628  
629  
630  
631  
632  
633  
634  
635  
636  
637  
638  
639  
640  
641  
642  
643  
644  
645  
646  
647  
648  
649  
650  
651  
652  
653  
654  
655  
656  
657  
658  
659  
660  
661  
662  
663  
664  
665  
666  
667  
668  
669  
670  
671  
672  
673  
674  
675  
676  
677  
678  
679  
680  
681  
682  
683  
684  
685  
686  
687  
688  
689  
690  
691  
692  
693  
694  
695  
696  
697  
698  
699  
700  
701  
702  
703  
704  
705  
706  
707  
708  
709  
710  
711  
712  
713  
714  
715  
716  
717  
718  
719  
720  
721  
722  
723  
724  
725  
726  
727  
728  
729  
730  
731  
732  
733  
734  
735  
736  
737  
738  
739  
740  
741  
742  
743  
744  
745  
746  
747  
748  
749  
750  
751  
752  
753  
754  
755  
756  
757  
758  
759  
760  
761  
762  
763  
764  
765  
766  
767  
768  
769  
770  
771  
772  
773  
774  
775  
776  
777  
778  
779  
780  
781  
782  
783  
784  
785  
786  
787  
788  
789  
790  
791  
792  
793  
794  
795  
796  
797  
798  
799  
800  
801  
802  
803  
804  
805  
806  
807  
808  
809  
810  
811  
812  
813  
814  
815  
816  
817  
818  
819  
820  
821  
822  
823  
824  
825  
826  
827  
828  
829  
830  
831  
832  
833  
834  
835  
836  
837  
838  
839  
840  
841  
842  
843  
844  
845  
846  
847  
848  
849  
850  
851  
852  
853  
854  
855  
856  
857  
858  
859  
860  
861  
862  
863  
864  
865  
866  
867  
868  
869  
870  
871  
872  
873  
874  
875  
876  
877  
878  
879  
880  
881  
882  
883  
884  
885  
886  
887  
888  
889  
890  
891  
892  
893  
894  
895  
896  
897  
898  
899  
900  
901  
902  
903  
904  
905  
906  
907  
908  
909  
910  
911  
912  
913  
914  
915  
916  
917  
918  
919  
920  
921  
922  
923  
924  
925  
926  
927  
928  
929  
930  
931  
932  
933  
934  
935  
936  
937  
938  
939  
940  
941  
942  
943  
944  
945  
946  
947  
948  
949  
950  
951  
952  
953  
954  
955  
956  
957  
958  
959  
960  
961  
962  
963  
964  
965  
966  
967  
968  
969  
970  
971  
972  
973  
974  
975  
976  
977  
978  
979  
980  
981  
982  
983  
984  
985  
986  
987  
988  
989  
990  
991  
992  
993  
994  
995  
996  
997  
998  
999  
1000

Inherited faults belonging to the Mesozoic rift system and reactivated in the present-day tectonic regime represent the potential sources of perhaps the largest earthquakes that occur beneath the Po Plain, such as the 3 January 1117,  $M_w$  6.7 *Veronese* earthquake (ID 6; Table 2; Figure 3) located to the south of the Lessini mountains. Updated macroseismic intensity data for this event clearly show that the area of greatest damage lies in the Adige plain south of Verona (GUIDOBONI *et al.*, 2005). Perhaps because of the widespread effects and the fact that

1 the epicentral area has always been considered an undeformed portion of the foreland, all  
2 previous investigators located the 1117 event 30-50 km away from the macroseismic  
3 epicenter; either along exposed fault systems, such as the Veneto thrust front (GALADINI *et*  
4 *al.*, 2005), or along known buried faults, such as the thrust underlying the Piadena anticline  
5 (GALLI, 2005).  
6  
7  
8  
9  
10

11 Our hypothesis for the source of the 1117 earthquake is included in DISS as ITIS140  
12 (ITCS076; Figure 7). Its identification and parameters are based on the analysis and joint  
13 interpretation of subsurface data and morphometric indicators of the drainage pattern in the  
14 portion of the Adige plain where the largest damage was reported. In the framework of an  
15 investigation of drainage patterns in the entire Po Plain, BURRATO *et al.* (2003) found that the  
16 Mincio and Adige river courses exhibit an anomalous behavior. A subsequent study identified  
17 drainage and topographic anomalies also along minor rivers of the area, all compatible with  
18 the existence of a buried reverse fault which would induce vertical relative ground motions in  
19 the region lying between the mid-course of the Adige and Mincio rivers. The best fitting  
20 reverse fault derived from modeling of these anomalies was seen to match a buried structure  
21 recognized in seismic exploration lines, a former extensional fault that is suitably oriented  
22 (ENE-WSW) for being reactivated under the current stress field. For an in-depth description  
23 of this source and its references the reader may refer to  
24 <http://diss.rm.ingv.it/dissHTML/ITCS076INF.html>.  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45

46 Owing to their location and inferred hypocentral depth, infrequent events beneath the  
47 Po Plain may be associated with the reactivation of inherited faults. Among these, the 15 May  
48 1951,  $M_w$  5.4 *Lodigiano* earthquake (ID 8) occurred in a poorly investigated region between  
49 the more advanced fronts of the Northern Apennines and those of the Southern Alps, north of  
50 the Emilia Arc (Figure 9a). Its location is made less certain by its unusual intensity pattern,  
51 which appears rather spread out thus suggesting a deeper source (MELONI *et al.*, 1988).  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

Nevertheless, the 1951 event falls outside the two compressional systems and far from any of the transverse structures discussed in the next section (Figure 3). For this reason we suggest it may have been generated by one of the inherited faults of the foreland, even if its true seismogenic source has not been identified yet. The location of this earthquake was already reported as unusual by CALOI *et al.* (1956), who remarked that it falls in a totally aseismic region. Owing to the presence of several productive gas fields in the epicentral area, they concluded that the event could be seen as an induced earthquake, which would explain its unusual location. Based on its presumably large depth, however, and to the ongoing compression between the Emilia Arc and the Southern Alps, we rather interpret the 1951 earthquake as a natural event generated by one of the inherited faults that exist in the metamorphic basement (ROGLEDI, 2010; Figure 9a).

Two other candidate earthquakes for having been generated by inherited fault systems are the 22 October 1796,  $M_w$  5.6 *Emilia orientale* and the 13 January 1909,  $M_w$  5.5 *Bassa Padana* “deep” earthquakes (ID 15 and 16, respectively). These events are located close to each other within the Ferrara-Romagna Arc. As discussed in the following section, they occurred beneath the Po Plain at a hypothesized depth that causes them to fall below the basal detachment of the thrust wedge. As discussed below, their causative faults are still under investigation and may belong to Group #4.

### 3.5. Transverse structures (Group #4)

The transverse structures are expressed as lineaments oriented mainly northeast-southwest in the Northern Apennines thrust belt, hence roughly perpendicular to the chain, and northwest-southeast across the Southern Alps. They were hypothesized as early as the ‘50s based on geomorphological observations and on evident lithological and facies discontinuities in the

1 regional geological texture (e.g. SIGNORINI, 1953; BOCCALETTI *et al.*, 1977; FAZZINI and  
2 GELMINI, 1982 for the Apennines; CASTELLARIN and VAI, 1986; CASTELLARIN *et al.*, 1998,  
3  
4 for the Alps). Although their nature and kinematics are still largely unknown, they seem to  
5  
6 subdivide the Northern Apennines and Southern Alps thrust fronts into 30-50 km-long  
7  
8 sections (e.g. CASTELLARIN *et al.*, 1985). In the first public release of the DISS database (v.  
9  
10 2.0, VALENSISE and PANTOSTI, 2001b) they were compiled, georeferenced and plotted along  
11  
12 with known seismogenic sources and major earthquakes, suggesting 1) that they play a  
13  
14 passive role in controlling the current distribution of seismic release, but also 2) that they may  
15  
16 themselves host significant earthquakes. Unfortunately there is little evidence for the exact  
17  
18 geometry and the activity of these lineaments, both at the surface and in the subsurface, and  
19  
20 even their role in the geodynamic framework of the Northern Apennines and Southern Alps is  
21  
22 still the matter of debate (e.g. SORGI *et al.* 1998; ELTER *et al.*, 2012).  
23  
24  
25  
26  
27  
28

29 Most of the CSSs discussed in this paper terminate where the most significant of such  
30  
31 transverse structures bound palaeogeographic domains, effectively acting as boundaries to  
32  
33 earthquake propagation. The CSSs of the Southern Alps are bounded to the east by the Schio-  
34  
35 Vicenza Line (Figure 7), a NW-SE, 120-km long, subvertical strike-slip fault (e.g.  
36  
37 PELLEGRINI, 1988; CASTALDINI and PANIZZA, 1991; VIGANÒ *et al.*, 2008). The Schio-Vicenza  
38  
39 Line does not appear to have generated earthquakes larger than magnitude 5.5, but significant  
40  
41 earthquakes are expected along the neighboring CSSs of the Eastern Southern Alps, shown in  
42  
43 blue in Figure 1 (see GALADINI *et al.*, 2005, and BURRATO *et al.*, 2008 for an overview).  
44  
45  
46  
47  
48

49 We interpreted the transverse structures as the brittle response of the upper lithosphere  
50  
51 to the lateral changes in the geometry of the subducting slab as reflected in the dip of the  
52  
53 foreland monocline (MARIOTTI and DOGLIONI, 2000). This interpretation is based on the  
54  
55 observation that 1) the thrust belts show undulations controlled by inherited Mesozoic horsts  
56  
57 and grabens (see section on “Palaeogeographic control on active tectonics”), with recesses  
58  
59  
60  
61  
62  
63  
64  
65

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

occurring around horsts and salients developing in grabens (Table 1), and that 2) the terminations of these undulations match the transverse structures and are reflected in the shape of the CSSs, resulting in first-order segmentation of the compressional fault systems.

The deeper earthquakes play a central, albeit poorly understood, role in the assessment of the seismogenic potential of these transverse structures. Over the past few decades a significant amount of moment has been released in relatively deep earthquakes generated by unknown sources. Figure 9a shows the lineaments (i.e. transverse structures) reported in the literature, and the instrumental and historical earthquakes deeper than 15 km (see Tables 2 and 3). The focal mechanisms of these deep earthquakes are both reverse and strike-slip. In detail:

- the source of the 13 September 1989,  $M_L$  4.7 earthquake (ID 40), having a depth of 40 km and a strike-slip focal mechanism, falls below the Schio-Vicenza Line and is hence assigned to it;
- the majority of deep instrumental and historical earthquakes (ID 41, 45, 11, 62, 29, and 63) fall in a relatively small area of the Apennines and Pedepennines. The 13 March 1832,  $M_w$  5.5 (ID 11) and the 17 September 1873,  $M_w$  5.4 (ID 29) earthquakes exhibit the characteristic signature of deep earthquakes (Figure 5). The 2 May 1987,  $M_L$  4.5 (ID 45) and the 9 November 1983,  $M_L$  4.8 (ID 62; Figure 5c) events are both reported at a depth around 25 km and exhibit strike-slip and transpressional focal mechanisms, respectively. The 25 January 2012,  $M_L$  5.0 (ID 41) and the 27 January 2012,  $M_L$  5.2 (ID 63) earthquakes exhibit a depth of 29 and 72 km with transtensional and reverse kinematics, respectively. The location of all these events corresponds to the location of significant lateral changes in the foreland monocline. The monocline plunges beneath the Apennines thrust belts and accretionary wedges with a dip that varies laterally between 14°, 8° and

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

23°. This area is a crucial crossroad as it controls the forward propagation of the shallow thrusts, ultimately causing a significant northward shift of the Po River near Guastalla. Furthermore this area of deformation falls at the northern end of a major transverse structure, namely the Enza Line (EL in Figure 9), a strike-slip fault inferred from stratigraphic and structural data displaying dip-slip kinematics in Middle-Late Pliocene-Pleistocene (CASTELLARIN *et al.*, 1985);

- we propose that the source of 3 October 2012,  $M_L$  4.5 earthquake (ID 61), having a depth around 30 km and a strike-slip focal mechanism, marks a less visible transverse structure located in between the Upper Val Trebbia and Stirone-Ongina Lines (CASTELLARIN *et al.*, 1985);
- the 25 June 1869,  $M_w$  5.4 earthquake (ID 30) is a deep event that occurred near the junction of the Apennines deep ramps and the Viareggio-Val di Lima-Bologna transverse structure (VVL in Figure 9). As such, it might belong equally well to Group #2 or #4;
- the 14 September 2003,  $M_w$  5.3 earthquake (ID 66) already described in Group #2 makes an interesting case. With a depth of about 20 km and a reverse focal mechanism its mainshock is likely to have been generated by one of the deep ramps; but the subsequent aftershock sequence delineated likely a deep, subvertical fault probably corresponding with the Prato-Sillaro Line (PSL in Figure 9). This transverse structure is inferred from remote sensing, surface geology and structural data (BOCCALETTI *et al.*, 1985; CASTELLARIN *et al.*, 1985);
- the 22 October 1796,  $M_w$  5.6 (ID 15) and 13 January 1909,  $M_w$  5.5 (ID 16; Figure 5b) earthquakes exhibit the characteristic signature of the deep earthquakes, and occurred at approximately the same location of the southeastern Po Plain (see section on “Seismicity and earthquake budgets”). These two events are therefore below the thrusts of the Ferrara-Romagna arc. In principle they may have been caused by as yet unknown inherited

1 structures of the Group #3. Their locations, however, fall near a strong lateral variation of  
2 the dip of the foreland monocline, possibly marking the extension of the Prato-Sillaro  
3 Line (PSL in Figure 9) beneath the Po Plain deposits. To the south, west of the Mugello  
4 basin, the same lineament appears to interrupt the continuity of the Etrurian Fault System,  
5 a major extensional system straddling the crest of the Northern Apennines (Figure 9a).  
6  
7 When placed in a palaeogeographic perspective, the Prato-Sillaro Line appears much as  
8 the mirror image to of the Enza Line, although less obvious. We conclude that the 1796  
9 and 1909 earthquakes may have been generated by the northeastern extension of the  
10 Prato-Sillaro Line, and should hence belong to Group #4;

- 21 • the 5 April 2009,  $M_L$  4.6 earthquake (ID 68), occurred with a transpressional focal  
22 mechanism below the shallow Pedepenninic Thrust Front, but at a depth of about 25 km.  
23  
24 Based on its location, this event could have been generated by the Montone Line (ML in  
25 Figure 9a), therefore belonging to Group #4;
- 26 • finally, the 6 June 2012,  $M_L$  4.5 earthquake (ID 60) occurred in the Adriatic Sea, just a  
27 few kilometers offshore, at the eastern end of the Ferrara-Romagna arc. Its 26 km depth  
28 and the dominantly strike-slip mechanism suggest it may be evidence for a sort of  
29 “rebound” of the eastern end of the arc only a few days after the strong shocks of 20 and  
30 29 May 2012.

31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46 In summary, a number of sizable historical and instrumental earthquakes of the  
47 Northern Apennines seem to follow well defined trends that correspond with the main  
48 mapped transverse lineaments. This circumstance is further stressed by the seismic release  
49 pattern delineated by the 2009-2013 sequences (Figure 9b). Indeed these mostly shallow  
50 sequences occurred far from the inherited faults described above (belonging to Group #3), but  
51 seem to delineate well the pattern of the transverse structures. These structures also play an

1 important passive role in the propagation of ground shaking caused by significant deeper  
2 earthquakes (e.g. see the 25 January 2012 earthquake:  
3 <http://mappe.haisentitoilterremoto.it/2221246460/index.html>, or the 27 January 2012  
4 earthquake: <http://mappe.haisentitoilterremoto.it/2221279330/mcs.jpg>, both of which  
5 propagated efficiently southeastward only up to the Prato-Sillaro Line). Similarly, the  
6 aftershocks of the 2012 *Emilia* sequence terminated against the Secchia Line (SL in Figure  
7 9b), which played an obvious passive role.  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21

## 22 **4. Discussion and conclusions**

### 23 24 25 26 27 **4.1. Identifying seismogenic sources in the Po Plain**

28 The correct identification of seismogenic sources in the Po Plain is a crucial and extremely  
29 complex task that requires unconventional data and innovative approaches and  
30 methodologies. As most of the seismogenic faults are blind and cannot be detected by  
31 standard field mapping, the vast majority of the relevant input must be derived from  
32 subsurface data, drainage and sedimentary patterns, and seismicity.  
33  
34  
35  
36  
37  
38  
39  
40  
41

42 Despite these unfavorable circumstances, the investigation of the local seismotectonic  
43 setting is somewhat easier than in other parts of the Italian peninsula. The Po Plain has  
44 undergone steady compression and shortening from the Upper Pliocene to Present, generating  
45 a relatively monotonous series of thrust faulting systems that are progressively younger as one  
46 moves from west to east and from the inner to the outer portions of the two confronting  
47 orogens, the Alps and the Apennines. In marked contrast, the inner portions of the Apennines  
48 have witnessed a recent and drastic change in the dominant stress field and the onset of  
49 significant regional uplift. The combination of these two circumstances makes field mapping  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65



1  
2 especially difficult and potentially misleading, as the limited cumulated effects of the present-  
3 day extensional tectonics are masked by the occurrence of faults generated under previous  
4 regimes and rejuvenated by the ongoing uplift (VALENSISE and PANTOSTI, 2001a).  
5  
6

7 Current slip rates are relatively low on faults of the Po Plain, implying more infrequent  
8 earthquakes and hence a lower seismic hazard. The analysis of cumulative strain over  
9 different time intervals, however, shows that at least in the southern portion of the Po Plain  
10 deformation used to be faster but has steadily slowed down in recent geological times  
11 (MAESANO *et al.*, submitted).  
12  
13  
14  
15  
16  
17  
18

19 The correct estimation of slip rates requires proper considerations of the effects of  
20 differential compaction (SCROCCA *et al.*, 2007; MAESANO *et al.*, 2013; MAESANO *et al.*,  
21 submitted). The cumulative shortening of the two confronting orogens has created significant  
22 relief in the subsurface, where carbonate ridges nearly reaching the topographic surface are  
23 juxtaposed to deep troughs filled by as many as 8,000 m of Pliocene-Pleistocene sediments.  
24 These deposits are naturally bound to reduce their volume; the expected volume reduction,  
25 however, is proportional to the thickness of the unconsolidated sedimentary layers, which  
26 varies greatly from place to place. As a result, the compaction will be differential, i.e. it will  
27 be more pronounced in the deep troughs than on top of the anticlines (e.g. MAESANO *et al.*,  
28 2013). The ensuing differential volume loss may simulate the outcomes of tectonic activity  
29 even over long time periods after activity has ceased. In other words, tectonic activity  
30 associated with crustal shortening promotes the creation of uplifted areas, where  
31 sedimentation is limited or absent, and lowlands, that act as sediment traps; but differential  
32 compaction itself induces relative thickness changes of the sedimentary layers, simulating the  
33 geometry of growth strata and causing a trade-off between the outcomes of genuine tectonic  
34 activity and standard sedimentary effects. All in all, differential compaction may lead to a  
35 gross overestimation of the tectonic rates, in the milder cases, or to mistaking a dead for an  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1 active fault, in the most severe instances. Assessing the role of differential compaction is  
2 hence a crucial step in the assessment of the earthquake potential of faults buried by a thick  
3  
4 blanket of unconsolidated sediments  
5  
6

7 Accurate seismic hazard assessment in the Po Plain is important due to the large  
8  
9 number of industries and critical infrastructures and to the concentration of over 10 million  
10  
11 people, about 20% of the country's population. And even though Po Plain earthquakes are  
12  
13 generally quite moderate compared to those located in peninsular Italy, anticipating where,  
14  
15 how frequently and how strongly that may strike takes on a special significance and requires  
16  
17 special care. As in many other *problematic* areas worldwide, no individual dataset alone may  
18  
19 allow to identify all seismogenic sources unambiguously, and resorting to a blend of diverse  
20  
21 observations becomes mandatory. Due to the limited geological strain rates and to the  
22  
23 sparseness of seismicity, any conclusion must be carefully constrained by regional-scale  
24  
25 geodynamic models and evidence for ongoing deformation (GPS). The seismotectonic model  
26  
27 presented in this paper is indeed the result of such blending, and is also a scheme that will be  
28  
29 easy to test as more data become available.  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40

#### 41 **4.2. Observed and expected seismicity**

42  
43  
44

45 The Po Plain is the locus of moderate-size (normally < M 6.0) and infrequent earthquakes, at  
46  
47 least compared to peninsular Italy, and probably for this reason its seismic hazard has long  
48  
49 been underrecognized. Earthquake codes have acknowledged the local earthquake potential  
50  
51 only since 2004, and it has taken six more years for the new provisions to be fully enforced.  
52  
53  
54 This has resulted in inadequate earthquake protection which largely explains the human loss  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1 and material caused by the May 2012 Emilia earthquakes ( $M_L$  5.9 and 5.8), when 27 people  
2 died in collapsed factory buildings (STUCCHI *et al.*, 2012).  
3

4 We subdivided the damaging Po Plain earthquakes into shallow and deep, depending  
5 on whether they occur above or below 15 km depth (Figure 3; Tables 2, 3). Shallow events  
6 are more damaging and sometimes catastrophic, whereas deep events usually do not cause  
7 extreme damage but are strongly felt over large areas (Figure 5). In summary the Po Plain is  
8 expected to experience (see Figure 5 and Table 5):  
9

- 10 • shallow damaging earthquakes, such as the 17 November 1570 *Ferrara* and the 20-29  
11 May 2012 *Emilia* events, which are responsible for 84-96% of the total moment release  
12 (depending on the time frame considered);  
13
- 14 • deep earthquakes, such as the 13 January 1909 *Bassa Padana* and the 9 November 1983  
15 *Parmense* events, which are responsible for 16-4% of the total moment release (depending  
16 on the time frame considered);  
17
- 18 • sequences with multiple mainshocks, such as the 1504-1505 *Bolognese*, the 1570 *Ferrara*,  
19 the 1781 *Faenza*, the 1916 *Rimini* and the 2012 *Emilia* events; in fact, the majority of  
20 crustal earthquakes, both historical and instrumental, exhibit this characteristic behavior  
21 (Table 4 and Figure 4); and  
22
- 23 • infrequent destructive earthquakes, such as the 3 January 1117,  $M_w$  6.7 *Veronese* event,  
24 that are difficult to anticipate as they are generated by the least known category of  
25 seismogenic sources of the Po Plain (*inherited faults*, Group #3).  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50

51 Shallow earthquakes occur following a relatively regular pattern along major  
52 identified buried thrusts, with a concentration on the external front of the Ferrara-Romagna  
53 Arc and on the Pedepenninic Thrust Front (Figure 3). In contrast, deep earthquakes are  
54 concentrated in relatively small areas, possibly coincident with the transverse structures  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1 (Figures 3b and 9a). All in all, the Northern Apennines structures (Emilia Arc, Ferrara-  
2 Romagna Arc and Pedeapenninic Thrust Front) exhibit a larger seismogenic release compared  
3  
4 to the Southern Alps (Southern Alps Outer Arc plus Southern Alps Mountain Front), both in  
5  
6 historical times and instrumental. More specifically (Figures 3, 7):  
7  
8  
9

- 10
- 11
- 12 • the earthquake potential of the main fronts of the Northern Apennines increases from west  
13 (Monferrato Arc, Emilia Arc) to east (Ferrara-Romagna Arc);  
14
- 15 • the Pedeapenninic Thrust Front, that lies close and beneath the main urban areas of  
16 Emilia-Romagna, has released significantly in historical times but has been almost totally  
17 quiescent in the past few decades;  
18
- 19 • the *deep ramps* host a small fraction of the total earthquake potential;  
20
- 21 • multiple sequences occur preferentially on shallow thrusts, and specifically on those  
22 belonging to the Emilia and Ferrara-Romagna Arcs.  
23

24  
25 Finally, Po Plain seismogenic sources exhibit a large variability in terms of maximum  
26 magnitude, ranging from 5.5 to 6.7 (Figure 10). Sources expected to generate the strongest  
27 earthquakes include that responsible for 1117 earthquake (ITIS140, ITCS076) and the *deep*  
28 *ramps* (ITCS027). Sources of the Ferrara-Romagna Arc, of the Pedeapenninic Thrust Front  
29 and the thrusts and backthrust of the outer arc of the Southern Alps are known to have  
30 generated earthquakes up to  $M_w$  6.1. Finally, sources of the Southern Alps Mountain Front, of  
31 the Giudicarie System and of the Emilia Arc have not exceeded  $M_w$  5.7 historically.  
32  
33

### 34 **4.3. Summary and open issues**

35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50

51 We described a large set of seismogenic sources encompassing the Po Plain. The vast  
52 majority of the sources exhibit a minimum and maximum faulting depth of 1-5 km and 7-10  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1 km, respectively, reflecting the characteristic geometries and depths of the Alps and  
2 Apennines accretionary wedges. Exceptions are the *deep ramps* (ITCS027), where  
3 earthquakes are assumed to take place at a depth of 12-22 km, and the *transverse structures*,  
4 that appear to generate seismicity over a wide depth range.  
5  
6  
7

8  
9 Due to obvious geological reasons, the accuracy of our seismotectonic model  
10 decreases rapidly as faulting depth increases. If it may be reassuring to learn that most of the  
11 moment is released by shallower and hence easier to identify sources, we must keep in mind  
12 that they also cause the strongest ground shaking. In contrast, future earthquakes are likely to  
13 be spawned by deep and largely unexplored seismogenic sources, but we also know that the  
14 associated ground shaking will be milder. The investigation of these deep sources is a priority  
15 for future research efforts. These will necessarily include an improved consideration of the  
16 role exerted on thrust development by the palaeogeography of the Alpine margin, a  
17 clarification of the role of the *transverse structures* cross-cutting the Northern Apennines, and  
18 a reassessment of the seismotectonic evidence supplied by seismicity.  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32

33  
34 Perhaps the main obstacle towards a better understanding and more accurate  
35 assessment of the earthquake potential of the Po Plain, however, is the question of the limited  
36 *earthquake efficiency* or *seismic coupling* of the local seismogenic sources. BARBA *et al.*  
37 (2010) have shown that the seismic moment released by the compressional earthquake  
38 sources encircling the Po Plain is less than 25% of the moment estimated from geological  
39 observations and geodynamic modeling. This begs the question: is low efficiency a permanent  
40 characteristic of the Po Plain, or perhaps of all similar thrust faulting systems worldwide?  
41 Does *low efficiency* imply that the same faults behave seismically and aseismically at the  
42 same time, or does it mean that many faults slip aseismically without ever generating  
43 earthquakes while a few only slip coseismically? There may well be a deficit in historical  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1 moment release, but how accurately do we know the historical earthquake record? Can we  
2 rule out the occurrence of rare large earthquakes that would rebalance the earthquake budget?  
3

4 Instrumental monitoring of the Po Plain has provided reliable earthquake locations and  
5 focal mechanisms over the past 30 years. In contrast, the historical seismicity record is likely  
6 to be incomplete for at least two reasons. The first and principal reason has to do with the  
7 environmental characteristics of large portions of the Po Plain. Unbeknown to many, this  
8 industrialized and heavily urbanized part of Italy was once covered by large forests and  
9 marshlands, and hence sparsely populated. Before the construction of large modern levees,  
10 some of which were completed as late as the end of the XVII century, many Po Plain rivers  
11 wandered across the plain driven by the distribution of topographic highs and lows. The  
12 second reason is that much of the seismic moment may have been released in deep  
13 earthquakes, but since these cause only mild shaking many of such events may have gone  
14 undetected through history and until relatively recent times.  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30

31 As a result, the pre-instrumental earthquake record may be locally incomplete,  
32 particularly in the marshy areas of the southern Po Plain between the Ferrara-Romagna Arc  
33 and the Pedepenninic Thrust Front. Much of the available information refers to earthquakes  
34 recorded at the cultural and economic centers, such as Ferrara and Mirandola, normally  
35 located in *dry spots* on top of buried anticlines, making it difficult to separate small local from  
36 larger and more distant events. This implies that the effective *completeness* of the Po Plain  
37 earthquake record may be as short as a few centuries, even where tectonic deformation is  
38 fastest such as in the central-southern Po Plain, thus inducing and explaining the known fast  
39 landscape changes.  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51

52 In summary, how accurate is the seismotectonic model described in this paper? The 20  
53 and 29 May 2012 Emilia-Romagna earthquakes and the associated sequence indeed validated  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1  
2 it, and the overall match between the observed seismicity and the current geological  
3 understanding is encouraging. Yet the biggest challenges may still lie ahead of us.  
4  
5  
6  
7  
8

9  
10 **Acknowledgements**

11  
12 We wish to thank all colleagues of the DISS Working Group, who helped characterizing the  
13 seismogenic sources of the Po Plain with constructive comments and discussions. We also  
14 thank Riccardo Caputo, Silvio Seno and an anonymous reviewer for their careful and  
15 thoughtful reviews; but we are especially grateful to the Associate Editor, Antonio Rovelli,  
16 for encouraging the submission of this very long contribution.  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

## References

- 1  
2  
3 ALBINI, P., and ROVIDA, A. (2010), The 12 May 1802 earthquake (N Italy) in its historical and  
4  
5 seismological context, *J. Seismol.* *14*, 629-651, doi:10.1007/s10950-010-9187-6.  
6
- 7 AMOROSI, A., FARINA, M., SEVERI, P., PRETI, D., CAPORALE, L., and DI DIO, G. (1996),  
8  
9 Genetically related alluvial deposits across active fault zones: an example of alluvial  
10  
11 fan-terrace correlation from the upper Quaternary of the southern Po Basin, Italy,  
12  
13 *Sediment. Geol.* *102*, 275-295, doi: 10.1016/0037-0738(95)00074-7.  
14  
15
- 16 AMOROSI, A., COLALONGO, M.L., FIORINI, F., FUSCO, F., PASINI, G., VAIANI, S.C., and SARTI,  
17  
18 G. (2004), Palaeogeographic and palaeoclimatic evolution of the Po Plain from 150-ky  
19  
20 core records, *Global and Planetary Change* *40*, 55-78, doi: 10.1016/S0921-  
21  
22 8181(03)00098-5.  
23  
24  
25
- 26 ANDERSON, H., and JACKSON, J. (1987), Active tectonics of the Adriatic region, *Geophys. J.*  
27  
28 *R. Astron. Soc.* *91*, 937-983.  
29  
30
- 31 ARCA, S., and BERETTA, G.P. (1985), Prima sintesi geodetico-geologica sui movimenti  
32  
33 verticali del suolo nell'Italia Settentrionale (1897-1957), *Boll. Geod. Sc. Aff.* *44*, 125-  
34  
35 156.  
36  
37  
38
- 39 BALLY, A.W., BURBI, L., COOPER, C., and GHELARDONI, R. (1986). Balanced sections and  
40  
41 seismic reflection profiles across the central Apennines, *Mem. Soc. Geol. It.* *35*, 257-  
42  
43 310.  
44  
45
- 46 BARATTA, M. (1901), *I terremoti d'Italia*, Arnaldo Forni Editore, Torino, Italy, pp. 952.  
47  
48
- 49 BARBA, S., CARAFA, M.M.C., and DOGLIONI, C. (2010), Time-independent nationwide  
50  
51 earthquake rates derived from models and geological data. In: BARBA, S., and  
52  
53 DOGLIONI, C., Project S1: Analysis of the seismic potential in Italy for the evaluation of  
54  
55 the seismic hazard, Final Report DPC-INGV 2007-2010 S1 Project,  
56  
57 [ftp://ftp.ingv.it/pro/dpcs1\\_dati/final\\_report/RUT01\\_deliv2\\_EQrate.docx](ftp://ftp.ingv.it/pro/dpcs1_dati/final_report/RUT01_deliv2_EQrate.docx).  
58  
59  
60  
61  
62  
63  
64  
65



- 1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65
- BARCHI, M.R., MINELLI, G., and PIALLI, G. (1998), The CROP 03 profile: A synthesis of results on deep structures of the northern Apennines, *Mem. Soc. Geol. It.* 52, 383-400.
- BARTOLINI, C., CAPUTO, R., and PIERI, M. (1996), Pliocene-Quaternary sedimentation in the Northern Apennine foredeep and related denudation, *Geological Magazine* 133, 255-273.
- BASILI, R., VALENSISE, G., VANNOLI, P., BURRATO, P., FRACASSI, U., MARIANO, S., TIBERTI, M.M. and BOSCHI, E. (2008), The Database of Individual Seismogenic Sources (DISS), version 3: summarizing 20 years of research on Italy's earthquake geology, *Tectonophysics* 453, 20-43, doi: 10.1016/j.tecto.2007.04.014.
- BASILI, R., KASTELIC, V., and VALENSISE, G. (2009), DISS3 tutorial series: Guidelines for compiling records of the Database of Individual Seismogenic Sources, version 3, *Rapporti Tecnici INGV*, 108, 20 pp.
- BERTOTTI, G., PICOTTI, V, BERNOULLI, D., and CASTELLARIN, A. (1993), From rifting to drifting: tectonic evolution of the Southalpine upper crust from the Triassic to the Early Cretaceous, *Sediment. Geol.* 86, 1-2, 53-76, doi: 10.1016/0037-0738(93)90133-P.
- BIGI, G., BONARDI, G., CATALANO, R., COSENTINO, D., LENTINI, F., PAROTTO, M., SARTORI, R., SCANDONE, P., and TURCO, E. (Eds.) (1992), *Structural Model of Italy 1:500,000*, CNR Progetto Finalizzato Geodinamica.
- BIGI, S., LENCI, F., DOGLIONI, C., MOORE, J.C., CARMINATI, E., and SCROCCA, D. (2003), Décollement depth versus accretionary prism dimension in the Apennines and the Barbados, *Tectonics* 22, 2, 1010, doi: 10.1029/2002TC001410.
- BIGNAMI, C., BURRATO, P., CANNELLI, V., CHINI, M., FALCUCCI, E., FERRETTI, A., GORI, S., KYRIAKOPOULOS, C., MELINI, D., MORO, M., NOVALI, F., SAROLI, M., STRAMONDO, S, VALENSISE, G., and VANNOLI, P. (2012), Coseismic deformation pattern of the Emilia

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

2012 seismic sequence imaged by Radarsat-1 interferometry, *Ann. Geophys.* *55*, 4,  
789-795, doi: 10.4401/ag6157.

BOCCALETTI, M., FAZZUOLI, M., LODDO, M., and MONGELLI, F. (1977), Heat-flow  
measurements on the Northern Apennine arc, *Tectonics* *41*, 1-3, 101-112, doi:  
10.1016/0040-1951(77)90182-2.

BOCCALETTI, M., COLI, M., EVA, C., FERRARI, G., GIGLIA, G., LAZZAROTTO, A., MERLANTI, F.,  
NICOLICH, R., PAPANI, G., and POSTPISCHL, D. (1985), Considerations on the  
seismotectonics of the Northern Apennines, *Tectonophysics* *117*, 7-38.

BOCCALETTI, M., and MARTELLI, L. (Eds.) (2004), *Carta sismotettonica della Regione Emilia-  
Romagna*, Scale 1:250,000. RER, Servizio Geologico, Sismico e dei Suoli.

BOCCALETTI, M., CORTI, G., and MARTELLI, L. (2011), Recent and active tectonics of the  
external zone of the Northern Apennines (Italy), *Int. J. Earth Sci.* *100*, 1331-1348, doi:  
10.1007/s00531-010-0545-y.

BONINI, L., TOSCANI, G., and SENO, S. (2014), Three-dimensional segmentation and different  
rupture behaviour during the 2012 Emilia seismic sequence (Northern Italy),  
*Tectonophysics*, doi: 10.1016/j.tecto.2014.05.006.

BOSCHI, E., GUIDOBONI, E., FERRARI, G., MARIOTTI, D., VALENSISE, G., and GASPERINI, P.  
(Eds.) (2000), *Catalogue of Strong Italian Earthquakes from 461 B.C. to 1980*, *Ann.  
Geofis.* *43*, 4, 609-868.

BOSCHI, E., and GUIDOBONI, E. (2003), *I terremoti a Bologna e nel suo territorio dal XII al  
XX secolo*, Istituto Nazionale di Geofisica e Vulcanologia - Storia Geofisica  
Ambiente, Editrice Compositori.

BOSELLINI, A., and HSU, K.J. (1973), Mediterranean Plate Tectonics and Triassic  
Palaeogeography, *Nature* *244*, 144-146, doi: 10.1038/244144a0.

- 1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65
- BRUNO, P.P.G., PAZZAGLIA, F.J., and PICOTTI, V. (2011), Evidence for active folding and faulting at the northern Apennines mountain front near Bologna, Italy from high resolution seismic reflection profiling, *Geophys. Res. Lett.*, 38, L16302, doi:10.1029/2011GL047828.
- BURRATO, P., CIUCCI, F., and VALENSISE, G. (2003), An inventory of river anomalies in the Po Plain, Northern Italy: evidence for active blind thrust faulting, *Ann. Geophys.* 5, 865-882, doi :10.4401/ag-3459.
- BURRATO, P., POLI, M. E., VANNOLI, P., ZANFERRARI, A., BASILI, R., and GALADINI, F. (2008), Sources of Mw 5+ earthquakes in northeastern Italy and western Slovenia: an updated view based on geological and seismological evidence, *Tectonophysics* 453, 157-176, doi: 10.1016/j.tecto.2007.07.009.
- BURRATO, P., VANNOLI, P., FRACASSI, U., BASILI, R., and VALENSISE, G. (2012), Is blind faulting truly invisible? Tectonic-controlled drainage evolution in the epicentral area of the May 2012, Emilia-Romagna earthquake sequence (northern Italy), *Ann. Geophys.* 55, 4, 525-531, doi: 10.4401/ag6182.
- CALDERONI, G., DI GIOVAMBATTISTA, R., BURRATO, P., and VENTURA, G. (2009), A seismic sequence from Northern Apennines (Italy) provides new insight on the role of fluids in the active tectonics of accretionary wedges, *Earth Planet. Sc. Lett.* 281, 1-2, 99-109, doi: 10.1016/j.epsl.2009.02.015.
- CALOI, P., DE PANFILIS, M., DI FILIPPO, D., MARCELLI, L., and SPADEA, M.C. (1956), Terremoti della Val Padana del 15-16 maggio 1951, *Ann. Geofis.* 9, 1, 63-105.
- CARAFÀ, M.M.C., and S. BARBA (2013), The stress field in Europe: optimal orientations with confidence limits, *Geophys. J. Int.*, 193, 531-548, doi: 10.1093/gji/ggt024.

- 1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65
- CARMINATI, E., and MARTINELLI, G. (2002), Subsidence rates in the Po plain (northern Italy):  
The relative impact of natural and anthropogenic causation, *Eng. Geol.* *66*, 241-255,  
doi: 10.1016/S0013-7952(02)00031-5.
- CARMINATI, E., and DOGLIONI, C. (2012), Alps Vs. Apennines: The paradigm of a tectonically  
asymmetric Earth, *Earth-Sci. Rev.* *112*, 67-96, doi: 10.1016/j.earscirev.2012.02.004.
- CASSANO, E., ANELLI, A., FICHERA, R., and CAPPELLI, V. (1986), Pianura Padana:  
interpretazione integrata di dati geologici e geofisici, Proceedings of the 73° Meeting  
of the Società Geologica Italiana, September 29-October 4, 1986, Rome, Italy, 27.
- CASTALDINI, D., and PANIZZA, M. (1991), Inventario delle faglie attive tra i Fiumi Po e Piave  
e il Lago di Como (Italia Settentrionale), *Il Quaternario* *4*, 2, 333-410.
- CASTALDINI, D., GASPERI, G., PANIZZA, M., and PELLEGRINI, M. (1979), Neotettonica dei  
Fogli 74 (Reggio nell'Emilia) (p.p.) e 75 (Mirandola) nell'intervallo da 18.000 B.P.  
all'Attuale (interv. V), C.N.R., Nuovi contributi alla realizzazione della Carta  
Neotettonica di Italia, publ. n. 251 of Progetto Finalizzato Geodinamica, 317-332.
- CASTELLARIN, A., EVA, C., GIGLIA, G., VAI, G.B., RABBI, E., PINI, G.A., and CRESTANA, G.  
(1985), Analisi strutturale del Fronte Appenninico Padano, *Giorn. Geol.* *3a*, 47, 1-2.
- CASTELLARIN, A., and VAI, G.B. (1986), Southalpine versus Po Plain Apenninic Arcs. In *The  
origin of arcs* (Ed. Wezel, F.C.) (Elsevier, Amsterdam) pp. 253-280.
- CASTELLARIN, A., SELLI, L., PICOTTI, V., and CANTELLI, L. (1998), La tettonica delle Dolomiti  
nel quadro delle Alpi Meridionali orientali, *Mem. Soc. Geol. It.* *53*, 133-143.
- CASTELLARIN, A., and CANTELLI, L. (2000), Neo-Alpine evolution of the Southern Eastern  
Alps, *J. Geodyn.* *30*, 251-274.
- CANTELLI, V., BERNARDINI, F., CAMASSI, R., CARACCILO, C.H., ERCOLANI, E., and  
POSTPISCHL, L. (2012), Looking for missing earthquake traces in the Ferrara-Modena

1 plain: an update on historical seismicity, *Ann. Geophys.* 55, 4, 519-524, doi:  
2 10.4401/ag-6110.  
3

4 CASTELLO, B., SELVAGGI, G., CHIARABBA, C., and AMATO, A. (2006), CSI Catalogo della  
5 sismicità italiana 1981-2002, v. 1.1. INGV-CNT, Roma, <http://www.ingv.it/CSI/>.  
6

7 CESCA, S., BRAUN, T., MACCAFERRI, F., PASSARELLI, L., RIVALTA, E., and DAHM, T. (2013),  
8 Source modelling of the M5-6 Emilia-Romagna, Italy, earthquakes (2012 May 20-29),  
9 *Geophys. J. Int.*, doi: 10.1093/gji/ggt069.  
10

11 CHANNELL, J.E.T. (1996), Paleomagnetism and paleogeography of Adria, in: Paleomagnetism  
12 and Tectonics of the Mediterranean Region, edited by A. MORRIS and D.H. TARLING,  
13 Geological Society of London Special Publication 105, 119-132.  
14

15 CIUCCI, F., BURRATO, P., and VALENSISE, G. (2002), Complex geomorphic response to blind  
16 thrust faulting along the northern margin of the Apennines near Mirandola (Po Plain),  
17 XXVIII General Assembly of the European Seismological Commission, Genoa, Italy  
18 1-6 September 2002, Book of Abstracts, 203.  
19

20 COWARD, M.P., DE DONATIS, M., MAZZOLI, S., PALTRINIERI, W., and WEZEL, F.-C. (1999),  
21 Frontal part of the northern Apennines fold and thrust belt in the Romagna-Marche  
22 area (Italy): Shallow and deep structural styles, *Tectonics* 18, 3, 559-574, doi:  
23 10.1029/1999TC900003.  
24

25 CUFFARO, M., RIGUZZI, F., SCROCCA, D., ANTONIOLI, F., CARMINATI, E., DIVANI, M., and  
26 DOGLIONI, C. (2010), On the geodynamics of the northern Adriatic plate, *Rend. Fis.*  
27 *Acc. Lincei* 21, 1, S253-S279, doi: 10.1007/s12210-010-0098-9.  
28

29 D'AGOSTINO, N., AVALLONE, A., CHELONI, D., D'ANASTASIO, E., MANTENUTO, S., and  
30 SELVAGGI, G. (2008), Active tectonics of the Adriatic region from GPS and  
31 earthquake slip vectors, *J. Geophys. Res.* 113, B12413, doi:10.1029/2008JB005860.  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

- 1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65
- DESIO, A. (1965), I rilievi isolati della Pianura Lombarda ed i movimenti tettonici del Quaternario, *Rend. Ist. Lomb. Acc. Sci. Lett. Sez. A* 99, 881-894.
- DEVOTI, R., ESPOSITO, A., PIETRANTONIO, G., PISANI, A.R., and RIGUZZI, F. (2011), Evidence of large scale deformation patterns from GPS data in the Italian subduction boundary, *Earth Planet. Sc. Lett.* 311, 3-4, 230-241, doi: 10.1016/j.epsl.2011.09.034.
- DISS WORKING GROUP (2010), Database of Individual Seismogenic Sources (DISS), Version 3.1.1: A compilation of potential sources for earthquakes larger than M 5.5 in Italy and surrounding areas, <http://diss.rm.ingv.it/diss/>, © INGV 2010 - Istituto Nazionale di Geofisica e Vulcanologia - doi: 10.6092/INGV.IT-DISS3.1.1.
- DOGLIONI, C., MONGELLI, F., and PIERI, P. (1994), The Puglia uplift (SE Italy): An anomaly in the foreland of the Apenninic subduction due to buckling of a thick continental lithosphere, *Tectonics* 13, 1309-1321, doi: 10.1029/94TC01501.
- ELTER, F.M., ELTER, P., EVA, C., EVA, E., KRAUS, R.K., PADOVANO, M., and SOLARINO, S. (2012), An alternative model for the recent evolution of the Northern-Central Apennines (Italy), *J. Geodyn.* 54, 55-63, doi: 10.1016/j.jog.2011.11.001.
- ERCOLANI, E., ROSSI, A., VECCHI, M., LESCHIUTTA, I., BERNARDINI, F., DEL MESE, S., CAMASSI, R., PONDRELLI, S., and TERTULLIANI, A. (2009), Rilievo macrosismico del terremoto emiliano del 23 dicembre 2008, *Quad. Geofis.* 71, 1-41, <http://istituto.ingv.it/l-ingv/produzione-scientifica/quaderni-di-geofisica/archivio/quaderni-di-geofisica-2009/>.
- FACCIOLI, E. (2013), Recent evolution and challenges in the Seismic Hazard Analysis of the Po Plain region, Northern Italy, *Bull. Earthquake Eng.* 11, 5-33, doi: 10.1007/s10518-012-9416-1.

- 1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65
- FANTONI, R., and FRANCIOSI, R. (2010), Tectono-sedimentary setting of the Po Plain and Adriatic foreland, *Rend. Fis. Acc. Lincei* 21, 1, S197-S209, doi: 10.1007/s12210-010-0102-4.
- FAZZINI, P., and GELMINI, R. (1982), Tettonica trasversale dell'Appennino settentrionale, *Mem. Soc. Geol. It.* 24, 299-309.
- FINETTI, I.R., BOCCALETTI, M., BONINI, M., DEL BEN, A., GELETTI, R., PIPAN, M., and SANI, F. (2001), Crustal section based on CROP seismic data across the North Tyrrhenian-Northern Apennines-Adriatic Sea, *Tectonophysics* 343, 135-163.
- GALADINI, F., POLI, M.E., and ZANFERRARI, A. (2005), Seismogenic sources potentially responsible for earthquakes with  $M \geq 6$  in the eastern Southern Alps (Thiene-Udine sector, NE Italy), *Geophys. J. Int.* 161, 739-762, doi: 10.1111/j.1365-246X.2005.02571.x.
- GALLI, P. (2005), I terremoti del gennaio 1117. Ipotesi di un epicentro nel cremonese, *Il Quaternario (It. J. Quat. Sci.)* 18, 2, 87-100.
- GALLI, P., GALADINI, F., and PANTOSTI, D. (2008), Twenty years of paleoseismology in Italy, *Earth-Sci. Rev.* 88, 1- 2, 89-117, doi: 10.1016/j.earscirev.2008.01.001.
- GHIELMI, M., MINERVINI, M., NINI, C., ROGLEDI, S., and ROSSI, M. (2013), Late Miocene–Middle Pleistocene sequences in the Po Plain - Northern Adriatic Sea (Italy): The stratigraphic record of modification phases affecting a complex foreland basin, *Mar. Petr. Geol.* 42, 50-81, doi: 10.1016/j.marpetgeo.2012.11.007.
- GUIDOBONI, E., and COMASTRI, A. (2005), Catalogue of earthquakes and tsunamis in the Mediterranean area from the 11th to the 15th century, INGV-SGA, Bologna, 1037 pp.
- GUIDOBONI, E., COMASTRI, A., and BOSCHI, E. (2005), The "exceptional" earthquake of 3 January 1117 in the Verona area (northern Italy): a critical time review and detection of

1 two lost earthquakes (lower Germany and Tuscany), *J. Geophys. Res.* *110*, B12309, doi:  
2 10.1029/2005JB003683.  
3

4 GUIDOBONI, E., FERRARI, G., MARIOTTI, D., COMASTRI, A., TARABUSI, G., and VALENSISE, G.  
5  
6 (2007), CFTI4MED, CATALOGUE OF STRONG Earthquakes in Italy (461 B.C.-1997) and  
7  
8 Mediterranean Area (760 B.C.-1500), INGV-SGA, <http://storing.ingv.it/cfti4med/>.  
9

10  
11 GUNDERSON, K.L., ANASTASIO, D.A., PAZZAGLIA, F.J., and PICOTTI, V. (2013), Fault slip rate  
12  
13 variability on 104-105 yr timescales for the Salsomaggiore blind thrust fault, Northern  
14  
15 Apennines, Italy, *Tectonophysics* *608*, 356-365, doi:10.1016/j.tecto.2013.09.018.  
16  
17

18  
19 GUNDERSON, K.L., PAZZAGLIA, F.J., PICOTTI, V., ANASTASIO, D.A., KODAMA, K.P.,  
20  
21 RITTENOUR, T., FRANKEL, K.F., PONZA, A., BERTI, C., NEGRI, A., and SABBATINI A.  
22  
23 (2014), Unraveling tectonic and climatic controls on synorogenic growth strata  
24  
25 (Northern Apennines, Italy), *Geol. Soc. Am. Bull.* *126*, 3-4, 532-552, doi:  
26  
27 10.1130/B30902.1.  
28  
29  
30

31 HEIDBACH, O., TINGAY, M., BARTH, A., REINECKER, J., KURFEB, D., and MÜLLER, B. (2008),  
32  
33 The World Stress Map database release 2008, doi:10.1594/GFZ.WSM.Rel2008.  
34  
35

36 ISIDE WORKING GROUP (2010), Italian Seismological Instrumental and parametric database:  
37  
38 <http://iside.rm.ingv.it>.  
39  
40

41 KASTELIC, V., VANNOLI, P., BURRATO, P., FRACASSI, U., TIBERTI, M.M., and VALENSISE, G.  
42  
43 (2013), Seismogenic sources in the Adriatic Domain, *Mar. Petrol. Geol.* *42*, 191-213,  
44  
45 doi: 10.1016/j.marpetgeo.2012.08.002.  
46  
47

48 LAVECCHIA, G., BONCIO, P., and CREATI, N. (2003), A lithospheric-scale seismogenic thrust in  
49  
50 central Italy, *J. Geodyn.* *36*, 79-94.  
51  
52

53 LAVECCHIA, G., BONCIO, P., CREATI, N., and BROZZETTI, F. (2004), Stile strutturale, stato  
54  
55 termo-meccanico e significato sismogenetico del thrust Adriatico: dati e spunti da una  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65



1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

revisione del profilo CROP 03 integrata con l'analisi di dati sismologici, *Boll. Soc. Geol. It.* *123*, 111-125.

LIVIO, F.A., BERLUSCONI, A., MICHETTI, A.M., SILEO, G., ZERBONI, A., TROMBINO, L., CREMASCHI, M., MUELLER, K., VITTORI, E., CARCANO C., and ROGLEDI S. (2009), Active fault-related folding in the epicentral area of the December 25, 1222 (Io = IX MCS) Brescia earthquake (Northern Italy): seismotectonic implications, *Tectonophysics*, 476, 1-2, 320-335, doi: 10.1016/j.tecto.2009.03.019.

LOCATI, M., CAMASSI, R., and STUCCHI, M. (Eds.) (2011), DBMI11, the 2011 version of the Italian Macroseismic Database. Milano, Bologna, <http://emidius.mi.ingv.it/DBMI11>, doi: 10.6092/INGV.IT-DBMI11.

MAESANO, F., TOSCANI, G., BURRATO, P., MIRABELLA, F., D'AMBROGI, C., and BASILI, R. (2013), Deriving thrust fault slip rates from geological modeling: Examples from the Marche coastal and offshore contraction belt, Northern Apennines, Italy, *Mar. Petrol. Geol.* *42*, 122-134, doi: 10.1016/j.marpetgeo.2012.10.008.

MAESANO, F., D'AMBROGI, C., BURRATO, P., and TOSCANI, G. (submitted), Slip-rates of blind thrusts in the Po sedimentary basin (Northern Apennines, Italy), submitted to *Tectonophysics* (April 2014).

MALAGNINI, L., HERRMANN, R.B., MUNAFÒ, I., BUTTINELLI, M., ANSELMINI, M., AKINCI, A., and BOSCHI, E. (2012), The 2012 Ferrara seismic sequence: Regional crustal structure, earthquake sources, and seismic hazard, *Geophys. Res. Lett.* *39*, L19302, doi: 10.1029/2012GL053214.

MARIOTTI, G., and DOGLIONI, C. (2000), The dip of the foreland monocline in the Alps and Apennines, *Earth Planet. Sc. Lett.* *181*, 191-202, doi: 10.1016/S0012-821X(00)00192-8.

- 1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65
- MASSIRONI, M., ZAMPIERI, D., and CAPORALI, A. (2006), Miocene to Present major fault linkages through the Adriatic indenter and the Austroalpine-Penninic collisional wedge (Alps of NE Italy). In: MORATTI, G., and CHALOUAN, A. (Eds.), *Active Tectonics of the Western Mediterranean Region and North Africa*, Special Publications, 262, Geological Society, London, 245-258.
- MELONI, F., and MOLIN, D. (1987), Il terremoto padano del 13 gennaio 1909, *Atti del 6° Convegno Annuale del GNGTS*, Roma, 1, 269-294.
- MELONI, F., MOLIN, D., and ROSSI A. (1988), Indagine macrosismica sui terremoti "profondi" del 27 ottobre 1914 e 25 ottobre 1972, *Atti del 7° Convegno Annuale del GNGTS*, Roma 1, 221-236.
- MICHETTI, A.M., GIARDINA, F., LIVIO, F., MUELLER, K., SERVA, L., SILEO, G., VITTORI, E., DEVOTI, R., RIGUZZI, F., CARCANO, C., ROGLEDI, S., BONADEO, L., BRUNAMONTE, F., and FIORASO, G. (2012), Active compressional tectonics, Quaternary capable faults, and the seismic landscape of the Po Plain (northern Italy), *Ann. Geophys.* 55, 5, 969-1001, doi: 10.4401/ag-5462.
- MONTONE, P., MARIUCCI, M.T., and PIERDOMINICI, S. (2012), The Italian present-day stress map, *Geophys. J. Int.* 189, 705-716, doi: 10.1111/j.1365-246X.2012.05391.x.
- MULARGIA, F. (2013), Why the next large earthquake is likely to be a big surprise, *Bull. Seism. Soc. Am.* 103, 2946-2952, doi:10.1785/0120130047.
- PELLEGRINI, G.B. (1988), Aspetti morfologici ed evidenze neotettoniche della linea Schio-Vicenza, *Suppl. Geogr. Fis. Dinam. Quat.* 1, 69-82.
- PESSINA, V., FRANCESCHINA, G., VANNOLI, P., PACOR, F., LUZI L. *et al.* (2006), Damage distribution and seismological model of the November 24, 2004, Salò (Northern Italy) earthquake, *First European Conference on Earthquake Engineering and Seismology*, Geneva, Switzerland, 3-8 September 2006, Paper Number: 1371.

- 1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65
- PESSINA, V., TERTULLIANI, A., CAMASSI, R., ROSSI, A., and SCARDIA, G. (2013), The revision of the October 30, 1901 earthquake, west of Lake Garda (northern Italy), *Boll. Geofis. Teor. Appl.* *54*, doi: 10.4430/bgta0083.
- PETRICCA, P., CARAFA, M.C., BARBA, S., and CARMINATI, E. (2013), Local, regional, and plate scale sources for the stress field in the Adriatic and Periadriatic region, *Mar. Petrol. Geol.* *42*, 160-181, doi: 10.1016/j.marpetgeo.2012.08.005.
- PEZZO, G, MERRYMAN BONCORI, J.P., TOLOMEI, C., SALVI, S., ATZORI, S., ANTONIOLI, A., TRASATTI, E., NOVALI, F., SERPELLONI, E., CANDELA, L., and GIULIANI, R. (2013), Coseismic Deformation and Source Modeling of the May 2012 Emilia (Northern Italy) Earthquakes, *Seism. Res. Lett.* *84*, 4, 645-655, doi: 10.1785/0220120171.
- PICCININI, D., CHIARABBA, C., AUGLIERA, P., and MONGHIDORO EARTHQUAKE GROUP (M.E.G.) (2006), Compression along the northern Apennines? Evidence from the Mw 5.3 Monghidoro earthquake, *Terra Nova* *18*, 89-94, doi: 10.1111/j.1365-3121.2005.00667.x.
- PICOTTI, V., and PAZZAGLIA F.J. (2008), A new active tectonic model for the construction of the Northern Apennines mountain front near Bologna (Italy), *J. Geophys. Res.* *113*, B8, doi: 10.1029/2007JB005307.
- PICOTTI, V., PONZA, A., and PAZZAGLIA, F.J. (2009), Topographic expression of active faults in the foothills of the Northern Apennines, *Tectonophysics* *474*, 285-294, doi: 10.1016/j.tecto.2009.01.009.
- PIERI, M., and GROPPPI, G., Subsurface geological structure of the Po Plain, Italy, In *Progetto Finalizzato Geodinamica*, C.N.R., Publ. n. 414, 1981.
- PONDRELLI, S., MORELLI, A., EKSTROM, G., MAZZA, S., BOSCHI, E., and DZIEWONSKI, A.M. (2002), European-Mediterranean regional centroid-moment tensors: 1997-2000, *Phys. Earth Planet. In.* *130*, 71-101.

- 1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65
- PONDRELLI, S., SALIMBENI, S., EKSTROM, G., MORELLI, A., GASPERINI, P., and VANNUCCI, G. (2006), The Italian CMT dataset from 1977 to the present, *Phys. Earth Planet. In.* *159*, 3-4, 286-303, doi: 10.1016/j.pepi.2006.07.008.
- PONDRELLI, S., SALIMBENI, S., MORELLI, A., EKSTROM, G., and BOSCHI, E. (2007), European-Mediterranean Regional Centroid Moment Tensor catalog: Solutions for years 2003 and 2004, *Phys. Earth Planet. In.* *164*, 90-112, doi: 10.1016/j.pepi.2007.05.004.
- PONDRELLI, S., SALIMBENI, S., MORELLI, A., EKSTRÖM, G., POSTPISCHL, L., VANNUCCI, G., and BOSCHI, E. (2011), European-Mediterranean Regional Centroid Moment Tensor Catalog: solutions for 2005-2008, *Phys. Earth Planet. In.* *185*, 3-4, 74-81 doi: 10.1016/j.pepi.2011.01.007.
- PONDRELLI, S., SALIMBENI, S., PERFETTI, P., and DANECEK, P. (2012), Quick regional centroid moment tensor solutions for the Emilia 2012 (northern Italy) seismic sequence, *Ann. Geophys.* *55*, 4, 615-621, doi: 10.4401/ag-6146.
- PONZA, A., PAZZAGLIA, F.J., and PICOTTI, V. (2010), Thrust-fold activity at the mountain front of the Northern Apennines (Italy) from quantitative landscape analysis, *Geomorphology* *123*, 211-231, doi: 10.1016/j.geomorph.2010.06.008.
- PRESTININZI, A., and ROMEO, R. (2000), Earthquake-induced ground failures in Italy, *Eng. Geol.* *58*, 387-397.
- RAVAGLIA, A., SENO, S., TOSCANI, G., and FANTONI, R. (2006), Mesozoic extension controlling the Southern Alps thrust front geometry under the Po Plain, Italy: Insights from sand- box models, *J. Struct. Geol.* *28*, 2084-2096, doi: 10.1016/j.jsg.2006.07.011.
- ROGLEDI, S. (2010), Assetto strutturale delle unità alpine nella pianura tra il lago d'Iseo e il Garda, Presented at the Workshop "Rischio sismico nella Pianura Padana", Brescia 24 November 2010, <http://cesia.ing.unibs.it/index.php/it/eventi/giornate-di-studio/119>.

- 1 ROVIDA, A., CAMASSI, R., GASPERINI, P., and STUCCHI, M. (Eds.) (2011), CPTI11, the 2011  
2 version of the Parametric Catalogue of Italian Earthquakes, Milano, Bologna,  
3  
4 <http://emidius.mi.ingv.it/CPTI/>.  
5  
6
- 7 SARAÒ, A., and PERUZZA, L. (2012), Fault-plane solutions from moment-tensor inversion and  
8 preliminary Coulomb stress analysis for the Emilia Plain, *Ann. Geophys.* 55, 4, doi:  
9 10.4401/ag-6134.  
10  
11
- 12 SCOGNAMIGLIO, L., MARGHERITI, L., MELE, F.M., TINTI, E., BONO, A., DE GORI, P., LAUCIANI,  
13 V., LUCENTE, F.P., MANDIELLO, A.G., MARCOCCI, C., MAZZA, S., PINTORE, S., and  
14 QUINTILIANI, M. (2012), The 2012 Pianura Padana Emiliana Seismic Sequence:  
15 Locations, Moment Tensors and Magnitudes, *Ann. Geophys.* 55, 4, doi: 10.4401/ag-  
16 6159.  
17  
18
- 19 SCROCCA, D., CARMINATI, E., DOGLIONI, C., and MARCANTONI, D. (2007), Slab retreat and  
20 active shortening along the central-northern Apennines. In: LACOMBE, O., LAVÉ, J.,  
21 ROURE, F., and VERGES, J. (Eds), *Thrust belts and Foreland Basins: from fold*  
22 *kinematics to hydrocarbon systems*, 471-487, Springer.  
23  
24
- 25 SERPELLONI, E., VANNUCCI, G., PONDRELLI, S., ARGNANI, A., CASULA, G., ANZIDEI, M.,  
26 BALDI, P., and GASPERINI, P. (2007), Kinematics of the Western Africa-Eurasia plate  
27 boundary from focal mechanisms and GPS data, *Geophys. J. Int.* 169, 1180-1200, doi:  
28 10.1111/j.1365-246X.2007.03367.x.  
29  
30
- 31 SERPELLONI, E., ANDERLINI, L., AVALLONE, A., CANNELLI, V., CAVALIERE, A., CHELONI, D.,  
32 D'AMBROSIO, C., ELISABETTA D'ANASTASIO, E., ESPOSITO, A., PIETRANTONIO, G.,  
33 PISANI, A.R., ANZIDEI, M., CECERE, G., D'AGOSTINO, N., DEL MESE, S., DEVOTI, R.,  
34 GALVANI, A., MASSUCCI, A., MELINI, D., RIGUZZI, F., SELVAGGI, G., and SEPE, V.  
35 (2012), GPS observations of coseismic deformation following the May 20 and 29,  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

- 1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65
- 2012, Emilia seismic events (northern Italy): data, analysis and preliminary models, *Ann. Geophys.* 55, 4, doi: 10.4401/ag-6168.
- SIGNORINI, R. (1935), Linee tettoniche trasversali nell'Appennino settentrionale, *Rend. Accad. Lincei, Cl. Sci. Fis. Mat. Nat.* 6, 21, 42-45.
- SORGI, C., DEFFONTAINES, B., HIPPOLYTE, J.C., and CADET, J.P. (1998), An integrated analysis of transverse structures in the Northern Apennines, Italy, *Geomorphology* 25, 193-206.
- STUCCHI, M., ALBINI, P., MIRTO, C., and REBEZ, A. (2004), Assessing the completeness of Italian historical earthquake data, *Ann. Geophys.* 47, 2-3, 659-673, doi: 10.4401/ag-3330.
- STUCCHI, M., GALADINI, F., ROVIDA, A., MORONI, A., ALBINI, P., MIRTO, C., and MIGLIAVACCA, P. (2008), Investigation of pre-1700 Earthquakes Between the Adda and the Middle Adige River Basins (Southern Alps), in: FRÉCHET, J., MEGHRAOUI, M., and STUCCHI, M. (Eds.), "Historical Seismology, Interdisciplinary Studies of Past and Recent Earthquakes", Springer 2008, ISBN 978-14020-8222-1; ISSN 1876-1682.
- STUCCHI, M., MELETTI, C., BAZZURRO, P., CAMASSI, R., CROWLEY, H., PAGANI, M., PINHO, R., and CALVI, G.M. (2012), I terremoti del maggio 2012 e la pericolosità sismica dell'area: che cosa è stato sottostimato? (The earthquakes of May 2012 and the seismic hazard of the area: anything underestimated?), *Progettazione Sismica* 01/2012, 63-73.
- TERTULLIANI, A., LESCHIUTTA, I., BORDONI, P., and MILANA, G. (2012a), Damage Distribution in L'Aquila City (Central Italy) during the 6 April 2009 Earthquake, *B. Seismol. Soc. Am.* 102, 4, 1543-1553, doi: 10.1785/0120110205.
- TERTULLIANI, A., ARCORACI, L., BERARDI, M., BERNARDINI, F., BRIZUELA, B., CASTELLANO, C., DEL MESE, S., ERCOLANI, E., GRAZIANI, L., MARAMAI, A., ROSSI, A., SBARRA, M.,

1 and VECCHI, M. (2012b), The Emilia 2012 sequence: a macroseismic survey, *Ann.*  
2 *Geophys.* *55*, 4, doi: 10.4401/ag-6140.  
3

4 TIZZANI, R., CASTALDO, R., SOLARO, G., PEPE, S., BONANO, M., CASU, F., MANUNTA, M.,  
5  
6 MANZO, M., PEPE, A., SAMSONOV, S., LANARI, R., and SANSOSTI, E. (2013), New  
7  
8 insights into the 2012 Emilia (Italy) seismic sequence through advanced numerical  
9  
10 modeling of ground deformation InSAR measurements, *Geophys. Res. Lett.* *40*, 10,  
11  
12 1971-1977, doi: 10.1002/grl.50290.  
13  
14  
15

16 TOSCANI, G., SENO, S., FANTONI, R., and ROGLEDI, S. (2006), Geometry and timing of  
17  
18 deformation inside a structural arc: the case of the western Emilian folds (Northern  
19  
20 Apennine front, Italy), *Boll. Soc. Geol. It.* *125*, 59-65.  
21  
22  
23

24 TOSCANI, G., BURRATO, P., DI BUCCI, D., SENO, S., and VALENSISE, G. (2009), Plio-  
25  
26 Quaternary tectonic evolution of the northern Apennines thrust fronts (Bologna-  
27  
28 Ferrara section, Italy): seismotectonic implications, *It. J. Geosc.* *128*, 605-613, doi:  
29  
30 10.3301/IJG2009.128.2.605.  
31  
32  
33

34 TOSCANI, G., BONINI, L., GALUPPO, C., SENO, S., BASILI, R., BURRATO, P., VALENSISE, G.,  
35  
36 D'AMBROGI, C., and MAESANO, F. (2013), D20 - Analogue models of deformation in  
37  
38 the Ferrara arc, Report of the DPC-INGV-S1 Project "Base-knowledge improvement  
39  
40 for assessing the seismogenic potential of Italy", 42 pp., available at:  
41  
42 <https://sites.google.com/site/ingvdpcprojects1/home>.  
43  
44  
45

46 VALENSISE, G., and PANTOSTI, D. (2001a), The investigation of potential earthquake sources  
47  
48 in peninsular Italy: a review, *J. Seismol.* *5*, 3, 287-306.  
49  
50

51 VALENSISE, G., and PANTOSTI, D. (Eds.) (2001b), Database of Potential Sources for  
52  
53 Earthquakes Larger than M 5.5 in Italy, *Ann. Geofis.* *44*, 4, 180 pp., with CD-ROM,  
54  
55 [http://diss.rm.ingv.it/diss/ Downloads.html](http://diss.rm.ingv.it/diss/Downloads.html), doi: 10.4401/ag-3562.  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

- 1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65
- VANNOLI, P., BASILI, R., and VALENSISE, G. (2004), New geomorphic evidence for anticlinal growth driven by blind-thrust faulting along the northern Marche coastal belt (central Italy), *J. Seismol.* 8, 3, 297-312.
- VANNOLI, P., BURRATO, P., FRACASSI, U., and VALENSISE, G. (2012), A fresh look at the seismotectonics of the Abruzzi (Central Apennines) following the 6 April 2009 L'Aquila earthquake ( $M_w$  6.3), *Ital. J. Geosc.* 131, 3, 309-329, doi: 10.3301/IJG.2012.03.
- VIGANÒ, A., BRESSAN, G., RANALLI, G., and MARTIN, S. (2008), Focal mechanism inversion in the Giudicarie–Lessini seismotectonic region (Southern Alps, Italy): insights on tectonic stress and strain, *Tectonophysics* 460, 106-115.
- WEBER, J., VRABEC, M., PAVLOVČIČ-PREŠEREN, P., DIXON, T., JIANG, Y., and STOPAR, B. (2010), GPS derived motion of the Adriatic microplate from Istria Peninsula and Po Plain sites, and geodynamic implications, *Tectonophysics* 483, 213-222, doi: 10.1016/j.tecto.2009.09.001.
- WEGMANN, K.W., and PAZZAGLIA, F.J. (2009), Late Quaternary fluvial terraces of the Romagna and Marche Apennines, Italy: Climatic, lithologic, and tectonic controls on terrace genesis in an active orogeny, *Quaternary Sci. Rev.* 28, 1-2, 137-165, doi: 10.1016/j.quascirev.2008.10.006.
- ZONNO, G., BASILI, R., MERONI, F., MUSACCHIO, G., MARTIN MAI, P., and VALENSISE, G. (2012), High-frequency maximum observable shaking map of Italy from fault sources, *Bull. Earthquake Eng.* 10, 4, 1075-1107, doi: 10.1007/s10518-012-9346-y.



## Figure Captions

**Figure 1:** Composite Seismogenic Sources of the DISS database. Sources of the Po Plain are shown in red and described in this work; sources of northeastern Italy and western Slovenia are shown in blue and described in BURRATO *et al.*, 2008; sources of the Adriatic Domain are shown in green and described in KASTELIC *et al.*, 2013; extensional sources of the Central Apennines are shown in yellow and described in VANNOLI *et al.*, 2012; other sources in orange.

**Figure 2:** Structural sketch of the Po Plain. Key - black lines: main structural elements (BIGI *et al.*, 1992); white lines: inherited faults (ROGLEDI, 2010); dashed lines: transverse structures (e.g. CASTELLARIN *et al.*, 1985); grey horizontal shading: Trento Platform (CUFFARO *et al.*, 2010). SAMF: Southern Alps Mountain Front; SAOA: Southern Alps Outer Arc; GS: Southern Alpine Giudicarie System; SVL: Schio-Vicenza Line; NAOA: Northern Apennines Outer Arcs; PTF: Pedepenninic Thrust Front; MA: Monferrato Arc; EA: Emilia Arc; FRA: Ferrara-Romagna Arc.

**Figure 3:** Historical and instrumental earthquakes from the CPTI11 Catalogue (<http://emidius.mi.ingv.it/CPTI11/>), Bollettino Sismico Italiano (<http://bollettinosismico.rm.ingv.it/>) and ISIDe (<http://iside.rm.ingv.it/>). Historical earthquakes have  $M \geq 5.3$  and are shown with squares. Instrumental earthquakes have  $M \geq 4.5$  and are shown with circles ( $M 4.5-4.9$ ) or stars ( $M \geq 5.0$ ). All earthquakes are keyed to Tables 2 and 3 through their ID. The IDs of instrumental earthquakes are shown in italic.

a) Available focal mechanisms (PONDRELLI *et al.*, 2006; TDMT database: <http://cnt.rm.ingv.it/tdmt.html>; see Table 3 for focal parameters.

b) Earthquake locations: *deep* historical and instrumental earthquakes are shown in bold; multiple events are shown with a grey pattern.

**Figure 4:** Largest Italian earthquake sequences ( $M_w \geq 5.7$ ) of the past 50 years (1962-2012: data from CPTI11; see Table 4). A multiple sequence includes at least two earthquakes with comparable magnitudes. Multiple sequences are shown with white lettering on black background. Inset shows frequency of multiple events for different kinematics.

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

**Figure 5:** Maps of macroseismic intensity V and higher for the 1570 (a), 1909 (b) and 1983 (c) earthquakes (LOCATI *et al.*, 2011) and for the 20 May 2012 (d) earthquake (TERTULLIANI *et al.*, 2012b). The earthquake epicenters are shown with white stars.  $N_V$  is the number of the data points with intensity V or larger. Notice the large felt area of the 1909 and 1983 earthquakes, suggesting that the depth of these events is larger than the depth of the 1570 and 2012 events.

**Figure 6:** Sketch showing the four groups of seismogenic sources identified in this work. Group #1: Shallow thrusts of the Northern Apennines, including the sub-emergent Pedepenninic Thrust Front; Group #2: Deep ramps of the Apennines thrusts; Group #3: Inherited faults cutting the foreland; Group #4: Transverse structures (or *lineaments*), interpreted as the response of the upper lithosphere to the variation of the dip of the regional monocline. EA: Emilia Arc; FRA: Ferrara-Romagna Arc; PTF: Pedepenninic Thrust Front.

**Figure 7:** Composite and Individual Sources of the Po Plain, respectively shown as red ribbons and black rectangles. Reaches of anomalous drainage (from BURRATO *et al.*, 2003) are marked in white. SAMF: Southern Alps Mountain Front; SAOA: Southern Alps Outer Arc; GS: Southern Alpine Giudicarie System; SVL: Schio-Vicenza Line; PTF: Pedepenninic Thrust Front; EA: Emilia Arc; FRA: Ferrara-Romagna Arc.

**Figure 8:** a) Sketch of the seismogenic sources of the Northern Apennines thrust fronts in the epicentral area of the 2012 seismic sequence, and b) simplified geological section. Contour lines of observed surface deformation from InSAR data (with maximum uplift value in cm) are shown in white (BIGNAMI *et al.*, 2012). The isolines of the dip of the foreland monocline are shown in grey (MARIOTTI and DOGLIONI, 2000, reinterpreted): numbers indicate the dip of the Apennines monocline along the three sections (MARIOTTI and DOGLIONI, 2000). The dashed line shows the Secchia Line (SL; northern segment: CASTALDINI *et al.*, 1979; southern segment: CASTELLARIN *et al.*, 1985).

**Figure 9:** Seismotectonic sketch of the Po Plain and principal paleogeographic elements. The isolines contour the dip of the foreland monocline (MARIOTTI and DOGLIONI, 2000, reworked). Grey ribbons: CSSs (DISS WORKING GROUP). White (in 9a)/grey (in 9b) solid lines: inherited faults from ROGLEDI (2010). Grey shaded area: Trento Platform from

CUFFARO *et al.* (2010). Grey dashed lines: transverse structures; SVL, Schio-Vicenza Line; VTL, Val Trebbia Line; SOL, Stirone-Ongina Line; TEL, Taro-Enza Line; EL, Enza Line; SL, Secchia Line; VVL, Viareggio-Val di Lima-Bologna Line; PSL, Prato-Sillaro Line; ML, Montone Line; AVML, Arbia-Val Marecchia Line (from CASTELLARIN *et al.*, 1985).

a) Map showing deep earthquakes with  $M > 4.5$ . Squares: historical (Table 2). Circles and stars: instrumental (Table 3) with  $M > 4.5$  and depth  $> 15$  km (circles,  $M 4.5-4.9$ ; stars  $M \geq 5.0$ ). EFS: Etrurian Fault System.

b) Map of earthquake sequences ( $M \geq 2.0$ ) that occurred in the interval 1 January 2009-31 December 2013 (ISIDE WORKING GROUP, 2010).

**Figure 10:** Maximum expected magnitude estimated for all the Composite Seismogenic Sources from the database DISS discussed in this work.

Characteristics	Basins (Lombardian/Belluno)	Platforms (Trento/Friuli)	Control on thrust geometry
Thickness of sedimentary sequence	thicker	thinner	---
Depositional facies	deep marine	shallow water carbonates	<i>number of detachment levels</i>
Multiple detachment horizons	yes	no	<i>presence of different wavelength structures</i>
Dip of foreland monocline	steep	shallow	<i>spacing among thrust fronts</i>
Depth of basal detachment	deep	shallow	<i>spacing among thrust fronts</i>
Spacing among thrust fronts	wide	small	<i>development of salients and recesses</i>
Trend/linearity of thrust front	salients	recesses	---

**Table 1:** Summary of the characteristics of palaeogeographic domains in the central Po Plain, and control exerted on thrust geometry (observations mostly from CUFFARO *et al.*, 2010, reinterpreted).

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49

ID	Date	Locality	Intensity	M <sub>w</sub>	Multiple	Deep	Description/Notes	Source(s)	Group	Tectonic structure
6	3 Jan 1117	Veronese	IX	6.7	N/A	N/A	GUIDOBONI and COMASTRI (2005) reported an independent earthquake (5 intensity points, I=VII-VIII) occurring on the same day, at the same hour, but 150 km to the south, in the territory of Pisa.	ITIS140; ITCS076	#3	N/A
4	25 Dec 1222	Basso Bresciano	IX	5.8	N/A	N	The source of this earthquake could be the either the thrust or the backthrust.	ITCS002 or ITCS072 (see "Notes")	#1	SAOA
33	30 Apr 1279	Rocca San Casciano	VII-VIII	5.6	N/A	N/A	Only 5 intensity datapoints. The CFTI catalogue reports 1 May 1279, M <sub>w</sub> 5.9, I=VIII (at 2:00 AM). The CPTI does not report an event on 1 May but rather two events on 30 April, one near Rocca San Casciano (I =VII-VIII), one near Camerino (I=X).	ITCS027	#2	DR
21	25 Jul 1365	Bologna	VII-VIII	5.4	N/A	N	Only one intensity datapoint available. Some sources refer to a 7 April shock, other more reliable sources to a 25 July shock. Two earthquakes struck Ferrara on 4 March (M <sub>w</sub> 4.8) and Verona on 21 September (M <sub>w</sub> 4.5).	ITCS047	#1	PTF
25	4 Aug 1383	Forlì	VII-VIII	5.4	N/A	N	Only one intensity datapoint available. Preceded by M <sub>w</sub> 4.1 shock on 24 July 1383 near Parma.	ITCS001	#1	PTF
1	26 Nov 1396	Monza	VII-VIII	5.4	N/A	N/A	Only one intensity datapoint available.	ITCS002	#1	SAOA
27	3 Jul 1428	Predappio	VIII	5.5	N/A	N	---	ITCS001	#1	PTF
9	11 Jun 1438	Parmense	VIII	5.6	N/A	N	---	ITCS009	#1	EA
26	11 Aug 1483	Romagna meridionale	VIII-IX	5.7	N/A	N	BARATTA (1901) reports a shock near Ferrara on 11 March 1483 and one near Cervia in 1484.	ITCS001	#1	PTF
18	5 Jun 1501	Appennino modenese	IX	6.0	N/A	N	---	ITCS046	#1	PTF
20	3 Jan 1505	Bolognese	VIII	5.6	Y	N	The earthquake sequence started on 31 Dec 1504 (M <sub>w</sub> 5.4) and ended 19 May 1505 (BOSCHI and GUIDOBONI, 2003).	ITIS091; ITCS047	#1	PTF
13	17 Nov 1570	Ferrara	VIII	5.5	Y	N	The earthquake sequence started on 17 November 1570, went on with closely spaced aftershocks up to early 1572, and gradually died out until 17 March 1574, when a somewhat stronger shock caused further damage in Finale Emilia	ITIS090; ITCS050	#1	FRA

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49

							(GUIDOBONI <i>et al.</i> , 2007).			
32	-- --- 1600	Palazzuolo	VII-VIII	5.4	N/A	N/A	Only one intensity datapoint available.		N/A	N/A
14	19 Mar 1624	Argenta	VIII-IX	5.5	N/A	N	---	ITIS141; ITCS012	#1	FRA
34	22 Mar 1661	Appennino romagnolo	X	6.1	N/A	N	---		4	AVML
22	11 Apr 1688	Romagna	IX	5.8	N/A	N	“... a large aftershock near Russi on 18 April 1688, a week after the mainshock” (BOSCHI <i>et al.</i> , 1997). Not reported in the CFTI catalogue.	ITIS100; ITCS109	#1	FRA
31	29 Oct 1725	Appennino Tosco-emiliano	VIII	5.4	N/A	N	Located about 10 km to the east of the 14 September 2003, M <sub>w</sub> 5.3, <i>Appennino Bolognese</i> earthquake (ID 66).		#4	PSL
23	4 Apr 1781	Romagna	IX-X	5.9	Y	N	---	ITIS093; ITCS001	#1	PTF
24	17 Jul 1781	Romagna	VIII	5.6	Y	N	---	ITCS001	#1	PTF
38	25 Dec 1786	Riminese	VIII	5.6	N/A	N	The Composite and Individual Sources responsible for this earthquake are described in KASTELIC <i>et al.</i> (2013).	ITIS035; ITCS039	#1	N/A
15	22 Oct 1796	Emilia orientale	VII	5.6	N/A	Y	This earthquake falls near the ITCS012, but at a deeper depth. The epicentral area is very close to that of the 1909 earthquake (ID 16).	---	#4	PSL
2	12 May 1802	Valle dell’Oglio	VIII	5.6	N/A	N	---	ITIS104; ITCS002	#1	SAOA
7	9 Oct 1828	Valle Staffora	VIII	5.8	Y	N	---	ITCS018	#1	EA
12	11 Sep 1831	Reggiano	VII-VIII	5.5	Y	N	The 1831 event fall at the junction between the EA and the FRA. Given the complex local seismotectonic pattern, this event may has been caused by two adjacent segments of the EA (ITCS009) or FRA (ITCS049).	ITCS009; ITCS049	#1	EA/ FRA
11	13 Mar 1832	Reggiano	VII-VIII	5.5	Y	Y	The 1832 event is deeper than the ITCS009 and the ITCS049.	---	#4	EL
30	25 Jun 1869	Media Valle del Reno	VII-VIII	5.4	N/A	Y	This is a deep event that occurred near the junction of the Apennines deep ramps and the Viareggio-Val di Lima-Bologna transverse structure. As such, it might be equally well assigned to Group #2 o #4.	---	#2/4	DR/ VVL
28	30 Oct 1870	Romagna	VIII	5.6	N/A	N	---	ITCS001	#1	PTF

29	17 Sep 1873	Liguria orientale	VI-VII	5.4	N/A	Y		---	#4	EL	
35	17 Mar 1875	Romagna sud-orientale	VIII	5.9	N/A	N	The Composite and Individual sources responsible for this earthquake are described in KASTELIC <i>et al.</i> , 2013.	ITIS036; ITCS039	#1	N/A	
5	7 Jun 1891	Valle d'Illasi	IX	5.9	Y	N	Strong, damaging aftershocks reported on 11 Jun, 15 Jun, 29 Jun, 7 Aug, 21 Aug 1891.	---	-	-	
17	4 Mar 1898	Valle del Parma	VII-VIII	5.4	N/A	N		---	ITCS046	#1	PTF
3	30 Oct 1901	Salò	VIII	5.7	N/A	N		---	ITIS069; ITCS048	#1	SAMF
16	13 Jan 1909	Bassa Padana	VI-VII	5.5	N/A	Y	From MELONI and MOLIN (1987). This earthquake falls near the ITCS012, but the ITCS012 is not responsible for it, because the 1909 event is deeper than the ITCS012. Epicentral area very close to that of the 1796 earthquake (ID15).	---	#4	PSL	
36	17 May 1916	Alto Adriatico	VIII	5.9	Y	N	The Composite and Individual Sources responsible for this earthquake are described in KASTELIC <i>et al.</i> (2013).	ITIS034; ITCS030	#1	N/A	
37	16 Aug 1916	Alto Adriatico	VIII	6.1	Y	N	The Composite and Individual Sources responsible for this earthquake are described in KASTELIC <i>et al.</i> (2013).	ITIS033; ITCS030	#1	N/A	
19	20 Apr 1929	Bolognese	VII-VIII	5.3	Y	N		BOSCHI and GUIDOBONI (2003).	ITIS103; ITCS047	#1	PTF
8	15 May 1951	Lodigiano	VI-VII	5.4	N/A	Y	From MELONI <i>et al.</i> (1988). This earthquake falls near the ITCS044, but the ITCS044 is not responsible for it, because the 1951 event is deeper than the ITCS044.	---	#3	UDS	
10	15 Jul 1971	Parmense	VIII	5.7	N/A	N		---	ITCS009	#1	EA

**Table 2:** Parameters of the largest historical earthquakes ( $M \geq 5.3$ ) that occurred in the study region (from BOSCHI and GUIDOBONI, 2003, and ROVIDA *et al.*, 2011). Positively shallow and deep historical earthquakes are highlighted in light grey and dark grey, respectively (the background is white when depth is undefined). Each earthquake is tentatively assigned to a Group and when possible also to a Tectonic structure. Y: Yes; N: No; N/A: Not Applicable. See Figure 3 for earthquake locations. Earthquakes belonging to the same sequence are listed together. EA: Emilia Arc; FRA: Ferrara-Romagna Arc; PTF: Pedepenninic Thrust Front; SAMF: Southern Alps Mountain Front;

1  
2  
3  
4  
5  
6 SAOA: Southern Alps Outer Arc; DR: Deep ramp; SVL: Schio-Vicenza Line; AVML: Arbia- Val Marecchia Line; PSL: Prato-Sillaro  
7 Line; VVL: Viareggio-Val di Lima-Bologna Line; EL: Enza Line; ML: Montone Line; UDS: Unknown Deep Structure.  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49



1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49

ID	Date	Time (hh mm ss)	Lat (°)	Lon (°)	Depth (km)	M <sub>L</sub>	Multiple	Strike (°)	Rake (°)	Dip (°)	Focal Mechanism Reference	Notes	Source(s)	Group	Tectonic structure
62	09 Nov 1983	16 29 52	44.698	10.375	28.0*	4.8	N	14; 262	29; 129	43; 71	PON	Falls close to ITCS009, but at a deeper depth.	---	#4	EL
44	24 Apr 1987	02 30 28	44.816	10.701	5.0	4.6	Y	-	-	-	-	---	ITCS049	#1	FRA
45	02 May 1987	20 43 54	44.811	10.723	24.0*	4.5	Y	45; 312	8; 163	73; 83	PON	Depth=26 km according to PONDRELLI <i>et al.</i> (2006).	---	#4	EL
40	13 Sep 1989	21 54 01	45.821	11.170	40.4*	4.7	N	56; 146	0; -179	89; 90	PON	Depth=26 km according to PONDRELLI <i>et al.</i> (2006).	---	#4	SVL
42	15 Oct 1996	09 56 01	44.798	10.817	5.0	4.9	N	217; 94	47; 132	53; 54	PON	Depth=17.8 km according to PONDRELLI <i>et al.</i> (2006).	ITCS049	#1	FRA
67	10 May 2000	16 52 12	44.245	11.941	13.3	4.5	Y	309; 120	97; 84	43; 47	PON	Depth=21 km according to PONDRELLI <i>et al.</i> (2002), 7-14 km according to CALDERONI <i>et al.</i> (2009).	ITCS001	#1	PTF
43	18 Jun 2000	07 42 07	44.808	10.707	5.0	4.5	N	308; 210	-161; -23	68; 73	PON	---	ITCS049	#1	FRA
66	14 Sep 2003	21 42 53	44.255	11.380	20.1°	5.0	N	246; 94	68; 107	40; 53	PON	°According to PICCININI <i>et al.</i> (2006). Depth=23 km according to PONDRELLI <i>et al.</i> (2007). M <sub>w</sub> 5.3 according to PICCININI <i>et al.</i> (2006).	ITIS058; ITCS027	#2	DR
39	24 Nov 2004	22 59 39	45.685	10.521	5.4*	5.2	N	57; 228	95; 83	56; 34	TDMT	*According to PESSINA <i>et al.</i> , (2006). Depth=15 km according to PONDRELLI <i>et al.</i> (2007).	ITCS048	#1	SAMF
64	23 Dec 2008	15 24 22	44.544	10.345	22.9	5.2	N	93; 280	86; 95	50; 40	TDMT	---	ITIS135; ITCS027	#2	DR
65	23 Dec 2008	21 58 27	44.527	10.355	23.7	4.8	N	96; 292	80; 102	51; 40	TDMT	---	ITCS027	#2	DR
68	05 Apr 2009	20 20 53	44.230	11.913	24.5	4.6	N	121; 267	113; 64	50; 45	TDMT	Falls close to ITCS001, but at a deeper depth.	---	#4	ML
59	17 Jul 2011	18 30 27	45.010	11.367	2.4	4.8	N	82; 269	85; 95	47; 43	TDMT	Foreshock of the 2012 Emilia sequence.	ITCS050	#1	FRA

41	25 Jan 2012	08 06 37	44.871	10.510	29.0	5.0	N	76; 307	120; -46	63; 40	TDMT	---	---	#4	UDS
63	27 Jan 2012	14 53 13	44.523	10.009	72.4	5.2	N	286; 113	87; 97	63; 27	TDMT	Unrelated to thrust tectonics due to its depth.	---	#4	UDS
54	20 May 2012	02 03 52	44.889	11.228	6.3	5.9	Y	103; 280	92; 88	46; 44	TDMT	2012 Emilia sequence	ITIS134; ITCS103	#1	FRA
55	20 May 2012	02 06 30	44.886	11.189	7.7	4.8	Y	-	-	-	---	2012 Emilia sequence	ITCS103	#1	FRA
56	20 May 2012	02 07 31	44.863	11.370	5.0	5.1	Y	-	-	-	---	2012 Emilia sequence	ITCS103	#1	FRA
46	20 May 2012	03 02 50	44.860	11.095	10.0	4.9	Y	279; 88	95; 81	64; 27	TDMT	2012 Emilia sequence	ITCS051	#1	FRA
57	20 May 2012	13 18 02	44.831	11.490	4.7	5.1	Y	291; 111	90; 90	49; 41	TDMT	2012 Emilia sequence	ITCS103	#1	FRA
58	20 May 2012	17 37 14	44.876	11.382	3.2	4.5	Y	67; 237	96; 81	59; 31	TDMT	2012 Emilia sequence	ITCS103	#1	FRA
47	29 May 2012	07 00 03	44.851	11.086	10.2	5.8	Y	271; 81	93; 81	71; 20	TDMT	2012 Emilia sequence	ITIS107; ITCS051	#1	FRA
48	29 May 2012	08 25 51	44.901	10.943	3.2	4.5	Y	67; 274	76; 114	61; 32	TDMT	2012 Emilia sequence	ITCS051	#1	FRA
49	29 May 2012	08 27 23	44.854	11.106	10.0	4.7	Y	-	-	-	---	2012 Emilia sequence	ITCS051	#1	FRA
50	29 May 2012	10 55 57	44.888	11.008	6.8	5.3	Y	279; 97	92; 88	48; 42	TDMT	2012 Emilia sequence	ITCS051	#1	FRA
51	29 May 2012	11 00 02	44.873	10.950	11.0	4.9	Y	-	-	-	---	2012 Emilia sequence	ITCS051	#1	FRA
52	29 May 2012	11 00 25	44.879	10.947	5.4	5.2	Y	-	-	-	---	2012 Emilia sequence	ITCS051	#1	FRA
53	03 Jun 2012	19 20 43	44.899	10.943	9.2	5.1	Y	271; 81	93; 81	71; 20	TDMT	2012 Emilia sequence	ITCS051	#1	FRA
60	06 Jun 2012	04 08 31	44.434	12.354	25.6	4.5	N	110; 17	-129; -3	88; 39	TDMT	Falls near ITCS012, but at a deeper depth.	---	#4	UDS
61	03 Oct 2012	14 41 28	44.750	9.631	32.2	4.5	N	308; 218	-175; -0	90; 85	TDMT	Falls near ITCS027, but at a deeper depth.	---	#4	UDS

**Table 3:** Parameters of the largest instrumental earthquakes ( $M \geq 4.5$ ) in the study region (from ISIDE and *Bollettino Sismico Italiano*).

Earthquakes shallower and deeper than 15 km are highlighted in light grey and dark grey, respectively (see Figure 3 for earthquake locations). FM Ref: Source of focal mechanism: TDMT, <http://cnt.rm.ingv.it/tdmt.html> (from 24 Nov 2004); PON, PONDRELLI *et al.*, 2006.

\*=Depth from CSI <http://csi.rm.ingv.it/> (CASTELLO *et al.*, 2006). Key to tectonic structures as in Table 2.

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49

#	Date	Locality	M <sub>w</sub>	Intensity	Kinematics	Multiple	Deep
1	1962, 21 August	Irpinia	6.1	IX	Normal	Y	N
2	1963, 19 July	Mar Ligure	6.0	VI	Thrust	Y	N
3	1968, 14 January	Valle del Belice	6.5	X	Thrust	Y	N
4	1976, 6 May	Friuli	6.4	IX-X	Thrust	Y	N
5	1978, 15 April	Golfo di Patti	6.0	VIII	Strike-slip	N	N
6	1979, 19 September	Valnerina	5.8	VIII-IX	Normal	N	N
7	1980, 23 November	Irpinia-Basilicata	6.7	X	Normal	Y	N
8	1984, 7 May	Appennino abruzzese	5.8	VIII	Normal	Y	N
9	1990, 5 May	Potentino	6.0	VII	Strike-slip	Y	Y
10	1997, 26 September	Appennino umbro-marchigiano	5.9	IX	Normal	Y	N
11	2002, 6 September	Palermo	5.8	VI	Thrust	N	N
12	2002, 31 October	Molise	5.8	VII-VIII	Strike-slip	Y	Y
13	2009, 6 April	L'Aquila	6.2	IX-X**	Normal	N	N
14	2012, 20 May	Emilia	5.9*	VIII***	Thrust	Y	N

**Table 4:** Summary of the 14 largest Italian earthquake sequences ( $M_w \geq 5.7$ ) of the past 50 years (1962-2012: data from CPTI11). See Figure 4 for earthquake locations. Ten out of 14 of these sequences were multiple or complex events, i.e. they were characterized by at least two mainshocks whose magnitude is within 0.3 units of each other, and two were “deep crustal”. As each sequence included at least two - but also more - individual earthquakes above the given magnitude threshold, the total number of events considered is nearly 30. \*M<sub>L</sub> from ISIDE DATABASE (2012); \*\* TERTULLIANI *et al.* (2012a); \*\*\* TERTULLIANI *et al.* (2012b).

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49

<b>Depth</b>	<b>Historical (1117-1982)</b> <i>dyne x cm</i>	<b>Instrumental (1983-2012)</b> <i>dyne x cm</i>	<b>Grand total</b> <i>dyne x cm</i>
<b>Shallow earthquakes (&lt;15 km)</b>	2.93x10 <sup>26</sup> (96% of total historical)	2.14x10 <sup>25</sup> (84% of total instrumental)	3.14x10 <sup>26</sup> (95% of grand total)
<b>Deep earthquakes (&gt;15 km)</b>	1.24x10 <sup>25</sup> (4% of total historical)	3.96x10 <sup>24</sup> (16% of total instrumental)	1.64x10 <sup>25</sup> (5% of grand total)
<b>Total moment release</b>	3.05x10 <sup>26</sup> (92% of grand total)	2.54x10 <sup>25</sup> (8% of grand total)	3.31x10 <sup>26</sup> (100% of total)

**Table 5:** Summary of observed *historical* vs *instrumental* and *shallow* vs *deep* moment release in the Po Plain. The earthquakes for which the depth could not be evaluated (Table 2) have been considered shallow events. See text for discussion.

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49

Source ID	Lat (°)	Lon (°)	Length (km)	Width (km)	Depth (km)	Strike (°)	Dip (°)	Rake (°)	Average Slip (m)	Slip rate (mm/a)	Recurrence (a)	Associated earthquake	M <sub>w</sub>	Group	Tectonic structure
ITIS069	45.634	10.514	7.0	5.0	6.5-9.0	231	30	90	0.35	0.10-0.50	700-3500	30 Oct 1901	5.7	#1	GS
ITIS104	45.389	9.793	6.5	4.7	2.5-5.8	275	45	90	0.50	0.10-0.50	1000-5000	12 May 1802	5.7	#1	SAOA
ITIS140	45.271	10.992	30.0	14.0	3.0-12.0	248	40	90	1.00	0.10-0.50	1000-5000	03 Jan 1117	6.7	#3	---
ITIS090	44.890	11.498	5.1	4.0	1.4-4.5	88	50	90	0.35	0.10-0.50	700-3500	17 Nov 1570	5.5	#1	NAOA-FRA
ITIS134	44.849	11.323	10.0	6.4	4.0-8.4	115	43	90	0.80	0.25-0.50	1600-3200	20 May 2012	6.1	#1	NAOA-FRA
ITIS107	44.848	11.074	9.0	5.9	4.0-7.0	108	30	90	0.40	0.50-1.04	385-800	29 May 2012	6.0	#1	NAOA-FRA
ITIS141	44.640	11.847	8.0	5.7	3.0-6.3	110	35	90	0.40	0.49-0.55	727-816	19 Mar 1624	5.8	#1	NAOA-FRA
ITIS100	44.384	11.943	9.1	6.0	2.5-5.0	119	25	90	1.00	0.10-0.30	10000-3333	11 Apr 1688	5.8	#1	NAOA-FRA
ITIS103	44.478	11.158	5.6	4.3	2.0-4.5	98	35	90	0.40	0.10-0.50	800-4000	20 Apr 1929	5.6	#1	PTF
ITIS091	44.470	11.243	5.0	3.9	2.0-4.2	90	35	90	0.40	0.10-0.50	800-4000	03 Jan 1505	5.5	#1	PTF
ITIS093	44.264	11.807	8.4	5.7	4.5-7.8	108	35	90	0.40	0.10-0.50	800-4000	04 Apr 1781	5.8	#1	PTF
ITIS135	44.547	10.334	4.9	3.9	18.5-21.7	98	55	79	0.30	0.10-0.50	600-3000	23 Dec 2008	5.4	#2	DR
ITIS058	44.248	11.397	4.0	3.4	16.4-19.1	94	53	107	0.30	0.10-0.50	600-3000	14 Sep 2003	5.3	#2	DR

**Table 6:** Geometric and kinematic parameters of the *ISSs*. The ID of each sources is the same used in the DISS database and shown in Figure 7.

Geometric coordinates refer to the centroid of the fault plane. Key to Groups: #1: Shallow thrust; #2: Deep ramp; #3: Inherited fault. Key to tectonic structures: GS: Southern Alpine Giudicarie System; SAMF: Southern Alps Mountain Front; SAOA: Southern Alps Outer Arc; NAOA: Northern Apennines Outer Arc; *FRA*: Ferrara-Romagna Arc; PTF: Pedepenninic Thrust Front; DR: Deep ramp.

Source ID	Min Depth (km)	Max depth (km)	Strike Min (°)	Strike Max (°)	Dip Min (°)	Dip Max (°)	Rake Min (°)	Rake Max (°)	Slip rate (mm/a)	$M_w$	Group	Tectonic Structures
ITCS048	5	10	205	265	25	45	70	100	0.10-0.50	5.7	#1	GS
ITCS010	5	10	265	295	25	45	80	100	0.10-0.50	5.5	#1	SAMF
ITCS072	1	7	70	100	30	45	80	100	0.10-0.50	6.1	#1	SAOA backthrust
ITCS073	3	9	200	250	25	45	70	100	0.10-0.50	5.5	#1	GS
ITCS002	2	9	230	340	25	45	80	100	0.10-0.50	6.1	#1	SAOA
ITCS076	2	14	240	260	30	50	80	100	0.10-0.50	6.7	#3	---
ITCS050	1	8	85	115	25	55	80	100	0.10-0.50	5.5	#1	NAOA
ITCS018	2	8	30	50	20	45	60	90	0.10-0.54*	5.5	#1	NAOA-EA
ITCS044	2	7	30	115	20	40	80	100	0.48-0.54*	5.5	#1	NAOA-EA
ITCS009	2	8	120	140	2	40	90	120	0.16-0.53*	5.6	#1	NAOA-EA
ITCS049	3	10	35	65	30	50	60	90	0.04-0.16*	5.5	#1	NAOA-FRA
ITCS103	3.5	10	110	120	40	50	80	100	0.25-0.50*	6.1	#1	NAOA-FRA
ITCS051	3	10	95	125	25	45	80	100	0.50-1.04*	6.0	#1	NAOA-FRA
ITCS012	2	8	85	150	20	40	80	120	0.49-0.55*	6.0	#1	NAOA-FRA
ITCS109	2.5	10	115	125	20	40	80	100	0.10-0.30*	6.0	#1	NAOA-FRA
ITCS011	2	10	110	140	25	45	80	100	0.15-0.33*	6.0	#1	NAOA-FRA
ITCS045	2	10	110	150	20	40	80	100	0.43-0.62*	5.5	#1	PTF
ITCS046	2	8	95	120	20	40	80	100	0.10-0.50	5.9	#1	PTF
ITCS047	2	8	85	135	20	40	80	100	0.10-0.50	6.0	#1	PTF
ITCS001	2	8	110	140	30	40	80	100	0.10-0.50	5.8	#1	PTF
ITCS027	12	22	90	160	20	55	70	110	0.10-0.50	6.2	#2	DR

**Table 7:** Geometric and kinematic parameters of the CSSs. Keys for Groups and Tectonic structures as in Table 6. \* Slip rate from MAESANO *et al.* (submitted).

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49

Reference	Event	Length (km)	Width (km)	Min depth (km)	Strike (°)	Dip (°)	Rake (°)	Maximum slip (m)	Uniform Slip (m)	M <sub>0</sub> (Nm)	M <sub>w</sub>	Method
GCMT	20 May	---	---	---	88/304	35/61	60/109	---	---	1.74E+18	6.1	CMT
GFZ	20 May	---	---	---	104/287	32/58	88/91	---	---	1.6E+18	6.1	MT
SLUEC	20 May	---	---	---	278/105	45/45	85/95	---	---	1.02E+18	5.94	RCMT
PONDRELLI <i>et al.</i> , 2012	20 May	---	---	---	279/109	60/30	85/99	---	---	1.81E+18	6.11	QRCMT
SCOGNAMIGLIO <i>et al.</i> , 2012; TDMT	20 May	---	---	---	280/103	44/46	88/92	---	---	7.00E+17	5.86	TDMT
MALAGNINI <i>et al.</i> , 2012	20 May	---	---	---	285	45	90	---	---	---	5.63	MT
SARAÒ and PERUZZA, 2012	20 May	---	---	---	282/97	51/39	93/86	---	---	1.37E+18	6.1	MT
CESCA <i>et al.</i> , 2013	20 May	---	---	---	103/286	25/65	87/91	---	---	1.89E+18	6.1	Seismological source inversion
BIGNAMI <i>et al.</i> , 2012	20 May	19	4	4.0	115	43	90	---	0.80	---	6.0	Modelling of InSAR data
SERPELLONI <i>et al.</i> , 2012	20 May	12.8	5.3	4.9	109	37.7	86	---	0.99	---	6.13	Modeling of GPS data
PEZZO <i>et al.</i> , 2013	20 May	34	11	1.0	114	40	90	1.20	---	---	---	Modelling of GPS and InSAR data
TIZZANI <i>et al.</i> , 2013	20 May	14.8	3.6	4.3	114	40	80	---	0.70	1.12E+18	---	Modelling of GPS and InSAR data
GCMT	29 May	---	---	---	91/291	29/63	72/99	---	---	7.97E+17	5.9	CMT
GFZ	29 May	---	---	---	97/283	30/60	85/93	---	---	6.6E+17	5.8	MT
PONDRELLI <i>et al.</i> , 2012	29 May	---	---	---	276/110	71/20	85/103	---	---	1.07E+18	5.96	QRCMT


1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49

SCOGNAMIGLIO <i>et al.</i> , 2012	29 May	---	---	---	275/95	52/38	90/90	---	---	3.51E+17	5.66	TDMT
MALAGNINI <i>et al.</i> , 2012	29 May	---	---	---	270	45	85	---	---	---	5.44	MT
SARAÒ and PERUZZA, 2012	29 May	---	---	---	274/97	64/26	89/93	---	---	7.66E+17	5.9	MT
CESCA <i>et al.</i> , 2013	29 May	---	---	---	103/281	27/63	92/89	---	---	8.81E+17	5.9	Seismological source inversion
BIGNAMI <i>et al.</i> , 2012	29 May	16	6	3.1	102	20	95	---	0.34	---	5.9	Modelling of InSAR data
SERPELLONI <i>et al.</i> , 2012	29 May	12.7	5.7	2.8	102	35.2	85.4	---	0.36	---	5.85	Modeling of GPS data
PEZZO <i>et al.</i> , 2013	29 May	32	7.5	1.0	95	45	85	0.54	---	---	---	Modelling of GPS and InSAR data
TIZZANI <i>et al.</i> , 2013	29 May	20	2.6	4.5	97	40	90	---	0.80	1.24E+18	---	Modelling of GPS and InSAR data


**Table 8:** Geometric and kinematic parameters of the 20 and 29 May 2012 earthquakes as proposed by various investigators and institutions. Sources: GCMT (Global CMT Catalogue), <http://www.globalcmt.org/>; GFZ (GFZ Moment tensor), <http://geofon.gfz-potsdam.de/eqinfo/list.php>; SLUEC (Saint Luis University Earthquake Center), [http://www.eas.slu.edu/eqc/eqc\\_mt/MECH.IT/](http://www.eas.slu.edu/eqc/eqc_mt/MECH.IT/); QRCMT (Quick Regional Moment Tensors), <http://autorcmt.bo.ingv.it/quicks.html>; TDMT (Time Domain Moment Tensor), <http://cnt.rm.ingv.it/tdmt.html>.



Figure\_1  
[Click here to download high resolution image](#)




Figure\_2  
[Click here to download high resolution image](#)







Figure\_3  
[Click here to download high resolution image](#)




Figure\_4  
[Click here to download high resolution image](#)








Figure\_6  
[Click here to download high resolution image](#)






Figure\_7  
[Click here to download high resolution image](#)




Figure\_8  
[Click here to download high resolution image](#)






Figure\_9a  
[Click here to download high resolution image](#)



Figure\_9b  
[Click here to download high resolution image](#)





Figure\_10  
[Click here to download high resolution image](#)

