

TiltDrone: A Fully-Actuated Tilting Quadrotor Platform

Peter Zheng , Xinkai Tan, Basaran Bahadir Kocer , Erdeng Yang, and Mirko Kovac 

Abstract—Multi-directional aerial platforms can fly in almost any orientation and direction, often maneuvering in ways their underactuated counterparts cannot match. A subset of multi-directional platforms is fully-actuated multirotors, where all six degrees of freedom are independently controlled without redundancies. Fully-actuated multirotors possess much greater freedom of movement than conventional multirotor drones, allowing them to perform complex sensing and manipulation tasks. While there has been comprehensive research on multi-directional multirotor control systems, the spectrum of hardware designs remains fragmented. This letter sets out the hardware design architecture of a fully-actuated quadrotor and its associated control framework. Following the novel platform design, a prototype was built to validate the control scheme and characterize the flight performance. The resulting quadrotor was shown in operation to be capable of holding a stationary hover at 30° incline, and track position commands by thrust vectoring [Video attachment: https://youtu.be/8HOQI_77CVg].

Index Terms—Aerial systems: mechanics and control, mechanism design, aerial systems: applications.

I. INTRODUCTION

UNMANNED Aerial Vehicles (UAVs) with multirotor configurations have gained popularity in aerial robotics

Manuscript received February 24, 2020; accepted June 24, 2020. Date of publication July 20, 2020; date of current version September 15, 2020. This letter was recommended for publication by Associate Editor F. Ruggiero and Editor J. Roberts upon evaluation of the Reviewers' comments. This work was supported in part by the Natural Environment Research Council under Grant NE/L002515/1, in part by the Grantham Institute - Climate Change and the Environment, Imperial College London; the South East Asia Rainforest Research Partnership; Engineering and Physical Sciences Research Council under Grants EP/R009953/1, EP/N018494/1, EP/R026173/1, and EP/S031464/1, in part by the EU H2020 AeroTwin project under Grant 810321. The work of M. Kovac was supported by the Royal Society Wolfson Fellowship under Grant RSWF/R1/18003. The Multi-Terrain Aerial Robotics Arena is supported through a philanthropic gift by Brahma Vasudevan. (Peter Zheng and Xinkai Tan contributed equally to this work.) (Corresponding author: Mirko Kovac.)

Peter Zheng is with the Aerial Robotics Laboratory, Imperial College London, London SW7 2AZ, U.K., and also with the Science and Solutions for a Changing Planet DTP and the Grantham Institute – Climate Change and the Environment, (e-mail: peter.zheng13@imperial.ac.uk).

Xinkai Tan, Basaran Bahadir Kocer, and Erdeng Yang are with the Aerial Robotics Laboratory, Imperial College London, London SW7 2AZ, U.K. (e-mail: xinkai453@hotmail.com; b.kocer@imperial.ac.uk; xhyed123@163.com).

Mirko Kovac is with the Aerial Robotics Laboratory, Imperial College London, London SW7 2AZ, U.K., and also with the Materials and Technology Centre of Robotics, Swiss Federal Laboratories for Materials Science and Technology, 8600 Dübendorf, Switzerland (e-mail: m.kovac@imperial.ac.uk).

This article has supplementary downloadable material available at <http://ieeexplore.ieee.org>, provided by the authors.

Digital Object Identifier 10.1109/LRA.2020.3010460




Fig. 1. The TiltDrone prototype in tilted horizontal, level, and tilted hovering flight (bottom left to right). The morphing TiltDrone can tilt up to 30 degrees, allowing it to traverse narrow areas such as dense foliage in forest environments (top).

research [1], enabling a variety of applications, from close proximity infrastructure maintenance to ecological monitoring [2]–[6]. Conventionally, rotors are fixed perpendicularly to the plane of the platform with steering achieved by differential thrust. Such a simple and effective design gave rise to the use of multirotor systems in applications which require robustness and high thrust-to-weight ratios.

Fixing the rotors in the same orientation on the platform couples the multirotor's rotational and translational degrees of freedom (DOFs). As a result, it is difficult to achieve the desired dexterity to conduct physical interactions, such as sensor installation and surface inspection, and aerial filming. Naturally, there is active interest in decoupling the DOFs, allowing the multirotor to fully actuate its 6-DOF [7].

In this letter, we define “multi-directional” as the ability to accelerate in any direction and orientation without coupling within the designed workspace. Multi-directional multirotor designs could broadly be grouped into three categories: fixed-tilt, uniaxial-tilt, and biaxial-tilt.

Multirotors with the motors fixed at various prescribed angles [8]–[13] can achieve full range multi-directional motion without any morphological change. They are simple to manufacture and are structurally robust [7]. However, this reduces the flight time due to the partial cancellation of the non-parallel thrust vectors.

Uniaxial-tilt multirotors actively rotate their rotors about the axis of the individual multirotor arm [14]–[19]. Although a full range of motion in 6-DOF is possible, all designs within this category will create opposing thrust vectors.




Fig. 2. Fully actuated quadrotor prototype (right) and its kinematic design (left).

Biaxial-tilt multirotors [20]–[22] successfully avoid the inefficiencies from cross-canceling rotor thrusts. Tilting can be synchronized such that the thrust axes remain parallel to each other. However, these designs will incur the weight penalty of the tilting mechanism.

To further assess the efficiency of multi-directional designs, we can regroup the drones by the level of mechanical actuation achieved. Although over-actuated systems are beneficial in handling component failures [16], the redundancies result in significant weight penalties.

Underactuated multi-directional flight can be achieved through torque modulation [23]. By installing flexible hinges at an angle, only two counter-rotating rotors are needed to generate directional and/or torsional forces. The aerial vehicle could tilt up to 8° , albeit with friction losses at the swashplateless hinge [24]. The relatively high frequency of throttle modulation also produces significant heating of the motor.

Fully-actuated designs can be both cost effective and simple to implement. Control allocation is direct as the input (actuator command) to output (position-orientation) mapping is unique, thus additional computation is not required. Currently, fully-actuated biaxial tilt-rotors with four propellers have been proven to be feasible and stable [22], [25]. However, aforementioned evaluations are limited to simulation environments.

In this letter, we introduce the hardware design architecture for the TiltDrone (Fig. 1). The TiltDrone design enables multi-directional motion on a fully-actuated quadrotor platform. The quadrotor design comprises of a biaxial rotor tilting mechanism, driven by twin linear servomotors in parallel (Fig. 2). The kinematic chain features spherical-cylindrical compound joints, allowing the upper and lower structure to remain a constant distance apart during actuation. The mechanism retains the quadrotor form at all tilt angles. This greatly reduces the complexity of the control. Section II sets out the geometrical constraints and design feasibility considerations. The control framework is discussed in Section III. The validation of the proposed design architecture and the control framework are presented in Section IV and the conclusions are drawn in Section V.

II. DESIGN

Translating the kinematics to a viable mechanism poses challenges in the design of biaxial-tilting quadrotors. The most critical consideration is the clearance requirements of the platform structure, which may not be immediately obvious when modeling with static drawings. The following design margins were derived with variables shown in Fig. 3. It is useful to




Fig. 3. Geometrical diagram of the tilting platform and a comparison of the prototype design level and tilted. The rotor workspaces are shaded in yellow. The workspaces can overlap as the rotors are tilted synchronously.

note that the rotor workspaces can overlap as rotor tilts are synchronized. To aid the visualization of the derivations, detailed diagrams are provided on our GitHub page.¹

A. Structural Sizing

The body of the drone is sized for an arbitrary design derived from Fig. 2 with predefined rotor height H_r , propeller diameter D_{prop} , and tilt angle α_{max} , $\forall |\alpha| \leq \pi/2$ (Fig. 3). Approximating the propeller as a cylindrical disk with a cross section thickness T_{prop} , one could obtain the minimum length l_b and height h_b of the quadrotor body. For propeller-propeller clearance when tilting

$$l_b > \sqrt{D_{prop}^2 + T_{prop}^2} \quad (1)$$

However, if the designed tilt angle is small, as defined by

$$\alpha_{max} \leq \arctan\left(\frac{T_{prop}}{D_{prop}/2}\right) \quad (2)$$

such that only propeller-propeller abrasion can occur, the alternative constraint (3) is applied.

$$l_b > \frac{D_{prop}}{\cos(\alpha_{max})} \quad (3)$$

The propeller-motor clearance is also considered in tandem with (1). The motor is approximated as a cylinder with diameter D_m . The body length is constrained such that

$$\text{if } \alpha_{max} \geq \arctan\left(\frac{2H_r}{D_{prop} + D_m}\right) \quad (4)$$

$$l_b > \sqrt{H_r^2 + \left(\frac{D_{prop} + D_m}{2}\right)^2} \quad (5)$$

$$\text{else } l_b > \frac{D_{prop} + D_m}{2 \cos \alpha_{max}} \quad (6)$$

¹<https://github.com/Aerial-Robotics-Laboratory/TiltDrone>




Fig. 5. (A) Swept volume of the rotor axis of rotation with linear servomotor axes s_1, s_2 rotated -45° from rotor axes XY , (B) attitude and polar coordinate presentation of the thrust vector, and (C) side view of the rotor and the compound joint.

C. Rotor Gimbal

The rotors are gimballed to allow tilting on the roll and pitch planes, restricting translation and yaw. Control rods extend down from the gimbal platform and slide through the swivel head ball joints. The four ball joint sockets are interconnected to form the planar mechanism.

It is critical to account for the area swept by the tilting rotor (i.e. the workspace). As the linear servomotors (servos) are mounted perpendicularly, the parallel mechanism sweeps out a square. The rotor axis with a radius of the rotor's height is confined within the plane defined by

$$H_r^2 = s_1^2 + s_2^2 + z^2 \quad (18)$$

$$z \geq \pm \tan(\alpha_{s_2, \max} - \frac{\pi}{2})s_1 \quad (19)$$

$$z \geq \pm \tan(\alpha_{s_1, \max} - \frac{\pi}{2})s_2 \quad (20)$$

where orthogonal axes s_1, s_2 , and z denotes the travel of Servo 1, Servo 2, and the vertical axis respectively (Fig. 5A). $\alpha_{s_1, \max}$ and $\alpha_{s_2, \max}$ are the maximum tilt relative to the servo planes. They are calculated by $\alpha_{s_i, \max} = \arctan S_i / (2Z_0)$ with S_1 and S_2 denoting the maximum length of servo travel, and Z_0 the perpendicular distance of the origin (center of rotation) to the servo plane (Fig. 5C).

Tracing the boundaries set by (19) and (20), the quadrotor structure and the gimbal mechanism must remain clear of the volumetric sweep by a full rotor tilt. This equates to a rotation of the rotor through an angle of

$$\beta_{s_1} = 2 \arctan \frac{S_1}{\sqrt{4Z_0^2 + S_2^2}} \quad (21)$$

about centerlines

$$\begin{bmatrix} s_1 \\ s_2 \\ z \end{bmatrix} = \begin{bmatrix} 0 \\ s_2 \\ \pm \cot(\alpha - \frac{\pi}{2})s_2 \end{bmatrix} \quad (22)$$

and angle

$$\beta_{s_2} = 2 \arctan \frac{S_2}{\sqrt{4Z_0^2 + S_1^2}} \quad (23)$$

about

$$\begin{bmatrix} s_1 \\ s_2 \\ z \end{bmatrix} = \begin{bmatrix} s_1 \\ 0 \\ \pm \cot(\alpha - \frac{\pi}{2})s_1 \end{bmatrix} \quad (24)$$

D. Tilting Mechanism

The quadrotor platform is configured in a “+” formation with the servomotors offset at -45° to the XY axes (Fig. 2). The rotor gimbals are linked via the ball joint housings with a cross shaped strut. This cancels out the gyroscopic precession of the rotors when actuated in flight [21]. Driven by the two servos, the planar mechanism tilts the rotors opposite to the direction of actuation.

The planar mechanism is inherently susceptible to twist. Although the mechanism is constrained by the servos, small unintended twists can occur due to manufacturing defects and unbalanced actuating forces. In such events, the rotors are vectored to induce yaw. The flight controller attempts to correct for yaw by accelerating one of the diagonal rotor pair to generate torque. However, this is insufficient as brushless DC motors have low moments of inertia and the propellers are optimized for a high lift-to-drag ratio. Thus, the thrust vector induced yaw remains the dominant term, resulting in an irrecoverable spin.

This design flaw occurs within the small-angle approximation regime. Therefore the resultant rotor angle is approximately $l_b / (2Z_0)$ times the twist of the mechanism. A more compact platform will reduce the effect of the twist. However, the more general solution is to use rigid and tight tolerance sliding components to restrict the twist angle.

III. CONTROL FRAMEWORK

This section sets out the conversion of attitude commands into the position of the servomotors, and the combination of thrust vectoring and body rotation when servo travel is exceeded. The parallel mechanism allows straightforward inversion of the kinematic equations. Therefore, although the results presented are of a simple PD-based position controller, it is reasonable to assume that most types of high-level control schemes can function on this platform due to having decoupled translational and attitude channels.

A. Control Architecture

Our system is autonomously controlled by an offboard RC signal, commanding roll and pitch angles, thrust, yaw rate and servo positions (Fig. 6). The high-level command inputs are given in the form of position XYZ , Yaw (γ), and body vector \vec{T} in global frame spherical coordinates (Fig. 5B). The position-orientation commands are sent to the high-level controller, where




Fig. 6. Control diagram of the fully-actuated platform with the augmented elements (red) of a traditional quadrotor attitude controller (blue).




Fig. 7. Control approach of various commanded thrust vectors (left) and actual behaviours of the quadrotor (right).

the feedback control loop is formed with odometry provided by a motion capture system.

The body vector commands feed into the *limiter* where they are saturated to prevent unattainable commands from entering the *control allocator*. The *control allocator* takes the output from the high-level controller and maps the attitude commands to servo positions. Pitch and roll are used for compensation when the desired polar angle is beyond the servo limit (Fig. 7). The commands are then sent to the quadrotor via a RC transmitter.




Fig. 8. Command modulation due to servomotor trim. This occurs within the *limiter* control block.

The discussions on the stability and the fully-actuated property are given in the Appendix.

B. Control Allocation

As the quadrotor receives attitude command and servo positions, the control allocation fundamentally resolves to a conversion between spherical, attitude, and Cartesian (servomotor) coordinates, as shown in Fig 5B. Although not strictly necessary for control allocation, the body vector command was used in spherical form. This is a more intuitive way to command tilt as we can prioritize the azimuth (tilt direction θ) over the polar angle (tilt angle ϕ). Roll α_R and pitch attitude α_P are given as

$$\alpha_R = -\arctan(\sin \theta \tan \phi) \quad (25)$$

$$\alpha_P = \arctan(\cos \theta \tan \phi) \quad (26)$$

They are further converted to servo positions by

$$s_1 = -\frac{\sqrt{2}}{2} Z_0 (\tan \alpha_R + \tan \alpha_P) \quad (27)$$

$$s_2 = -\frac{\sqrt{2}}{2} Z_0 (\tan \alpha_R - \tan \alpha_P) \quad (28)$$

Solving the geometrical conversion from servo position to polar orientation we get

$$\theta = \arctan\left(\frac{s_1 + s_2}{-s_1 + s_2}\right) + \pi \quad (29)$$

$$\phi = \arctan\left(\sqrt{s_1^2 + s_2^2}\right) \quad (30)$$

The prototype platform was designed with $S_1 = S_2 = 2Z_0$. Solving for the tilt limits with $-S_i/2 \leq s_i \leq S_i/2$ and (25)-(28), the positive polar angle must satisfy

$$\phi \leq \arctan\sqrt{\frac{1 \pm \sin 2\theta}{1 \mp \sin 2\theta} + 1} \quad (31)$$

for Servo 1 and Servo 2 respectively. However, incorporating servo trimming is inconvenient in spherical coordinates due to the non-linear mapping of attitude vector addition in spherical space. The *limiter* maps the commands onto the Cartesian servo coordinate frame. We then solve for the maximum possible magnitude of the command vector given an offset from the origin and the servo travel limits (Fig. 8). This gives the constraint equations

$$\text{if } s_{1,2} > 1$$

$$\begin{bmatrix} s_{1,2} \\ s_{2,1} \end{bmatrix} = \begin{bmatrix} 1 \\ \frac{(1-s_{1,2})(s_{2,1}-s_{2,1\text{trim}})}{s_{1,2}-s_{1,2\text{trim}}} + s_{2,1\text{trim}} \end{bmatrix} \quad (32)$$

TABLE I
PHYSICAL PARAMETERS

Item name	Unit(s)	Per unit weight (g)	Subtotal (g)	% Total weight
DYS SE2008	4	33	132	14.7
DAI T5040C	4	4.2	16.8	1.9
mightyZap L12-20PT3	2	51	101	11.2
Airbot Typhoon32 4in1	1	16.8	16.8	1.9
Airbot Omnibus F4 SD	1	7.2	7.2	1.3
Biaxial-tilting mechanism	1	307	307	34.1
4-Cell LiPo Battery	1	162	162	18
Peripherals			156.5	17.4
Total		738	899.3	

if $s_{1,2} < -1$

$$\begin{bmatrix} s_{1,2} \\ s_{2,1} \end{bmatrix} = \begin{bmatrix} -1 \\ \frac{(-1-s_{1,2})(s_{2,1}-s_{2,1\text{trim}})}{s_{1,2}-s_{1,2\text{trim}}} + s_{2,1\text{trim}} \end{bmatrix} \quad (33)$$

With the saturated output given, the *limiter* remaps the control output to give the feasible command input. Accounting for the servo trims, (29) and (30) are modified to give

$$\theta_{\text{command}} = \arctan \left(\frac{s_1 - s_{1\text{trim}} + s_2 - s_{2\text{trim}}}{-s_1 - s_{1\text{trim}} + s_2 - s_{2\text{trim}}} \right) + \pi \quad (34)$$

$$\phi_{\text{command}} = \arctan \left(\sqrt{(s_1 - s_{1\text{trim}})^2 + (s_2 - s_{2\text{trim}})^2} \right) \quad (35)$$

the actual (post-*limiter*) commands.

IV. RESULTS AND DISCUSSION

A 5 in propeller prototype platform was manufactured to validate the design. The gimbals and the planar mechanism were 3D-printed on the Markforged Mark 2 with *Onyx* filament. Continuous carbon fiber (CF) were added where possible for stiffness. An Omnibus F4 V3 flight controller was used with an unmodified version of the *Betaflight* 4.1 firmware [30]. The servomotors are controlled through pulse width modulation (PWM) commands sent from the flight controller with the *Servo Tilt* feature. Though initially designed with $\alpha_{\text{max}} = 45^\circ$ in all directions, issues noted during manufacturing and testing limited the stable hovering tilt angle to 30° .

A. Manufacturing

Other than the tilting mechanism and the structure of the prototype platform, the components listed in Table I were sourced from consumer grade suppliers. During the modelling stage, physical considerations caused deviations from the idealized design. They were:

- the need to house the linear servos between the rotors resulted in an approximately 40% increase from the minimum structural length
- the drone structure and mechanism height dimensions were enlarged to increase stiffness and toughness
- the rotor height was increased to give sufficient space to design the gimbal

There were also a number of limitations due to component availability and manufacturing techniques such as:




Fig. 9. Step response of conventional and fully-actuated flight at 0° tilt.

- the ball bearings, which form the passive compound joints, were approximately limited to a $\pm 40^\circ$ cone
- the radial bearings, which form the passive universal joints, limited the minimum size of the gimbal - this resulted in an increased rotor height
- complex geometries limited the use of continuous CF reinforced plates and tubes in the structure

Asymmetric component alignments were considered. For example, one could offset the linear servo pistons out of the horizontal plane. This reduces the size of the platform by allowing the servos to be placed closer to the drone center. However, it would create unbalanced sliding friction in the mechanism which must be accounted for in the control system, if significantly large.

The tilt limit due to the ball bearings can be circumvented by employing a ‘‘H’’ configuration. Allowing the opposing bearing socket pairs to rotate with additional revolute joints at the junctions of the mechanism, similar to [4], increases the tilt angle of a single axis. However, owing to parallel linear actuation, the design imposes a tilt limit of 90° .

A rough design performance evaluation can be conducted. The biaxial-tilting mechanism account for all the 3D-printed parts. The rule of mixtures with an approximate continuous CF ratio of 15% gives a tensile modulus of 10.2 GPa [31]. A like-for-like exchange with quasi-isotropic CF-Epoxy material (35.3 GPa) may reduce its weight by 71% [32]. The peripheral stack (inc. CF mounting plate, minor electronics) can be optimized by a 50% weight reduction. Under such optimistic projections, the frame weight of 167g is somewhat comparable to an open-sourced 5 in propeller frame (149.1g) [33]. Therefore, the TiltDrone can achieve flight endurance comparable to a conventional underactuated quadrotor if the weight and size of the linear servomotor is reduced in future iterations.

B. Testing

Flight tests, using a PD position controller, were conducted to compare the cases with and without fully-actuated motion (i.e. conventional flight) (Fig. 9). The intention of the comparison study is to explore full-actuation, where the system can follow a trajectory while keeping commanded attitude angles. Accordingly, our design provides the decoupled control property and

TABLE II
STEP RESPONSE MEAN ABSOLUTE ERROR AND STANDARD DEVIATION WITH CONVENTIONAL (CONV) AND FULLY-ACTUATED (FA) FLIGHT

	MAE _{conv}	MAE _{FA}	STD _{conv}	STD _{FA}
x (m)	0.0463	0.0477	0.0691	0.0513
y (m)	0.0664	0.0415	0.0706	0.0508
z (m)	0.0074	0.0250	0.0102	0.0364
Roll (deg)	NA	4.0400	NA	0.2839
Pitch (deg)	NA	2.6304	NA	0.3639




Fig. 10. Comparing pitch response due to step position command of conventional and fully-actuated flight at 0° tilt. The selected time interval from the step response flight - a similar pattern is observed at 20th s for the pitch angle and 5th & 15th s for the roll angle.




Fig. 11. Static fully-actuated flight at various roll axis tilt.

the results show that position tracking errors in the two flight modes are comparable (Table II).

In all flight tests, sudden z deviations occur when discontinuous servo position commands were given. As the servo positions were not fed back into the controller, it could not account for the rotor angle during the transition. Since the platform did not deviate away from the target position when initially responding to a step command, we conclude that the inertia of the mechanism is insignificant. Evidently, with aggressive maneuvers, the fully-actuated platform showed a noticeable reduction in rolling and pitching (Fig. 10).

At static hover, the prototype reached a maximum stable tilt of 30° (Fig. 11). The lack of an integral controller resulted in the initial constant offset. The subsequent change in the offset when tilting is likely due to the backlash in the servo and the mechanism. The closed loop stability is discussed in the Appendix. As the main focus of this study is to provide a new

design, hardware configuration, and experimental evaluation - the extensive stability analysis is excluded.

We noted that the prototype tilting mechanism was prone to uncontrollable yaw spins if manufactured with loose tolerance. The prototype uses the servomechanisms as both actuators and twist constraints. This is not ideal as the servo pistons are not sufficiently rigid. Ideally, the servo pistons are not required to constrain the twisting of the planar mechanism. This small angle induced issue was partially resolved by adding a passive, twist-restricting, linear rail. Alternatively, a third servomotor could be added as active yaw control. Although the platform becomes over-actuated with the redundant servomotor, it will gain greater yaw authority through thrust vectoring.

V. CONCLUSION

A fully-actuated, biaxial-tilting, quadrotor hardware design architecture has been presented. A prototype was built to validate the proposed design approach. By placing the rotors on a two axis gimbal and tilting them in unison with a parallel mechanism driven by two linear servomotors, a simple control allocator is able to decouple the platform's rotation and translation. The prototype platform reached a 30° tilt in flight. By leveraging our system, it may be possible to fly through narrow openings, or exert forces on different surfaces with reduced effort on the control design. In particular, the ability to tilt while hovering can be exploited to place sensors on previously inaccessible locations.

In future works, greater maneuverability can be attained by combining tilting and pitching. This may require advancements in trajectory planning and optimization-based control. The subsequent prototype platform will feature a gimballed flight controller, tilting with the rotors. We suspect this may be more intuitive for a human pilot. It also further simplifies the control allocation as the flight controller will always remain parallel to the rotor plane. In addition, the scalability and optimization of the design warrant further studies.

APPENDIX

For the translational and attitude channels of the system, an eigenvalue problem is defined based on the mathematical model. Following similar derivations for the PD-based controller, the selected control parameters are based on the worst-case degradation of the control actions for different channels. This affects the transitions between the angles which can be seen in Fig. 10. We tuned parameters of PD altitude and position control for static pitching conditions at the maximum kinematically allowable tilt angle, where the close-loop margins are the narrowest. Therefore, the parameters selected while controlling the system at higher angles stabilizes the system at lower angles.

Taking the sum of all thrusts generated by each rotor T_i [34],

$$\mathbf{F}^W(\alpha_R, \alpha_P, \mathbf{u}) = \mathbf{R}_B \sum_{i=1}^4 \mathbf{T}_i^B(\mathbf{T}_i, \alpha_R, \alpha_P) \quad (36)$$

$$= \mathbf{R}_B \mathbf{F}_1(\alpha_R, \alpha_P) \mathbf{u}, \quad (37)$$

where $\mathbf{u} = [T_1, T_2, T_3, T_4]$ and $\mathbf{F}_1(\alpha_R, \alpha_P) \in \mathbb{R}^{3 \times 4}$ depend on α_R and α_P . Taking the sum of the torques $\boldsymbol{\tau}^W(\alpha_R, \alpha_P, \mathbf{u})$:

$$\mathbf{F}_2(\alpha_R, \alpha_P)\mathbf{u} = \sum_{i=1}^4 \mathbf{f}_i^B(\mathbf{p}^B \times \mathbf{f}_i^B(\mathbf{T}_i, \alpha_R, \alpha_P) \quad (38)$$

$$+ \boldsymbol{\tau}_i^B(\mathbf{T}_i, \alpha_R, \alpha_P)), \quad (39)$$

The equations of motions in a compact form:

$$\begin{bmatrix} m\ddot{\mathbf{p}}_B \\ \mathbf{J}\dot{\boldsymbol{\omega}}_B \end{bmatrix} = - \begin{bmatrix} mg\mathbf{e}_3 \\ \boldsymbol{\omega}_B \times \mathbf{J}\boldsymbol{\omega}_B \end{bmatrix} + \begin{bmatrix} \mathbf{R}_B \mathbf{F}_1(\alpha_R, \alpha_P) \\ \mathbf{F}_2(\alpha_R, \alpha_P) \end{bmatrix} \mathbf{u} \quad (40)$$

Two generic configuration can be obtained for the actuation considering $\mathbf{G} = \mathbf{F}_1^T(\cdot)\mathbf{F}_2^T(\cdot)$:

- $\alpha_R = \alpha_P = 0 \Rightarrow \text{rank}(\mathbf{G}(\mathbf{R}_B, \alpha_R, \alpha_P)) = 4$
- $\alpha_R \in A \setminus \{0\}$ and $\alpha_P \in A \setminus \{0\} \Rightarrow \text{rank}(\mathbf{G}(\mathbf{R}_B, \alpha_R, \alpha_P)) = 6$

$\alpha_{i\max}, \forall |\alpha_i| < \pi/2$, where A is the set that α_i belongs to.

It is naturally interpreted that the system turns out to be a conventional quadrotor when the tilting angles on the rotors are locked vertically to the quadrotor plane. Otherwise, it is fully-actuated within the configuration space. For the excluded symbols due to the space limitation, interested readers can refer to [19], [34]. The stability and fully-actuated aspects are further expanded on our GitHub page referred above.

ACKNOWLEDGMENT

The authors would like to thank Mr Feng Xiao for aiding the software development and video recording, and reviewing this work. The authors would also like to thank Dr Salua Hamaza and Mr Hussain Noor for reviewing the manuscripts.

REFERENCES

- [1] C. F. Liew, D. DeLatte, N. Takeishi, and T. Yairi, "Recent developments in aerial robotics: A survey and prototypes overview," 2017. [Online]. Available: <http://arxiv.org/abs/1711.10085>
- [2] P. Chermprayong, K. Zhang, F. Xiao, and M. Kovac, "An integrated delta manipulator for aerial repair: A new aerial robotic system," *IEEE Robot. Automat. Mag.*, vol. 26, no. 1, pp. 54–66, Mar. 2019.
- [3] S. Hamaza *et al.*, "Sensor installation and retrieval operations using an unmanned aerial manipulator," *IEEE Robot. Automat. Lett.*, vol. 4, no. 3, pp. 2793–2800, Jul. 2019.
- [4] K. Kawasaki, Y. Motegi, M. Zhao, K. Okada, and M. Inaba, "Dual connected bi-copter with new wall trace locomotion feasibility that can fly at arbitrary tilt angle," in *Proc. IEEE/RSJ Int. Conf. Intell. Robots Syst.*, 2015, pp. 524–531.
- [5] B. B. Kocer, M. E. Tiryaki, M. Pratama, T. Tjahjowidodo, and G. G. L. Seet, "Aerial robot control in close proximity to ceiling: A force estimation-based nonlinear mpc," in *Proc. IEEE/RSJ Int. Conf. Intell. Robots Syst.*, 2019, pp. 2813–2819.
- [6] J. Paneque-Gálvez, M. K. McCall, B. M. Napolitano, S. A. Wich, and L. P. Koh, "Small drones for community-based forest monitoring: An assessment of their feasibility and potential in tropical areas," *Forests*, vol. 5, no. 6, pp. 1481–1507, 2014.
- [7] R. Rashad, J. Goeres, R. G. Aarts, J. B. Engelen, and S. Stramigoli, "Fully actuated multirotor UAVs: A literature review," *IEEE Robot. Automat. Mag.*, doi: [10.1109/MRA.2019.2955964](https://doi.org/10.1109/MRA.2019.2955964).
- [8] A. Franchi, R. Carli, D. Bicego, and M. Ryll, "Full-pose tracking control for aerial robotic systems with laterally-bounded input force," *IEEE Trans. Robot.*, vol. 34, no. 2, pp. 534–541, Apr. 2018.
- [9] G. Jiang and R. Voyles, "Hexrotor uav platform enabling dextrous interaction with structures-flight test," in *Proc. IEEE Int. Symp. Safety, Secur., Rescue Robot.*, 2013, pp. 1–6.
- [10] D. Brescianini and R. D'Andrea, "Design, modeling and control of an omni-directional aerial vehicle," in *Proc. IEEE Int. Conf. Robot. Automat.*, 2016, pp. 3261–3266.
- [11] A. Weinstein, C. Liu, C. Kobata, D. Shanks, and P. Boyle, "The VI: A holonomic aerial vehicle. video," 2017. [Online]. Available: https://www.youtube.com/watch?v=GAE_7TSXbQo, Accessed: Sep. 24, 2019.
- [12] S. Park *et al.*, "ODAR : Aerial manipulation platform enabling omnidirectional wrench generation," *IEEE/ASME Trans. Mechatronics*, vol. 23, no. 4, pp. 1907–1918, Aug. 2018.
- [13] J. Y. Lee, K. K. Leang, and W. Yim, "Design and control of a fully-actuated hexrotor for aerial manipulation applications," *J. Mechanisms Robot.*, vol. 10, no. 4, pp. 1–10, 2018.
- [14] M. Kamel *et al.*, "Voliro: An omnidirectional hexacopter with tiltable rotors," 2018. [Online]. Available: <http://arxiv.org/abs/1801.04581>
- [15] D. Kastelan, M. Konz, and J. Rudolph, "Fully actuated tricopter with pilot-supporting control," *IFAC-PapersOnLine*, vol. 48, no. 9, pp. 79–84, 2015.
- [16] A. Nemati, "Designing, modeling and control of a tilting rotor quadcopter," Ph.D. dissertation, Dept. Elect. Eng. Comput. Syst., Univ. Cincinnati, Cincinnati, OH, USA, 2016.
- [17] Y. Long and D. J. Cappelleri, "Linear control design, allocation, and implementation for the Omnicopter MAV," in *Proc. IEEE Int. Conf. Robot. Automat.*, 2013, pp. 289–294.
- [18] M. Ryll, H. H. Bühlhoff, and P. R. Giordano, "A novel overactuated quadrotor unmanned aerial vehicle: Modeling, control, and experimental validation," *IEEE Trans. Control Syst. Technol.*, vol. 23, no. 2, pp. 540–556, Mar. 2015.
- [19] M. Ryll, D. Bicego, M. Giurato, M. Lovera, and A. Franchi, "FAST-Hex – A morphing hexarotor: Design, mechanical implementation, control and experimental validation," 2020. [Online]. Available: <http://arxiv.org/abs/2004.06612>
- [20] A. F. Senkul and E. Altug, "System design of a novel tilt-roll rotor quadrotor UAV," *J. Intell. Robot. Syst.*, vol. 84, no. 1–4, pp. 575–599, 2016.
- [21] A. B. Junaid, A. D. D. C. Sanchez, J. B. Bosch, N. Vitzilaios, and Y. Zweiri, "Design and implementation of a dual-axis tilting quadcopter," *Robotics*, vol. 7, no. 4, pp. 1–20, 2018.
- [22] M. Odelga, P. Stegagno, and H. H. Bühlhoff, "A fully actuated quadrotor uav with a propeller tilting mechanism: Modeling and control," in *Proc. IEEE Int. Conf. Adv. Intell. Mechatronics*, 2016, pp. 306–311.
- [23] J. Paulos, B. Caraher, and M. Yim, "Emulating a fully actuated aerial vehicle using two actuators," in *Proc. IEEE Int. Conf. Robot. Automat.*, 2018, pp. 7011–7016.
- [24] J. Paulos and M. Yim, "Cyclic blade pitch control without a swashplate for small helicopters," *J. Guid., Control, Dyn.*, vol. 41, no. 3, pp. 689–700, 2018.
- [25] R. Ji, J. Ma, and S. S. Ge, "Modeling and control of a tilting quadcopter," *IEEE Trans. Aerosp. Electron. Syst.*, doi: [10.1109/TAES.2019.2955525](https://doi.org/10.1109/TAES.2019.2955525).
- [26] A. Desbiez, F. Expert, M. Boyron, J. Dipieri, S. Viollet, and F. Ruffier, "X-Morf: A crash-separable quadrotor that morfs its X-geometry in flight," in *Proc. Workshop Res., Educ. Develop. Unmanned Aerial Syst.*, 2017, pp. 222–227.
- [27] V. Riviere, A. Manecy, and S. Viollet, "Agile robotic fliers: A morphing-based approach," *Soft Robot.*, vol. 5, no. 5, pp. 541–553, 2018. [Online]. Available: <http://www.liebertpub.com/doi/10.1089/soro.2017.0120>
- [28] D. Falanga, K. Kleber, S. Mintchev, D. Floreano, and D. Scaramuzza, "The foldable drone: A morphing quadrotor that can squeeze and fly," *IEEE Robot. Automat. Lett.*, vol. 4, no. 2, pp. 209–216, Apr. 2019.
- [29] N. Bucki and M. W. Mueller, "Design and control of a passively morphing quadcopter," in *Proc. IEEE Int. Conf. Robot. Automat.*, 2019, pp. 9116–9122.
- [30] D. Nixon *et al.*, "Betaflight," 2020. [Online]. Available: <https://betaflight.com/>
- [31] Markforged. "Material datasheet composites," 2019. [Online]. Available: https://static.markforged.com/markforged_composites_datasheet.pdf, Accessed on: May 13, 2020.
- [32] EasyComposites. "EasyComposites - Single sided high strength carbon fibre sheet - specification," 2019. [Online]. Available: <https://www.easycarbon.com.uk/#!/cured-carbon-fibre-products/rigid-carbon-fibre-sheet/High-Strength-Carbon-Fibre-Sheet.html>
- [33] "Open source FPV drone frame - Source One," 2019. [Online]. Available: https://github.com/tbs-trappy/source_one, Accessed: May 13, 2020.
- [34] A. Franchi, *Platforms With Multi-directional Total Thrust*. Berlin, Germany: Springer, 2019, pp. 53–65.