

UVES/VLT high resolution spectroscopy of GRB 050730 afterglow: probing the features of the GRB environment[★]

V. D'Elia¹, F. Fiore¹, E. J. A. Meurs², G. Chincarini^{3,4}, A. Melandri⁵, L. Norci⁶, L. Pellizza⁷, R. Perna⁸, S. Piranomonte¹, L. Sbordone¹, L. Stella¹, G. Tagliaferri³, S. D. Vergani^{2,6}, P. Ward², L. Angelini⁹, L. A. Antonelli¹, D. N. Burrows¹⁰, S. Campana³, M. Capalbi¹¹, A. Cimatti¹², E. Costa¹³, G. Cusumano¹⁴, M. Della Valle¹², P. Filliatre⁷, A. Fontana¹, F. Frontera¹⁵, D. Fugazza³, N. Gehrels⁹, T. Giannini¹, P. Giommi¹¹, P. Goldoni¹⁶, D. Guetta¹, G. Israel¹, D. Lazzati⁸, D. Malesani¹⁷, G. Marconi¹⁸, K. Mason¹⁹, S. Mereghetti²⁰, F. Mirabel²¹, E. Molinari³, A. Moretti³, J. Nousek¹⁰, M. Perri¹¹, L. Piro¹³, G. Stratta¹¹, V. Testa¹, and M. Vietri²²

(Affiliations can be found after the references)

Received 29 September 2006 / Accepted 19 February 2007

ABSTRACT

Aims. The aim of this paper is to study the Gamma Ray Burst (GRB) environment through the analysis of the optical absorption features due to the gas surrounding the GRB.

Methods. To this purpose we analyze high resolution spectroscopic observations ($R = 20\,000\text{--}45\,000$, corresponding to 14 km s^{-1} at 4200 \AA and 6.6 km s^{-1} at 9000 \AA) of the optical afterglow of GRB050730, obtained with UVES@VLT ~ 4 h after the GRB trigger.

Results. The spectrum shows that the ISM of the GRB host galaxy at $z = 3.967$ is complex, with at least five components contributing to the main absorption system. We detect strong C II*, Si II*, O I* and Fe II* fine structure absorption lines associated to the second and third component.

Conclusions. For the first three components we derive information on the relative distance from the site of the GRB explosion. Component 1, which has the longest wavelength, highest positive velocity shift, does not present any fine structure nor low ionization lines; it only shows very high ionization features, such as C IV and O VI, suggesting that this component is very close to the GRB site. From the analysis of low and high ionization lines and fine structure lines, we find evidences that the distance of component 2 from the site of the GRB explosion is 10–100 times smaller than that of component 3. We evaluated the mean metallicity of the $z = 3.967$ system obtaining values $\approx 10^{-2}$ of the solar metallicity or less. However, this should not be taken as representative of the circumburst medium, since the main contribution to the hydrogen column density comes from the outer regions of the galaxy while that of the other elements presumably comes from the ISM closer to the GRB site. Furthermore, difficulties in evaluating dust depletion correction can modify significantly these values.

The mean [C/Fe] ratio agrees well with that expected by single star-formation event models. Interestingly the [C/Fe] of component 2 is smaller than that of component 3, in agreement with GRB dust destruction scenarios, if component 2 is closer than component 3 to the GRB site.

Key words. gamma rays: bursts – cosmology: observations – Galaxy: abundances – galaxies: ISM – line: identification – line: profiles

1. Introduction

For a few hours after their onset, Gamma Ray Bursts (GRBs) are the brightest beacons in the far Universe, offering a superb opportunity to investigate both GRB physics and high redshift galaxies. Tens of minutes after a GRB, its optical afterglow can be as bright as magnitude 13–15. High resolution (a few tens of km s^{-1} in the optical band), high quality (signal to noise > 10 per resolution element) spectra can therefore be gathered, provided that the afterglow is observed on such a short time scale by 8 m class telescopes.

Fiore et al. (2005) studied the UVES high resolution spectroscopy of GRB020813 and GRB021004 afterglows; they showed that the InterStellar Medium (ISM) of GRB host galaxies is complex when resolved down to a width of a few tens of km s^{-1} , with many components contributing to each main absorption system, and spanning a total velocity range of up to thousands of km s^{-1} . Velocity ranges of hundreds of km s^{-1} were found on the high resolution spectra obtained

with MIKE@MagellanII and HIRES@Keck on GRB051111 and GRB050730 (Chen et al. 2005a; Prochaska et al. 2006, PCB06 hereafter; Penprase et al. 2006).

The absorption systems can be divided into three broad categories. First, those associated with the GRB surrounding medium, second, those produced by the ISM of the host galaxy along the line of sight but distant enough not to be strongly modified by the GRB, and third the intergalactic matter along the line of sight. We discuss these three systems in turn.

The physical, dynamical and chemical status of the circumburst medium in the star-forming region hosting the GRB progenitor can be modified by the explosive event, through shock waves and ionizing photons. Blueshifted absorbers may be ionized and even radiatively and/or collisionally accelerated by the GRB and its afterglow. Circumstellar absorption lines in gamma-ray burst afterglow spectra can be used to determine the main properties of the star progenitors (van Marle et al. 2005). The variability of the intensity of absorption lines can be used to determine the location and density of the absorber, following Perna & Loeb (1998), Boettcher et al. (2002), Draine & Hao (2002), Mirabal et al. (2002), Perna & Lazzati (2002), Perna et al. (2003). The temperature and density of the absorbing gas

[★] Based on observations collected at the European Southern Observatory, ESO, the VLT/Kueyen telescope, Paranal, Chile, in the framework of programs 075.A-0603.

can be also accurately determined by studying particular line ratios, namely those of a fine structure transition to its ground state.

High resolution spectra do not reveal only the circumburst matter. They can also be used to probe the ISM of the host galaxy along the line of sight. The study of the ISM of $z \gtrsim 1$ galaxies has so far relied upon Lyman-break galaxies (LBGs) at $z = 3-4$ (see e.g. Steidel et al. 1999) and galaxies which happen to be along lines of sight to bright background quasars (QSOs). However, LBGs are characterized by pronounced star-formation and their inferred chemical abundances may be related to these regions rather than being representative of typical high- z galaxies. Faint metal line systems along the line of sight to quasars probe mainly galaxy haloes, rather than their bulges or discs. Taking advantage of ultra-deep *Gemini* multi-object spectrograph observations, Savaglio et al. (2004, 2005) studied the ISM of a sample of faint *K* band selected galaxies at $1.4 < z < 2.0$, finding MgII and FeII abundances much higher than in QSO systems and similar to those in GRB host galaxies. Such studies will hardly be extended to higher redshift with the present generation of 8 m class telescopes, because of the faintness of high- z galaxies. On the other hand, GRB afterglows provide an independent tool to study the ISM of high z galaxies.

Finally, GRB afterglow high resolution spectra can be used to probe the Ly- α forest and the high- z intergalactic medium. Using GRBs as remote beacons opens up the opportunity to highlight any deviation from what is already known as quasar forests. For example the so-called ‘‘proximity effect’’ (the feedback of QSOs on their local IGM) should be much reduced for GRBs.

The need to disentangle the contribution to the absorption spectra coming from these three different categories renders high resolution spectroscopy the ideal technique to study GRB optical afterglows.

Therefore we set up a program to observe bright optical afterglows of promptly localized GRBs with UVES@VLT, taking advantage of the capabilities of the GRB-dedicated *Swift* satellite. *Swift* was launched in November 2004, and provides GRB positions (2–3' precision) in <10 s, X-ray afterglow positions (5'' precision) in <100 s, and an optical finding chart in <300 s (few arcsec to sub-arcsec positional accuracy). These characteristics, together with the possibility of quick follow-up with UVES@VLT in RRM (Rapid Response Mode), offers the opportunity to obtain high resolution spectra of GRBs with delays from a few hours down to a few tens of minutes from the event.

To date, five GRBs have been observed with UVES@VLT after a *Swift* trigger: GRB050730, GRB050820A, GRB050922C, GRB060418 and GRB060607A.

In this paper, we present high resolution spectroscopy of GRB050730. This GRB was detected by *Swift* on 2005 July 30 19:58:23 UT (Holland et al. 2005, Sota et al. 2005) at RA(J2000) = 14^h08^m17^s.14 and Dec(J2000) = –03^d46'17".8. 133 s later, *Swift*'s XRT started to observe the X-ray afterglow in WT mode (Barthelmy et al. 2005). Chen et al. (2005b) found the redshift of the GRB at $z = 3.967$ with the MIKE echelle spectrograph on Magellan II, starting the observation ~ 4 h after the burst. The redshift was confirmed by Rol et al. (2005) using the ISIS spectrograph on the William Herschel Telescope at the Observatorio del Roque de los Muchachos on La Palma.

Starling et al. (2005) show an early WHT ISIS optical spectroscopy of GRB050730, finding that the host is a low metallicity galaxy, with low dust content. PCB06 present an analysis of the MIKE high resolution spectrum of GRB050730, treating the various absorption features as single Voigt profiles. Our main goal is instead that of trying to disentangle the relative contribution of

the various components (in velocity space) contributing to each absorption system, making a step forward with respect to Chen et al. (2005a) and PCB06.

We focus here on the study of the local medium surrounding the GRB, and in particular on the analysis of the fine structure absorption lines produced by the gas in the host galaxy. The comparison of such absorption features and their corresponding ground states yields information about the gas density, the temperature and the radiation field. A detailed analysis of the intervening absorption systems and of the Ly- α forest will be presented in a forthcoming paper.

The paper is organized as follows. Section 2 presents the observations and data reduction; Sect. 3 gives a brief description of the absorbing systems identified from the spectra; Sect. 4 is devoted to the analysis of the fine structure lines and to the estimate of the physical quantities characterizing the host galaxy gas; in Sect. 5 the results are discussed and conclusions are drawn.

2. Observations and data reduction

In the framework of ESO programs 075.A-0603 we observed the afterglow of GRB050730 with the high resolution UV-visual echelle spectrograph (UVES, Dekker et al. 2000), mounted at the VLT-UT2 telescope. Table 1 gives the log of the observations. Both UVES dichroics were used, employing the red as well as the blue arm. This allowed us to achieve a particularly wide spectral coverage, extending from ~ 3200 Å to ~ 9500 Å. In order to maximize the signal to noise ratio the CCD was rebinned by 2×2 pixels. The data reduction has been performed using the UVES pipeline (Ballester et al. 2000). The final useful spectra extend from about 3750 Å to about 9780 Å and were rebinned to 0.1 Å. The resolution element, set to two pixels, ranges then from 14 km s^{-1} at 4200 Å to 6.6 km s^{-1} at 9000 Å. The noise spectrum, used to determine the errors on the best fit line parameters, has been calculated from the real, background subtracted and rebinned spectrum, using line free regions. This therefore takes into account both statistical errors and systematic errors in the pipeline processing as well as the background subtraction.

3. Absorbing systems


Figure 1 shows the high resolution spectrum of GRB050730, with a cut-off at both the bluest and reddest end, where the signal-to-noise ratio becomes too small. The spectrum exhibits a large number of absorption features, belonging to different absorption systems. The main system is due to the gas in the host galaxy, at redshift $z_{\text{GRB}} = 3.96764$. This value confirms the previous redshift determinations for this GRBs. We identified four more intervening absorbers at $z < z_{\text{GRB}}$ not related to the GRB host galaxy but rather to galaxies along the line of sight. Each system is briefly described in the next subsections.

3.1. The host environment at $z = 3.967$

This is the system with the greatest number of features on the GRB line of sight. Figure 1 clearly shows the Ly- α absorption at ~ 6000 Å. The redshift inferred from this feature is confirmed by a large number of metal-line transitions. The precise value, which we calculated from the analysis of the narrowest lines associated with the host galaxy, is $z = 3.96764$. The spectrum exhibits a large number of absorption lines, from neutral hydrogen (Ly- α , Ly- β , Ly- γ), via neutral metal-absorption lines (OI) and low ionization lines (C II, Si II, Al II, Ni II, Fe II, P II, S II)

Table 1. Journal of observations.

Date UT	Dichroic	B. Arm C.W.	R. Arm C.W.	Slit ^a	Seeing ^a	Exposure ^b	Time since GRB ^c
07/31/05 00:07:17	1	3460 Å	5800 Å	1	≤1	50	4.15
07/31/05 01:02:09	2	4370 Å	8600 Å	1	≤1	50	5.07

^a arcsec; ^b min; ^c h.**Fig. 1.** The full high resolution spectrum of GRB050730. Dashed lines represent the noise spectrum. The spectrum is cut-off at the bluest and reddest end, where the signal-to-noise ratio becomes too small.

to high-ionization absorption features (C IV, Si IV, N V, O VI). In addition, strong fine structure lines (C II*, Si II*, O I*, O II**, Fe II*, Fe II**, Fe II***) have been identified, meaning either that the GRB environment is composed of a high density gas or that an intense radiation field is exciting such features.

The ISM of the host galaxy is complex, with many components contributing to the absorption system. This complex environment, together with a detailed study of the fine structure lines

aimed at estimating the physical quantities of the circumburst gas, will be described in the next section.

3.2. The intervening absorber at $z = 3.564$

This system presents neutral hydrogen features ($Ly-\alpha$, $Ly-\beta$), neutral metal-absorption lines (C I, Si I), low ionization lines (Al II, Mg II, Si II, Fe II) and high ionization lines (C IV, Si IV, N V). The redshift calculated from these features is $z \sim 3.56395$.

3.3. The intervening absorber at $z = 2.262$

This system presents only a few neutral metal-absorption lines (O I, Si I, Al I) and some low ionization transitions (Al II, Fe II). The redshift of this system is $z \sim 2.26181$.

3.4. The intervening absorber at $z = 2.253$

This is actually a double absorption system, the redshifts of the two components being $z \sim 2.2526$ and $z \sim 2.2536$. It shows neutral metal-absorption lines (Si I, Mg I), low ionization transitions (Si II, Fe II, Mg II) and possibly a C IV high ionization line.

3.5. The intervening absorber at $z = 1.772$

This is another double absorption system, the redshifts of the two components being $z \sim 1.7723$ and $z \sim 1.7729$. The system shows neutral metal-absorption lines (Mg I, Fe I) and low ionization transitions (Mg II, Fe II).

4. The main system at $z = 3.967$: physical properties of the GRB environment

This section, as well as the rest of the paper, is devoted to the study of the main absorption system of the spectrum, produced by the gas in the host environment, located close to the GRB explosion site.

The analysis of the GRB environment is intricate due to the complexity of the absorption lines of the spectrum, which in several cases can hardly be fitted with a single Voigt profile. This means that many components contribute to the gas in the GRB environment. In other words, several shells of gas which may be close to or far from each other, appear mixed together in the spectrum (in velocity space). Our main goal is to disentangle their relative contribution.

The identification of the components of the absorption lines and the fitting procedures will be discussed in the next subsection.

4.1. Absorption features of the GRB environment

The gas surrounding the GRB constitutes a complex environment, and this is reflected in the complexity of the absorption features. The presence of several components is indicative of

clumpy gas in the GRB environment, composed of different absorbing regions each with different physical properties. For example, a first component is present for the high ionization lines O VI and (less intensely) C IV, but not for Si IV and lower ionization lines (Fig. 2). This means that this particular component probably comes from a region very close to the GRB site, where it experienced a very intense flux of radiation ionizing the atoms several times.

If the absorption features are treated as a single Voigt profile, we obtain very bad fitting parameters and very high χ^2 values. The identification of the different components is somewhat subjective, the true message being that the geometry and kinematics of the ISM clouds probed by the GRB line of sight are complex. We decided to use the C IV $\lambda 1548, 1550$ Å and Si IV $\lambda 1393, 1402$ Å doublets, which have the wider velocity range, to identify the different components constituting the circumburst matter. Figure 2 shows C IV $\lambda 1550$ Å at $z = 3.9676$. For this line we obtain a good fit ($\chi^2 = 1.04$) if we assume that five different components contribute to the absorption features.

In the following, the components are numbered so that the first component is the one with the longest wavelength and the highest, positive, velocity shift with respect to a zero point arbitrarily placed at $z = 3.96764$, and so on. We next fixed the redshifts of the C IV components and tried to fit the Si IV doublet with the same five Voigt profiles. We did not obtain a good fit for the following reasons. First, the Si IV doublet does not exhibit the first and the last components that we see in the C IV (i.e., there are only three components), and second, a single central component is not enough to model the central part of the Si IV features alone. More precisely, the central component (number 3) must be splitted in two parts (3a and 3b) in order to obtain a good fit for Si IV; in fact, such a feature does not show saturation in its central part, while C IV does. This is clearly visible especially for Si IV $\lambda 1402$ Å (Fig. 2). Thus, using four components to represent Si IV, the first and the last being fixed at the redshift of the second and the fourth of C IV, we obtain a good fit ($\chi^2 = 0.64$) for this feature. All the further features we analyzed have been fitted fixing the redshift of the components to those we identified for either C IV or Si IV. Case by case, we decided to fit groups of elements with either C IV or Si IV, the choice depending on the extension of the lines and the saturation of the central part of the features. We specify that in these fitting procedures, the redshift of the components has been linked to that of C IV or Si IV, which in turn has been fixed to the values we find in the C IV and Si IV fit. Similarly, the column densities and Doppler parameters of the components of C IV and Si IV has been fixed while fitting these pilot lines together with other ones.

Finally, since the two central components of Si IV (3a and 3b) can not be resolved in the case of C IV, the corresponding column densities are computed separately, but summed together in the analysis as if we were dealing with a single component.

We detected several absorption fine structure features in the spectrum at the GRB redshift. The gas can be excited to such states via collisional effects (if the density is sufficiently high) or by the absorption of UV photons followed by the spontaneous radiative decay to an excited level of the ground state. Such lines can be very important in determining some physical properties of the gas, and thus we will consider them carefully. The next subsections describe the fits we performed to obtain the column densities of the elements that show fine structure transitions. The column densities corresponding to each component are reported in Tables 2 and 3.




Fig. 2. The C IV $\lambda 1550$ Å and Si IV $\lambda 1402$ Å absorption features together with the O VI $\lambda 1031, 1037$ Å doublet. Each component is identified with progressive numbers from the highest wavelength to the lowest one.




Fig. 3. The C II $\lambda 1036, 1037^*$ Å fine structure doublet. The solid line represents the five Voigt components fit.




Fig. 4. The C II $\lambda 1334, 1335^*$ Å fine structure doublet. The solid line represents the five Voigt components fit.

4.1.1. The ion CII


For this ion, we identified two fine structure doublets, namely C II $\lambda 1036$ Å C II* $\lambda 1037$ Å and C II $\lambda 1335$ Å C II* $\lambda 1337$ Å. We fitted these doublets together with C IV (Figs. 3 and 4). We note that only the second and third components out of the five in the fits in Fig. 2 are present in the excited fine structure levels, with a possible indication of the first component for C II* $\lambda 1037$ Å.

Table 2. Logarithmic ion column densities in cm^{-2} for the components of the main absorption system at $z = 3.967$.

Velocity shift ^a (component)	C II	C IV	O I	Si II	Si IV	Fe II
+32.6 (1)	Blend	14.4 ± 0.08	NO	NO	NO	NO
+2.4 (2)	14.33 ± 0.15	14.86 ± 0.08	SAT	14.68 ± 0.23	15.53 ± 0.11	15.24 ± 0.06
-44.0 (3a)	14.81 ± 0.13	14.75 ± 0.12	14.94 ± 0.09	13.62 ± 0.06	13.72 ± 0.09	14.66 ± 0.22
-44.0b (3b)			13.43 ± 0.11	13.60 ± 0.07	14.11 ± 0.10	
-90.2 (4)	12.98 ± 0.3	13.57 ± 0.13	NO	12.53 ± 0.24	13.21 ± 0.03	NO
-154.6 (5)	12.75 ± 0.35	13.04 ± 0.06	NO	NO	NO	NO

^a km s^{-1} .**Table 3.** Logarithmic ion column densities of excited fine structure states in cm^{-2} for the components of the main absorption system at $z = 3.967$.

Vel. ^a (Comp)	C II*	O I*	O I**	Si II*	Fe II*	Fe II**	Fe II***
+2.4 (2)	14.69 ± 0.26	SAT	14.64 ± 0.05	14.44 ± 0.09	14.29 ± 0.03	13.74 ± 0.08	13.60 ± 0.09
-44.0 (3a)	14.55 ± 0.09	13.56 ± 0.08	13.46 ± 0.09	13.41 ± 0.15	<13.14	NO	NO
-44.0b (3b)		NO	12.55 ± 0.60	13.66 ± 0.11	NO	NO	NO

^a km s^{-1} .**Fig. 5.** The Si II $\lambda 1304, 1309^*$ Å fine structure doublet and O I $\lambda 1302, 1304^*, 1306^{**}$ Å fine structure triplet. The solid line is the four Voigt components fit.


The fifth component, which is the one with the lowest redshift, is present only for C II $\lambda 1036$ Å; the blending of C II* $\lambda 1037$ Å by C II $\lambda 1036$ Å makes impossible to say whether this component is present in the excited level or not. The C II $\lambda 1335$ Å doublet appears to be saturated; this is evident by looking at the best fit, which is completely flat in the center of this line complex. Therefore, we use only the C II $\lambda 1036$ Å doublet to evaluate the electron density and temperature.

4.1.2. The ion Si II

For this ion, we identified three fine structure doublets: Si II $\lambda 1304$ Å (Si II* $\lambda 1309$ Å), Si II $\lambda 1526$ Å (Si II* $\lambda 1533$ Å) and Si II $\lambda 1260$ Å (Si II* $\lambda 1265$ Å). We fitted the first two doublets together with Si IV (Figs. 5 and 6). The first of these doublets has been fitted with the O I fine structure triplet too.

The third doublet falls in the Ly- α absorption gap. A reliable analysis of this feature is difficult because a correct subtraction of the continuum is not possible. Moreover, the excited level is further splitted into two sublevels, which blend with each other and render it impossible to fit the contribution of the various components.

As for C II, only the second and possibly the third component is present in the excited fine structure levels. Finally, the

**Fig. 6.** The Si II $\lambda 1526, 1533^*$ Å fine structure doublet. The solid line is the four Voigt components fit. The $\lambda 1533$ line is blended by several telluric features.

third component of the Si II* $\lambda 1533$ Å, if present, would fall in a region rich of telluric features, and thus can hardly be useful in determining the physical parameters of the gas.

4.1.3. The atom O I

This atom is present with the O I $\lambda 1302, 1304^*, 1306^{**}$ Å fine structure triplet (Fig. 5). It has been fitted with a four component profile, together with the Si IV components and the Si II $\lambda 1304, 1309^*$ Å fine structure doublet. As for previous ions, the only components present in the excited fine structure levels are the second and the third (splitted in 3a and 3b). The second component appears to be saturated both in the ground and in the first excited level O I $\lambda 1304^*$ Å, and will not be used in the analysis.

4.1.4. The ion Fe II

This ion is present in a wide variety of flavors. In this paper, we concentrate on the fine structure multiplet around $\lambda = 1600$ Å. This multiplet shows the following absorption features: Fe II $\lambda 1608$ Å, Fe II $\lambda 1611$ Å, Fe II* $\lambda 1618$ Å, Fe II* $\lambda 1621$ Å, Fe II** $\lambda 1629$ Å, Fe II*** $\lambda 1634$ Å, Fe II*** $\lambda 1636$ Å. Figure 7 presents the multiplet, together with the Si IV $\lambda 1393$ Å absorption feature.




Fig. 7. The Fe II 1608 fine structure multiplet, together with the Si IV 1393 absorption feature. The solid line represents the double Voigt component fit.

We can see that the Fe II excited levels only show the second component, while the ground state also includes the third component. We obtain a good fit with a single Voigt profile for the excited levels and a double line profile for the ground state. The central wavelengths of these Voigt profiles have been fixed to the redshifts of the second and third components of CIV.

In the next subsections we will describe in detail the physics which relates the fine structure transitions to the density and temperature of the gas that produces these features (provided that the fine levels are excited by collisional effects).

4.2. Fine structure line excitation via collisions

For ions with a doublet fine structure in the ground state, the ratio between the population density of the higher and the lower level is:

$$\frac{n_2}{n_1} = \frac{Q_{12} + w_{12}}{Q_{21} + w_{21}}, \quad (1)$$

where Q_{12} and Q_{21} are the collision rates from level 1 to level 2 and vice versa, and w_{12} (w_{21}) is the photon absorption (decay) rate between the two levels (Bahcall & Wolf 1968). Q_{12} and Q_{21} can be written in the form $Q = \sum_j \langle \sigma v \rangle_j N_j$, where each kind of exciting particle (proton, electron, etc.) is denoted by j , σ is the collisional cross section for the process involving the j th species, whose density and average speed are N_j and $\langle v \rangle_j$, respectively.

We are interested in the situation in which level 2 is the excited fine structure of the ground state 1. The excited fine structure levels can be produced by photon pumping or collisional excitations. Generally, the following mechanisms can be responsible for this excitation: (i) direct excitation by IR photons; (ii) excitation to upper levels through absorption of UV photons, followed by the spontaneous decay to an excited level of the ground state (indirect UV pumping); (iii) collisions with charged particles (mainly electrons) or with neutral hydrogen. PCB06 showed that the excitation rate by UV pumping is larger than IR pumping, rendering the latter excitation mechanism unimportant for gas observed in GRB afterglow spectra. In the following, we will elaborate the scenario in which collisions are the main mechanism responsible for the production of fine structure transitions and discuss subsequently (Sect. 4.4) the situation in which indirect UV pumping is at work.

If we assume that the collisions between electrons and ions represent the main process responsible for the excitation of the

fine structure levels, Eq. (1) simplifies since the quantities of the parameter Q now refer only to electrons. In particular, for the C II and Si II fine structure doublets, Eq. (1) becomes:

$$n_e = \frac{75 T_4^{0.5}}{\left[2 \frac{N(\text{CII})}{N(\text{CII}^*)} e^{91.75/T} - 1 \right]}, \quad (2)$$

and

$$n_e = \frac{1.28 \times 10^3 T_4^{0.5}}{\left[2 \frac{N(\text{SiII})}{N(\text{SiII}^*)} e^{413/T} - 1 \right]}, \quad (3)$$

respectively (Srianand & Petitjean 2001). These equations have been derived taking into account that the radiative excitation from the ground to the excited state is forbidden, and using the statistical weights; the radiative decay rates and the energy gaps are given in Bahcall & Wolf (1968). Here n_e is the electron density, N is the column density of the element in parentheses (the asterisk refers to excited fine structure levels) and T_4 is the kinetic temperature in units of 10^4 K.

For a fine structure system with multiple levels, the situation is more complicated, unless we assume that electron-ion collisions are dominant with respect to the radiative processes. If this is the case, the w terms in Eq. (1) can be neglected, and the electron density disappears, yielding:

$$\frac{n_i}{n_j} = \frac{g_i}{g_j} \exp[-E_{ij}/kT], \quad (4)$$

in the case of thermal equilibrium (PCB06). Equation (4) tells us that the levels are populated according to a Boltzmann distribution; here g_i is the degeneracy of the state i , $E_{ij} = E_i - E_j$ is the energy difference between the state i and j and T is the excitation temperature.

4.3. Temperature and density of the gas in the case of collisional excitation

In this section we try to obtain an estimate of the temperature and density of the gas in the GRB environment. We showed in the previous section that the excited states of the fine structure transitions present some absorption only in the second and third component of the five identified. For this reason, the physical quantities can be computed or constrained only in these two cases.

We proceed in the following way. First of all, we assume that the electron-ion collisions are the main mechanism responsible for the production of the excited fine structure feature (PCB06).

For fine structure doublets (C II and Si II), we plot in Fig. 8 the electron density as a function of the ratio between the absorbing columns of the ground state with respect to the excited one (N/N^*), using Eqs. (2) and (3), and for different values of the temperature. In this plot, vertical lines are loci of constant N/N^* . We then draw vertical lines corresponding to our measure of the ratio N/N^* and to the corresponding errors. In this way we can constrain the density of the gas for a fixed interval of temperature, and even constrain the temperature itself, if both the C II and Si II present an excited fine structure absorption.

For fine structure multiplets, we use Eq. (4) under the assumption of thermal equilibrium. Fitting the ratio of the column densities to their multiplicity factors with respect to the energy difference between each excited state and the ground state, we can obtain a measure of the temperature of the gas. Such a temperature can constrain the gas density using the plots of Eqs. (2) and (3) for the fine structure doublets, or can be used as an input




Fig. 8. *Top panel:* the electron density as a function of the ratio between the absorbing columns of the ground state with respect to the excited one, for three different values of the temperature, calculated for the C II fine structure doublets. Vertical lines represent the observed (N/N^*) ratio (solid line) and its 1σ errors (dashed lines). The figure refers to the second component of the host environment gas. *Bottom panel:* same as top panel, but for Si II fine structure doublets.

for the PopRatio software package (Silva & Viegas 2001), to estimate the electron density independently once the ratio between the column densities of the fine structure levels of the multiplets is known.

As previously remarked, only component 2 and 3 of the main absorption system feature fine structure transition; in the following sub-subsections we present the analysis of such components.

4.3.1. Component $z = 3.967_2$

This component features high column densities for all the ground states: C II, O I, Si II and Fe II. The excited fine structure levels appear in all their flavors: we have strong C II*, O I* / O I** and Si II* columns; moreover Fe II is present with its first three excited levels. We plot the electron density as a function of (N/N^*) for three different temperatures, namely $T = 10^4$, $T = 5 \times 10^3$ and $T = 10^3$ K, for C II (Fig. 8, top panel) and




Fig. 9. The ratios between column density and degeneracy of the excited fine structure Fe II levels as a function of their energy gap to the ground state. The solid line represents our best fit to the data.

Si II (Fig. 8, bottom panel). For C II we used the 1036–1037 Å feature, because C II $\lambda 1334$ Å is saturated.

We can see from Fig. 8 that both for C II and Si II the observed column densities can only put a lower limit to the electron density, independently of the temperature of the gas. This lower limit lies in the range $50 \div 200 \text{ cm}^{-3}$ and $100 \div 300 \text{ cm}^{-3}$ for temperatures of $10^3 \div 10^4$ K, for C II and Si II respectively.

For this component, we also made a fit to the temperature using Eq. (4) and the Fe II multiplet data (Fig. 9). The value we found is $T = 2600^{+3000}_{-900}$ K (90% confidence limit); such a value agrees with that found by PCB06, for the same GRB.

The same fit has not been performed for the O I, because its ground state appears to be saturated.

4.3.2. Component $z = 3.967_3$

This component features high column densities for the ground states of the C II, O I and Fe II, while that of Si II is very low. As for the excited fine structure levels, we have strong C II* and low O I* columns; Fe II excited levels are absent. Si II* is difficult to treat. Apart from the $\lambda 1265$ line that falls in the Ly- α absorption gap, the $\lambda 1533$ line is blended with several telluric features (Fig. 6). The last flavor of Si II, the $\lambda 1309$ line, shows a hint of a possible absorption feature (Fig. 5); however, since the corresponding ground state is very lowly populated, this feature is somewhat suspect. As for the second component, we plot the electron density as a function of (N/N^*) for three different temperatures, namely $T = 10^4$, $T = 5 \times 10^3$ and $T = 10^3$ K, for C II and Si II (Fig. 10). For C II we used the $\lambda 1036$ – 1037 feature, because C II $\lambda 1334$ Å is saturated.

Figure 10, top panel indicates that the electron density inferred from C II lies in the range $10 \div 60 \text{ cm}^{-3}$ for a temperature of $10^3 \div 10^4$ K. If we consider the plot for Si II, the density appears to be higher than $\sim 200 \text{ cm}^{-3}$, if we assume a temperature of $\sim 10^3$ K. Thus, there is no overlap between the two solutions. As we discussed above, the Si II* $\lambda 1309$ Å is a suspicious feature, because the corresponding ground state (Si II $\lambda 1304$ Å) is poorly populated, while for the other elements the ground state is very highly populated when an excited level is present. In the following, we will consider either that Si II* $\lambda 1309$ Å is real or it is not.

For this component, we also estimate a temperature using Eq. (4) and O I triplet data. The value we find is $T = 10^3$ K, but




Fig. 10. *Top panel:* the electron density as a function of the ratio between the absorbing columns of the ground state with respect to the excited one, for three different values of the temperature, calculated for the C II fine structure doublets. Vertical lines represent the observed (N/N^*) ratio (solid line) and its 1σ errors (dashed lines). The figure refers to the third component of the host environment gas. *Bottom panel:* same as top panel, but for Si II fine structure doublets.

we only have two points in the fit so the errors are too large to put an acceptable constraint on the temperature.

4.4. Fine structure line excitation via indirect UV pumping

In the previous sections we assumed that fine structure excited levels are produced by collisions. The other, competitive mechanism is indirect UV pumping. In fact, the fine structure levels can be excited by the absorption of a UV photon to an upper level followed by the spontaneous decay to an excited lower level. If this mechanism is at work, we cannot use the fine structure abundances to gather information about the temperature and density of the gas, but only on the strength of the radiation field. PCB06 (using the PopRatio code developed by Silva & Viegas 2001, 2002) analyzed the relation between the far UV radiation field intensity and the relative fraction of excited fine structure states with respect to their ground levels (for O I, Si II and Fe II, see their Figs. 7 and 8). In the following subsections, we will use their plots to estimate the radiation field intensity from our

column density data, in the case that the fine structure transitions are produced by indirect UV pumping.

4.4.1. Component $z = 3.967_2$

As we showed before, this is the component which presents more fine structure excited states. We evaluate the ratio between the ground and the first excited levels for Fe II($\lambda 1608-1611 \text{ \AA}$ and $\lambda 1618^*-1621^* \text{ \AA}$) as well as the ratio between the Si II $\lambda 1526 \text{ \AA}$ and Si II* $\lambda 1533 \text{ \AA}$ fine structure levels. The O I ground state is saturated and can not be used in the analysis. Using Fig. 7 of PCB06, we find that the two ratios are compatible with a radiation field intensity of $G/G_0 = 5 \times 10^5$, $G_0 = 1.6 \times 10^{-3} \text{ erg cm}^{-2} \text{ s}^{-1}$ being the Habing constant. A consistent result is obtained estimating the ratios of the absorbing column of the first excited level of Fe II to the second and third ones, and using Fig. 8 of PCB06. Again, we find that the two ratios yield a value of $G/G_0 = 5 \times 10^5$. The 90% confidence interval for the field intensity is $G/G_0 = 10^5 \div 10^6$.

4.4.2. Component $z = 3.967_3$

This component exhibits the C II fine structure doublet, the O I triplet and possibly the Si II excited level. As we discussed in Sect. 4.3.2, the Si II* detection is uncertain. Nevertheless, using the O I and Si II ratios between the ground and first excited level, we find two different values for the radiation field intensity: $G/G_0 = 10^5$ and $G/G_0 = 10^6$, respectively. These values do not overlap at the 90% confidence limit. Since the detection of Si II* is uncertain, we cannot exclude in this way that the fine structure excited levels in this component are produced by indirect UV pumping. However, the theoretical lines representing the Fe II*/Fe II and O I*/O I abundance ratios as a function of the radiation field in Fig. 8 of PCB06, approach each other very closely. This means that we should observe a similar column of Fe II* with respect to Fe II, as we observe for O I* with respect to O I. Since $N_{\text{OI}^*}/N_{\text{OI}} = 0.04$, and $N_{\text{FeII}} = 14.66 \text{ cm}^{-2}$ (see Tab. 2), we expect $N_{\text{FeII}^*} = 13.26 \text{ cm}^{-2}$. However, this is not the case, because the upper limit that we found for the first excited level of the Fe II is $N_{\text{FeII}^*} < 13.14 \text{ cm}^{-2}$ at the 90% confidence level. On the other hand, if the fine structure states of the third component are produced by collisions, the O I*/O I abundance ratio would yield an electron density of a few tens cm^{-3} , compatible with that found for the C II fine structure doublet in Sect. 4.3.2, and the ratio Fe II*/Fe II would be 10 times smaller the O I*/O I one (see Fig. 9 in PCB06). This means that we expect $N_{\text{FeII}^*} = 11.96 \text{ cm}^{-2}$, a value consistent with the observed upper limit.

4.5. Neutral elements and gas distance from the GRB

The presence of neutral elements in the spectra of GRB afterglows is important, because it can put strong constraints on the distance of the gas from the GRB. This is because the first ionization potential of the elements usually lies below the 1 Ryd threshold. Thus, the intense radiation coming from the GRB would easily ionize the neutral elements, without the screening of the Hydrogen atoms, the first ionization potential of which is at higher energies. PCB06 observed the Mg I $\lambda 2852 \text{ \AA}$ transition in GRB051111, and they put a lower limit of 50 pc to the distance of the gas from the GRB. Moreover, they refined this limit to 80 pc since no variability of the Mg I line has been observed.

In GRB050730, we observe many O I transitions. Oxygen, however, has a first ionization potential that lies just above the 1 Ryd threshold, and can exist in its neutral state even in the presence of a strong radiation field, because the Hydrogen screens it from the UV photons. We can not observe the Mg I $\lambda 2852$ Å transition because of the redshift of our GRB. In addition, we do not observe any other neutral element in the afterglow so we can not put any constraint on the gas distance from the GRB this way. The upper limit that we find for the neutral carbon absorption line (C I $\lambda 1656$ Å) is $N_{\text{C I}^*} < 13.2 \text{ cm}^{-2}$ at the 90% confidence level.

Some considerations on the relative distance of the different shells of gas from the GRB can be pursued. Component 1 of the $z = 3.967$ system, the one with the longest wavelength, highest positive velocity shift (see Sect. 4.1), does not present any fine structure or low ionization lines; it only shows very high ionization features, such as CIV and O VI, suggesting that this component is very close to the GRB site. Moreover, if we assume that the fine structure lines of the shells are produced by the same mechanism (collisions or UV pumping), we can also say something about component 2 and 3. In fact, in the case of collisional excitations we, can estimate the electron density of the gas and this can be related to the distance r using the definition of the ionization parameter:

$$U = \frac{L_{\text{phot}}}{4\pi r^2 c n_e}, \quad (5)$$

where L_{phot} is the number of ionizing photons and c is the speed of light. A time independent estimate of U with photoionization codes like CLOUDY (Ferland 2002) is inappropriate in the case of a strongly variable phenomenon such as a GRB. Nevertheless, if we assume the electron density found in Sect. 4.3 for the third component ($10 \div 100 \text{ cm}^{-3}$) and for the second one ($10^3 \div 10^6 \text{ cm}^{-3}$) we can conclude (using the scaling law of Eq. (5)) that the gas belonging to the third component lies $10 \div 100$ times farther from the GRB than that belonging to the second one.

In a similar way, we can assume that indirect UV pumping is at work. In this case, the distance increases as the square root of the UV flux. If we trust the estimate of the radiation field intensity evaluated only from the O I*/O I ratio for the third component, we can conclude that the gas in the second component is a few ten times closer to the GRB than that of the third one.

4.6. Metallicity

Figure 11 shows the Ly- β and Ly- γ absorption features. It is impossible to discriminate between the five components identified from the analysis of C IV and Si IV. The hydrogen absorption features result in very broad lines with two extended wings, which reach well beyond the velocity range of the heavier ions. Since a component by component analysis is not possible, we can only estimate the metallicity of the circumburst material in terms of the ratio $[X/H]$ between the total absorption column of the X element with respect to that of hydrogen. Since the latter mainly includes hydrogen in the outer regions of the galaxy, we will underestimate the metallicity.

Table 4 shows our estimate of the metallicity. The second column presents the column densities of the different ions, being the sum of the columns of the five components of the ground states and of the excited fine structure levels, if these are present. The third column of Table 4 is the total column density for each element, and is obtained adding the column densities of the various ions through which the element appears in the spectrum. We




Fig. 11. The Ly- β and Ly- γ absorption features, together with the CIV $\lambda 1548$ and CIV $\lambda 1550$ doublet. The red line represents the five Voigt component fit.

Table 4. Metallicity.

Ion	$\log N \text{ (cm}^{-2}\text{)}$	$\log N^a \text{ (cm}^{-2}\text{)}$	$[X/H]$	$[X/H]_{\odot}$
H I	22.05 ± 0.29	–	–	–
C II	15.23 ± 0.15	–	–	–
C IV	15.19 ± 0.09	–	–	–
C		15.51 ± 0.12	-6.54 ± 0.41	-2.93 ± 0.41
O I	SAT	–	–	–
O VI	SAT	–	–	–
Si II	14.96 ± 0.15	–	–	–
Si IV	15.55 ± 0.12	–	–	–
Si		15.65 ± 0.13	-6.40 ± 0.42	-1.94 ± 0.42
Fe II	15.39 ± 0.10	15.39 ± 0.10	-6.66 ± 0.39	-2.11 ± 0.43

^a Total column density of the element.

could not get an estimate of the column density of Oxygen, because the absorption features of O I and O VI are saturated. Not surprisingly, we obtain a metallicity of $10^{-2} \div 10^{-3}$ relative to the solar one, in agreement with the paper by Starling et al. (2005). It should also be noted that these estimates are not corrected for depletion in dust grains. In the Galactic ISM only $\sim 1\%$ of the iron is in the gas phase while the rest is locked in dust grains (Savage & Sembach 1996). The situation can be very different in a GRB host galaxy, and in particular, in the GRB surrounding medium (Waxman & Draine 2002; Draine & Hao 2002; Perna & Lazzati 2002; Perna et al. 2003), because the intense GRB radiation field can efficiently destroy dust grains. Caution should therefore be used in using mean metallicity estimates.

We can also calculate the ratio $[C/Fe]$, representative of the enrichment of the α elements relative to iron. We measure a mean $[C/Fe] = 0.08 \pm 0.24$, consistent with the value predicted by the models of Pipino & Matteucci (2004, 2006) for a galaxy younger than 1 Gyr subject to a burst of star-formation. In such a case Pipino & Matteucci (2006) also predict a low $[Fe/H]$ value, close to that in Table 4. Again, we warn that mean abundance estimates may be affected by large systematic uncertainties.

A safer approach is to estimate the $[C/Fe]$ of each component of the $z = 3.967$ system. We find that $[C/Fe]$ of component 2 is -0.15 ± 0.13 while that of component 3 is $+0.53 \pm 0.23$. Indeed, note in Tables 2 and 3 that while the total carbon column density of component 2 and 3 are similar, the total column density of

iron of component 3 is about four times less than that of component 2. A similar conclusion applies to silicon. The total silicon column density of component 3 is also about 10 times less than that of component 2. Interestingly, Perna et al. (2003) found that silicates tend to be destroyed more efficiently than graphite if a dusty medium is exposed to the intense GRB radiation field. This would leave more iron free in the gas phase in clouds closer to the GRB site than in farther clouds, in agreement with our suggestion that component 2 is 10–100 times closer to the GRB site than component 3.

5. Conclusions

In this paper we present high resolution ($R = 20\,000\text{--}45\,000$, corresponding to 14 km s^{-1} at 4200 \AA and 6.6 km s^{-1} at 9000 \AA) spectroscopy of the optical afterglow of Gamma Ray Burst GRB050730, observed by UVES@VLT ~ 4 h after the trigger.

We confirm that the redshift of the host galaxy is $z = 3.96764$. Four intervening systems between $z = 3.56$ and $z = 1.77$ have been identified along the GRB line of sight, in addition to the main system at the redshift of the host galaxy.

For what concerns the main absorption system, the spectrum shows that the ISM of the GRB host galaxy is complex, with at least five components contributing to this main absorption system at $z = 3.967$. Such components are identified in this paper with progressive numbers with decreasing velocity values.

These absorption lines appear in different flavors, from neutral hydrogen ($\text{Ly-}\alpha$, $\text{Ly-}\beta$, $\text{Ly-}\gamma$), to neutral metal-absorption lines (OI), and via low ionization lines (C II, Si II, Mg II, Al II, Ni II, Fe II, P II, S II) to high-ionization absorption features (C IV, Si IV, N V, O VI).

In addition, we detect strong C II*, Si II*, O I* and Fe II* fine structure absorption features in components 2 and 3 (no Fe II* in the last component). The ratio of these lines to their ground states are used to constrain the gas density and temperature, under the assumption that they are produced via collisional excitation, or alternatively by UV pumping. If collisional excitation is at work, we find that the gas producing the fine structure features has a temperature of a few thousand K, and an electron density $n_e = 10^3 \div 10^6\text{ cm}^{-3}$ (component 2) or $n_e = 10 \div 10^2\text{ cm}^{-3}$ (component 3). On the other hand, if UV pumping is the process responsible for the fine structure features, the radiation field exciting the gas has an intensity of $G/G_0 = 10^5 \div 10^6$.

We speculate that the excitation mechanisms of the fine structure lines may be different, with component 3 probably excited by collisions, and component 2 by UV pumping. This is because the observed O I*/O I ratio in component 3 would imply a similar Fe II*/Fe II ratio in the case of UV pumping, which is not observed. On the other hand, the radiation field intensities calculated from the fine structure ratios for component 2 are all in agreement with each other.

Component 1, the one with the longest wavelength, highest positive velocity shift, does not present any fine structure or low ionization lines; it only shows very high ionization features, such as C IV and O VI, suggesting that this component is very close to the GRB site.

For the first three components we can derive information on the relative distance to the site of the GRB explosion. Both for collisional excitation and UV pumping, component 2 appears to be 10–100 times closer to the GRB site than component 3.

As to the metallicity, for the system at $z = 3.967$ we obtain mean values $\approx 10^{-2}$ of the solar metallicity or less. However, this should not be taken as representative of the circumburst

medium, since the main contribution to the hydrogen column density comes from the outer regions of the galaxy while that of the other elements presumably comes from the ISM closer to the GRB site and since the correction for dust depletion is highly uncertain. It is however interesting to note that the mean [C/Fe] ratio agrees well with that expected by the single star-formation event models of Pipino and Matteucci (2004, 2006).

We could also measure the [C/Fe] of the single components 2 and 3. The [C/Fe] ratio of component 2 is -0.15 ± 0.13 , marginally different from that of component 3, 0.54 ± 0.23 . Although the result is significant at only 2.6σ confidence level, it is interesting to speculate on its origin. If the cloud responsible for the absorption component 2 is closer than the cloud producing component 3 to the GRB site, we expect that dust destruction in this cloud, due to the interaction of the GRB radiation field with the medium, is more efficient than in the cloud responsible for component 3. Since silicates tend to be destroyed more efficiently than graphite (Perna, Lazzati & Fiore 2003), we expect more iron and silicon freed in the gas phase in cloud 2 than in cloud 3, as observed.

Acknowledgements. We acknowledge support from contract ASI/I/R/039/04 (Swift). FF acknowledges support from contract ASI/I/R/023/05/0. We thank Roberto Maiolino for useful discussions. R.P. and D.L. acknowledge support by NSF grant AST-0507571.

References

- Bahcall, J. N., & Wolf, R. A. 1968, *ApJ*, 152, 701
 Barthelmy, S., et al. 2005, *GCN Circ*, 3704
 Ballester, P., Modigliani, A., Boitquin, O., et al. 2000, *ESO Messenger*, 101, 31
 Boettcher, M., Fryer, C. L., & Dermer, C. D. 2002, *ApJ*, 567, 441
 Chen, H. W., Prochaska, J. X., Bloom, J. S., & Thompson, I. B. 2005a, *ApJ*, 634, L25
 Chen, H. W., et al. 2005b, *GCN Circ*, 3709
 Draine, B. T., & Hao, L. 2002, *ApJ*, 569, 780
 Ferland, G. S. 2002, University of Kentucky Dept. of Physics and Astronomy, Internal Report
 Fiore, F., D'Elia, V., Lazzati, D., et al. 2005, *ApJ*, 624, 853
 Holland, S. T., et al. 2005, *GCN Circ*, 3704
 Mirabal, N., Halpern, J. P., Kulkarni, S. R., et al. 2002, *ApJ*, 578, 818
 Penprase, B. E., Berger, E., Fox, D. B., et al. 2006, *ApJ*, 646, 358
 Perna, R., & Loeb, A. 1998, *ApJ*, 501, 467
 Perna, R., & Lazzati, D. 2002, *ApJ*, 580, 261
 Perna, R., Lazzati, D., & Fiore, F. 2003, *ApJ*, 585, 775
 Pipino, A., & Matteucci, F. 2004, *MNRAS*, 347, 968
 Pipino, A., & Matteucci, F. 2006, *MNRAS*, 365, 1114
 Prochaska, J. X., Chen, H. W., & Bloom, J. S. 2006, *ApJ*, 648, 95 (PCB06)
 Rol, E., et al. 2005, *GCN Circ*, 3710
 Savage, B. D., & Sembach, K. R. 1996, *ApJ*, 470, 893
 Savaglio, S., Fall, S. M., & Fiore, F. 2003, *ApJ*, 585, 638
 Savaglio, S., Glazebrook, K., Crampton, D., et al. 2004, *ApJ*, 602, 51
 Savaglio, S., Glazebrook, K., Le Borgne, et al. 2005, *ApJ*, 635, 260
 Silva, A. I., & Viegas, S. M. 2001, *Computer Phys. Commun.*, 139, 319
 Silva, A. I., & Viegas, S. M. 2002, *MNRAS*, 329, 135
 Sota, A., Castro-Tirado, A. J., Guziy, S., et al. 2005, *GCN Circ*, 3705
 Starling, R. L. C., Vreeswijk, P. M., Ellison, S. L., et al. 2005, *A&A*, 442, L21
 Steidel, C. C., Adelberger, K. L., Giavalisco, M., Dickinson, M., & Pettini, M. 1999, *ApJ*, 519, 1
 Srianand, R., & Petitjean, P. 2001, *A&A*, 373, 816
 Srianand, R., Petitjean, P., & Ledoux, C. 2000, *Nature*, 408, 931
 van Marle, A. J., Langer, N., & Garcia-Segura, G. 2005, *A&A*, 444, 837
 Waxman, E., & Draine, B. T. 2002, *ApJ*, 537, 796
 Vreeswijk, P. M., Ellison, S. L., Ledoux, C., et al. 2004, *A&A*, 419, 927

¹ INAF - Osservatorio Astronomico di Roma, Via Frascati 33, 00044 Monteporzio Catone, Italy

² Dunsink Observatory, Castleknock, Dublin 15, Ireland

³ INAF, Osservatorio Astronomico di Brera, via E. Bianchi 46, 23807 Merate (LC), Italy

- ⁴ Università di Milano Bicocca, Piazza della Scienza 3, 20126 Milano, Italy
- ⁵ Astronomic Research Institute, Liverpool John Moores University, Twelve Quays House, Egerton Wharf, Birkenhead CH41 1LD, UK
- ⁶ School of Physical Sciences and NCPST, Dublin City University, Glasnevin, Dublin 9, Ireland
- ⁷ CEA Saclay, DSM/DAPNIA/Service d'Astrophysique, Bat. 709, L'Orme des Merisiers, 91191 Gif-sur-Yvette Cedex, France
- ⁸ JILA, Campus Box 440, University of Colorado, Boulder, CO 80309-0440, USA
- ⁹ NASA-Goddard Space Flight Center, Greenbelt, Maryland, 20771, USA
- ¹⁰ Department of Astronomy and Astrophysics, Pennsylvania State University, University Park, Pennsylvania 16802, USA
- ¹¹ ASI Science Data Center, Via G. Galilei, 00044 Frascati (Roma), Italy
- ¹² INAF - Osservatorio Astronomico di Arcetri, Largo E. Fermi 5, 50125 Firenze, Italy
- ¹³ INAF - Roma, Via Fosso del Cavaliere 100, 00133 Roma, Italy
- ¹⁴ INAF - Istituto di Astrofisica Spaziale e Fisica Cosmica di Palermo, Via U. La Malfa 153, 90146 Palermo, Italy
- ¹⁵ Università di Ferrara, Via Paradiso 12, 44100 Ferrara, Italy
- ¹⁶ UMR 7164, 11 place M. Berthelot, 75231 Paris, France
- ¹⁷ International School for Advanced Physics, Via Beirut 2-4, 34014 Trieste, Italy
- ¹⁸ European Southern Observatory, Casilla 19001, Santiago, Chile
- ¹⁹ PPARC, Polaris House, North Star Avenue, Swindon SN2 1SZ, UK
- ²⁰ INAF-Istituto di Astrofisica Spaziale e Fisica Cosmica, Via Bassini, 15, 20133 Milano, Italy
- ²¹ European Southern Observatory-Vitacura, Casilla 19001, Santiago 19, Chile
- ²² Scuola Normale Superiore, Piazza dei Cavalieri 7, 56126 Pisa, Italy